

FEDERAL REGISTER

VOLUME 31 • NUMBER 174

Thursday, September 8, 1966 • Washington, D.C.


Pages 11737-11850

(Part II begins on page 11793)

Agencies in this issue—

The President
Agricultural Stabilization and
Conservation Service
Civil Aeronautics Board
Coast Guard
Consumer and Marketing Service
Emergency Planning Office
Federal Aviation Agency
Federal Communications Commission
Federal Maritime Commission
Federal Power Commission
Federal Trade Commission
Fish and Wildlife Service
Food and Drug Administration
Housing and Urban Development
Department
Immigration and Naturalization
Service
Internal Revenue Service
Interstate Commerce Commission
Land Management Bureau
National Park Service
Reclamation Bureau
Securities and Exchange Commission
Small Business Administration
State Department

Detailed list of Contents appears inside.



How To Find U.S. Statutes and United States Code Citations

[Revised Edition—1965]

This pamphlet contains typical legal references which require further citing. The official published volumes in which the citations may be found are shown alongside each reference—with suggestions as to the logical sequence to follow in using them. Additional finding aids, some especially useful in citing current legislation, also have been in-

cluded. Examples are furnished at pertinent points and a list of references, with descriptions, is carried at the end.

This revised edition contains illustrations of principal finding aids and reflects the changes made in the new master table of statutes set out in the 1964 edition of the United States Code.

Price: 10 cents

Compiled by Office of the Federal Register, National Archives and Records Service, General Services Administration

[Published by the Committee on the Judiciary, House of Representatives]

**Order from Superintendent of Documents, U.S. Government Printing Office
Washington, D.C. 20402**



Area Code 202

Phone 963-3261

Published daily, Tuesday through Saturday (no publication on Sundays, Mondays, or on the day after an official Federal holiday), by the Office of the Federal Register, National Archives and Records Service, General Services Administration (mail address National Archives Building, Washington, D.C. 20408), pursuant to the authority contained in the Federal Register Act, approved July 26, 1935 (49 Stat. 500, as amended; 44 U.S.C., Ch. 8B), under regulations prescribed by the Administrative Committee of the Federal Register, approved by the President (1 CFR Ch. I). Distribution is made only by the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402.

The FEDERAL REGISTER will be furnished by mail to subscribers, free of postage, for \$1.50 per month or \$15 per year, payable in advance. The charge for individual copies varies in proportion to the size of the issue (15 cents for the first 80 pages and 5 cents for each additional group of 40 pages, as actually bound). Remit check or money order, made payable to the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402.

The regulatory material appearing herein is keyed to the CODE OF FEDERAL REGULATIONS, which is published, under 50 titles, pursuant to section 11 of the Federal Register Act, as amended. The CODE OF FEDERAL REGULATIONS is sold by the Superintendent of Documents. Prices of books and pocket supplements are listed in the first FEDERAL REGISTER issue of each month.

There are no restrictions on the republication of material appearing in the FEDERAL REGISTER or the CODE OF FEDERAL REGULATIONS.

Contents

THE PRESIDENT

EXECUTIVE ORDER

- Prescribing regulations governing allowance of travel expenses of claimants and beneficiaries of the Veterans' Administration and their attendants..... 11741

EXECUTIVE AGENCIES

AGRICULTURAL STABILIZATION AND CONSERVATION SERVICE

Notices

- Sugarbeets; hearing..... 11771

AGRICULTURE DEPARTMENT

See Agricultural Stabilization and Conservation Service; Consumer and Marketing Service.

CIVIL AERONAUTICS BOARD

Notices

- Condor Flugdienst G.m.b.H.; hearing..... 11773
In-flight entertainment charge; postponement of oral argument..... 11773

COAST GUARD

Notices

- Equipment, installations, or materials; approval and termination of approval..... 11763

CONSUMER AND MARKETING SERVICE

Rules and Regulations

- Almonds; salable and surplus percentages for 1966-67 crop year..... 11744
Oranges, Valencia, in Arizona and California; handling limitation..... 11743
Potatoes, Irish; expenses and rate of assessment:
Colorado..... 11743
Washington..... 11743
Special milk program for children; definition of milk..... 11743

Proposed Rule Making

- Olives in California; handling..... 11758

Notices

- Carcass identification; changes in lists of establishments..... 11771

EMERGENCY PLANNING OFFICE

Notices

- Nebraska; major disaster..... 11783

FEDERAL AVIATION AGENCY

Rules and Regulations

- Airway, jet route low and high altitude reporting points, and control area; extension, designation, and alteration..... 11745
Control zones and transition area; alteration..... 11745
Federal aid to airports; exclusive rights prohibition..... 11747
IFR altitudes; miscellaneous amendments..... 11745

Proposed Rule Making

- Control area, control zone, and transition area; revocation, alteration and designation..... 11760
Controlled airspace; alteration (2 documents)..... 11761
Transition areas:
Alteration (2 documents)..... 11759, 11760
Designation..... 11759

FEDERAL COMMUNICATIONS COMMISSION

Rules and Regulations

- Tort claims handling; delegation of authority..... 11755

Proposed Rule Making

- FM broadcast stations; table of assignments..... 11761

Notices

- Hearings, etc.:
Bay Broadcasting Co..... 11773
Camden, N.J., and L & P Broadcasting Corp..... 11773
Chapman Radio and Television Co. et al..... 11773
Harriscop, Inc., and Family Broadcasting, Inc..... 11773

FEDERAL MARITIME COMMISSION

Notices

- Agreements filed for approval:
Isthmian Lines, Inc., and Sealand Service, Inc..... 11783
Pacific Far East Line, Inc., and Saipan Shipping Co..... 11783

FEDERAL POWER COMMISSION

Notices

- Hearings, etc.:
Ashland Oil & Refining Co. et al..... 11774
Community Natural Gas Co., Inc., and Midwestern Gas Transmission Co..... 11782
Continental Oil Co. et al..... 11774
Idaho Power Co..... 11782
Texaco Inc., et al..... 11780
United Gas Pipe Line Co..... 11782

FEDERAL TRADE COMMISSION

Rules and Regulations

Prohibited trade practices:

- Beatrice Foods Co..... 11750
Brown Shoe Co..... 11754
Kalin, Benjamin D., et al..... 11751
McDonald, Thomas Harris, and McDonald & Son Golf Co..... 11752
M. Hat Shoppe, Inc., et al..... 11753
Phillips Petroleum Co., et al..... 11747
Thomas F. Lukens Metal Co. and Mitchell Steinberg..... 11750
Smarz, William, and Mercantile and Medical Credit Adjusters..... 11751
Steinberger Bros., Inc., et al..... 11750
Tri-Valley Packing Assn..... 11753

FISH AND WILDLIFE SERVICE

Rules and Regulations

- Big game hunting; Crab Orchard National Wildlife Refuge, Illinois..... 11757
Migratory game bird hunting:
Erie National Wildlife Refuge, Pennsylvania..... 11757
Eufaula National Wildlife Refuge, Alabama..... 11756
Havas Lake National Wildlife Refuge, Arizona and California..... 11756
Malheur National Wildlife Refuge, Oregon..... 11757

Notices

- McKinley, Levi; loan application..... 11771
Murphy, Harlan Truitt; hearing..... 11771

FOOD AND DRUG ADMINISTRATION

Rules and Regulations

- Fruit preserves and jams; identity standard for optional use of concentrated fruit ingredients; confirmation of effective date..... 11754
Phenmetrazine and its salts; listing as drug subject to control; confirmation of effective date..... 11754
Tolerances for pesticide chemicals in or on raw agricultural commodities; procedural regulations; deletion of obsolete material..... 11754

Notices

- Filing of petitions:
Continental Can Co., Inc..... 11772
E. I. du Pont de Nemours and Co..... 11772
FMC Corp..... 11772
Geigy Chemical Corp..... 11772
Koppers Co., Inc..... 11772

HEALTH, EDUCATION, AND WELFARE DEPARTMENT

See Food and Drug Administration.

(Continued on next page)

HOUSING AND URBAN DEVELOPMENT DEPARTMENT

Notices

Acting Assistant Secretary for
Demonstrations and Intergov-
ernmental relations; designa-
tion 11773

IMMIGRATION AND NATURALIZATION SERVICE

Rules and Regulations

Nonimmigrant classes; deporta-
tion of aliens in U.S.; miscel-
laneous amendments 11744

INTERIOR DEPARTMENT

See Fish and Wildlife Service;
Land Management Bureau; Na-
tional Park Service; Reclama-
tion Bureau.

INTERNAL REVENUE SERVICE

Rules and Regulations

Income tax; consolidated return
regulations 11794

Proposed Rule Making

Income tax; consolidated return
regulations (2 documents) 11845,
11850

INTERSTATE COMMERCE COMMISSION

Rules and Regulations

Explosives and other dangerous
articles; postponement of effec-
tive date 11756

Notices

Motor carriers:
Alternate route deviation no-
tices 11786
Applications and certain other
proceedings 11787
Filing of intrastate applica-
tions 11788
Temporary authority applica-
tions 11788
Transfer proceedings (2 docu-
ments) 11790, 11791

JUSTICE DEPARTMENT

See Immigration and Naturali-
zation Service.

LAND MANAGEMENT BUREAU

Rules and Regulations

PUBLIC LAND ORDERS:
Alabama 11755
Alaska (2 documents) 11755
Arizona 11755

Notices

Nevada State Office and Nevada
Land Office; change of mailing
address 11770

NATIONAL PARK SERVICE

Notices

Supervisory archeologist, South-
west Archeological Center,
Globe, Ariz.; delegation of au-
thority 11771

RECLAMATION BUREAU

Notices

Manti-Lasal National Forest,
Utah; transfer of administra-
tive jurisdiction of certain
lands 11770

SECURITIES AND EXCHANGE COMMISSION

Notices

Hearings, etc.:
American & Foreign Power Co.,
Inc 11783
American Seating Co. 11785
Itek Corp. et al. 11785

SMALL BUSINESS ADMINISTRATION

Notices

New Mexico and Texas; disaster
area 11785

STATE DEPARTMENT

Rules and Regulations

Visas; immigration pool for fiscal
year 1967; correction 11755

TREASURY DEPARTMENT

See Coast Guard; Internal Rev-
enue Service.

List of CFR Parts Affected

(Codification Guide)

The following numerical guide is a list of the parts of each title of the Code of Federal Regulations affected by documents published in today's issue. A cumulative list of parts affected, covering the current month to date appears at the end of each issue beginning with the second issue of the month.

A cumulative guide is published separately at the end of each month. The guide lists the parts and sections affected by documents published since January 1, 1966, and specifies how they are affected.

3 CFR

PROCLAMATIONS:
November 5, 1906 (revoked in part
by PLO 4083) 11755
33 (revoked in part by PLO 4083) 11755
1066 (revoked in part by PLO
4083) 11755
EXECUTIVE ORDERS:
11142 (superseded by EO 11302) 11741
11302 11741

7 CFR

215 11743
908 11743
946 11743
948 11743
981 11744
PROPOSED RULES:
932 11758

8 CFR

214 11744
243 11744

14 CFR

71 (2 documents) 11745
75 11745
95 11745
151 11747
PROPOSED RULES:
71 (6 documents) 11759-11761

16 CFR

13 (10 documents) 11747, 11750-11754

21 CFR

29 11754
120 11754
166 11754

22 CFR

42 11755

26 CFR

1 11794
PROPOSED RULES:
1 (2 documents) 11845, 11850

43 CFR

PUBLIC LAND ORDERS:
4019 (corrected by PLO 4081) 11755
4080 11755
4081 11755
4082 11755
4083 11755

47 CFR

0 11755
PROPOSED RULES:
73 11761

49 CFR

71-79 11756

50 CFR

32 (5 documents) 11756, 11757

Presidential Documents

Title 3—THE PRESIDENT

Executive Order 11302

PRESCRIBING REGULATIONS GOVERNING THE ALLOWANCE OF TRAVEL EXPENSES OF CLAIMANTS AND BENEFICIARIES OF THE VETERANS' ADMINISTRATION AND THEIR ATTENDANTS

By virtue of the authority vested in me by Section 111 of Title 38 of the United States Code, as amended by the Act of June 18, 1966 (Public Law 89-455), it is hereby ordered as follows:

SECTION 1. The Administrator of Veterans' Affairs may authorize or approve the payment of the actual necessary expenses of travel, including lodging and subsistence, of any claimant or beneficiary of the Veterans' Administration traveling to or from a Veterans' Administration facility, or other place, in connection with vocational rehabilitation or counseling, or for the purpose of examination, treatment, or care. The Administrator may authorize or approve such payment to the claimant or beneficiary, or, in his discretion, to the person who or the organization which has actually paid the expenses of such travel, including lodging and subsistence.

SEC. 2. The Administrator of Veterans' Affairs may authorize or approve in lieu of actual necessary expenses of travel, including lodging and subsistence, payment of an allowance of not more than five cents a mile to any claimant or beneficiary of the Veterans' Administration traveling to or from a Veterans' Administration facility, or other place, in connection with vocational rehabilitation or counseling, or for the purpose of examination, treatment, or care. In addition to such mileage allowance, the Administrator may allow reimbursement for the actual cost of ferry fares, and bridge, road, and tunnel tolls. In his discretion, the Administrator may authorize or approve such payment and such reimbursement to the person who or the organization which has actually paid the expenses of such travel, including lodging and subsistence.

SEC. 3. Whenever a claimant or beneficiary requires an attendant other than an employee of the Veterans' Administration for the performance of travel specified in Sections 1 and 2 hereof, the travel expenses of such attendant may be allowed in the same manner and to the same extent that travel expenses are allowed to such claimant or beneficiary.

SEC. 4. Payment of the following expenses or allowances in connection with vocational rehabilitation, counseling, or upon termination of examination, treatment, or care, may be made before the completion of travel:

- a. The mileage allowance and fare and tolls authorized by Section 2 hereof.
- b. Actual local travel expenses.
- c. The expense of hiring an automobile or ambulance, or the fee authorized for services of a non-employee attendant.

THE PRESIDENT

SEC. 5. The Administrator of Veterans' Affairs may prescribe such rules and regulations not inconsistent herewith as may be necessary to effectuate the provisions of this order.

SEC. 6. Executive Order No. 11142 of February 12, 1964, is hereby superseded.

LYNDON B. JOHNSON

THE WHITE HOUSE,
September 6, 1966.

[F.R. Doc. 66-9885; Filed, Sept. 6, 1966; 1:24 p.m.]

Rules and Regulations

Title 7—AGRICULTURE

Chapter II—Consumer and Marketing Service (School Lunch Program), Department of Agriculture

[Amdt. 1]

PART 215—SPECIAL MILK PROGRAM FOR CHILDREN

Definition of Milk

Paragraph (k) of § 215.2 of the regulations for the operation of the Special Milk Program for Children (30 F.R. 14910) is hereby amended as follows:

§ 215.2 Definitions.

(k) "Milk" means unflavored milk which meets State and local standards for fluid whole milk and flavored milk made from fluid whole milk which meets such standards, except that, in those areas of Alaska and Hawaii where a sufficient supply of fresh fluid whole milk cannot be obtained, "milk" shall include recombined or reconstituted fluid whole milk.

This amendment shall be effective upon publication.

Approved: September 2, 1966.

[SEAL] ORVILLE L. FREEMAN,
Secretary.

[F.R. Doc. 66-9847; Filed, Sept. 7, 1966;
8:51 a.m.]

Chapter IX—Consumer and Marketing Service (Marketing Agreements and Orders; Fruits, Vegetables, Nuts), Department of Agriculture

[Valencia Orange Reg. 176, Amdt. 1]

PART 908—VALENCIA ORANGES GROWN IN ARIZONA AND DESIGNATED PART OF CALIFORNIA

Limitation of Handling

Findings. (1) Pursuant to the marketing agreement, as amended, and Order No. 908, as amended (7 CFR Part 908), regulating the handling of Valencia oranges grown in Arizona and designated part of California, effective under the applicable provisions of the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601-674), and upon the basis of the recommendation and information submitted by the Valencia Orange Administrative Committee, established under the said amended marketing agreement and order, and upon other available information, it is hereby found that the limitation of handling of such Valencia oranges, as hereinafter provided, will tend to effectuate the declared policy of the act.

(2) It is hereby further found that it is impracticable and contrary to the public interest to give preliminary notice, engage in public rule-making procedure, and postpone the effective date of this amendment until 30 days after publication thereof in the FEDERAL REGISTER (5 U.S.C. 1001-1011) because the time intervening between the date when information upon which this amendment is based became available and the time when this amendment must become effective in order to effectuate the declared policy of the act is insufficient, and this amendment relieves restriction on the handling of Valencia oranges grown in Arizona and designated part of California.

Order, as amended. The provisions in paragraph (b) (1) (ii) of § 908.476 (Valencia Orange Regulation 176, 31 F.R. 11344) are hereby amended to read as follows:

§ 908.476 Valencia Orange Regulation 176.

- (b) Order. (1) * * *
(ii) District 2: 425,000 cartons.

(Secs. 1-19, 48 Stat. 31, as amended; 7 U.S.C. 601-674)

Dated: September 2, 1966.

PAUL A. NICHOLSON,
Deputy Director, Fruit and
Vegetable Division, Consumer
and Marketing Service.

[F.R. Doc. 66-9808; Filed, Sept. 7, 1966;
8:48 a.m.]

PART 946—IRISH POTATOES GROWN IN WASHINGTON

Expenses and Rate of Assessment

Notice of rule making regarding the proposed expenses and rate of assessment, to be made effective under Marketing Agreement No. 113, and Order No. 946 (7 CFR Part 946), regulating the handling of Irish potatoes grown in the State of Washington, was published in the FEDERAL REGISTER August 2, 1966 (31 F.R. 10368). This regulatory program is effective under the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601 et seq.). The notice afforded interested persons an opportunity to file data, views, or arguments pertaining thereto not later than 15 days after its publication in the FEDERAL REGISTER. None was filed.

After consideration of all relevant matters, including the proposals set forth in the aforesaid notice which were recommended by the State of Washington Potato Committee, established pursuant to the said marketing agreement and order, it is hereby found and determined that:

§ 946.218 Expenses and rate of assessment.

(a) The reasonable expenses that are likely to be incurred during the fiscal year ending May 31, 1967, by the State of Washington Potato Committee to perform its functions and for such other purposes as the Secretary determines to be appropriate, will amount to \$23,666.76.

(b) The rate of assessment to be paid by each handler in accordance with Marketing Agreement No. 113 and this part shall be two-tenths of 1 cent (\$0.002) per hundredweight, or equivalent quantity, of potatoes handled by him, as the first handler thereof, during said fiscal year.

(c) Terms used in this section shall have the same meaning as when used in the said marketing agreement and order.

It is hereby found that good cause exists for not postponing the effective time of this action until 30 days after publication in the FEDERAL REGISTER (5 U.S.C. 1003) in that: (1) The relevant provisions of said marketing agreement and this part require that the rate of assessment fixed for a particular fiscal period shall be applicable to all assessable potatoes from the beginning of such period, and (2) the current fiscal year began June 1, 1966, and the rate of assessment herein fixed will automatically apply to all assessable potatoes beginning with such date.

(Secs. 1-19, 48 Stat. 31, as amended; 7 U.S.C. 601-674)

Dated: September 1, 1966.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Veg-
etable Division, Consumer and
Marketing Service.

[F.R. Doc. 66-9809; Filed, Sept. 7, 1966;
8:48 a.m.]

[Area 3]

PART 948—IRISH POTATOES GROWN IN COLORADO

Expenses and Rate of Assessment

Notice of rule making regarding the proposed expenses and rate of assessment for Area No. 3 (Northern Colorado), to be effective under Marketing Agreement No. 97 and Order No. 948, both as amended (7 CFR Part 948), was published in the August 16, 1966, FEDERAL REGISTER (31 F.R. 10888). This regulatory program is effective under the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601-674).

The notice afforded interested persons an opportunity to file written data, views, or arguments pertaining thereto not later than the 15th day after publication in the FEDERAL REGISTER. None was filed.

After consideration of all relevant matters, including the proposals set forth in the aforesaid notice which were recommended by the Area Committee for Area No. 3, established pursuant to the said marketing agreement and order, it is hereby found and determined that:

§ 948.251 Expenses and rate of assessment.

(a) The reasonable expenses that are likely to be incurred by the Area Committee for Area No. 3, established pursuant to Marketing Agreement No. 97 and this part (Order No. 948), both as amended, to enable such committee to perform its functions pursuant to the provisions of the aforesaid amended agreement and order during the fiscal period ending May 31, 1967, will amount to \$2,500.

(b) The rate of assessment to be paid by each handler in Area No. 3 pursuant to Marketing Agreement No. 97 and this part (Order No. 948), both as amended, shall be \$0.00125 per hundredweight of potatoes handled by him as the first handler thereof during said fiscal period.

(c) Unexpended income in excess of expenses for the fiscal period ending May 31, 1967, may be carried over as a reserve.

(d) Terms used in this section shall have the same meaning as when used in Marketing Agreement No. 97, as amended, and this part.

It is hereby found that good cause exists for not postponing the effective date of this section until 30 days after publication in the *FEDERAL REGISTER* (5 U.S.C. 1003) in that: (1) The relevant provisions of this part require that the rate of assessment for a particular fiscal period shall be applicable to all assessable potatoes from the beginning of such period, and (2) the current fiscal period began on June 1, 1966, and the rate of assessment herein will apply to all assessable potatoes beginning with such date.

(Secs. 1-19, 48 Stat. 31, as amended; 7 U.S.C. 601-674)

Dated: September 1, 1966.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Consumer and Marketing Service.

[F.R. Doc. 66-9810; Filed, Sept. 7, 1966; 8:48 a.m.]

PART 981—ALMONDS GROWN IN CALIFORNIA

Salable and Surplus Percentages for 1966-67 Crop Year

Notice was published in the August 18, 1966, issue of the *FEDERAL REGISTER* (31 F.R. 10963) regarding a proposal to establish salable and surplus percentages applicable to California almonds for the 1966-67 crop year beginning July 1, 1966. The percentages are based on unanimous recommendations of the Almond Control Board and other available information in accordance with the applicable provisions of the marketing agreement, as amended, and Order No. 981, as

amended (7 CFR Part 981), regulating the handling of almonds grown in California, effective under the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601-674).

The notice afforded interested persons opportunity to submit written data, views, or arguments with respect to the proposal. None were submitted within the prescribed time.

After consideration of all relevant matters presented, including those in the notice, the information and recommendations submitted by the Committee, and other available information, it is found that to establish salable and surplus percentages as hereinafter set forth will tend to effectuate the declared policy of the act.

Therefore, the salable and surplus percentages for almonds received by handlers for their own accounts during the 1966-67 crop year are established as follows:

§ 981.216 Salable and surplus percentages for almonds during the crop year beginning July 1, 1966.

The salable and surplus percentages during the crop year beginning July 1, 1966, shall be 80 percent and 20 percent, respectively.

It is further found that good cause exists for not postponing the effective time of this action until 30 days after publication in the *FEDERAL REGISTER* (5 U.S.C. 1003(c)) in that: (1) The relevant provisions of said amended marketing agreement and this part require that salable and surplus percentages designated for a particular crop year shall be applicable to all almonds received by handlers for their own accounts during such year; and (2) the current crop year began on July 1, 1966, and the percentages established herein will automatically apply to all such almonds beginning with such date.

(Secs. 1-19, 48 Stat. 31, as amended; 7 U.S.C. 601-674)

Dated: September 1, 1966.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Consumer and Marketing Service.

[F.R. Doc. 66-9844; Filed, Sept. 7, 1966; 8:51 a.m.]

Title 8—ALIENS AND NATIONALITY

Chapter I—Immigration and Naturalization Service, Department of Justice

PART 214—NONIMMIGRANT CLASSES

PART 243—DEPORTATION OF ALIENS IN UNITED STATES

Miscellaneous Amendments

The following amendments to Chapter I of Title 8 of the Code of Federal Regulations are hereby prescribed:

§ 214.2 [Amended]

1. The first sentence of subdivision (ii) *Petition for alien to perform other temporary service or labor* of subparagraph (2) *Supporting evidence* of paragraph (h) *Temporary employees* of § 214.2 *Special requirements for admission, extension, and maintenance of status* is amended to read as follows: "Either a certification from the Secretary of Labor or his designated representative stating that qualified persons in the United States are not available and that the employment of the beneficiary will not adversely affect the wages and working conditions of workers in the United States similarly employed, or a notice that such a certification cannot be made shall be attached to every non-immigrant visa petition to accord an alien a classification under section 101 (a) (15) (H) (ii) of the Act."

2. Section 243.8 is amended to read as follows:

§ 243.8 Imposition of sanctions.

The provisions of section 243(g) of the Act have been applied to residents of the Union of Soviet Socialist Republics, Czechoslovakia, and Hungary; those provisions do not apply to an alien who is residing in Estonia, Latvia, or Lithuania who is not a national, citizen, or subject of the Union of Soviet Socialist Republics. The sanctions imposed on residents of the Union of Soviet Socialist Republics, Czechoslovakia, and Hungary pursuant to section 243(g) may be waived in an individual case for the beneficiary of a petition accorded a status under section 201(b) or section 203(a) of the Act. The sanctions also may be waived upon an individual request by the Department of State in behalf of a visa applicant. Upon approval of a visa petition or upon an individual request by the Department of State in behalf of a visa applicant, the district director will determine whether sanctions shall be waived. However, the regional commissioner or the Deputy Associate Commissioner, Travel Control, may direct that any case or class of cases be referred to him for such determination. (Sec. 103, 66 Stat. 173; 8 U.S.C. 1103)

This order shall be effective on the date of its publication in the *FEDERAL REGISTER*. Compliance with the provisions of section 4 of the Administrative Procedure Act (60 Stat. 238; 5 U.S.C. 1003) as to notice of proposed rule making and delayed effective date is unnecessary in this instance because the rule prescribed by § 214.2(h) (2) (ii) relates to agency procedure and the rule prescribed by § 243.8 confers benefits upon persons affected thereby.

Dated: September 2, 1966.

RAYMOND F. FARRELL,
Commissioner of Immigration and Naturalization.

[F.R. Doc. 66-9814; Filed, Sept. 7, 1966; 8:48 a.m.]

Title 14—AERONAUTICS AND SPACE

Chapter I—Federal Aviation Agency

SUBCHAPTER E—AIRSPACE

[Airspace Docket No. 66-SW-21]

PART 71—DESIGNATION OF FEDERAL AIRWAYS, CONTROLLED AIRSPACE, AND REPORTING POINTS

Alteration of Control Zones and Transition Area; Correction

On August 19, 1966, F.R. Doc. 66-9005 was published in the FEDERAL REGISTER (31 F.R. 11014) which designated the Killeen, Tex., Fort Hood AAF and Robert Gray AAF control zones and the Killeen, Tex., transition area to become effective October 13, 1966. This action eliminated the requirement for the presently designated Killeen, Tex., control zone and transition area; therefore, action is taken herein for the revocation of these designations.

Since this amendment will impose no additional burden on any person, notice and public procedures are unnecessary, and the effective date of the rule may be retained as initially adopted.

In consideration of the foregoing, F.R. Doc. 66-9005, is amended, effective as follows:

1. In the fourth paragraph, the words "the Killeen, Tex., control zones are designated as follows:" are deleted, and the words "the Killeen, Tex., control zone is revoked and the following control zones are designated:" are substituted therefor.

2. In the fifth paragraph, "designated" is changed to "redesignated."

(Sec. 307(a), Federal Aviation Act of 1958; 49 U.S.C. 1348)

Issued in Fort Worth, Tex., on August 29, 1966.

A. L. COULTER,
Acting Director, Southwest Region.

[F.R. Doc. 66-9779; Filed, Sept. 7, 1966; 8:45 a.m.]

[Airspace Docket No. 66-AL-30]

PART 71—DESIGNATION OF FEDERAL AIRWAYS, CONTROLLED AIRSPACE, AND REPORTING POINTS

PART 75—ESTABLISHMENT OF JET ROUTES

Extension of Airway, Designation of Jet Route and Low and High Altitude Reporting Points, and Alteration of Control Area

On June 11, 1966, a notice of proposed rule making was published in the FEDERAL REGISTER (31 F.R. 8242) stating that the Federal Aviation Agency was considering amendments to Parts 71 and 75 of the Federal Aviation Regulations which would extend, redesignate, and designate certain Alaskan airways, jet routes, and reporting points.

Interested persons were afforded an opportunity to participate in the pro-

posed rule making through submission of comments. No comments were received.

Subsequent to publication of the notice, a flight check of the proposed Augustine, Alaska, Intersection, indicates that this intersection would be unsatisfactory for air traffic control use. Accordingly, it will not be designated as a low altitude reporting point.

In consideration of the foregoing, Parts 71 and 75 of the Federal Aviation Regulations are amended, effective 0001 e.s.t., November 10, 1966, as hereinafter set forth.

1. Section 71.125 (31 F.R. 2045) is amended as follows:

a. In V-438 "From Shuyak, Alaska, RBN via Homer, Alaska;" is deleted and "From Kodiak, Alaska, via Homer, Alaska, including an W alternate;" is substituted therefor and "The airspace below 2,000 feet MSL outside the United States is excluded." is added at the end of text.

b. V-506 is amended to read:

V-506 From Kodiak, Alaska, via INT of Kodiak 332° and King Salmon, Alaska, 097° radials; King Salmon; Bethel, Alaska; Nome, Alaska; to Kotzebue, Alaska, excluding the airspace below 2,000 feet MSL outside the United States.

2. Section 71.161 (31 F.R. 2049) is amended by adding the following:

Jet Route No. 123, From INT of Kodiak, Alaska, 107° radial and the NW boundary Anchorage Oceanic Control Area at latitude 57°29' N., longitude 150°30' W., via Kodiak to King Salmon, Alaska.

Jet Route No. 125, From Kodiak, Alaska, to Anchorage, Alaska.

3. Section 71.163 (31 F.R. 2050) is amended as follows: In Control 1217 "The airspace below 2,000 feet MSL outside the United States is excluded." is added at the end of text.

4. Section 71.211 (31 F.R. 2289) is amended by adding the following:

Kodiak, Alaska.
Marble INT: INT Kodiak, Alaska, 107° radial and NW boundary Anchorage Oceanic Control Area at latitude 57°29' N., longitude 150°30' W.

5. Section 71.213 (31 F.R. 2290) is amended by adding the following:

Kodiak, Alaska.
Marble INT: INT of Kodiak, Alaska, 107° radial and NW boundary Anchorage Oceanic Control Area at latitude 57°29' N., longitude 150°30' W.

6. Section 75.100 (31 F.R. 2346) is amended by adding the following:

Jet Route No. 123 From INT Kodiak, Alaska, 107° radial and NW boundary Anchorage Oceanic Control Area at latitude 57°29' N., longitude 150°30' W., via Kodiak; to King Salmon, Alaska.

Jet Route No. 125 From Kodiak, Alaska, to Anchorage, Alaska.

(Sec. 307(a), 1110, Federal Aviation Act of 1958 (49 U.S.C. 1348); E.O. 10854 (24 F.R. 9365))

Issued in Washington, D.C., on August 30, 1966.

H. B. HELSTROM,
Chief, Airspace and Air
Traffic Rules Division.

[F.R. Doc. 66-9780; Filed, Sept. 7, 1966; 8:45 a.m.]

SUBCHAPTER F—AIR TRAFFIC AND GENERAL OPERATING RULES

[Reg. Docket No. 7583; Amdt. 95-145]

PART 95—IFR ALTITUDES

Miscellaneous Amendments

The purpose of this amendment to Part 95 of the Federal Aviation Regulations is to make changes in the IFR altitudes at which all aircraft shall be flown over a specified route or portion thereof. These altitudes, when used in conjunction with the current changeover points for the routes or portions thereof, also assure navigational coverage that is adequate and free of frequency interference for that route or portion thereof.

As a situation exists which demands immediate action in the interest of safety, I find that compliance with the notice and procedure provisions of the Administrative Procedure Act is impracticable and that good cause exists for making this amendment effective within less than 30 days from publication.

In consideration of the foregoing and pursuant to the authority delegated to me by the Administrator (24 F.R. 5662), Part 95 of the Federal Aviation Regulations is amended, effective October 13, 1966, as follows:

1. By amending Subpart C as follows:

Section 95.679 *Blue Federal airway 79* is amended to read in part:

From, to, and MEA

Haines, Alaska, LF/RBN; Burwash Landing, Y.T. LFR; #11,000. #For that airspace over U.S. territory.

Section 95.1001 *Direct routes—United States* is amended to delete:

Harrison INT, Ga.; Norcross, Ga., VOR; 3,000.

Section 95.1001 *Direct routes—United States* is amended by adding:

San Diego, Calif., VOR via SAN, 110° rad; United States-Mexican border; 5,600.
San Diego, Calif., VOR via SAN, 120° rad; United States-Mexican border; 4,600.
Avenal, Calif., VOR COP 65 AVE; San Jose, Calif., VOR; *10,000. *6700—MOCA. MAA—39,000.
Columbus, Ga., LOM; Geneva INT, Ga.; *2,200. *1900—MOCA. Via CSE LOM 046° rad.
Dunoir, Wyo., VOR; Billings, Mont., VORTAC; 18,000. MAA—45,000.

Section 95.1001 *Direct routes—United States* is amended to read in part:

Fort Myers, Fla., VOR; Sarasota, Fla., VOR; *2,000. *1,500—MOCA.
Sarasota, Fla., VOR; Arcadia INT, Fla.; *2,000. *1,500—MOCA.
Sarasota, Fla., VOR; La Belle, Fla., VOR; *2,000. *1,500—MOCA.
Norcross, Ga., VOR; Buckhead INT, Ga.; 3,000. Kennesaw INT, Ga.; Buckhead INT, Ga.; 3,300.

Puerto Rico Routes

Route 1:

*Hawaii INT, P.R.; Cabo Rojo INT, P.R.; *8,500. *8,500—MRA. **1,300—MOCA.

Route 9:

*Hawaii INT, P.R.; Ponce, P.R., VOR; 2,500. *8,500—MRA.

Section 95.6003 VOR Federal airway 3 is amended to read in part:

From, to, and MEA

Savannah, Ga., VOR; Vance, S.C., VOR; *1,900. *1,500—MOCA.

Section 95.6007 VOR Federal airway 7 is amended to read in part:

Evansville, Ind., VOR; *Decker INT, Ind.; 2,100. *2,300—MRA.

Section 95.6008 VOR Federal airway 8 is amended to read in part:

Ontario, Calif., VOR; *Rialto INT, Calif.; 5,000. *9,000—MCA Rialto INT, North-east-bound.

Rialto INT, Calif.; Lucerne INT, Calif.; 10,500. Lucerne INT, Calif.; Hector, Calif., VOR; *10,000. *9,000—MOCA.

Section 95.6011 VOR Federal airway 11 is amended to read in part:

Weston INT, Ky.; Evansville, Ind., VOR; 2,100. Evansville, Ind., VOR via E alter.; Augusta INT, Ind., via E alter.; 2,100.

Section 95.6015 VOR Federal airway 15 is amended to read in part:

Silver INT, Tex.; Washington INT, Tex.; *2,000. *1,600—MOCA.

Washington INT, Tex.; College Station, Tex., VOR; 1,800.

Sealy INT, Tex., via W alter.; Independence INT, Tex., via W alter.; *2,100. *1,500—MOCA.

Independence INT, Tex., via W alter.; College Station, Tex., VOR via W alter.; 1,800.

College Station, Tex., VOR via W alter.; Barclay INT, Tex., via W alter.; *2,500. *1,800—MOCA.

Section 95.6016 VOR Federal airway 16 is amended to read in part:

*Moreno INT, Calif.; Banning INT, Calif., eastbound; 13,000. Westbound; 9,000. *12,000—MCA Moreno INT, eastbound.

Wink, Tex., VOR via S alter.; Notrees DME Fix, Tex., via S alter.; 5,500.

Notrees DME Fix, Tex., via S alter.; Midland, Tex., VOR via S alter.; *4,500. *4,400—MOCA.

Section 95.6017 VOR Federal airway 17 is amended to read in part:

Leming INT, Tex.; Losoya INT, Tex.; *2,500. *1,600—MOCA.

Losoya INT, Tex.; Bellaire INT, Tex.; *2,500. *1,800—MOCA.

Bellaire INT, Tex.; San Antonio, Tex., VOR; *2,500. *2,200—MOCA.

Section 95.6018 VOR Federal airway 18 is amended to read in part:

St. George INT, S.C.; Charleston, S.C., VOR; *1,800. *1,300—MOCA.

Section 95.6021 VOR Federal airway 21 is amended to read in part:

Ontario, Calif., VOR; *Rialto INT, Calif.; 5,000. *9,000—MCA Rialto INT, northeast-bound.

Rialto INT, Calif.; Lucerne INT, Calif.; 10,500. Lucerne INT, Calif.; Hector, Calif., VOR; *10,000. *9,000—MOCA.

Section 95.6037 VOR Federal airway 37 is amended to read in part:

Blythwood INT, S.C.; Fort Mill, S.C., VOR; *2,400. *2,000—MOCA.

*Tillman INT, S.C.; **Wixon INT, S.C., ***2,000. *3,000—MRA. **3,300—MRA. ***1,300—MOCA.

Wixon INT, S.C.; Allendale, S.C., VOR; *2,000. *1,300—MOCA.

Section 95.6051 VOR Federal airway 51 is amended to read in part:

From, to, and MEA

Highway, Tenn., VOR via W alter.; *Bakerton INT, Ky., via W alter.; **2,800. *4,500—MRA. **2,300—MOCA.

Bakerton INT, Ky., via W alter.; New Hope, Ky., VOR via W alter.; *2,800. *2,300—MOCA.

Section 95.6053 VOR Federal airway 53 is amended to read in part:

Charleston, S.C., VOR; St. George INT, S.C.; *1,800. *1,300—MOCA.

Section 95.6054 VOR Federal airway 54 is amended to read in part:

Ennis INT, Tex.; *Scurry INT, Tex.; **5,000. *2,600—MRA. **1,800—MOCA.

Section 95.6062 VOR Federal airway 62 is amended to read in part:

Cisco INT, Tex.; *Mill INT, Tex.; **6,000. *3,500—MRA. **3,900—MOCA.

Plainview, Tex., VOR; Lubbock, Tex., VOR; *5,000. *4,600—MOCA.

Section 95.6068 VOR Federal airway 68 is amended to read in part:

*Comfort INT; **Boerne INT, Tex.; ***3,100. *4,000—MRA. **5,000—MRA. ***2,800—MOCA.

Boerne INT, Tex.; Van Raub INT, Tex.; *3,100. *2,800—MOCA.

Section 95.6076 VOR Federal airway 76 is amended to read in part:

Hyman, Tex., VOR; San Angelo, Tex., VOR; *4,400. *4,000—MOCA.

Section 95.6081 VOR Federal airway 81 is amended to read in part:

Lubbock, Tex., VOR; Plainview, Tex., VOR; *5,000. *4,600—MOCA.

Section 95.6094 VOR Federal airway 94 is amended to read in part:

Wink, Tex., VOR; Notrees DME Fix, Tex.; 5,500.

Notrees DME Fix, Tex.; Midland, Tex., VOR; *4,500. *4,400—MOCA.

Dyess, Tex., VOR; *Mill INT, Tex.; **6,000. *3,500—MRA. **3,900—MOCA.

Section 95.6097 VOR Federal airway 97 is amended to read in part:

Woodstock INT, Ill.; Janesville, Wis., VOR; *2,900. *2,500—MOCA.

Section 95.6138 VOR Federal airway 138 is amended to read in part:

Grand Island, Nebr., VOR; Seward INT, Nebr.; *4,000. *3,200—MOCA.

Section 95.6140 VOR Federal airway 140 is amended to read in part:

Freedom INT, Ky., via N alter.; *Bakerton INT, Ky., via N alter.; **5,500. *4,500—MRA. **3,100—MOCA.

Section 95.6155 VOR Federal airway 155 is amended to read in part:

Augusta, Ga., VOR; Monetta INT, S.C.; *2,200. *2,000—MOCA.

Section 95.6157 VOR Federal airway 157 is amended to read in part:

Lotts INT, Ga.; Allendale, S.C., VOR; *2,000. *1,600—MOCA.

Section 95.6159 VOR Federal airway 159 is amended to read in part:

Palm Beach, Fla., VOR; Parkway INT, Fla.; *1,500. *1,300—MOCA.

From, to, and MEA

Parkway INT, Fla.; Pluto INT, Fla.; *1,500. *1,100—MOCA.

Section 95.6163 VOR Federal airway 163 is amended to read in part:

Leming INT, Tex.; Losoya INT, Tex.; *2,500. *1,600—MOCA.

Losoya INT, Tex.; Bellaire INT, Tex.; *2,500. *1,800—MOCA.

Bellaire INT, Tex.; San Antonio, Tex., VOR; *2,500. *2,200—MOCA.

Section 95.6177 VOR Federal airway 177 is amended to read in part:

Marengo INT, Ill.; Janesville, Wis., VOR; *2,700. *2,500—MOCA.

Section 95.6185 VOR Federal airway 185 is amended to read in part:

Savannah, Ga., VOR; Sardis INT, Ga.; *2,000. *1,500—MOCA.

Section 95.6198 VOR Federal airway 198 is amended to read in part:

*Comfort INT, Tex.; **Boerne INT, Tex.; ***3,100. *4,000—MRA. **5,000—MRA.

Boerne INT, Tex.; Van Raub INT, Tex.; *3,100. *2,800—MOCA.

Section 95.6210 VOR Federal airway 210 is amended to read in part:

Peach Springs, Ariz., VOR; Grand Canyon, Ariz., VOR; *10,000. *9,500—MOCA.

Grand Canyon, Ariz., VOR; Tuba City, Ariz., VOR; 9,500.

Section 95.6216 VOR Federal airway 216 is amended to read in part:

Janesville, Wis., VOR; *Wind Lake INT, Wis.; **3,000. *3,000—MRA. **2,500—MOCA.

Section 95.6257 VOR Federal airway 257 is amended to read in part:

Prescott, Ariz., VOR; Grand Canyon, Ariz., VOR; *10,000. *9,000—MOCA.

*Grand Canyon, Ariz., VOR; Bryce Canyon, Utah, VOR; **13,000. *12,800—MCA

Grand Canyon VOR, northbound. **11,400—MOCA.

Section 95.6264 VOR Federal airway 264 is amended to read in part:

*Moreno INT, Calif., via S alter.; Banning INT, Calif., via S alter., eastbound; 13,000.

Westbound; 9,000. *12,000—MCA Moreno INT, eastbound.

Section 95.6266 VOR Federal airway 266 is amended to read in part:

South Boston, Va., VOR; Lawrenceville, Va., VOR; 2,000.

Section 95.6402 Hawaii VOR Federal airway 2 is amended to read in part:

High Tide INT, Hawaii; Breakers INT, Hawaii; *3,000. *1,000—MOCA.

Section 95.6415 Hawaii VOR Federal airway 15 is amended to read in part:

*Molokai, Hawaii, VOR; **Maui, Hawaii, VOR; ***8,000. *5,000—MCA Molokai

VOR, eastbound. **6,500—MCA Maui

VOR, westbound. ***7,500—MOCA.

Int. 097° M rad, South Kauai VOR and 119°

M rad, Lihue VOR; Breakers INT, Hawaii; *3,000. *1,000—MOCA.

Section 95.6440 VOR Federal airway 440 is amended to read in part:

*Puntilla Lake INT, Alaska; **Windy Fork

INT, Alaska; ***10,000. *11,000—MRA.

8,600—MCA Windy Fork INT, south-eastbound. *9,500—MOCA.

Section 95.6444 VOR Federal airway 444 is amended to read in part:

From, to, and MEA

Bettles, Alaska, VOR; Hess Creek INT, Alaska, *12,000. *5,300—MOCA.

Section 95.6449 VOR Federal airway 449 is amended to read in part:

Brookfield INT, N.Y.; Deansboro INT, N.Y.; 3,600.

Deansboro INT, N.Y.; Clinton INT, N.Y.; 3,300.

Section 95.6456 VOR Federal airway 456 is amended to read in part:

Big Mountain, Alaska, LF/RBN; *Copper INT, Alaska, northeastbound; **11,500. South-westbound; 6,000. *12,000—MCA Copper INT, northeastbound. **6,000—MOCA.

Section 95.6492 VOR Federal airway 492 is amended to read in part:

Pluto INT, Fla., via N alter.; Parkway INT, Fla., via N alter.; *1,500. *1,100—MOCA. Parkway INT, Fla., via N alter.; Palm Beach, Fla., VOR via N alter.; *1,500. *1,300—MOCA.

Section 95.6504 VOR Federal airway 504 is amended to read in part:

Nenana, Alaska, VOR; Rampart INT, Alaska; *7,000. *6,400—MOCA. Rampart INT, Alaska; Bettles, Alaska, VOR; *7,000. *6,800—MOCA.

Section 95.7086 Jet Route No. 86 is amended by adding:

From, to, MEA, and MAA

Boulder, Nev., VORTAC; Peach Springs, Ariz., VOR; 18,000; 45,000.

Peach Springs, Ariz., VOR; Winslow, Ariz., VORTAC; 18,000; 45,000.

Winslow, Ariz., VORTAC; El Paso, Tex., VORTAC; #29,000; 45,000. #MEA is established with a gap in navigation signal coverage.

2. By amending Subpart D as follows: Section 95.8003 VOR Federal airway changeover points:

Airway segment: From; to—Changeover point: Distance; from

V-15 is amended to read in part: Molokai, Hawaii, VOR; Maui, Hawaii, VOR; 13; Maui.

V-16 is amended to read in part: Ontario, Calif., VOR; Palm Springs, Calif., VOR; 34; Ontario.

V-174 is amended to delete: Henderson, W. Va., VORTAC; Elkins, W. Va., VORTAC; 49; Henderson.

V-210 is amended to read in part: Peach Springs, Ariz., VOR; Tuba City, Ariz., VOR; 57; Peach Springs.

V-257 is amended to delete: Prescott, Ariz., VOR; Bryce Canyon, Utah, VOR; 98; Prescott.

V-257 is amended by adding: Grand Canyon, Ariz., VOR; Bryce Canyon, Utah, VOR; 79; Grand Canyon.

V-264 is amended to read in part: Ontario, Calif., VOR via S alter.; Palm Springs, Calif., VOR via S alter.; 34; Ontario. (Secs. 307, 1110, Federal Aviation Act of 1958 (49 U.S.C. 1348, 1510))

Issued in Washington, D.C., on August 29, 1966.

JAMES F. RUDOLPH,
Acting Director,

Flight Standards Service.

[F.R. Doc. 66-9728; Filed, Sept. 7, 1966; 8:45 a.m.]

SUBCHAPTER I—AIRPORTS

[Docket No. 7595; Amdt. 151-14]

PART 151—FEDERAL AID TO AIRPORTS

Exclusive Rights Prohibition

The purposes of this amendment are to conform § 151.121 with current Agency policy on exclusive rights and to correct the references contained in § 151.41(c) (2).

In making grant agreements under the Federal-aid Airport Program, FAA formerly permitted the continuing existence of exclusive rights at airports to engage in the sale of gasoline and oil, and even new grants of such rights, if the airport had in the past received a transfer of surplus property under section 13(g) of the Surplus Property Act of 1944 (50 U.S.C. App. 1622(g)). (Sec. 13(g) (2) (c) prohibits exclusive rights for the use of airports that receive surplus property but excludes "the sale of gasoline and oil" for aircraft from its definition of activities for which exclusive rights may not be granted.) This was reflected in the last sentence of the sponsor's assurance set forth in § 151.121. The new exclusive rights policy of October 25, 1965 (30 F.R. 13661), requires as a condition on FAAP grants that the sponsor (including the operator of a "surplus airport") agree to the prospective application at all its airports of the unqualified prohibition of exclusive rights in section 308(a) of the Federal Aviation Act (49 U.S.C. 1349). To reflect this change of policy, the assurance in § 151.121 is reworded, and the present last sentence is deleted.

The preceding (next to last) sentence of the assurance, as now set forth in § 151.121, sets an absolute deadline for steps to terminate existing exclusive rights. The new policy merely requires termination at the earliest renewal, cancellation, or expiration date of the agreement establishing the exclusive right. This sentence is amended to conform it to the new policy.

Section 151.41(c) (2) of Part 151 contains a reference to the Federal Airport Act erroneously reading "section 13(3)" instead of "section 13(a)(3)". This error is being corrected.

The procedural requirements of section 4 of the Administrative Procedure Act do not apply to this amendment because it relates to public grants, benefits, and contracts and merely conforms § 151.121 to previously published Agency policy.

In consideration of the foregoing, Part 151 is amended, effective October 8, 1966, as follows:

1. Section 151.41(c) (2) is amended to read as follows:

§ 151.41 Project costs.

(c) * * *

(2) Be reasonable in amount (or be subject to partial disallowance under section 13(a) (3) of the Federal Airport Act (49 U.S.C. 1112(a) (3)));

2. The covenant set forth in § 151.121 is amended to read as follows:

§ 151.121 Procedures: offer; sponsor assurances.

The sponsor will not grant or permit any exclusive right forbidden by section 308(a) of the Federal Aviation Act of 1958 on the airport or any airport that it may subsequently acquire. In furtherance of the policy of the FAA under this covenant the sponsor agrees that, unless authorized by the Administrator, it will not, either directly or indirectly, grant or permit any person, firm, or corporation the exclusive right for the conduct of any aeronautical activities on the airport or any airport subsequently acquired by it, including, but not limited to, charter flights, pilot training, aircraft rental and sightseeing, aerial photography, crop dusting, aerial advertising and surveying, air carrier operations, aircraft sales and services, sale of aviation petroleum products whether or not conducted in conjunction with other aeronautical activity, repair and maintenance of aircraft, sale of aircraft parts, and any other activities which because of their direct relationship to the operation of aircraft can be regarded as an aeronautical activity. The sponsor further agrees that it will terminate any such exclusive right (including any exclusive right to engage in the sale of gasoline or oil, or both) now existing at the airport or at any airport owned or controlled by the sponsor, at the earliest renewal, cancellation, or expiration date applicable to the agreement that established the exclusive right, and certifies that there is no exclusive right not subject to termination under this provision.

(Secs. 1-15, 17-21, Federal Airport Act (49 U.S.C. 1101-1114, 1116-1120); secs. 308(a), 313(a), Federal Aviation Act of 1958 (49 U.S.C. 1349, 1354))

Issued in Washington, D.C., on August 31, 1966.

WILLIAM F. MCKEE,
Administrator.

[F.R. Doc. 66-9781; Filed, Sept. 7, 1966; 8:45 a.m.]

Title 16—COMMERCIAL PRACTICES

Chapter I—Federal Trade Commission

[Docket No. C-1088]

PART 13—PROHIBITED TRADE PRACTICES

Phillips Petroleum Co. et al.

Subpart—Acquiring corporate stock or assets: § 13.7 Joint ventures.¹ Subpart—Combining or conspiring: § 13.395 To control marketing practices and conditions; § 13.452 To limit production; § 13.470 To restrain and monopolize trade.

(Sec. 6, 38 Stat. 721; 15 U.S.C. 46. Interpret or apply sec. 5, 38 Stat. 719, as amended; sec. 7, 38 Stat. 731, as amended; 15 U.S.C. 45, 18) [Cease and desist order, Phillips Petroleum Co. et al., Bartlesville, Okla., Docket C-1088, Aug. 2, 1966]

¹ New section added.

In the Matter of Phillips Petroleum Co., a Corporation; National Distillers & Chemical Corp., a Corporation; Alamo Industries, Inc., a Corporation; and A-B Chemical Corp., a Corporation

Consent order requiring the dissolution of major joint ventures in the polyolefin plastics field between Phillips Petroleum Co. of Oklahoma and National Distillers & Chemical Corp. of New York City, and requiring divestiture of the resin plant and three acquisitions made by one of these joint ventures, and requiring the construction of two new resin plants by Phillips and banning future acquisitions and joint ventures by Phillips or National.

The order to cease and desist, including further order requiring report of compliance therewith, is as follows:

A. DISSOLUTION OF ALAMO INDUSTRIES, INC., JOINT VENTURE

I. *It is ordered*, That, within ninety (90) days from the effective date of this order, National Distillers & Chemical Corp. (hereinafter referred to as "National") shall sell to Phillips Petroleum Co. (hereinafter referred to as "Phillips"), and Phillips shall purchase from National, capital stock, bonds, debentures, and other securities and interests held by National in Alamo Industries, Inc. (hereinafter referred to as "Alamo"), in accordance with Exhibit A. After such purchase has been completed, Phillips shall comply with the terms of this order which are applicable to Alamo.

II. *It is further ordered*, That, within two (2) years from the effective date of this order, Alamo and/or Phillips shall divest absolutely and in good faith, to a purchaser or purchasers approved by the Federal Trade Commission, the facilities for the production of polypropylene resin known as the Monument Plant and located at Houston, Tex., including, but not limited to, all properties, machinery, equipment, raw material reserves, if any, and all contract rights pertaining to the operation of said facilities to the end that such divested facilities be established as a going concern and effective competitor in the manufacture and sale of polypropylene resins; that Phillips shall grant to the purchaser or purchasers of the aforesaid Monument Plant a license of polypropylene patents and know-how providing for a minimum annual royalty of \$200,000 for the first five (5) years, and otherwise at such royalty and upon such terms as were originally provided by Phillips' present license to Alamo; that Phillips shall continue to supply propylene feedstock to the Monument Plant for a term of three (3) years from the sale of the Monument Plant, or for such longer term as, with the approval of the Federal Trade Commission, the purchaser or purchasers may reasonably require, at prices not to exceed the current market price as determined from time to time and under a contract the same in form and substance as Phillips' present propylene supply contract with Alamo, except that the minimum annual quantity shall be

15 million pounds and the maximum annual quantity shall be 40 million pounds; and that Phillips or Alamo shall, at the option of such purchaser or purchasers, agree to manage and operate the aforesaid Monument Plant for such purchaser or purchasers upon such terms as provided by the management agreement now in effect between Phillips and Alamo, but in no event shall such management agreement be for a term of more than five (5) years; and that Phillips may require such purchaser or purchasers to enter into a contract with Phillips, upon reasonable terms and conditions, for the supply of polypropylene resin to cover the requirements of Alamo until Phillips has constructed, in accordance with paragraph III of this order, a new polypropylene plant and until such new plant is in commercial production, or until Alamo has made other arrangements for its polypropylene supply, but in no event shall such contract be for a term of more than five (5) years.

III. *It is further ordered*, That, within three (3) years from the date of divestiture of the Monument Plant as ordered by paragraph II of this order (if such divestiture is accomplished within the two (2) year period therein specified), Phillips shall construct, or cause one of its subsidiaries to construct, facilities for the production of polypropylene resin with a minimum annual rated capacity of 35 million pounds.

IV. *It is further ordered*, That, within two (2) years from the effective date of this order, Alamo and/or Phillips shall divest absolutely and in good faith, to a purchaser or purchasers approved by the Federal Trade Commission, the synthetic film production and manufacturing facilities at Stratford, Conn., heretofore purchased by Alamo from National, including, but not limited to, all properties, plants, machinery, equipment, raw material reserves, if any, and all contract rights pertaining to the operation of said facilities to the end that such divested facilities be established as a going concern and effective competitor in the manufacture and sale of synthetic film; and that National, to the extent that it is legally free to do so, shall grant to such purchaser or purchasers a license of the patents and know-how relating to synthetic film heretofore licensed to Alamo.

V. *It is further ordered*, That, within two (2) years from the effective date of this order, Alamo and/or Phillips shall divest absolutely and in good faith, to a purchaser or purchasers approved by the Federal Trade Commission, the rope business of Alamo's subsidiary, Wall Industries, Inc. (hereinafter referred to as "Wall"), including, but not limited to, the plant located at Beverly, N.J., all machinery and equipment located in said plant, related marketing facilities, and all other properties, plants, machinery, equipment, trade names, contract rights, trademarks, and goodwill relating to said rope business, together with all improvements relating to said rope business, to the end that such business be established as a going concern and effective competitor in the manufacture and

sale of rope; and that if, after two (2) years from the effective date of this order, Alamo and/or Phillips have been unable to divest Wall's rope business as aforesaid despite bona fide efforts to do so, Alamo and/or Phillips shall divest such other assets of Wall as shall be necessary to effectuate the divestiture of such rope business.

VI. *It is further ordered*, That, within ninety (90) days from the effective date of this order, Alamo shall sell to National, and National shall purchase from Alamo, all capital stock, bonds, debentures, other securities, and all other interests held by Alamo in Beacon Manufacturing Co., in accordance with Exhibit A.

VII. *It is further ordered*, That Phillips shall grant to National, at National's request made within five (5) years of the date of the aforesaid sale of Alamo's stock by National to Phillips, licenses to Phillips' and/or Alamo's polypropylene process and licenses under United States patents or know-how relating to products using polypropylene in accordance with Exhibit A, to the end that National have available to it all necessary know-how and licenses under patents to enter, if it so desires, the polypropylene field.

B. DISSOLUTION OF A-B CHEMICAL CORP. JOINT VENTURE

VIII. *It is further ordered*, That, within ninety (90) days from the effective date of this order, Phillips shall sell to National, and National shall purchase from Phillips, all the capital stock, bonds, debentures, other securities, and all other interests held by Phillips in A-B Chemical Corp. (hereinafter referred to as "A-B"), in accordance with Exhibit B.

IX. *It is further ordered*, That, within five (5) years from the effective date of this order, Phillips shall enter independently into the production of low density polyethylene resin at a newly constructed plant with a minimum annual rated capacity of 140 million pounds. Phillips shall promptly initiate the steps necessary for construction of said plant, and shall continue to use its best efforts to construct such plant and to bring it into production at the earliest possible date.

X. *It is further ordered*, That National shall grant to Phillips, at Phillips' request made within five (5) years from the date of the aforesaid sale of A-B's stock by Phillips, and in connection with its construction of the low density polyethylene plant referred to the preceding paragraph, a license to National's high pressure polyethylene process, in accordance with Exhibit B, to the end that Phillips may utilize National's process, if it so desires, in its independent entry into the production of low density polyethylene resin.

XI. *It is further ordered*, That National shall take certain steps to establish in the low density polyethylene resin business any two firms or companies approved and/or chosen by the Federal Trade Commission, on terms and conditions set forth in the form of agreement annexed hereto as Exhibit C, to the end that competition in low density polyethylene resin be fostered by entry of new pro-

ducers: *Provided, however, That if National shall have then granted a license to anyone covering National's high-pressure polyethylene process in the United States, its territories, possessions or Puerto Rico (other than to a licensee who is either already in the high-pressure polyethylene resin business using a process not directly or indirectly obtained from National or is a company at least 50 percent of whose voting stock is owned by National) upon more favorable scope, terms and conditions than those set forth in Exhibit C, then Exhibit C shall be amended to be not less favorable to the licensee than the most favorable license granted to such other licensee.*

C. DISSOLUTION OF ATLANTIC POLYMERS, N.V. JOINT VENTURE

XII. It is further ordered, That, within ninety (90) days from the effective date of this order, Phillips shall sell to National, and National shall purchase from Phillips, all capital stock, bonds, debentures, other securities and all other interests held by Phillips in Atlantic Polymers, N.V. (a Belgian corporation now engaged in the construction of a plant for the production of polyethylene resin in Belgium), in accordance with Exhibit D.

D. DIVESTITURE OF NATIONAL'S INTEREST IN AMERICAN RENOLIT CORP.

XIII. It is further ordered, That, within ninety (90) days from the effective date of this order, National shall sell to Phillips, and Phillips shall purchase from National, all capital stock, bonds, debentures, other securities, and all other interests held by National in American Renolit Corp. (a Delaware corporation engaged in the production of polyvinyl chloride), in accordance with Exhibit E.

E. BAN ON FUTURE ACQUISITIONS AND JOINT VENTURES

XIV. It is further ordered, That: (1) For a period of ten (10) years from the effective date of this order, Phillips shall not acquire, directly or indirectly, through subsidiaries, joint ventures or otherwise, the whole or any part of the stock, share capital or assets (other than products sold in the course of business and patents, licenses or know-how) of any domestic concern theretofore engaged principally or as one of its major commodity lines in the manufacture, processing, conversion or sale of any polypropylene or low density polyethylene resin or fabricated product (except a concern the business activities of which in polypropylene or low density polyethylene are limited to processing, conversion or fabrication and which in the year prior to Phillips' acquisition accounted for total sales of polypropylene and high and low density polyethylene products not exceeding one million dollars (\$1,000,000)), without the prior approval of the Federal Trade Commission, and

(2) For a period of five (5) years from the effective date of this order, Phillips shall not acquire, directly or indirectly, through subsidiaries, joint ventures or

otherwise, the whole or any part of the stock, share capital or assets (other than products sold in the course of business and patents, licenses or know-how) of any domestic concern theretofore engaged principally or as one of its major commodity lines in the manufacture, processing, conversion or sale of any high density polyethylene resin or fabricated product (except a concern the business activities of which in high density polyethylene are limited to processing, conversion or fabrication and which in the year prior to Phillips' acquisition accounted for total sales of polypropylene and polyethylene products not exceeding one million dollars (\$1,000,000)), without the prior approval of the Federal Trade Commission.

XV. It is further ordered, That: (1) For a period of ten (10) years from the effective date of this order, National shall not acquire, directly or indirectly, through subsidiaries, joint ventures, or otherwise, the whole or any part of the stock, share capital or assets used in the manufacture or sale of high or low density polyethylene resin (other than products sold in the course of business and patents, licenses or know-how) of any domestic concern engaged (and in the case of joint ventures, to be engaged) principally or as one of its major commodity lines in the manufacture or sale of high or low density polyethylene resin, without the prior approval of the Federal Trade Commission;

(2) For a period of five (5) years from the effective date of this order, National shall not acquire, directly or indirectly, through subsidiaries, joint ventures or otherwise, the whole or any part of the stock, share capital or assets (other than products sold in the course of business and patents, licenses or know-how) of any domestic concern theretofore engaged in the conversion, fabrication or sale of any high or low density polyethylene product where such concern, in the year prior to National's acquisition had total sales of polypropylene and high and low density polyethylene products in excess of five million dollars (\$5,000,000), without the prior approval of the Federal Trade Commission;

(3) For a period of five (5) years from the effective date of this order, National shall not acquire, directly or indirectly, through subsidiaries, joint ventures or otherwise, the whole or any part of the stock, share capital or assets used in the manufacture or sale of polypropylene resin (other than products sold in the course of business and patents, licenses or know-how) of any domestic concern then or at any time in the past engaged principally or as one of its major commodity lines in the manufacture or sale of polypropylene resin, without the prior approval of the Federal Trade Commission; and

(4) For a period of five (5) years from the effective date of this order, National, if it shall have authorized entry into the business of producing polypropylene resin, shall not acquire, directly or indirectly, through subsidiaries, joint ventures or otherwise, the whole or any part of the stock, share capital or assets

(other than products sold in the course of business and patents, licenses or know-how) of any domestic concern theretofore engaged in the conversion, fabrication or sale of polypropylene products where such concern, in the year prior to National's acquisition, had total sales of polypropylene and high and low density polyethylene products in excess of five million dollars (\$5,000,000) without the prior approval of the Federal Trade Commission.

XVI. It is further ordered, That, for a period of twenty (20) years from the effective date of this order, Phillips and National shall cease and desist from engaging together, directly or indirectly, in any future joint ventures involving the manufacture, processing, conversion, fabrication or sale of any polyolefin or polyolefin product, without the prior approval of the Federal Trade Commission.

F. GENERAL PROVISIONS

XVII. It is further ordered, That, pending divestiture or sale, respondents shall not make or permit any deterioration in any of the plants, machinery, building, equipment or other property or assets of the companies and plants described in this order which may impair their present capacity or market value, unless such capacity or value is restored prior to divestiture or sale.

XVIII. It is further ordered, That in the event that respondents, despite bona fide efforts to do so, are unable to divest any or all of the facilities required to be divested by this order or are unable to construct new plants in accord with this order within the specified time, respondents may apply to the Federal Trade Commission at such time for relief from such obligations; and the Federal Trade Commission may issue such orders as it deems appropriate regarding such obligations and the disposition of facilities not yet divested.

XIX. It is further ordered, That:

(1) Within ninety (90) days from the effective date of this order, Phillips, National and Alamo shall report in writing to the Federal Trade Commission their compliance with paragraphs I, VI, VIII, XII, and XIII of this order;

(2) Within ninety (90) days from the effective date of this order, and every ninety (90) days thereafter until the divestitures required by paragraphs II, IV, and V of this order have been completed, Phillips and Alamo shall report in writing to the Federal Trade Commission their plans for effecting such divestitures and the actions they have taken in implementation thereof, including, in addition to such other information as may be required, (a) the name, address and official capacity of the individual or individuals designated to carry out each divestiture and to negotiate with interested parties, (b) a brochure, presentation or other writing containing all of the essential information necessary to permit an interested party to evaluate each of the businesses to be divested, including a description and listing of its assets, (c) the efforts made and to be made in advertising and affirmatively announcing the availability of each of the

businesses to be divested, (d) the particular efforts made to locate and interest prospective purchasers not previously engaged in the industry, (e) a summary of contacts and negotiations relating to the sale of facilities ordered to be divested, including the identities of all parties expressing interest in the acquisition of any of the businesses to be divested and, subject to any legally recognized privilege, copies of all written communications pertaining to negotiations, offers to buy or indications of interest in the acquisitions of the whole or any part of any of the businesses to be divested, and (f) copies of all agreements and forms of agreement relating directly or indirectly to proposed sale of the whole or any part of the businesses to be divested.

(3) Within ninety (90) days from the effective date of this order, and every ninety (90) days thereafter until the terms of paragraphs III and IX of this order have been complied with, Phillips shall report in writing to the Federal Trade Commission the steps it has taken to construct plants in compliance with such paragraphs.

Issued: August 2, 1966.

By the Commission.

[SEAL] JOSEPH W. SHEA,
Secretary.

[F.R. Doc. 66-9785; Filed, Sept. 7, 1966;
8:46 a.m.]

[Docket No. C-1089]

PART 13—PROHIBITED TRADE PRACTICES

Thomas F. Lukens Metal Co. and Mitchell Steinberg

Subpart—Misbranding or mislabeling: § 13.1200 *Content*. Subpart—Misrepresenting oneself and goods—Goods: § 13.1605 *Content*.

(Sec. 6, 38 Stat. 721; 15 U.S.C. 46. Interpret or apply sec. 5, 38 Stat. 719, as amended, 15 U.S.C. 45) [Cease and desist order, Thomas F. Lukens Metal Co. et al., Philadelphia, Pa., Docket C-1089, Aug. 2, 1966]

Consent order requiring a Philadelphia distributor of commercial solders to cease misrepresenting the tin content of its products.

The order to cease and desist, including further order requiring report of compliance therewith, is as follows:

It is ordered, That respondents Thomas F. Lukens Metal Co., a corporation, and its officers, and Mitchell Steinberg, individually and as an officer of said corporation, and respondents' agents, representatives and employees, directly or through any corporate or other device, in connection with the offering for sale, sale or distribution of solders, in commerce, as "commerce" is defined in the Federal Trade Commission Act, do forthwith cease and desist from:

(1) Using the designation 50-50 alone or in conjunction with the words "by volume" to designate, describe or refer to a commercial solder which does not contain 50 percent tin by weight: *Provided, however*, That it shall be a defense

in any enforcement proceeding hereunder for respondents to establish that the tin content of a solder is within the permissible variations in composition allowed in the sampling procedures set forth in the then existing Specifications for Solder Metal as published by the American Society for Testing and Materials.

(2) Using the designation 40-60 alone or in conjunction with the words "by volume" to designate, describe or refer to a commercial solder which does not contain 40 percent tin by weight, *Provided, however*, That it shall be a defense in any enforcement proceeding hereunder for respondents to establish that the tin content of a solder is within the permissible variations in composition allowed in the sampling procedures set forth in the then existing Specifications for Solder Metal as published by the American Society for Testing and Materials.

(3) Misrepresenting by any numerical designation or in any other manner the tin content of any of their solders, *Provided, however*, That it shall be a defense in any enforcement proceeding hereunder for respondents to establish that the tin content of a solder is within the permissible variations in composition allowed in the sampling procedures set forth in the then existing Specifications for Solder Metal as published by the American Society for Testing and Materials.

It is further ordered, That the respondents herein shall, within sixty (60) days after service upon them of this order, file with the Commission a report in writing setting forth in detail the manner and form in which they have complied with this order.

Issued: August 2, 1966.

By the Commission.

[SEAL] JOSEPH W. SHEA,
Secretary.

[F.R. Doc. 66-9786; Filed, Sept. 7, 1966;
8:46 a.m.]

[Docket No. C-1090]

PART 13—PROHIBITED TRADE PRACTICES

Beatrice Foods Co.

Subpart—Discriminating in price under section 2, Clayton Act—Payment for services or facilities for processing or sale under 2(d): § 13.825 *Allowances for services or facilities*.

(Sec. 6, 38 Stat. 721; 15 U.S.C. 46. Interpret or applies sec. 2, 49 Stat. 1526; 15 U.S.C. 13) [Cease and desist order, Beatrice Foods Co., Chicago, Ill., Docket C-1090, Aug. 2, 1966]

Consent order requiring a Chicago, Ill., wholesale food processor, to cease discriminating among its competing customers in paying promotional allowances for its oriental food products, in violation of section 2(d) of the Clayton Act.

The order to cease and desist, including further order requiring report of compliance therewith, is as follows:

It is ordered, That respondent, the Beatrice Foods Co., a corporation, and its officers, employees, agents, and representatives, directly or through any corporate or other device, in or in connection with the offering for sale, sale or distribution of any of its oriental food products in commerce, as "commerce" is defined in the Clayton Act, as amended, do forthwith cease and desist from:

Paying or contracting for the payment of anything of value to, or for the benefit of, any customer of respondent as compensation or in consideration for any services or facilities furnished by or through such customer in connection with the offering for sale, sale or distribution of respondent's oriental food products, unless such payment or consideration is made available on proportionally equal terms to all other customers competing in the distribution of such products.

It is further ordered, That the respondent herein shall, within sixty (60) days after service upon it of this order, file with the Commission a report in writing setting forth in detail the manner and form in which it has complied with this order.

Issued: August 2, 1966.

By the Commission.

[SEAL] JOSEPH W. SHEA,
Secretary.

[F.R. Doc. 66-9787; Filed, Sept. 7, 1966;
8:46 a.m.]

[Docket No. C-1091]

PART 13—PROHIBITED TRADE PRACTICES

Steinberger Bros., Inc., et al.

Subpart—Furnishing false guaranties: § 13.1053 *Furnishing false guaranties*: 13.1053-90 Wool Products Labeling Act. Subpart—Invoicing products falsely: § 13.1108 *Invoicing products falsely*: 13.1108-40 Federal Trade Commission Act. Subpart—Misbranding or mislabeling: § 13.1185 *Composition*: 13.1185-90 Wool Products Labeling Act; § 13.1212 *Formal regulatory and statutory requirements*: 13.1212-90 Wool Products Labeling Act.

(Sec. 6, 38 Stat. 721; 15 U.S.C. 46. Interpret or apply sec. 5, 38 Stat. 719, as amended, secs. 2-5, 54 Stat. 1128-1130; 15 U.S.C. 45, 68) [Cease and desist order, Steinberger Bros., Inc., et al., New York, N.Y., Docket C-1091, August 2, 1966]

In the Matter of Steinberger Bros., Inc., a corporation, and Franklin Steinberger and Howard Steinberger, individually and as officers of said corporation

Consent order requiring a New York City clothing importer and wholesaler, to cease misbranding and falsely invoicing its wool products and furnishing false guaranties for them.

The order to cease and desist, including further order requiring report of compliance therewith, is as follows:

It is ordered, That respondents Steinberger Bros., Inc., a corporation, and its

officers, and Franklin Steinberger and Howard Steinberger, individually and as officers of said corporation, and respondents' representatives, agents and employees, directly or through any corporate or other device, do forthwith cease and desist from introducing into commerce, or offering for sale, selling, transporting, distributing or delivering for shipment in commerce wool yarn or any other wool products, as "commerce" and "wool product" are defined in the Wool Products Labeling Act of 1939:

1. Which are falsely and deceptively stamped, tagged, labeled or otherwise identified as to the character or amount of the constituent fibers contained therein.

2. Unless each such product has securely affixed thereto or placed thereon a stamp, tag, label or other means of identification correctly showing in a clear and conspicuous manner each element of information required to be disclosed by section 4(a)(2) of the Wool Products Labeling Act of 1939;

3. To which is affixed a label wherein the term "mohair" is used in lieu of the word "wool" in setting forth the required information on labels affixed to such wool products unless the fibers described as mohair are entitled to such designation and are present in at least the amount stated.

It is further ordered, That respondents Steinberger Bros., Inc., a corporation, and its officers, and Franklin Steinberger and Howard Steinberger, individually and as officers of said corporation, and respondents' representatives, agents and employees, directly or through any corporate or other device, do forthwith cease and desist from furnishing a false guaranty that any wool product is not falsely or deceptively stamped, tagged, labeled, or otherwise identified when respondents have reason to believe that such wool product may be introduced, sold, transported, or distributed in commerce.

It is further ordered, That respondents Steinberger Bros., Inc., a corporation, and its officers, and Franklin Steinberger and Howard Steinberger, individually and as officers of said corporation, and respondents' representatives, agents and employees, directly or through any corporate or other device, in connection with the offering for sale, sale or distribution of yarn or any other textile products in commerce, as "commerce" is defined in the Federal Trade Commission Act, do forthwith cease and desist from misrepresenting the character or amount of constituent fibers contained in yarn or any other textile products on invoices or shipping memoranda applicable thereto or in any other manner.

It is further ordered, That the respondents herein shall, within sixty (60) days after service upon them of this order, file with the Commission a report in writing setting forth in detail the manner and form in which they have complied with this order.

Issued: August 2, 1966.

By the Commission.

[SEAL] JOSEPH W. SHEA,
Secretary.
[F.R. Doc. 66-9788; Filed, Sept. 7, 1966;
8:46 a.m.]

[Docket No. C-1092]

PART 13—PROHIBITED TRADE PRACTICES

William Smarz and Mercantile and Medical Credit Adjusters

Subpart—Furnishing means and instrumentalities of misrepresentation or deception: § 13.1055 *Furnishing means and instrumentalities of misrepresentation or deception*. Subpart—Misrepresenting oneself and goods—Business status, advantages or connections: § 13.1390 *Concealed subsidiary, fictitious collection agency, etc.*; § 13.1430 *Government indorsement, sanction or sponsorship*; § 13.1440 *Identity*; § 13.1490 *Nature*. Subpart—Securing information by subterfuge: § 13.2168 *Securing information by subterfuge*.

(Sec. 6, 38 Stat. 721; 15 U.S.C. 46. Interpret or apply sec. 5, 38 Stat. 719, as amended, 15 U.S.C. 45) [Cease and desist order, Mercantile and Medical Credit Adjusters, Jersey City, N.J., Docket C-1092, Aug. 3, 1966]

Consent order requiring a Jersey City, N.J., collection agency to cease using deceptive means to collect delinquent accounts or implying that the information it solicits is for some official government purpose.

The order to cease and desist, including further order requiring report of compliance therewith, is as follows:

It is ordered, That the respondent William Smarz, trading and doing business as Mercantile & Medical Credit Adjusters, or any other name or names, and respondent's representatives, agents and employees, directly or through any corporate or other device, in connection with the business of obtaining information concerning delinquent debtors, or the offering for sale, sale or distribution of forms, or other material, for use in obtaining information concerning delinquent debtors, or in the collection of, or attempt to collect, delinquent accounts in commerce, as "commerce" is defined in the Federal Trade Commission Act, do forthwith cease and desist from:

1. Using, or placing in the hands of others for use, any form, questionnaire or other material, printed or written, which does not clearly and conspicuously reveal that the purpose for which the information is requested is that of obtaining information concerning alleged delinquent debtors.

2. Representing, or placing in the hands of others any means by which they may represent, directly or by implication, that money or a free gift or any other thing of value, is being held for the person from whom information is sought.

3. Using the name "Bureau of Accounting Audits, N.T.B. Division, Depart-

ment 88 'L' Section" or any other name or words of similar import to designate, describe or refer to respondent's business; or representing, directly or by implication, that any private inquiries, forms or communications emanate from or are connected with an official or governmental agency or are used to solicit information for official or governmental purposes.

4. Misrepresenting, in any manner, the identity of the sender or origin of any inquiry, the purpose for which information is sought, or the nature or status of respondent's business.

5. Placing in the hands of others the means and instrumentalities whereby they may misrepresent in any manner the purpose for which information is sought by them or the nature or status of their business.

It is further ordered, That the respondent herein shall, within sixty (60) days after service upon him of this order, file with the Commission a report in writing setting forth in detail the manner and form in which he has complied with this order.

Issued: August 3, 1966.

By the Commission.

[SEAL] JOSEPH W. SHEA,
Secretary.
[F.R. Doc. 66-9789; Filed, Sept. 7, 1966;
8:46 a.m.]

[Docket No. C-1093]

PART 13—PROHIBITED TRADE PRACTICES

Benjamin D. Kalin et al.

Subpart—Advertising falsely or misleadingly: § 13.30 *Composition of goods*: 13.30-30 Fur Products Labeling Act; § 13.73 *Formal regulatory and statutory requirements*: 13.73-10 Fur Products Labeling Act; § 13.95 *Identity of product*: 13.95-20 Fur Products Labeling Act. Subpart—Invoicing products falsely: § 13.1108 *Invoicing products falsely*: 13.1108-45 Fur Products Labeling Act. Subpart—Misbranding or mislabeling: § 13.1185 *Composition*: 13.1185-30 Fur Products Labeling Act; § 13.1212 *Formal regulatory and statutory requirements*: 13.1212-30 Fur Products Labeling Act. Subpart—Neglecting, unfairly or deceptively, to make material disclosure: § 13.1845 *Composition*: 13.1845-30 Fur Products Labeling Act; § 13.1852 *Formal regulatory and statutory requirements*: 13.1852-35 Fur Products Labeling Act.

(Sec. 6, 38 Stat. 721; 15 U.S.C. 46. Interpret or apply sec. 5, 38 Stat. 719, as amended; sec. 8, 65 Stat. 179; 15 U.S.C. 45, 69f) [Cease and desist order, Kalin's Furs and Fashions et al., Sioux City, Iowa, Docket C-1093, Aug. 3, 1966]

In the Matter of Benjamin D. Kalin, an Individual Trading as Kalin's Furs & Fashions, and Kalin's

Consent order requiring a Sioux City, Iowa, retail furrier to cease misbranding, falsely invoicing, and deceptively advertising its fur products.

The order to cease and desist, including further order requiring report of compliance therewith, is as follows:

It is ordered, That respondent Benjamin D. Kalin, an individual trading as Kalin's Furs & Fashions, and Kalin's, or under any other name, and respondent's representatives, agents and employees, directly or through any corporate or other device, do forthwith cease and desist from introducing into commerce, selling, advertising or offering for sale in commerce, or transporting or distributing in commerce, any fur product; or from selling, advertising, offering for sale, transporting or distributing, any fur product which is made in whole or in part of fur which has been shipped and received in commerce, as the terms "commerce," "fur" and "fur product" are defined in the Fur Products Labeling Act;

A. Unless there is securely affixed to each such product a label showing in words and in figures plainly legible all of the information required to be disclosed by each of the subsections of section 4(2) of the Fur Products Labeling Act.

B. To which fur product is affixed a label required by section 4(2) of the Fur Products Labeling Act and the rules and regulations promulgated thereunder:

1. Which fails to set forth the term "natural" as part of the information required to be disclosed on such label under the Fur Products Labeling Act and the rules and regulations promulgated thereunder, to describe a fur product which is not pointed, bleached, dyed, tip-dyed, or otherwise artificially colored.

2. Which fails to disclose that such fur product is composed in whole or in substantial part of paws, tails, bellies, sides, flanks, gills, ears, throats, heads, scrap pieces or waste fur.

3. That does not comply with the minimum size requirements of 1 3/4 inches by 2 3/4 inches.

4. Which fails to completely set out information required under section 4(2) of the Fur Products Labeling Act and the rules and regulations thereunder on one side of such label.

5. Which fails to set forth information required under section 4(2) of the Fur Products Labeling Act and the rules and regulations thereunder in a legible manner in letters of equal size and conspicuousness.

6. Which sets forth information required under section 4(2) of the Fur Products Labeling Act and the rules and regulations promulgated thereunder in handwriting.

7. Which fails to set forth information under section 4(2) of the Fur Products Labeling Act and the rules and regulations promulgated thereunder in the sequence required by Rule 30 of the aforesaid rules and regulations.

8. Which fails to set forth separately on a label attached to any such fur product composed of two or more sections containing different animal fur the information required under section 4(2) of the Fur Products Labeling Act and the rules and regulations promulgated thereunder with respect to the fur comprising each section.

9. Which fails to set forth the item number or mark assigned to each such fur product.

It is further ordered, That respondent Benjamin D. Kalin, an individual trading as Kalin's Furs & Fashions, and Kalin's, or under any other name, and respondent's representatives, agents and employees, directly or through any corporate or other device, in connection with the introduction, into commerce, or the sale, advertising, or offering for sale in commerce, of any fur product; or in connection with the sale, advertising, offering for sale, transportation or distribution, of any fur product which is made in whole or in part of fur which has been shipped and received in commerce, as the terms "commerce," "fur" and "fur product" are defined in the Fur Products Labeling Act do forthwith cease and desist from:

A. Falsely or deceptively invoicing fur products by:

1. Failing to furnish invoices, as the term "invoice" is defined in the Fur Products Labeling Act, showing in words and figures plainly legible all the information required to be disclosed in each of the subsections of section 5(b) (1) of the Fur Products Labeling Act.

2. Setting forth on invoices pertaining to fur products any false or deceptive information with respect to the name or designation of the animal or animals that produced the fur contained in such fur product.

3. Setting forth information required under section 5(b) (1) of the Fur Products Labeling Act and the rules and regulations promulgated thereunder in abbreviated form.

4. Failing to set forth the term "Dyed Broadtail-processed Lamb" in the manner required where an election is made to use that term instead of the words "Dyed Lamb."

5. Failing to set forth the term "natural" as part of the information required to be disclosed on invoices under the Fur Products Labeling Act and rules and regulations promulgated thereunder to describe fur products which are not pointed, bleached, dyed, tip-dyed or otherwise artificially colored.

6. Failing to set forth on invoices the item number or mark assigned to each such fur product.

B. Falsely or deceptively advertising fur products through the use of any advertisement, representation, public announcement, or notice which is intended to aid, promote or assist, directly or indirectly, in the sale, or offering for sale of any fur product, and which:

1. Fails to set forth in words and figures plainly legible all the information required to be disclosed by each of the subsections of section 5(a) of the Fur Products Labeling Act.

2. Falsely or deceptively identifies any such fur product as to the name or designation of the animal or animals that produced the fur contained in the fur product.

3. Sets forth the name or names of any animal or animals other than the name of the animal producing the furs

contained in the fur product as specified in the Fur Products Name Guide, and as prescribed by the rules and regulations.

4. Fails to set forth the term "Dyed Broadtail-processed Lamb" in the manner required where an election is made to use that term instead of the words "Dyed Lamb".

5. Fails to set forth the term "natural" as part of the information required to be disclosed in advertisements under the Fur Products Labeling Act and the rules and regulations promulgated thereunder to describe fur products which are not pointed, bleached, dyed, tip-dyed, or otherwise artificially colored.

6. Fails to set forth all parts of the information required under section 5(a) of the Fur Products Labeling Act and the rules and regulations promulgated thereunder in type of equal size and conspicuousness and in close proximity with each other.

C. Failing to maintain full and adequate records disclosing the facts upon which pricing claims and representations of the types described in subsections (a), (b), (c), and (d) of Rule 44 of the rules and regulations promulgated under the Fur Products Labeling Act, are based.

It is further ordered, That the respondent herein shall, within sixty (60) days after service upon him of this order, file with the Commission a report in writing setting forth in detail the manner and form in which he has complied with this order.

Issued: August 3, 1966.

By the Commission.

[SEAL]

JOSEPH W. SHEA,
Secretary.

[F.R. Doc. 66-9790; Filed, Sept. 7, 1966;
8:46 a.m.]

[Docket No. C-1094]

PART 13—PROHIBITED TRADE PRACTICES

Thomas Harris McDonald and
McDonald & Son Golf Co.

Subpart—Furnishing means and instrumentalities of misrepresentation or deception: § 13.1055 *Furnishing means and instrumentalities of misrepresentation or deception.* Subpart—Misrepresenting oneself and goods—Goods: § 13.1695 *Old, secondhand, reclaimed or reconstructed as new.* Subpart—Neglecting, unfairly or deceptively, to make material disclosure: § 13.1880 *Old, used, or reclaimed as unused or new.*

(Sec. 6, 38 Stat. 721; 15 U.S.C. 46. Interpret or apply sec. 5, 38 Stat. 719, as amended, 15 U.S.C. 45) [Cease and desist order, McDonald & Son Golf Co., Batavia, Ill., Docket C-1094, Aug. 3, 1966]

In the Matter of Thomas Harris McDonald, an Individual Trading as McDonald & Son Golf Company

Consent order requiring a Batavia, Ill., reconditioner of used golf balls, to cease failing to disclose on the golf balls themselves, on the wrappers, or boxes, that

said balls are previously used golf balls which have been rewashed or repainted.

The order to cease and desist, including further order requiring report of compliance therewith, is as follows:

It is ordered, That the respondent, Thomas Harris McDonald, an individual trading and doing business as McDonald & Son Golf Co., or under any other trade name or names, and respondent's representatives, agents and employees, directly or through any corporate or other device, in connection with the offering for sale, sale and distribution of used, rewashed or repainted golf balls in commerce, as "commerce" is defined in the Federal Trade Commission Act, do forthwith cease and desist from:

1. Placing clearly to disclose on the boxes in which respondent's rewashed or repainted golf balls are packaged, on the wrapper and on said golf balls themselves, that they are previously used balls which have been rewashed or repainted: *Provided, however*, That disclosure need not be made on the golf balls themselves if respondent establishes that the disclosure on the boxes and/or wrappers is such that retail customers, at the point of sale, are informed that the golf balls are previously used and have been rewashed or repainted.

2. Placing any means or instrumentality in the hands of others whereby they may mislead the public as to the prior use and rewashed or repainted nature of their golf balls.

It is further ordered, That the respondent herein shall, within sixty (60) days after service upon him of this order, file with the Commission a report in writing setting forth in detail the manner and form in which he has complied with this order.

Issued: August 3, 1966.

By the Commission.

[SEAL] JOSEPH W. SHEA,
Secretary.

[F.R. Doc. 66-9791; Filed, Sept. 7, 1966;
8:46 a.m.]

[Docket No. C-1095]

PART 13—PROHIBITED TRADE PRACTICES

M. Hat Shoppe, Inc., et al.

Subpart—Invoicing products falsely: § 13.1108 *Invoicing products falsely*: 13.1108-45 Fur Products Labeling Act. Subpart—Misbranding or mislabeling: § 13.1185 *Composition*: 13.1185-30 Fur Products Labeling Act; § 13.1212 *Formal regulatory and statutory requirements*: 13.1212-30 Fur Products Labeling Act; § 13.1325 *Source or origin*: Subpart—Neglecting, unfairly or deceptively, to make material disclosure: § 13.1845 *Composition*: 13.1845-30 Fur Products Labeling Act; § 13.1852 *Formal regulatory and statutory requirements*: 13.1852-35 Fur Products Labeling Act.

(Sec. 6, 38 Stat. 721; 15 U.S.C. 46. Interpret or apply sec. 5, 38 Stat. 719, as amended; sec. 6, 65 Stat. 179; 15 U.S.C. 45, 69f) [Cease and

desist order, Muriel Hats et al., New York, N.Y., Docket C-1095, Aug. 4, 1966]

In the Matter of M. Hat Shoppe, Inc., a Corporation, Doing Business as Muriel Hats, and Jacob Hirsch and Sadie Hirsch, Individually and as Officers of Said Corporation

Consent order requiring a New York City manufacturing and retailing furrier to cease misbranding and falsely invoicing its fur products.

The order to cease and desist, including further order requiring report of compliance therewith, is as follows:

It is ordered, That respondents M. Hat Shoppe, Inc., a corporation, doing business as Muriel Hats or under any other name, and its officers, and Jacob Hirsch and Sadie Hirsch, individually and as officers of said corporation, and respondents' representatives, agents, and employees, directly or through any corporate or other device, in connection with the introduction, or manufacture for introduction, into commerce, or the sale, advertising or offering for sale in commerce, or the transportation or distribution in commerce, of any fur product; or in connection with the manufacture for sale, sale, advertising, offering for sale, transportation or distribution of any fur product which is made in whole or in part of fur which has been shipped and received in commerce; as the terms "commerce", "fur" and "fur product" are defined in the Fur Products Labeling Act, do forthwith cease and desist from:

A. Misbranding fur products by:

1. Falsely or deceptively labeling or otherwise identifying any such fur product as to the name or designation of the animal or animals that produced the fur contained in the fur product.

2. Failing to affix labels to fur products showing in words and in figures plainly legible all of the information required to be disclosed by each of the subsections of section 4(2) of the Fur Products Labeling Act.

3. Setting forth on labels attached to fur products the name or names of any animal or animals other than the name of the animal producing the fur contained in the fur product as specified in the Fur Products Name Guide, and as prescribed by the rules and regulations.

4. Setting forth information required under section 4(2) of the Fur Products Labeling Act and rules and regulations promulgated thereunder in abbreviated form on labels affixed to fur products.

5. Failing to disclose on labels that fur products are composed in whole or in substantial part of paws, tails, bellies, sides, flanks, gills, ears, throats, heads, scrap pieces or waste fur.

6. Affixing to fur products labels that do not comply with the minimum size requirements of 1 1/4 inches by 2 3/4 inches.

7. Setting forth information required under section 4(2) of the Fur Products Labeling Act and the rules and regulations promulgated thereunder in handwriting on labels affixed to fur products.

8. Failing to set forth information required under section 4(2) of the Fur Products Labeling Act and the rules and regulations promulgated thereunder on

labels in the sequence required by Rule 30 of the aforesaid rules and regulations.

9. Failing to set forth on labels the item number or mark assigned to each such fur product.

B. Falsely or deceptively invoicing fur products by:

1. Failing to furnish invoices, as the term "invoice" is defined in the Fur Products Labeling Act, showing in words and figures plainly legible all the information required to be disclosed by each of the subsections of section 5(b)(1) of the Fur Products Labeling Act.

2. Failing to set forth on invoices the item number or mark assigned to each fur product.

It is further ordered, That the respondents herein shall, within sixty (60) days after service upon them of this order, file with the Commission a report in writing setting forth in detail the manner and form in which they have complied with this order.

Issued: August 4, 1966.

By the Commission.

[SEAL] JOSEPH W. SHEA,
Secretary.

[F.R. Doc. 66-9792; Filed, Sept. 7, 1966;
8:46 a.m.]

[Dockets 72250., 74960.]

PART 13—PROHIBITED TRADE PRACTICES

Tri-Valley Packing Association

Subpart—Discriminating in price under section 2, Clayton Act—Price discrimination under 2(a): § 13.715 *Charges and price differentials*; Discriminating in price under section 2, Clayton Act—Payment for services or facilities for processing or sale under 2(d): § 13.824 *Advertising expenses*.

(Sec. 6, 38 Stat. 721; 15 U.S.C. 46. Interpret or apply sec. 2, 49 Stat. 1526; 15 U.S.C. 13) [Cease and desist order, Tri-Valley Packing Association, San Francisco, Calif., Dockets 7225 and 7496, July 28, 1966]

Order in two consolidated proceedings, following remand for further proceedings by Court of Appeals, Ninth Circuit, dated March 18, 1964, 329 F.2d 694, the Commission's cease and desist order of May 10, 1962, 27 F.R. 8070, requiring a San Francisco canner of fruits and vegetables to cease discriminating in price and paying promotional allowances among its competing customers in violation of sections 2 (a) and (d) of the Clayton Act.

The modified order to cease and desist, including further order requiring report of compliance therewith, is as follows:

It is ordered, That respondent, Tri-Valley Growers, a corporation, and its officers, representatives, agents and employees, directly or through any corporate or other device in, or in connection with, the sale of food products in commerce, as "commerce" is defined in the amended Clayton Act, do forthwith cease and desist from:

1. Discriminating in the price of such products of like grade and quality by sell-

ing to any purchaser at net prices higher than the net prices charged any other purchaser who, in fact, competes with the purchaser paying the higher price or with customers of such purchaser.

2. Paying or contracting for the payment of anything of value to or for the benefit of any customer of respondent, pursuant to a specially tailored or negotiated arrangement, as compensation or in consideration for any services or facilities furnished by or through such customer, in connection with the offering for sale, sale or distribution of any of respondent's products, unless such payment or consideration is made available on proportionally equal terms to all other customers competing in the distribution of such products with the favored customer.

It is further ordered, That respondent, Tri-Valley Growers, shall, within sixty (60) days after service of this order upon it file with the Commission a report, in writing, setting forth in detail the manner and form in which it has complied with the terms of the order contained herein.

Issued: July 28, 1966.

By the Commission.

[SEAL] JOSEPH W. SHEA,
Secretary.

[F.R. Doc. 66-9793; Filed, Sept. 7, 1966;
8:47 a.m.]

[Docket No. 7606]

PART 13—PROHIBITED TRADE PRACTICES

Brown Shoe Co.

Subpart—Dealing on exclusive and tying basis: § 13.670 *Dealing on exclusive and tying basis*: 13.670-20 Federal Trade Commission Act.

(Sec. 6, 38 Stat. 721; 15 U.S.C. 46. Interpret or apply sec. 5, 38 Stat. 719, as amended, 15 U.S.C. 45) [Modified order to cease and desist, Brown Shoe Co., St. Louis, Mo., Docket 7606, Aug. 3, 1966]

Order modifying pursuant to a unanimous decision of the U.S. Supreme Court, 86 S. Ct. 1501, which reversed a decision of the Eighth Circuit, Court of Appeals, 339 F. 2d 45, modifying a cease and desist order, 28 F.R. 2672, issued February 20, 1963, by deleting language dealing with resale price maintenance but directing enforcement of the exclusive dealing prohibition of the original order.

The modified order to cease and desist, including further order requiring report of compliance therewith, is as follows:

Now, therefore, it is hereby ordered, That the aforesaid order to cease and desist be, and it hereby is, modified, in accordance with the said final decree of the court of appeals to read as follows:

It is ordered, That respondent Brown Shoe Co., Inc., its officers, representatives, agents, employees, subsidiaries,

successors, and assigns, directly or through any corporate or other device, in or in connection with the offering for sale, sale and distribution of shoes, in interstate commerce, do forthwith cease and desist from: Entering into, continuing in operation or effect, or enforcing any agreement or understanding with any customer or prospective customer or imposing any condition upon any customer or prospective customer, which has the purpose or effect of precluding such customer or prospective customer from independently determining whether shoes will be purchased by such customer or prospective customer from any competitor of respondent or from independently determining the volume of such shoes to be purchased.

It is further ordered, That respondent, Brown Shoe Co., Inc., a corporation, shall within sixty (60) days after service upon it of this order, file with the Commission a report in writing, setting forth in detail the manner and form in which it has complied with this modified order.

Issued: August 3, 1966.

By the Commission.

[SEAL] JOSEPH W. SHEA,
Secretary.

[F.R. Doc. 66-9794; Filed, Sept. 7, 1966;
8:47 a.m.]

Title 21—FOOD AND DRUGS

Chapter I—Food and Drug Administration, Department of Health, Education, and Welfare

SUBCHAPTER B—FOOD AND FOOD PRODUCTS

PART 29—FRUIT BUTTERS, FRUIT JEL-LIES, FRUIT PRESERVES, AND RELATED PRODUCTS

Fruit Preserves and Jams; Confirmation of Effective Date of Order Amending Identity Standard To Permit Optional Use of Concentrated Fruit Ingredients

In the matter of amending the standard of identity for fruit preserves and jams (21 CFR 29.3) to permit the optional use of concentrated fruit ingredients in the manufacture of these foods:

Pursuant to the provisions of the Federal Food, Drug, and Cosmetic Act (secs. 401, 701, 52 Stat. 1046, 1055 as amended, 70 Stat. 919, 72 Stat. 948; 21 U.S.C. 341, 371), and in accordance with the authority delegated to the Commissioner of Food and Drugs by the Secretary of Health, Education, and Welfare (21 CFR 2.120; 31 F.R. 3008), notice is given that no objections were filed to the order in the above-identified matter published in the FEDERAL REGISTER of July 20, 1966 (31 F.R. 9796). Accordingly, the amendments promulgated by that order will become effective September 18, 1966.

(Secs. 401, 701, 52 Stat. 1046, 1055 as amended, 70 Stat. 919, 72 Stat. 948; 21 U.S.C. 341, 371)

Dated: September 1, 1966.

J. K. KIRK,
Acting Commissioner of
Food and Drugs.

[F.R. Doc. 66-9833; Filed, Sept. 7, 1966;
8:50 a.m.]

PART 120—TOLERANCES AND EXEMPTIONS FROM TOLERANCES FOR PESTICIDE CHEMICALS IN OR ON RAW AGRICULTURAL COMMODITIES

Subpart B—Procedural Regulations

DELETION OF OBSOLETE MATERIAL

Effective upon publication of this order in the FEDERAL REGISTER, Part 120 is amended by deleting §§ 120.36 and 120.37, which are obsolete.

(Sec. 701(a), 52 Stat. 1055; 21 U.S.C. 371(a))

Dated: September 1, 1966.

J. K. KIRK,
Acting Commissioner of
Food and Drugs.

[F.R. Doc. 66-9834; Filed, Sept. 7, 1966;
8:50 a.m.]

SUBCHAPTER C—DRUGS

PART 166—DEPRESSANT AND STIMULANT DRUGS; DEFINITIONS, PROCEDURAL AND INTERPRETATIVE REGULATIONS

Listing of Phenmetrazine and Its Salts as Drugs Subject to Control; Confirmation of Effective Date

In the matter of listing phenmetrazine and its salts (Preludin) as depressant or stimulant drugs within the meaning of section 201(v) of the Federal Food, Drug, and Cosmetic Act:

Pursuant to the provisions of the Federal Food, Drug, and Cosmetic Act (secs. 201(v), 511, 701, 52 Stat. 1055, as amended, 79 Stat. 227 et seq.; 21 U.S.C. 321(v), 360a, 371), and under the authority delegated by the Secretary of Health, Education, and Welfare to the Commissioner of Food and Drugs (21 CFR 2.120; 31 F.R. 3008), notice is given that no objections were filed to the order in the above-identified matter published in the FEDERAL REGISTER of July 23, 1966 (31 F.R. 10029).

Accordingly, the amendment promulgated by that order will become effective September 21, 1966.

(Secs. 201(v), 511, 701, 52 Stat. 1055, as amended, 79 Stat. 227 et seq.; 21 U.S.C. 321(v), 360a, 371)

Dated: September 1, 1966.

JAMES L. GODDARD,
Commissioner of Food and Drugs.

[F.R. Doc. 66-9835; Filed, Sept. 7, 1966;
8:50 a.m.]

Title 22—FOREIGN RELATIONS

Chapter I—Department of State

[Dept. Reg. 108.539]

PART 42—VISAS: DOCUMENTATION OF IMMIGRANTS UNDER IMMIGRATION AND NATIONALITY ACT, AS AMENDED

Immigration Pool for Fiscal Year 1967

Correction

In F.R. Doc. 66-9393 appearing in the issue for Tuesday, August 30, 1966, at page 11416, the section designation and heading should read as follows:

§ 42.60 Allocation of numbers during the transition period.

Title 43—PUBLIC LANDS: INTERIOR

Chapter II—Bureau of Land Management, Department of the Interior

APPENDIX—PUBLIC LAND ORDERS

[Public Land Order 4080]

[Miscellaneous 68465]

ALABAMA

Opening of Land Subject to Section 24 of the Federal Power Act

By virtue of the authority contained in section 24 of the Federal Power Act of June 10, 1920 (41 Stat. 1075; 16 U.S.C. 818), as amended, it is ordered as follows:

In DA-13—Alabama, the Federal Power Commission determined that the power value of the following described land, withdrawn in part in Project No. 2165, will not be injured or destroyed by its restoration under appropriate public land laws, subject to the provisions of section 24 of the Federal Power Act:

HUNTSVILLE MERIDIAN

WILLIAM B. BANKHEAD NATIONAL FOREST

T. 12 S., R. 6 W.,
Sec. 10, SE $\frac{1}{4}$ SW $\frac{1}{4}$.

Containing 39.75 acres.

At 10 a.m. on September 12, 1966, the project land shall be open to such forms of disposition as may by law be made of national forest lands, subject to valid existing rights, the provisions of existing withdrawals, and to the requirements of applicable law, and subject to the provisions of section 24 of the Federal Power Act, supra, and to the right of the licensee for Project No. 2165, its successors and assigns, to occupy and use the project lands for project purposes, and to the condition that the patentee and his successors shall use the project lands in a manner which will not endanger health, create a nuisance, or otherwise be incompatible with overall project recreational uses.

Inquiries concerning the lands should be addressed to the Manager, Eastern

States Land Office, Bureau of Land Management, Washington, D.C. 20240.

HARRY R. ANDERSON,
Assistant Secretary of the Interior.

SEPTEMBER 1, 1966.

[F.R. Doc. 66-9801; Filed, Sept. 7, 1966;
8:47 a.m.]

[Public Land Order 4081]

[Anchorage 067495]

ALASKA

Correction of Public Land Order No. 4019

By virtue of the authority vested in the President by section 1 of the act of June 4, 1897 (30 Stat. 34, 36; 16 U.S.C. 473), and pursuant to Executive Order No. 10355 of May 26, 1952 (17 F.R. 4831), it is ordered as follows:

Public Land Order No. 4019 of May 20, 1966, so far as it describes "lot 12," Homestead No. 1139, for elimination from the Tongass National Forest, is hereby corrected to read "lot 10."

HARRY R. ANDERSON,
Assistant Secretary of the Interior.

SEPTEMBER 1, 1966.

[F.R. Doc. 66-9802; Filed, Sept. 7, 1966;
8:47 a.m.]

[Public Land Order 4082]

[Anchorage AA-30]

ALASKA

Exclusion of Land From Chugach National Forest

By virtue of the authority vested in the President by section 1 of the act of June 4, 1897 (30 Stat. 34, 36; 16 U.S.C. 473), and pursuant to Executive Order No. 10355 of May 26, 1952 (17 F.R. 4831), it is ordered as follows:

The following described tract of land, occupied as a homestead, is hereby excluded from the Chugach National Forest and restored, subject to valid existing rights, for purchase as a homestead under section 10 of the act of May 14, 1898 (30 Stat. 413; 48 U.S.C. 461), as amended:

Homestead No. 200, Trall Lake Group,
Lot 12, U.S. Survey 2528.

Containing 4.85 acres.

HARRY R. ANDERSON,
Assistant Secretary of the Interior.

SEPTEMBER 1, 1966.

[F.R. Doc. 66-9803; Filed, Sept. 7, 1966;
8:48 a.m.]

[Public Land Order 4083]

[Arizona 25]

ARIZONA

Elimination of Lands From Coronado National Forest

By virtue of the authority vested in the President by the act of June 4, 1897 (30 Stat. 34, 36, 16 U.S.C. 473), and pursuant to Executive Order No. 10355 of

May 26, 1952 (17 F.R. 4831), it is ordered as follows:

Proclamations No. 33 of July 30, 1902, and No. 1066 of July 1, 1910, and the Proclamation of November 5, 1906, creating and enlarging the Chiricahua Forest Reserve, now the Coronado National Forest, are hereby revoked so far as they affected the following described lands:

GILA AND SALT RIVER MERIDIAN

T. 16 S., R. 29 E.,
Sec. 24, lots 3 and 4, E $\frac{1}{2}$ SW $\frac{1}{4}$, and SE $\frac{1}{4}$;
Sec. 35;
Sec. 36, lots 1 and 2, E $\frac{1}{2}$ NW $\frac{1}{4}$, E $\frac{1}{2}$, and SW $\frac{1}{4}$.
T. 16 S., R. 29 $\frac{1}{2}$ E.,
Sec. 24, lots 1 to 4, incl., E $\frac{1}{2}$ W $\frac{1}{2}$, and E $\frac{1}{2}$;
Sec. 25, lots 1 to 4, incl., E $\frac{1}{2}$ W $\frac{1}{2}$, and E $\frac{1}{2}$;
Sec. 36, lots 1 to 4, incl., E $\frac{1}{2}$ W $\frac{1}{2}$, and E $\frac{1}{2}$.
T. 16 S., R. 30 E.,
Sec. 19, lots 1 to 4, incl., and E $\frac{1}{2}$ W $\frac{1}{2}$;
Sec. 30, lots 1 to 4, incl., and E $\frac{1}{2}$ W $\frac{1}{2}$;
Sec. 31, lots 1 to 4, incl., and E $\frac{1}{2}$ W $\frac{1}{2}$.

The areas described aggregate 4,282.45 acres in Cochise County. The lands remain withdrawn for the Chiricahua National Monument.

HARRY R. ANDERSON,
Assistant Secretary of the Interior.

SEPTEMBER 1, 1966.

[F.R. Doc. 66-9804; Filed, Sept. 7, 1966;
8:48 a.m.]

Title 47—TELECOMMUNICATION

Chapter I—Federal Communications Commission

[FCC 66-781]

PART 0—COMMISSION ORGANIZATION

Delegations of Authority Regarding Handling of Tort Claims

At a session of the Federal Communications Commission held at its offices in Washington, D.C., on the 31st day of August, 1966;

The Commission has reexamined its delegations of authority for handling tort claims (§§ 0.211(d) and 0.251(a) of the rules) in light of the recent amendment of the Federal Tort Claims Act. Public Law 89-506, enacted on July 18, 1966, among other things, removes the present limitation of \$2,500 for the administrative handling of tort claims with respect to all such claims accruing after January 18, 1967.

It would, therefore, be conducive to the prompt and orderly disposition of the Commission's business to amend the present delegation to the Chairman, as set forth in § 0.211(d) of the rules, by increasing the monetary limitation from \$2,500 to \$5,000. This amendment would, of course, be effective only with respect to tort claims accruing after January 18, 1967. Claims accruing prior to that date will continue to be subject to the statutory limitation of \$2,500 for administrative handling by the Commission through the Chairman.

Section 0.251(a) of the rules delegates to the General Counsel the responsibility for handling tort claims when the Chair-

man is absent. Since the Chairman's functions, in his absence, are generally carried on by an Acting Chairman, it would be more in accord with the Commission's organizational structure to delete the delegation to the General Counsel now set forth in § 0.251(a).

Authority for these amendments is contained in sections 4(i), 5(d), and 303(r) of the Communications Act of 1934, as amended. Because the amendments relate to agency management and organization, compliance with the notice and effective date provisions of section 4 of the Administrative Procedure Act is unnecessary.

In view of the foregoing: *It is ordered*, Effective September 9, 1966, that §§ 0.211(d) and 0.251(a) of the Commission's rules are amended as set forth below.

(Sec. 4, 48 Stat. 1066, as amended; 47 U.S.C. 154. Interpret or apply sec. 303, 48 Stat. 1082, as amended; sec. 5, 66 Stat. 713; 47 U.S.C. 303, 155.)

Released: September 2, 1966.

FEDERAL COMMUNICATIONS
COMMISSION,¹

[SEAL] BEN F. WAPLE,
Secretary.

1. In Part 0 of Chapter 1 of Title 47 of the Code of Federal Regulations, § 0.211(d) is revised to read as follows:
§ 0.211 Chairman.

(d) To act within the purview of the Federal Tort Claims Act, as amended, 28 U.S.C. § 2672, upon tort claims directed against the Commission where the amount of damages does not exceed \$5,000.

2. In Part 0 of Chapter 1 of Title 47 of the Code of Federal Regulations, § 0.251(a) is deleted and the word "reserved" is inserted in lieu thereof.

§ 0.251 Authority delegated.

(a) [Reserved]

[F.R. Doc. 66-9825; Filed, Sept. 7, 1966; 8:49 a.m.]

Title 49—TRANSPORTATION

Chapter I—Interstate Commerce Commission

SUBCHAPTER A—GENERAL RULES AND REGULATIONS

[Docket No. 3666; Order 71]

PARTS 71-79—EXPLOSIVES AND OTHER DANGEROUS ARTICLES

Notice of Postponement of Effective Date of Amendments

AUGUST 31, 1966.

The outstanding order (31 F.R. 9067, July 1, 1966) in the above-captioned proceeding not yet having become effective,

¹ Commissioners Bartley, Cox, and Wadsworth absent.

and an appropriate petition for reconsideration of amendments to §§ 73.22(a) and 73.315(b) having been filed by various parties to the proceeding, the mandatory effective date of the order only insofar as the amendments to §§ 73.22(a) and 73.315(b) are concerned is stayed pending disposition of the matter. Except as provided herein, the mandatory effective date of Order No. 71, dated June 8, 1966, remains as September 5, 1966.

By the Commission.

[SEAL] H. NEIL GARSON,
Secretary.

[F.R. Doc. 66-9848; Filed, Sept. 7, 1966; 8:51 a.m.]

Title 50—WILDLIFE AND FISHERIES

Chapter I—Bureau of Sport Fisheries and Wildlife, Fish and Wildlife Service, Department of the Interior

PART 32—HUNTING

Eufaula National Wildlife Refuge, Ala.

The following special regulation is issued and is effective on date of publication in the FEDERAL REGISTER.

§ 32.12 Special regulations; migratory game birds; for individual wildlife refuge areas.

ALABAMA

EUFULA NATIONAL WILDLIFE REFUGE

Public hunting of mourning doves on the Eufaula National Wildlife Refuge, Ala., is permitted only on the area designated by signs as open to hunting. This open area, comprising 180 acres, is delineated on a map available at the refuge headquarters and from the Regional Director, Bureau of Sport Fisheries and Wildlife, 809 Peachtree-Seventh Building, Atlanta, Ga. 30323. Hunting shall be in accordance with all applicable State and Federal regulations governing the hunting of mourning doves subject to the following special conditions:

(1) Hunting dates and hours are as follows: October 1 (12 noon until 5:30 p.m.); October 5 (12 noon until 5:25 p.m.); October 8 (12 noon until 5:20 p.m.); October 12 (12 noon until 5:15 p.m.); October 15 (12 noon until 5:10 p.m.).

(2) Each hunter must have on his person a validated refuge hunting permit. Hunters will be selected by an impartial drawing to be held September 17 on the refuge. Applications for the hunt will be accepted only during the period September 9-16 and may be submitted by mail or in person to the Refuge Manager Eufaula National Wildlife Refuge, Post Office Box 258, Eufaula, Ala. 36027.

(3) No hunters will be permitted within hunting areas before 11:45 a.m. each day. All hunters must be situated in hunting area before 1 p.m. each day.

(4) All firearms must be encased and/or unloaded when outside designated hunting area.

(5) Each hunter who successfully takes a limit of mourning doves must leave the hunting area immediately.

(6) Retrievers used by hunters shall be under the control of the owner at all times.

(7) All hunters must check in and out of the refuge at the designated checking station.

(8) All litter (paper, empty shell boxes, etc.) must be removed by individual hunters.

(9) Wounded or dead doves falling outside the hunting area may be recovered but firearms must be left inside hunting area.

(10) Vehicle parking will be limited to areas designated by refuge personnel.

The provisions of this special regulation supplement the regulations which govern hunting on wildlife refuge areas generally which are set forth in Title 50, Code of Federal Regulations, Part 32, and are effective through October 15, 1966.

WALTER A. GRESH,
Regional Director, Bureau of
Sport Fisheries and Wildlife.

AUGUST 30, 1966.

[F.R. Doc. 66-9795; Filed, Sept. 7, 1966; 8:47 a.m.]

PART 32—HUNTING

Havasu Lake National Wildlife Refuge, Arizona and California

The following special regulation is issued and is effective on date of publication in the FEDERAL REGISTER. The limited time ensuing from the date of the adoption of the Federal migratory game bird regulations to and including the establishment of State hunting seasons makes it impracticable to give public notice of proposed rule making.

§ 32.12 Special regulations; migratory game birds; for individual wildlife refuge areas.

ARIZONA AND CALIFORNIA

HAVASU LAKE NATIONAL WILDLIFE REFUGE

The public hunting of doves on the Havasu Lake National Wildlife Refuge, Arizona, and California, is permitted only on the area designated by signs as open to hunting. This open area, comprising 9,526 acres, is delineated on maps available at refuge headquarters, Needles, Calif., and from the Regional Director, Bureau of Sport Fisheries and Wildlife, Post Office Box 1306, Albuquerque, N. Mex. 87103. Hunting seasons are as follows: Arizona—white-winged doves only, from September 1 through September 25, 1966, inclusive; mourning doves, from September 1 through September 25, 1966, inclusive, and from December 9, 1966 through January 2, 1967, inclusive. California—doves, both species, from September 1 through October 2, 1966, inclusive, and from December 10 through December 18, 1966, inclusive. Hunting shall be in accordance with all appli-

cable State and Federal regulations covering the hunting of doves subject to the following special condition:

(1) Hunting is prohibited within one-fourth mile of any occupied dwelling or concession operation.

The provisions of this special regulation supplement the regulations which govern hunting on wildlife refuge areas generally which are set forth in Title 50, Code of Federal Regulations, Part 32, and are effective through January 2, 1967.

JOHN C. GATLIN,
Regional Director,
Albuquerque, N. Mex.

AUGUST 31, 1966.

[F.R. Doc. 66-9796; Filed, Sept. 7, 1966;
8:47 a.m.]

PART 32—HUNTING

Malheur National Wildlife Refuge, Oreg.

The following special regulations are issued and are effective on date of publication in the FEDERAL REGISTER. The limited time ensuing from the date of the adoption of the Federal migratory game bird regulations to and including the establishment of State hunting seasons makes it impracticable to give public notice of proposed rule making.

§ 32.12 Special regulations; migratory game birds; for individual wildlife refuge areas.

OREGON

MALHEUR NATIONAL WILDLIFE REFUGE

Public hunting of ducks, geese, coots and gallinules on the Malheur National Wildlife Refuge is permitted from October 8, 1966, through January 5, 1967, only on the area designated by signs as open to hunting. This open area, comprising 19,400 acres, is delineated on a map available at refuge headquarters and from the Regional Director, Bureau of Sport Fisheries and Wildlife, 730 Northeast Pacific Street, Portland, Oreg. 97208. Hunting shall be in accordance with all applicable State and Federal regulations subject to the following special conditions:

(1) Camping is permitted in designated areas only.

(2) A Federal permit is not required but hunters will report at such checking stations as may be established when entering or leaving the area.

The provisions of this special regulation supplement the regulations which govern hunting on wildlife refuge areas generally which are set forth in Title

50, Code of Federal Regulations, Part 32, and are effective through January 5, 1967.

PAUL T. QUICK,
Regional Director, Bureau of
Sport Fisheries and Wildlife.

AUGUST 26, 1966.

[F.R. Doc. 66-9798; Filed, Sept. 7, 1966;
8:47 a.m.]

PART 32—HUNTING

Erie National Wildlife Refuge, Pa.

The following special regulation is issued and is effective on date of publication in the FEDERAL REGISTER. The limited time ensuing from the date of the adoption of the Federal migratory game bird regulations to and including the establishment of State hunting seasons makes it impracticable to give public notice of proposed rule making.

§ 32.12 Special regulations; migratory game birds; for individual wildlife refuge areas.

PENNSYLVANIA

ERIE NATIONAL WILDLIFE REFUGE

The public hunting of ducks and coots on the Erie National Wildlife Refuge, Pa., is permitted only on the area designated by signs as open to hunting. This open area, comprising 1,792 acres, is delineated on maps available at refuge headquarters, Guys Mills, Pa., and from the Regional Director, Bureau of Sport Fisheries and Wildlife, U.S. Post Office and Courthouse, Boston, Mass. 02109.

Hunting shall be in accordance with all applicable State and Federal regulations covering the hunting of ducks and coots subject to the following special condition:

(1) The open season for hunting ducks and coots on the refuge extends from October 8, 1966, through October 15, 1966, inclusive, and from November 4, 1966, through November 26, 1966, inclusive.

The provisions of this special regulation supplement the regulations which govern hunting on wildlife areas generally, which are set forth in Title 50, Code of Federal Regulations, Part 32, and are effective through November 26, 1966.

EUGENE E. CRAWFORD,
Acting Regional Director, Bu-
reau of Sport Fisheries and
Wildlife, Boston, Mass.

AUGUST 24, 1966.

[F.R. Doc. 66-9799; Filed, Sept. 7, 1966;
8:47 a.m.]

PART 32—HUNTING

Crab Orchard National Wildlife Refuge, Ill.

The following special regulations are issued and are effective on date of publication in the FEDERAL REGISTER.

§ 32.32 Special regulations; big game; for individual wildlife refuge areas.

ILLINOIS

CRAB ORCHARD NATIONAL WILDLIFE REFUGE

The public hunting of white-tailed deer on the Crab Orchard National Wildlife Refuge, Ill., is permitted only on the area designated by signs as open to public hunting. These open areas, comprising 9,380 acres, are delineated on maps available at refuge headquarters and from the office of the Regional Director, Bureau of Sport Fisheries and Wildlife, 1006 West Lake Street, Minneapolis, Minn. 55408.

Hunting deer by use of bow and arrow is permitted from one-half hour before sunrise to one-half hour before sunset, c.s.t., from October 1 to November 15, 1966, inclusive, and from November 21 to December 31, 1966, inclusive, except that it shall be unlawful to take deer by bow and arrow devices from December 6 to December 12, 1966, inclusive. Taking of deer by bow and arrow shall be in accordance with all applicable State regulations in Article III, Administrative Order—1966.

Hunting deer by use of shotgun rifle slugs is permitted from 6:30 a.m. to 4:00 p.m., c.s.t., on November 18, 19, and 20, inclusive, and on December 9, 10, and 11, 1966, inclusive. Taking of deer by shotgun rifle slugs shall be in accordance with all applicable State regulations in Article II, Administrative Order—1966.

The provisions of this special regulation supplement the regulations which govern hunting on wildlife refuge areas generally, which are set forth in Title 50, Code of Federal Regulations, Part 32, and are effective through December 31, 1966.

LOYAL A. MEHRHOFF, Jr.,
Project Manager, Crab Orchard
National Wildlife Refuge,
Post Office Box J, Carterville,
Ill.

AUGUST 31, 1966.

[F.R. Doc. 66-9797; Filed, Sept. 7, 1966;
8:47 a.m.]

Proposed Rule Making

DEPARTMENT OF AGRICULTURE

Consumer and Marketing Service

[7 CFR Part 932]

OLIVES GROWN IN CALIFORNIA

Proposed Handling

Notice is hereby given that the Department is considering rules and regulations, hereinafter set forth, pursuant to the applicable provisions of the marketing agreement and Order No. 932 (7 CFR Part 932) regulating the handling of olives grown in California. This is a regulatory program effective under the Agricultural Marketing Agreement Act of 1937, as amended (7 U.S.C. 601-674).

The rules and regulations were proposed by the Olive Administrative Committee, established under the marketing agreement and order as the agency to administer the terms and provisions thereof. The rules and regulations are as follows:

§ 932.108 Noncanning olives.

"Noncanning olives" means those olives which, pursuant to the requirements of § 932.51(a)(2), are to be disposed of as other than canned ripe olives.

§ 932.129 Nomination procedure—producers.

Prior to March 16 of each odd-numbered year, the committee shall cause a nomination meeting to be held in each district for the purposes of obtaining nominees for producer members and alternate members for such district. Nominations for members and balloting thereon shall precede nomination and balloting for alternate members. The candidate for each position to be filled who receives the highest number of votes shall be the nominee for the position: *Provided*, That such candidate receives a majority of the ballots cast. If no candidate receives the majority of the ballots cast, the two candidates who received the highest number of votes shall participate in a run-off to determine which is the nominee.

§ 932.151 Incoming regulations.

(a) *Inspection stations.* Natural condition olives shall be sampled and size-graded only at an inspection station which shall be a plant of a handler, or other place where such olives are normally received, having facilities for sampling and size-grading such olives which are satisfactory to the Inspection Service and the committee: *Provided*, That upon prior application to, and approval by, the committee, a handler may have olives size-graded at an inspection station other than the one where the lot was sampled.

(b) *Lot identification.* Immediately upon receipt of each lot of natural con-

dition olives for which inspection is required, the handler shall complete Form OAC-2 "Lot Identification Tag," or such other lot identification form as may be approved by the committee, which shall contain at least the following: (1) Lot number; (2) date; (3) variety; and (4) number and type containers. Pending completion of size-grading of such lot, or the sampling of such lot if it is to be size-graded by sample, the handler shall maintain identity of such lot of olives with its corresponding lot identification tag.

(c) *Weighing.* Each lot of natural condition olives for which inspection is required shall be separately weighed to determine the net weight of olives. If the lot is to be size-graded by sample, the lot shall be weighed upon receipt by the handler. If the lot is to be size-graded by lot, the net weight shall be determined after size-grading by weighing all of the component parts resulting from the size-grading operations (including culls), and totaling such weights.

(d) *Incoming inspection.*—(1) *General.* The handler is responsible for the proper performance of all actions connected with the identification of lots of olives, the weighing of boxes or bins, the taking of samples, the size-grading of samples, and the furnishing of necessary personnel for the carrying out of such actions. All such actions shall be performed under the supervision of the Inspection Service.

(2) *Certification.* For each lot of olives that are size-graded, the handler shall complete Form OAC-3 "Report of Size-Grade of Natural Condition Olives," which shall contain at least the following: (i) Name of handler; (ii) name of producer; (iii) county of production; (iv) applicable lot number; (v) weight certificate number; (vi) net weight; (vii) number and type of containers; (viii) date received; (ix) time received; (x) method of size-grade determination (sample or lot); (xi) weight of sample, if size-graded by sample; and (xii) the quantity of olives in each size designation. The completed Form OAC-3 shall be furnished to the Inspection Service which shall certify thereon that the lot was size-graded as required by § 932.51 if in accordance with the facts.

(e) *Disposition of noncanning olives.*—(1) *Notification and inspection of noncanning olives.* Prior to disposition of noncanning olives the handler shall complete Form OAC-5 "Report of Non-canning Olive Inspection and Disposition," which shall contain the following: (i) Type and number of containers; (ii) type of olives (undersize or culls); (iii) net weight; (iv) variety; (v) outlet (green olives, olive oil, etc.); and (vi) consignee. Before disposition of such olives, the completed Form OAC-5 shall be furnished to the Inspection Service which shall inspect the olives for con-

formance with the information contained thereon, and, if correct, so certify in the space provided thereon.

(2) *Control and surveillance.* Noncanning olives that have been reported on Form OAC-5 and inspected by the Inspection Service shall, unless such olives are disposed of immediately after being inspected under supervision of the inspector, be identified by fixing to each bin or pallet of boxes an O.A.C. Control Card which may be obtained from the committee. Such olives shall be kept separate and apart from other olives in the handler's possession and shall be disposed of only in the outlet shown on Form OAC-5 and under the supervision of an inspector of the Inspection Service.

(3) *Time period for disposition.* All required disposition of noncanning olives shall be completed not later than September 30 of the crop year following the one in which the obligation is incurred or such later date that a handler may specify in a notice filed with the committee at least 15 days prior to September 15 of such subsequent crop year: *Provided*, That such notice shows that such handler has a sufficient quantity of olives held in storage to meet his obligation and such later date is not later than the date when he will have completed his disposition of olives of the crop year of obligation.

(4) *Olives not subject to incoming inspection.* Except as otherwise prescribed in § 932.51(b), any lot of olives to be used solely in the production of green olives or canned ripe olives of the "tree ripened" type shall not be subject to incoming inspection: *Provided*, That the applicable requirements of § 932.51(b) are met and the handler notifies the Inspection Service, in writing, that such lot is to be so used. Notice may be given by writing on the weight certificate "Lot to be used solely for use in the production of green olives or tree ripened olives" and a copy of such weight certificate given to the Inspection Service.

§ 932.152 Outgoing regulations.

(a) *Inspection stations.* Processed olives shall be sampled and graded only at an inspection station which shall be any olive processing plant having facilities for in-line inspection which are satisfactory to the Inspection Service and the committee.

(b) *Inspection.*—(1) *General.* Inspection of packaged olives for conformance with § 932.52 shall be in-line inspection. No handler shall perform the final processing operations which immediately precede the packaging of the olives unless an inspector is present when the olives are so processed. In addition, no handler shall pit olives until after such olives have been inspected for size prescribed in § 932.52(a)(2).

(2) *Pitting operations.* Pitted olives that meet the size requirements for packaging as canned whole ripe olives but

are held in containers prior to final processing shall be identified to the satisfaction of the Inspection Service and be held separate and apart from other olives until such time as they are submitted for in-line inspection prior to being packaged. Pitted olives which, prior to pitting, did not meet the size requirements for packaging as canned whole ripe olives but meet the applicable size requirements specified in § 932.52 for halved, sliced, chopped, or minced styles of canned ripe olives, shall be identified to the satisfaction of the Inspection Service and be held separate and apart from other olives until such time as they are submitted for in-line inspection prior to being packaged.

(c) *Certification.* (1) Each handler shall furnish daily to the Inspection Service a copy of a pack report for the preceding work day which shall contain at least the following: (i) The total number of cases of packaged olives; (ii) number of cans per case; (iii) can size; (iv) can code; (v) variety; (vi) fruit size; and (vii) style.

(2) The Inspection Service shall issue for each day's pack a signed certificate covering the quantities of such packaged olives which meet all applicable grade and size requirements. Each such certificate shall contain at least the following: (i) Date; (ii) place of inspection; (iii) name and address of handler; (iv) can code; (v) variety; (vi) fruit size; (vii) can size; (viii) style; (ix) total number of cases; (x) number of cans per case; and (xi) statement that packaged olives meet the effective minimum standards for canned ripe olives as warranted by the facts.

(d) *Olives which fail to meet grade and size requirements.* (1) Whenever any portion of a handler's daily pack of packaged olives fails to meet all applicable grade and size requirements, the Inspection Service shall issue a signed report covering such olives. Each such report shall contain at least the following: (i) Date; (ii) place of inspection; (iii) name and address of handlers; (iv) can code; (v) variety; (vi) fruit size; (vii) can size; (viii) style; (ix) total number of cases; (x) number of cans per case; and (xi) reason why the applicable requirements were not met.

(2) All such packaged olives shall be kept separate and apart from other packaged olives and shall be so identified by control cards or other means satisfactory to the Inspection Service and the committee that their identity is readily apparent. Such packaged olives may be reprocessed under supervision of the Inspection Service.

§ 932.154 Interhandler transfer.

(a) Except as provided in this section, Form OAC-6 "Report of Interhandler Transfer" shall be completed by the transferring handler on all lots of olives, whether natural condition, processed, not packaged, that are transferred from one handler to another. This form shall contain at least the following: (1) Name and address of both the transferring and receiving handler; (2) date of transfer; (3) condition (natural condition, processed, not packaged); (4) weight and number and size of each type of container; (5) variety; and (6) other identification (standard size, culls, style, etc.). Two copies of such completed form shall accompany the load to the receiving handler who shall certify on such copies the receipt of such olives and shall forward one of the certified copies to the committee within 10 days following receipt of such olives.

(b) Undersize or cull olives that are transferred from one handler to another and for which the transferring handler desires credit toward satisfaction of his obligation under § 932.51(a)(2) need only be accompanied by two copies of Form OAC-5 "Report of Noncanning Olives Inspection and Disposition": *Provided*, That such transfers are carried out under the supervision of the Inspection Service.

All persons who desire to submit written data, views, or arguments for consideration in connection with the proposal may file the same, in quadruplicate, with the Hearing Clerk, U.S. Department of Agriculture, Room 112, Administration Building, Washington, D.C. 20250, not later than the seventh day after publication of the notice in the FEDERAL REGISTER. All written submissions made pursuant to this notice will be made available for public inspection at the Office of the Hearing Clerk during regular business hours (7 CFR 1.27(b)).

Dated: September 2, 1966.

PAUL A. NICHOLSON,
Deputy Director, Fruit and Vegetable Division, Consumer and Marketing Service.

[F.R. Doc. 66-9845; Filed, Sept. 7, 1966; 8:51 a.m.]

FEDERAL AVIATION AGENCY

[14 CFR Part 71]

[Airspace Docket No. 66-EA-42]

TRANSITION AREA

Proposed Alteration

The Federal Aviation Agency is considering amending § 71.181 of Part 71 of the Federal Aviation Regulations so as to alter the Cleveland, Ohio, 700-foot floor transition area (31 F.R. 2171).

A new VOR instrument approach procedure to Strongsville Airport, Strongsville, Ohio, has been implemented. An alteration of the Cleveland, Ohio, 700-foot floor transition area will be required to include controlled airspace for Strongsville Airport IFR arrival and departure procedures.

Interested persons may submit such written data or views as they may desire. Communications should be submitted in triplicate to the Director, Eastern Region, Attention: Chief, Air Traffic Division, Federal Aviation Agency, Federal Building, John F. Kennedy International Airport, Jamaica, N.Y. 11430. All communications received within 30 days after publication in the FEDERAL REGISTER

will be considered before action is taken on the proposed amendment. No hearing is contemplated at this time, but arrangements for informal conferences with Federal Aviation Agency officials may be made by contacting the Chief, Airspace and Standards Branch, Eastern Region.

Any data or views presented during such conferences must also be submitted in writing in accordance with this notice in order to become part of the record for consideration. The proposal contained in this notice may be changed in the light of comments received.

The official docket will be available for examination by interested persons at the Office of the Regional Counsel, Federal Aviation Agency, Federal Building, John F. Kennedy International Airport, Jamaica, N.Y.

The Federal Aviation Agency, having completed a review of the airspace requirements for the terminal area of Cleveland, Ohio, proposes the airspace action hereinafter set forth:

Amend § 71.181 of Part 71 of the Federal Aviation Regulations so as to add in the description of the Cleveland, Ohio, 700-foot floor transition area following the phrase, "Burke-Lakefront 3-mile radius area to 10 miles NW of the airport;"; the phrase, "within a 5-mile radius of the center, 41°19'25" N., 81°51'50" W., of Strongsville Airport, Strongsville, Ohio, and within 2-miles each side of the Strongsville VOR 261° radial extending from the Strongsville Airport 5-mile radius area to 8 miles W of the VOR;".

This amendment is proposed under section 307(a) of the Federal Aviation Act of 1958 (72 Stat. 749; 49 U.S.C. 1348).

Issued in Jamaica, N.Y., on August 15, 1966.

WAYNE HENDERSHOT,
Deputy Director, Eastern Region.

[F.R. Doc. 66-9773; Filed, Sept. 7, 1966; 8:45 a.m.]

[14 CFR Part 71]

[Airspace Docket No. 66-EA-41]

TRANSITION AREA

Proposed Designation

The Federal Aviation Agency is considering amending § 71.181 of Part 71 of the Federal Aviation Regulations so as to designate a 700-foot floor transition area for Dunkirk, N.Y.

A new instrument approach procedure for Dunkirk Municipal Airport, Dunkirk, N.Y., has been authorized. A 700-foot floor transition area will be required to protect IFR arrival and departure procedures at Dunkirk Municipal Airport, Dunkirk, N.Y.

Interested persons may submit such written data or views as they may desire. Communications should be submitted in triplicate to the Director, Eastern Region, Attention: Chief, Air Traffic Division, Federal Aviation Agency, Federal Building, John F. Kennedy International Airport, Jamaica, N.Y. 11430. All communications received within 30 days after publication in the FEDERAL REGISTER

will be considered before action is taken on the proposed amendment. No hearing is contemplated at this time, but arrangements for informal conferences with Federal Aviation Agency officials may be made by contacting the Chief, Airspace and Standards Branch, Eastern Region.

Any data or views presented during such conferences must also be submitted in writing in accordance with this notice in order to become part of the record for consideration. The proposal contained in this notice may be changed in the light of comments received.

The official docket will be available for examination by interested persons at the Office of the Regional Counsel, Federal Aviation Agency, Federal Building, John F. Kennedy International Airport, Jamaica, N.Y.

The Federal Aviation Agency, having completed a review of the airspace requirements for the terminal area of Dunkirk, N.Y., proposes the airspace action hereinafter set forth:

Amend § 71.181 of Part 71 of the Federal Aviation Regulations so as to designate a 700-foot floor transition area for Dunkirk, N.Y., as follows:

DUNKIRK, N.Y.

That airspace extending upward from 700 feet above the surface within a 5-mile radius of the center, 42°29'35" N., 79°16'20" W., of Dunkirk Municipal Airport, Dunkirk, N.Y.; within 2 miles northwest and 5 miles southeast of the Dunkirk, N.Y. VOR 046° radial extending from the VOR to 12 miles NE of the VOR; and within 2 miles each side of the Runway 15 centerline extended from the 5-mile radius area to 10 miles southeast of the lift-off end of the runway.

This amendment is proposed under section 307(a) of the Federal Aviation Act of 1958 (72 Stat. 749; 49 U.S.C. 1348).

Issued in Jamaica, N.Y., on August 19, 1966.

WAYNE HENDERSHOT,
Deputy Director, Eastern Region.

[F.R. Doc. 66-9774; Filed, Sept. 7, 1966;
8:45 a.m.]

[14 CFR Part 71]

[Airspace Docket No. 66-EA-33]

TRANSITION AREA

Proposed Alteration

The Federal Aviation Agency is considering amending § 71.181 of Part 71 of the Federal Aviation Regulations so as to alter the Jefferson, Ohio, 700-foot floor transition area (31 F.R. 2205).

A new VOR instrument approach procedure to Germack Airport, Geneva, Ohio, will require additional 700-foot floor transition area airspace. Because of the proximity between Ashtabula-Jefferson and Germack Airports the requirements for Germack Airport can be included in the Jefferson, Ohio, transition area description.

Interested persons may submit such written data or views as they may desire. Communications should be submitted in triplicate to the Director, Eastern Region, Attention: Chief, Air

Traffic Division, Federal Aviation Agency, Federal Building, John F. Kennedy International Airport, Jamaica, N.Y. 11430. All communications received within 30 days after publication in the FEDERAL REGISTER will be considered before action is taken on the proposed amendment. No hearing is contemplated at this time, but arrangements may be made for informal conferences with Federal Aviation Agency officials by contacting the Chief, Airspace and Standards Branch, Eastern Region.

Any data or views presented during such conferences must also be submitted in writing in accordance with this notice in order to become part of the record for consideration. The proposal contained in this notice may be changed in the light of comments received.

The official docket will be available for examination by interested persons at the Office of the Regional Counsel, Federal Aviation Agency, Federal Building, John F. Kennedy International Airport, Jamaica, N.Y.

The Federal Aviation Agency, having completed a review of the airspace requirements for the terminal area of Jefferson, Ohio, proposes the airspace action hereinafter set forth:

Amend § 71.181 of Part 71 of the Federal Aviation Regulations so as to delete the description of the Jefferson, Ohio, 700-foot floor transition area and insert in lieu thereof the following:

JEFFERSON, OHIO

That airspace extending upward from 700 feet above the surface within a 5-mile radius of the center, 41°45'15" N., 80°46'25" W., of the Ashtabula-Jefferson Airport, Jefferson, Ohio; and within 2 miles each side of the Jefferson, Ohio VOR 061° radial extending from the 5-mile radius area to 8 miles northeast of the VOR and within a 5-mile radius of the center, 41°46'40" N., 80°54'15" W., of Germack Airport, Geneva, Ohio.

This amendment is proposed under section 307(a) of the Federal Aviation Act of 1958 (72 Stat. 749; 49 U.S.C. 1348).

Issued in Jamaica, N.Y., on August 19, 1966.

WAYNE HENDERSHOT,
Deputy Director, Eastern Region.

[F.R. Doc. 66-9775; Filed, Sept. 7, 1966;
8:45 a.m.]

[14 CFR Part 71]

[Airspace Docket No. 66-AL-1]

CONTROL AREA EXTENSION, CONTROL ZONE, AND TRANSITION AREA

Proposed Revocation, Alteration, and Designation

The Federal Aviation Agency is considering amendments to Part 71 of the Federal Aviation Regulations that would alter the controlled airspace in the vicinity of Cold Bay, Alaska, as follows:

1. The Cold Bay control area extension would be revoked.

2. The Cold Bay control zone would be redesignated as that airspace within a 5-mile radius of Cold Bay, Alaska, Airport

(latitude 55°12' N., longitude 162°43' W.); within 2 miles each side of the Cold Bay VOR 335° True radial and 2 miles each side of the Cold Bay ILS localizer north course, extending from the 5-mile radius zone to 12 miles north of the Cold Bay radio range.

3. The Cold Bay transition area would be designated as that airspace extending upward from 700 feet above the surface within 2 miles each side of the 041° True bearing from the Cold Bay radio range, extending from the radio range to 6 miles northeast of the radio range, and within 2 miles each side of the 263° True bearing from the Cold Bay radio range, extending from the radio range to 6 miles west of the radio range; and that airspace extending upward from 1,200 feet above the surface within 5 miles southeast of the 041° True bearing from the Cold Bay radio range, extending from the radio range to 18 miles northeast of the radio range; within 5 miles south of the 263° True bearing from the Cold Bay radio range, extending from the radio range to 18 miles west of the radio range; and within the arc of an 18-mile radius circle centered on the Cold Bay radio range, extending clockwise from the 263° True bearing to the 041° True bearing from the radio range.

The amended control zone and proposed transition area would provide controlled airspace for aircraft executing prescribed instrument approach and departure procedures for the Cold Bay Airport. The Cold Bay control area extension would be revoked since it would no longer be required for air traffic control purposes.

As parts of these proposals relate to the navigable airspace outside the United States, this notice is submitted in consonance with the ICAO International Standards and Recommended Practices.

Applicability of International Standards and Recommended Practices, by the Air Traffic Service, FAA, in areas outside domestic airspace of the United States is governed by Article 12 and Annex 11 to the Convention on International Civil Aviation (ICAO), which pertains to the establishment of air navigation facilities and services necessary to promoting the safe, orderly and expeditious flow of civil air traffic. Its purpose is to insure that civil flying on international air routes is carried out under uniform conditions designed to improve the safety and efficiency of air operations.

The International Standards and Recommended Practices in Annex 11 apply in those parts of the airspace under the jurisdiction of a contracting state, derived from ICAO, wherein air traffic services are provided and also whenever a contracting state accepts the responsibility of providing air traffic services over high seas or in airspace of undetermined sovereignty. A contracting state accepting such responsibilities may apply the International Standards and Recommended Practices to civil aircraft in a manner consistent with that adopted for airspace under its domestic jurisdiction.

In accordance with Article 3 of the Convention on International Civil Aviation, Chicago, 1944, state aircraft are exempt from the provisions of Annex 11 and its Standards and Recommended Practices. As a contracting state, the United States agreed by Article 3(d) that its state aircraft will be operated in international airspace with due regard for the safety of civil aircraft.

Since this action involves, in part, the designation of navigable airspace outside the United States, the Administrator has consulted with the Secretary of State and the Secretary of Defense in accordance with the provisions of Executive Order 10854.

Interested persons may participate in the proposed rule making by submitting such written data, views, or arguments as they may desire. Communications should identify the airspace docket number and be submitted in triplicate to the Director, Alaskan Region, Attention: Chief, Air Traffic Division, Federal Aviation Agency, 632 Sixth Avenue, Anchorage, Alaska 99501. All communications received within 30 days after publication of this notice in the FEDERAL REGISTER will be considered before action is taken on the proposed amendments. The proposals contained in this notice may be changed in the light of comments received.

An official docket will be available for examination by interested persons at the Federal Aviation Agency, Office of the General Counsel, Attention: Rules Docket, 800 Independence Avenue SW., Washington, D.C. 20553. An informal docket also will be available for examination at the office of the Regional Air Traffic Division Chief.

These amendments are proposed under the authority of sections 307(a) and 1110 of the Federal Aviation Act of 1958 (49 U.S.C. 1348, 1510) and Executive Order 10854 (24 F.R. 9565).

Issued in Washington, D.C., on August 30, 1966.

H. B. HELSTROM,
Chief, Airspace and Air
Traffic Rules Division.

[F.R. Doc. 66-9776; Filed, Sept. 7, 1966;
8:45 a.m.]

[14 CFR Part 71]

[Airspace Docket No. 66-SO-41]

CONTROLLED AIRSPACE

Proposed Alteration

The Federal Aviation Agency is considering an amendment to Part 71 of the Federal Aviation Regulations which would alter VOR Federal Airway No. 7 between Cross City, Fla., and Dothan, Ala.

Interested persons may participate in the proposed rule making by submitting such written data, views, or arguments as they may desire. Communications should identify the airspace docket number and be submitted in triplicate to the Director, Southern Region, Attention: Chief, Air Traffic Division, Federal Aviation Agency, Post Office Box 20636, Atlanta, Ga. 30320. All communications received within 45 days after publication of this notice in the FEDERAL REGISTER will be considered before action is taken on the proposed amendments. The proposals contained in this notice may be changed in the light of comments received.

An official docket will be available for examination by interested persons at the Federal Aviation Agency, Office of the General Counsel, Attention: Rules Docket, 800 Independence Avenue SW., Washington, D.C. 20553. An informal docket also will be available for examination at the office of the Regional Air Traffic Division Chief.

Victor 7 is presently designated in part from Cross City, Fla., via INT of Cross City 311° and Tallahassee, Fla., 137° radials; Tallahassee; Dothan, Ala., including a W alternate from Cross City to Dothan via INT of Cross City 287° and Marianna, Fla., 141° radials, and Marianna, excluding the airspace between the main and the W alternate. On April 12, 1966, Airspace Docket No. 65-SO-89 was published as a notice of proposed rule making in the FEDERAL REGISTER (31 F.R. 5665), proposing the designation of a floor of 1,200 feet AGL on Federal Airway No. 7 and its W alternate between Cross City and Dothan. Airspace Docket No. 65-SO-89 does not propose to alter the exclusion from Federal Airway No. 7 of the airspace between the main airway and the W alternate. It is proposed herein, however, to remove this exclusion to provide controlled airspace between the main airway and the W alternate for radar vectoring. Such action would permit more effective utilization of available radar and would permit the transitioning of flights between airways bordering this area.

This amendment is proposed under the authority of section 307(a) of the Federal Aviation Act of 1958 (49 U.S.C. 1348).

Issued in Washington, D.C., on August 30, 1966.

H. B. HELSTROM,
Chief, Airspace and Air
Traffic Rules Division.

[F.R. Doc. 66-9777; Filed, Sept. 7, 1966;
8:45 a.m.]

[14 CFR Part 71]

[Airspace Docket No. 66-SO-42]

CONTROLLED AIRSPACE

Proposed Alteration

The Federal Aviation Agency is considering an amendment to Part 71 of the Federal Aviation Regulations which would alter VOR Federal Airway No. 18 between Augusta, Ga., and Charleston, S.C.

Interested persons may participate in the proposed rule making by submitting such written data, views, or arguments as they may desire. Communications should identify the airspace docket number and be submitted in triplicate to the Director, Southern Region, Attention: Chief, Air Traffic Division, Federal Aviation Agency, Post Office Box 20636, Atlanta, Ga. 30320. All communications received within 45 days after publication of this notice in the FEDERAL REGISTER will be considered before action is taken on the proposed amendments. The proposals contained in this notice may be changed in the light of comments received.

An official docket will be available for examination by interested persons at the Federal Aviation Agency, Office of the General Counsel, Attention: Rules Docket, 800 Independence Avenue SW., Washington, D.C. 20553. An informal docket will also be available for examination at the office of the Regional Air Traffic Division Chief.

Federal Airway No. 18 is presently designated in part from Augusta, Ga., via INT of Augusta 097° and Charleston, S.C., 300° radials; Charleston, including an S alternate from Augusta to Charleston via INT of Augusta 157° and Allendale, S.C., 262° radials and Allendale, excluding the airspace between the main and this alternate airway. On April 12, 1966, Airspace Docket No. 65-SO-89 was published as a notice of proposed rule making in the FEDERAL REGISTER (31 F.R. 5665), and proposes designation of a 1,200 feet AGL floor on Federal Airway No. 18 between Augusta and Charleston. Airspace Docket No. 65-SO-89 does not propose to alter the exclusion from Federal Airway No. 18 of the airspace between the main airway and the S alternate. It is proposed herein, however, to alter this exclusion by excluding only the airspace within Restricted Area R-6004. Such action is required to provide controlled airspace to permit more effective utilization of available radar for vectoring flights between airways bordering this area.

This amendment is proposed under the authority of section 307(a) of the Federal Aviation Act of 1958 (49 U.S.C. 1348).

Issued in Washington, D.C., on August 30, 1966.

H. B. HELSTROM,
Chief, Airspace and Air
Traffic Rules Division.

[F.R. Doc. 66-9778; Filed, Sept. 7, 1966;
8:45 a.m.]

FEDERAL COMMUNICATIONS COMMISSION

[47 CFR Part 73]

[Docket No. 16762]

FM BROADCAST STATIONS

Table of Assignments; Order Extending Time for Filing Reply Comments

In the matter of amendment of § 73.202 Table of assignments, FM broadcast stations (Reedsburg, Wis., Portland, Ind., Brazil, Ind., Winner, S. Dak., Ardmore, Okla., Hutchinson and St. Cloud, Minn., Gonzales, Tex., Cullman, Ala., Deland,

Winter Park, Live Oak, and Ocala, Fla., Rockford, Ill., Adrian and Jackson, Mich., and Corinth, Miss.); Docket No. 16762, RM-969, RM-984, RM-967, RM-971, RM-974, RM-977, RM-978, RM-983, RM-988, RM-987, RM-989, RM-990.

1. On July 14, 1966, the Commission issued a notice of proposed rulemaking (FCC 66-637) in the above-entitled matter inviting comments on a number of changes in the FM Table of Assignments, including changes in the communities of Adrian and Jackson, Mich., RM-989. The time for filing comments was specified as August 15, 1966, and for filing reply comments August 31, 1966. On August 26, 1966, the Commission received from Gerity Broadcasting Co., petitioner in RM-989, a request for extension of

time in which to file reply comments from August 31, 1966, to September 15, 1966.

2. In its request for an extension of time to file reply comments, petitioner states that it requires the additional time in order to consider and prepare an appropriate reply comment to the comments and extensive counter-proposal filed by Washtenaw Broadcasting Co. in RM-989. Washtenaw Broadcasting Co. has not filed an objection. We have considered the request and are of the view that the extension is warranted in this case and that it will serve the public interest.

3. *Accordingly, it is ordered*, On this 31st day of August, 1966, that the request of Gerity Broadcasting Co. for an extension

of time to file reply comments in RM-989 to September 15, 1966, is granted. The extension of time granted herein pertains solely to RM-989.

4. This action is taken pursuant to the authority contained in sections 4(i), 5(d)(1), and 303(r) of the Communications Act of 1934, as amended, and § 0.281(d)(8) of the Commission's rules and regulations.

Released: September 2, 1966.

FEDERAL COMMUNICATIONS
COMMISSION,
[SEAL] BEN F. WAPLE,
Secretary.

[F.R. Doc. 66-9826; Filed, Sept. 7, 1966;
8:49 a.m.]

Notices

DEPARTMENT OF THE TREASURY

Coast Guard

[CGFR 66-43]

EQUIPMENT, INSTALLATIONS, OR MATERIALS

Approval and Termination of Approval Notice

1. Various items of lifesaving, fire-fighting and miscellaneous equipment, installations and materials used on vessels subject to Coast Guard inspection or on certain motorboats and other pleasure craft are required by various laws and regulations in 46 CFR Chapter I to be of types approved by the Commandant, U.S. Coast Guard. The purpose of this document is to notify all concerned that certain approvals were granted or terminated, as described in this document during the period from March 16, 1965, to March 16, 1966 (List Nos. 3-66, 4-66, 5-66, 6-66, 7-66, 8-66, 9-66, 10-66, and 11-66). These actions were taken in accordance with the procedures set forth in 46 CFR 2.75-1 to 2.75-50, inclusive. For certain types of equipment, installation and materials, specifications have been prescribed by the Commandant and are published in 46 CFR Parts 160 to 164, inclusive (Subchapter Q—Specifications).

2. The statutory authorities for granting approvals of equipment and the delegations of authority to the Commandant, U.S. Coast Guard, are set forth with the specific specifications governing the item and are set forth in 46 CFR Parts 160 to 164, inclusive (Subchapter Q—Specifications). The general authorities regarding approvals are set forth in sections 367, 375, 390b, 416, 481, 489, 526p and 1333 in Title 46, U.S. Code, section 1333 in Title 43, U.S. Code and section 198 in Title 50, U.S. Code while the implementing regulations requiring such equipment are in 46 CFR Chapter I or 3 CFR Chapter I. The delegations of authority for the Commandant, U.S. Coast Guard to take appropriate actions with respect to approvals are set forth in section 632 of Title 14, U.S. Code, Treasury Department Order 120 dated July 31, 1950, 15 F.R. 6521, and other Treasury Department orders issued since that date with respect to performance of functions under various laws dealing with specific subjects. These delegations are also listed with the implementing regulations in 46 CFR Chapter I or 33 CFR Chapter I.

3. In Part I of this document are listed the approvals which shall be in effect for a period of 5 years from the dates issued, unless sooner canceled or suspended by proper authority.

4. In Part II of this document are listed the approvals which have been terminated. Notwithstanding this ter-

mination of approvals of the items as listed in Part II, such equipment may be used so long as it is in good and serviceable condition.

PART I—APPROVALS OF EQUIPMENT, INSTALLATIONS, OR MATERIALS

LIFE PRESERVERS, KAPOK, ADULT AND CHILD (JACKET TYPE) MODELS 3 AND 5

Approval No. 160.002/56/1, Model 5, child kapok life preserver, U.S.C.G. Specification Subpart 160.002, manufactured by International Cushion Co., 1110 Northeast Eighth Avenue, Fort Lauderdale, Fla. 33311, effective January 21, 1966. (It supersedes Approval No. 160.002/56/1 dated Nov. 4, 1963, to show correction.)

WINCHES, LIFEBOAT

Approval No. 160.015/79/0, Type 55-G lifeboat winch, approval is limited to technical components and for a maximum working load of 11,120 pounds pull at the drums (5,560 pounds per fall) identified by general assembly dwg. No. 1013-2R, dated April 1958, manufactured by Marine Safety Equipment Corp., Foot of Paynter's Road, Farmingdale, N.J. 07727, effective February 28, 1966. (It is an extension of Approval No. 160.015/79/0 dated Mar. 3, 1961.)

Approval No. 160.015/88/0, Type CGB-135 MV lifeboat winch, approval is limited to mechanical components only, and for a maximum working load of 13,500 pounds pull at the drums (6,750 pounds per fall) identified by general arrangement dwg. W-80489 (Rev. A), dated June 10, 1963, and drawing list dated October 22, 1965, manufactured by General Bronze Corp., Steel Weldments Division, Bedford Park, Ill., for Welin Davit and Boat Division of Continental Copper & Steel Industries, Inc., Perth Amboy, N.J. 08861, effective January 27, 1966.

LAMPS, SAFETY, FLAME

Approval No. 160.016/2/2, Koehler Model 289-1A, naphtha burning, key lock, flame safety lamp, dwg. Nos. 289-1A dated November 10, 1960, and 257-30A dated December 2, 1947, manufactured by Koehler Manufacturing Co., Marlboro, Mass. 01752, effective March 15, 1966. (It is an extension of Approval No. 160.016/2/2 dated Mar. 21, 1961.)

SEA ANCHORS, LIFEBOAT

Approval No. 160.019/12/0, sea anchor, U.S.C.G. dwg. No. MMI-562, and specification dated November 1, 1943, revised August 24, 1944, and company specification dated February 28, 1961, manufactured by Jacksonville Ship Chandlery & Awning Co., 835 East Bay Street, Post Office Box 395, Jacksonville, Fla. 32202, effective February 23, 1966. (It is an extension of Approval No. 160.019/12/0 dated Mar. 10, 1961.)

LIFEBOATS

Approval No. 160.027/69/0, 7.0' x 9.0' x 4" rectangular, laminated fabric-covered, unicellular plastic foam buoyant mat lifeboat; 15-person capacity; Vorenkamp dwg. No. 1, Rev. 1 dated January 2, 1966, and specifications dated January 4, 1966, manufactured by Salerco, Inc., c/o Pan Air Corp., Post Office Box 26425, New Orleans, La., effective January 21, 1966.

LINE-THROWING APPLIANCE, SHOULDER GUN TYPE (AND EQUIPMENT)

Approval No. 160.031/4/0, Bridger 45/70 Model N shoulder-gun type line-throwing appliance, assembly dwg. No. A-604, dated October 28, 1950, manufactured by Naval Co., Old Easton Highway, Doylestown, Pa. 18901, effective February 23, 1966. (It is an extension of Approval No. 160.031/4/0 dated Mar. 21, 1961.)

DAVITS

Approval No. 160.032/160/1, gravity davit, Type 30-22, approved for a maximum working load of 22,240 pounds per set (11,120 pounds per arm) using 2-part falls, identified by general arrangement dwg. No. 3015-1E, dated August 15, 1958, and drawing list dated February 17, 1966, manufactured by Marine Safety Equipment Corp., Foot of Paynter's Road, Farmingdale, N.J. 07727, effective March 2, 1966. (It supersedes Approval No. 160.032/160/0 dated Mar. 2, 1961, to show change in design.)

Approval No. 160.032/168/0, Type G-105S, gravity davit (formerly Type 60-75), approved for a maximum working load of 22,000 pounds per set (11,000 pounds per arm), using 2-part falls; identified by general arrangement dwg. D-80661 (Rev. C) dated October 9, 1964, or general arrangement dwg. D-80663 (Rev. B) dated September 2, 1964; approval limited to installation on following vessels:

Dwg. D-80661 (Rev. C) Avondale Shipyards, Inc.: Hull Nos. 1052, 1053, 1054, 1055; 1066, 1067, 1068, and 1069.

Dwg. D-80663 (Rev. B) Sun Shipbuilding & Dry Dock Co.: Hull Nos. 635, 636, 637, and 638.

manufactured by General Bronze Corp., Steel Weldments Division, Bedford Park, Ill., for Welin Davit and Boat Division of Continental Copper & Steel Industries, Inc., Perth Amboy, N.J. 08861, effective January 27, 1966. (Does not meet 1960 SOLAS strength requirement for a 10 degree trim of the vessel.)

LIFEBOATS

Approval No. 160.035/20/5, 24.0' x 8.0' x 3.5' steel, oar-propelled lifeboat, 40-person capacity, identified by general arrangement dwg. No. G-2440, Rev. A dated 15 October 1965, manufactured by C. C. Galbraith & Son, Inc., Maple Place and

Manchester Avenue, Post Office Box 185, Keyport, N.J. 07735, effective March 14, 1966. (It supersedes Approval No. 160.035/20/4 dated July 15, 1965.)

Approval No. 160.035/102/6, 24.0' x 8.0' x 3.5' steel, motor-propelled lifeboat without radio cabin or searchlight (Class 1), 37-person capacity, identified by general arrangement and construction dwg. No. 55-R-2425 dated April 21, 1955, and revised November 8, 1965, manufactured by Lane Lifeboat & Davit Corp., 150 Sullivan Street, Brooklyn, N.Y. 11231, effective March 14, 1966. (It supersedes Approval No. 160.035/102/5 dated July 9, 1965.)

Approval No. 160.035/110/2, 28.0' x 9.79' x 4.13' steel, motor-propelled lifeboat without radio cabin or searchlight (Class 1), 62-person capacity, identified by general arrangement dwg. No. 28-001-01 dated September 11, 1946, and revised January 30, 1966, manufactured by Lane Lifeboat & Davit Corp., 150 Sullivan Street, Brooklyn, N.Y. 11231, effective February 9, 1966. (It supersedes Approval No. 160.035/110/1 dated June 8, 1961.)

Approval No. 160.035/281/2, 26.0' x 9.0' x 3.83' steel, oar-propelled lifeboat, 53-person capacity, identified by general arrangement dwg. No. 26-9S dated December 1, 1965, manufactured by Marine Safety Equipment Corp., Foot of Paynter's Road, Farmingdale, N.J. 07727, effective January 21, 1966. (It reinstates and supersedes Approval No. 160.035/281/1 which was terminated July 11, 1965.)

Approval No. 160.035/447/0, 26.0' x 9.0' x 3.96' aluminum, motor-propelled Class 1 lifeboat, 53-person capacity, identified by general arrangement dwg. No. 28-1G, Rev. A dated January 19, 1966, manufactured by Marine Safety Equipment Corp., Foot of Paynter's Road, Farmingdale, N.J. 07727, effective February 9, 1966.

JACKKNIFE (WITH CAN OPENER)

Approval No. 160.043/1/0, Type S702 jackknife (with can opener), dwg. No. 1160 dated August 11, 1950, manufactured by Camillus Cutlery Co., Camillus, N.Y. 13031, effective January 18, 1966. (It is an extension of Approval No. 160.043/1/0 dated Jan. 27, 1961.)

PUMPS, BILGE, LIFEBOAT

Approval No. 160.044/11/1, size No. 2 lifeboat bilge pump, identified by master dwg. No. E-2450, Rev. B dated December 15, 1959, manufactured by Blackmer Bilge Pump, Grand Rapids, Mich., effective March 16, 1965. (It is an extension of Approval No. 160.044/11/1 dated Mar. 16, 1960.)

BUOYANT VESTS, KAPOK OR FIBROUS GLASS, ADULT AND CHILD

NOTE: Approved for use on motorboats of Classes A, 1, or 2 not carrying passengers for hire

Approval No. 160.047/493/0, Type Model AK-1, adult kapok buoyant vest, U.S.C.G. Specification Subpart 160.047, manufactured by Liberty Cork Co., Inc., 123 Whitehead Avenue, South River, N.J. 08882, effective January 31, 1966. (It is

an extension of Approval No. 160.047/493/0 dated Feb. 6, 1961.)

Approval No. 160.047/494/0, Type I, Model CKM-1, child kapok buoyant vest, U.S.C.G. Specification Subpart 160.047, manufactured by Liberty Cork Co., Inc., 123 Whitehead Avenue, South River, N.J. 08882, effective January 31, 1966. (It is an extension of Approval No. 160.047/494/0 dated Feb. 6, 1961.)

Approval No. 160.047/495/0, Type I, Model CKS-1, child kapok buoyant vest, U.S.C.G. Specification Subpart 160.047, manufactured by Liberty Cork Co., Inc., 123 Whitehead Avenue, South River, N.J. 08882, effective January 31, 1966. (It is an extension of Approval No. 160.047/495/0 dated Feb. 6, 1961.)

Approval No. 160.047/595/0, Model LG-191 "Super-Buoyant" adult kapok buoyant vest, drawing No. 1 and bill of materials dated December 3, 1965, manufactured by Stearns Manufacturing Co., Division Street at 30th, St. Cloud, Minn. 56301, effective February 18, 1966.

BUOYANT CUSHIONS, KAPOK OR FIBROUS GLASS

Approval No. 160.048/5/1, special approval for 14" x 17" x 2" rectangular ribbed-typed kapok buoyant cushions, 21-oz. kapok, dwg. No. C-31 dated September 15, 1965, and bill of materials dated December 29, 1965, manufactured by the American Pad & Textile Co., Tapatco Division, Fairfield, Calif. 94534, effective January 14, 1966. (It supersedes Approval No. 160.048/5/0 dated June 14, 1963, to show change in specifications.)

Approval No. 160.048/46/0, group approval for rectangular and trapezoidal kapok buoyant cushions, U.S.C.G. Specification Subpart 160.048, sizes and weights of kapok filling to be as per Table 160.048-4(c) (1) (i), manufactured by Billy Boy Products Division, Crotty Corp., Quincy, Mich. 49082, Plant: Montgomery, Mich., effective February 28, 1966. (It is an extension of Approval No. 160.048/46/0 dated Mar. 6, 1961.)

Approval No. 160.048/57/0, group approval for rectangular and trapezoidal kapok buoyant cushions, U.S.C.G. Specification Subpart 160.048, sizes and weights of kapok filling to be as per Table 160.048-4(c) (1) (i), manufactured by Crawford Manufacturing Co., Inc., 3d and Decatur Streets, Richmond, Va. 23212, and 12th and Graham Streets, Emporia, Kans. 66801, effective February 23, 1966. (It is an extension of Approval No. 160.048/57/0 dated Mar. 8, 1961.)

Approval No. 160.048/58/0, group approval for rectangular and trapezoidal kapok buoyant cushions, U.S.C.G. Specification Subpart 160.048, sizes and weights of kapok filling to be as per Table 160.048-4(c) (1) (i), manufactured by Atlantic-Pacific Manufacturing Corp., 124 Atlantic Avenue, Brooklyn, N.Y., for James Bliss & Co., Inc., 342 Atlantic Avenue, Boston, Mass. 02210, effective March 6, 1966. (It is an extension of Approval No. 160.048/58/0 dated Mar. 6, 1961.)

Approval No. 160.048/226/1, special approval for 14" x 17" x 2" rectangular ribbed-type kapok buoyant cushions, 21-oz. kapok, dwg. No. 160.048-7(c) dated

January 6, 1966, manufactured by Buddy Schoellkopf Products Inc., 148 Fordyce Street, Dallas, Tex. 75207, Plant: Mineola, Tex., effective March 7, 1966. (It supersedes Approval No. 160.048/226/0 dated Nov. 7, 1963, to show change in specifications and in address.)

Approval No. 160.048/241/0, special approval for 13.25" x 17" x 2" rectangular ribbed-type kapok buoyant cushions, 20-oz. kapok, dwg. No. 5001, Rev. 1 dated October 30, 1965, and bill of materials dated October 30, 1965, manufactured by Boyce Manufacturing Co., Acworth, Ga. 30101, effective February 8, 1966. (It supersedes Approval No. 160.048/241/0 dated Jan. 14, 1966, to show correction.)

BUOYANT CUSHIONS, UNICELLULAR PLASTIC FOAM

NOTE: Approved for use on motorboats of Classes A, 1, or 2 not carrying passengers for hire

Approval No. 160.049/31/5, special approval for 20" x 14" x 2 3/4" rectangular vinyl-dip-coated unicellular plastic foam buoyant cushions, dwg. No. 3, dated September 30, 1965, manufactured by Jones & Yandell Division, American Tent Co., Post Office Box 270, Canton, Miss. 39046, effective March 7, 1966. (It supersedes Approval No. 160.049/31/4 dated Sept. 14, 1962, to show change in specifications.)

BUOYANT VESTS, UNICELLULAR PLASTIC FOAM, ADULT AND CHILD

NOTE: Approved for use on motorboats of Classes A, 1, or 2 not carrying passengers for hire

Approval No. 160.052/101/2, Type II, Model JV-L, adult unicellular plastic foam buoyant vest, dwg. JV-L No. 3, dated October 1, 1962, and bill of materials dated January 21, 1966, manufactured by Jones & Yandell Division, American Tent Co., Post Office Box 270, Canton, Miss. 39046, effective March 10, 1966. (It supersedes Approval No. 160.052/101/2 dated Oct. 12, 1962, to show change in specifications.)

Approval No. 160.052/102/2, Type II, Model JV-M, child medium unicellular plastic foam buoyant vest, dwg. JV-M No. 3 dated September 29, 1962, and bill of materials dated January 21, 1966, manufactured by Jones & Yandell Division, American Tent Co., Post Office Box 270, Canton, Miss. 39046, effective March 10, 1966. (It supersedes Approval No. 160.052/102/2 dated Oct. 12, 1962, to show change in specifications.)

Approval No. 160.052/103/2, Type II, Model JV-S, child small unicellular plastic foam buoyant vest, dwg. JV-S No. 3 dated September 29, 1962, and bill of materials dated January 21, 1966, manufactured by Jones & Yandell Division, American Tent Co., Post Office Box 270, Canton, Miss. 39046, effective March 10, 1966. (It supersedes Approval No. 160.052/103/2 dated Oct. 12, 1962, to show change in specifications.)

Approval No. 160.052/131/1, Type II, Model "A", adult unicellular plastic foam buoyant vest, dwg. Nos. 11 and 12 dated March 3, 1961, Rev. 1 dated June 1, 1963, and bill of materials dated September 29, 1965, manufactured by Craw-

ford Manufacturing Co., Inc., 3d and Decatur Streets, Richmond, Va. 23212; 12th and Graham Streets, Emporia, Kans. 66801; and 5550 Paramount Boulevard, Long Beach, Calif. 90805, effective March 16, 1966. (It supersedes Approval No. 160.052/131/1 dated Nov. 3, 1965, to show change in address.)

Approval No. 160.052/132/1, Type II, Model "M", child medium unicellular plastic foam buoyant vest, dwg. Nos. 11 and 13 dated March 3, 1961, Rev. 1 dated June 1, 1963, and bill of materials dated September 29, 1965, manufactured by Crawford Manufacturing Co., Inc., 3d and Decatur Streets, Richmond, Va. 23212; 12th and Graham Streets, Emporia, Kans. 66801; and 5550 Paramount Boulevard, Long Beach, Calif. 90805, effective March 16, 1966. (It supersedes Approval No. 160.052/132/1 dated Nov. 3, 1965, to show change in address.)

Approval No. 160.052/133/1, Type II, Model "S", child small unicellular plastic foam buoyant vest, dwg. Nos. 11 and 14 dated March 3, 1961, Rev. 1 dated June 1, 1963, and bill of materials dated September 29, 1965, manufactured by Crawford Manufacturing Co., Inc., 3d and Decatur Streets, Richmond, Va. 23212; 12th and Graham Streets, Emporia, Kans. 66801; and 5550 Paramount Boulevard, Long Beach, Calif. 90805, effective March 16, 1966. (It supersedes Approval No. 160.052/133/1 dated Nov. 3, 1965, to show change in address.)

Approval No. 160.052/150/0, Type II, Model "A", adult unicellular plastic foam buoyant vest, dwg. Nos. 11 and 12 dated March 3, 1961, Rev. 1 dated June 1, 1963, and bill of materials dated September 29, 1965, manufactured by Crawford Manufacturing Co., Inc., 3d and Decatur Streets, Richmond, Va. 23212; 12th and Graham Streets, Emporia, Kans. 66801; and 5550 Paramount Boulevard, Long Beach, Calif. 90805, for Montgomery Ward & Co., Inc., 619 West Chicago Avenue, Chicago, Ill. 60610, effective March 16, 1966. (It supersedes Approval No. 160.052/150/0 dated Oct. 11, 1961, to show change in address of manufacturer.)

Approval No. 160.052/151/0, Type II, Model "M", child medium unicellular plastic foam buoyant vest, dwg. Nos. 11 and 13 dated March 3, 1961, Rev. 1 dated June 1, 1963, and bill of materials dated September 29, 1965, manufactured by Crawford Manufacturing Co., Inc., 3d and Decatur Streets, Richmond, Va. 23212; 12th and Graham Streets, Emporia, Kans. 66801; and 5550 Paramount Boulevard, Long Beach, Calif. 90805, for Montgomery Ward & Co., Inc., 619 West Chicago Avenue, Chicago, Ill. 60610, effective March 16, 1966. (It supersedes Approval No. 160.052/151/0 dated Oct. 11, 1961, to show change in address of manufacturer.)

Approval No. 160.052/152/0, Type II, Model "S", child small unicellular plastic foam buoyant vest, dwg. Nos. 11 and 14 dated March 3, 1961, Rev. 1 dated June 1, 1963, and bill of materials dated September 29, 1965, manufactured by Crawford Manufacturing Co., Inc., 3d and Decatur Streets, Richmond, Va. 23212; 12th and Graham Streets, Emporia, Kans. 66801;

and 5550 Paramount Boulevard, Long Beach, Calif. 90805, for Montgomery Ward & Co., Inc., 619 West Chicago Avenue, Chicago, Ill. 60610, effective March 16, 1966. (It supersedes Approval No. 160.052/152/0 dated Oct. 11, 1961, to show change in address of manufacturer.)

Approval No. 160.052/246/0, Type II, Model 66-L, adult unicellular plastic foam buoyant vest, dwg. No. 3 dated July 7, 1963, and bill of materials dated January 20, 1966, manufactured by Jones & Yandell Division, American Tent Co., Post Office Box 270, Canton, Miss. 39046, effective March 10, 1966. (It supersedes Approval No. 160.052/246/0 dated Oct. 8, 1963, to show change in specifications.)

Approval No. 160.052/247/0, Type II, Model 66-M, child medium unicellular plastic foam buoyant vest, dwg. No. 2, dated July 7, 1963, and bill of materials dated January 20, 1966, manufactured by Jones & Yandell Division, American Tent Co., Post Office Box 270, Canton, Miss. 39046, effective March 10, 1966. (It supersedes Approval No. 160.052/247/0 dated Oct. 8, 1963, to show change in specifications.)

Approval No. 160.052/248/0, Type II, Model 66-S, child small unicellular plastic foam buoyant vest, dwg. No. 1 dated July 7, 1963, and bill of materials dated January 20, 1966, manufactured by Jones & Yandell Division, American Tent Co., Post Office Box 270, Canton, Miss. 39046, effective March 10, 1966. (It supersedes Approval No. 160.052/248/0 dated Oct. 8, 1963, to show change in specifications.)

Approval No. 160.052/251/0, Type II, Model 57008, child small vinyl-dip coated unicellular plastic foam buoyant vest, Hawthorn dwg. No. CS-1, Rev. 1 dated November 26, 1963, and bill of materials dated October 25, 1965, manufactured by Hawthorn Co., New Haven, Mo. 63068, for Sears, Roebuck & Co., 925 South Homan Avenue, Chicago, Ill. 60607, effective November 29, 1965. (It supersedes Approval No. 160.052/251/0 dated Nov. 29, 1963, to show change in specification.)

Approval No. 160.052/286/0, Type II, Model NP, adult unicellular plastic foam buoyant vest, dwg. Nos. 21 and 22, Rev. 1 dated June 24, 1963, and bill of materials dated October 1, 1965, manufactured by Noble Products Co., Caldwell, Ohio 43724, effective January 14, 1966. (It supersedes Approval No. 160.052/286/0 dated Mar. 4, 1964, to show change in specifications.)

Approval No. 160.052/287/0, Type II, Model MP, child medium unicellular plastic foam buoyant vest, dwg. Nos. 21 and 23, Rev. 1 dated June 24, 1963, and bill of materials dated October 1, 1965, manufactured by Noble Products Co., Caldwell, Ohio 43724, effective January 14, 1966. (It supersedes Approval No. 160.052/287/0 dated Mar. 4, 1964, to show change in specifications.)

Approval No. 160.052/288/0, Type II, Model OP, child small unicellular plastic foam buoyant vest, dwg. Nos. 21 and 24, Rev. 1 dated June 24, 1963, and bill of materials dated October 1, 1965, manufactured by Noble Products Co., Caldwell, Ohio 43724, effective January 14,

1966. (It supersedes Approval No. 160.052/288/0 dated Mar. 4, 1964, to show change in specifications.)

Approval No. 160.052/313/0, Type II, Model LVA-300, adult, molded vinyl-dipped unicellular plastic foam buoyant vest, dwg. No. 5581-D, Rev. 2 dated October 25, 1965, manufactured by Carlon Rubber Products Co., 1 New Haven Avenue, Derby Conn. 06418, effective January 24, 1966. (It supersedes Approval No. 160.052/313/0 dated Apr. 23, 1965, to show change in specifications.)

Approval No. 160.052/314/0, Type II, Model LVCM-200, child medium, molded vinyl-dipped unicellular plastic foam buoyant vest, dwg. No. 5622-B, Rev. 2 dated October 28, 1965, manufactured by Carlon Rubber Products Co., 1 New Haven Avenue, Derby, Conn. 06418, effective January 24, 1966. (It supersedes Approval No. 160.052/314/0 dated Apr. 23, 1965, to show change in specifications.)

Approval No. 160.052/315/0, Type II, Model LVCS-100, child small, molded vinyl-dipped unicellular plastic foam buoyant vest, dwg. No. 5623-B, revision 2 dated October 28, 1965, manufactured by Carlon Rubber Products Co., 1 New Haven Avenue, Derby, Conn. 06418, effective January 24, 1966. (It supersedes Approval No. 160.052/315/0 dated Apr. 23, 1965, to show change in specifications.)

Approval No. 160.052/325/0, Type II, Model LVA-300, adult molded vinyl-dipped unicellular plastic foam buoyant vest, Carlon dwg. No. 5581-D, Rev. 2 dated October 25, 1965, manufactured by Carlon Rubber Products, 1 New Haven Avenue, Derby, Conn. 06418, for Acme Products, Inc., 307 Racebrook Road, Orange, Conn. 06477, effective January 14, 1966.

WORK VESTS, UNICELLULAR PLASTIC FOAM

Approval No. 160.053/7/1, unicellular plastic foam work vest as per military specification MIL-17653A, U.S.C. Specification Subpart 160.053, dwg. No. 21975 dated August 6, 1965, and dwg. No. 8211-2 dated December 15, 1965, manufactured by Atlantic-Pacific Manufacturing Corp., 124 Atlantic Avenue, Brooklyn, N.Y. 11201, effective March 10, 1966. (It supersedes Approval No. 160.053/7/1 dated Aug. 20, 1965, to show alternate construction.)

Approval No. 160.053/8/1, unicellular plastic foam work vests, as per Military Specification MIL-L-17653A or MIL-L-17653B, U.S.C.G. Specification Subpart 160.053, and the special provisions of Corps of Engineers Invitation No. CIVENG-46-022-66-72, manufactured by The Safeguard Corp., 930 York Street, Box 14037, Post Office Annex, Cincinnati, Ohio 45214, effective March 4, 1966. (It supersedes Approval No. 160.053/8/0 dated Apr. 1, 1964, to show change in construction.)

DESALTER KITS

Approval No. 160.058/3/0, desalter kit, sea water; cylindrical container and contents identified by dwg. B-0010, dated October 20, 1965, and bill of materials (sheets 1 to 5), dated December 13, 1965, manufactured by Ionac Chemical Co.,

Birmingham Road, Birmingham, N.J. 08011, effective February 16, 1966.

PROTECTING COVER FOR LIFEBOATS

Approval No. 160.065/1/0, "Gentex Catenary Lifeboat Cover," Type I, protecting cover for the occupants of all types of aluminum, steel and fibrous glass reinforced plastic (FRP) lifeboats, for lengths of 16' through 37' lifeboats, identified by general arrangement dwg. No. 65H1544, dated June 18, 1965, manufactured by Gentex Corp., Carbondale, Pa., effective January 10, 1966. (Modifications to the cover and supports may be necessary in the case of some motor-propelled lifeboats equipped with vertical (dry) exhaust lines, radio cabins and antenna masts.)

SAFETY VALVES (POWER BOILERS)

Approval No. 162.001/262/0, Type 1910 GC consolidated safety relief valve, dwg. 1900G, approved for 300-lb. ASA pressure temperature ratings with a maximum temperature of 450° F., manufactured by Manning, Maxwell & Moore, Inc., Post Office Box 1430, Alexandria, La., effective January 18, 1966.

RELIEF VALVES (HOT WATER HEATING BOILERS)

Approval No. 162.013/8/1, Type No. D175 dual unit relief valve for hot water heating boiler, relieving capacity 175,000 B.t.u. per hour at a maximum set pressure of 30 p.s.i., dwg. No. RRP2-14, dated November 10, 1955, approved for 3/4" inlet size, manufactured by Bell & Gossett Co., 8200 North Austin Avenue, Morton Grove, Ill., effective February 16, 1966. (It is an extension of Approval No. 162.013/8/1 dated Mar. 10, 1961.)

Approval No. 162.013/9/1, Type No. D250 dual unit relief valve for hot water heating boiler, relieving capacity 250,000 B.t.u. per hour at a maximum set pressure of 30 p.s.i., dwg. No. RRP2-14, dated November 10, 1955, approved for 3/4" inlet size, manufactured by Bell & Gossett Co., 8200 North Austin Avenue, Morton Grove, Ill., effective February 16, 1966. (It is an extension of Approval No. 162.013/9/1 dated Mar. 10, 1961.)

Approval No. 162.013/31/0, Type No. 3300 relief valve for hot water heating boiler, relieving capacity 3,300,000 B.t.u. per hour at a maximum set pressure of 30 p.s.i., dwg. No. RA-25, dated January 27, 1955, approved for 1 1/2" inlet size, manufactured by Bell & Gossett Co., 8200 North Austin Avenue, Morton Grove, Ill., effective February 16, 1966. (It is an extension of Approval No. 162.013/31/0 dated Mar. 10, 1961.)

Approval No. 162.013/32/0, Type No. 3300-15 relief valve for hot water heating boiler, relieving capacity 2,000,000 B.t.u. per hour at a maximum set pressure of 15 p.s.i., dwg. No. RA-25, dated January 27, 1955, approved for 1 1/2" inlet size, manufactured by Bell & Gossett Co., 8200 North Austin Avenue, Morton Grove, Ill., effective February 16, 1966. (It is an extension of Approval No. 162.013/32/0 dated Mar. 10, 1961.)

Approval No. 162.013/33/0, Type No. 4100 relief valve for hot water heating

boiler, relieving capacity, 4,100,000 B.t.u. per hour at a maximum set pressure of 30 p.s.i., dwg. No. RA-26, dated January 13, 1955, approved for 2" inlet size, manufactured by Bell & Gossett Co., 8200 North Austin Avenue, Morton Grove, Ill., effective February 16, 1966. (It is an extension of Approval No. 162.013/33/0 dated Mar. 10, 1961.)

Approval No. 162.013/34/0, Type No. 4100-15 relief valve for hot water heating boiler, relieving capacity 2,500,000 B.t.u. per hour at a maximum set pressure of 15 p.s.i., dwg. No. RA-26, dated January 13, 1955, approved for 2" inlet size, manufactured by Bell & Gossett Co., 8200 North Austin Avenue, Morton Grove, Ill., effective February 16, 1966. (It is an extension of Approval No. 162.013/34/0 dated Mar. 10, 1961.)

FLAME ARRESTERS FOR TANK VESSELS

Approval No. 162.016/30/1, Oceco Type E-21-B flame arrester, cast iron body, extensible bank assembly, aluminum arrester plates, bolted end covers, dwg. No. HOC-195-A, revised November 10, 1950, approved for sizes 3", 4", 6", 8", and 10", manufactured by The Johnston & Jennings Co., 4700 West Division Street, Chicago, Ill., effective January 18, 1966. (It is an extension of Approval No. 162.016/30/1 dated Jan. 27, 1961.)

SAFETY RELIEF VALVES, LIQUEFIED COMPRESSED GAS

Approval No. 162.018/32/2, Style JO-25 safety relief valve for liquefied petroleum gas and anhydrous ammonia service, full nozzle type metal to metal seat, 150 p.s.i. primary service pressure rating, dwg. No. HV-60 dated September 3, 1954, revised December 30, 1965, approved for inlet diameters of 1 inch through 6 inches for a maximum set pressure of 300 p.s.i.g., manufactured by Crosby Valve & Gage Co., Wrentham, Mass., effective January 21, 1966. (It supersedes Approval No. 162.018/32/1 dated June 21, 1965, to show change in construction.)

Approval No. 162.018/33/2, Style JO-35 safety relief valve for liquefied petroleum gas and anhydrous ammonia service, full nozzle type metal to metal seat, 300 p.s.i. primary service pressure rating, dwg. No. HV-61 dated September 3, 1954, revised January 3, 1966, approved for inlet diameters of 1 inch through 6 inches for a maximum set pressure of 300 p.s.i.g., manufactured by Crosby Valve & Gage Co., Wrentham, Mass., effective January 21, 1966. (It supersedes Approval No. 162.018/33/1 dated June 21, 1965, to show change in construction.)

Approval No. 162.018/59/0, Crosby Style JB-25 safety relief valve for liquefied compressed gas service, dwg. No. HV-207 dated December 14, 1965, approved for inlet diameters of 1 1/2 inch through 6 inches for a maximum set pressure of 165 p.s.i. for orifices F, G, H, J, K, L, M, N, P, and Q, and a maximum set pressure of 100 p.s.i. for orifice R, with a maximum temperature of 450° F., manufactured by Crosby Valve & Gage Co., Wrentham, Mass., effective January 21, 1966.

Approval No. 162.018/60/0, Crosby Style JB-25-3 safety relief valve for

liquefied compressed gas service, dwg. HV-209 dated December 14, 1965, approved for inlet diameters of 1 1/2 inch through 6 inches inclusive, for a maximum set pressure of 275 p.s.i. for orifices F, G, H, J, K, L, M, N, and P; 165 p.s.i. for orifice Q; and 100 p.s.i. for orifice R, with a maximum temperature of 450° F., manufactured by Crosby Valve & Gage Co., Wrentham, Mass., effective January 21, 1966.

Approval No. 162.018/61/0, Crosby Style JB-26 safety relief valve for liquefied compressed gas service, dwg. HV-208 dated December 14, 1965, approved for inlet diameters of 1 1/2 inch through 6 inches inclusive, for a maximum set pressure of 92 p.s.i., with a maximum temperature of 800° F., manufactured by Crosby Valve & Gage Co., Wrentham, Mass., effective January 21, 1966.

Approval No. 162.018/62/0, Crosby Style JB-26-3 safety relief valve for compressed gas service, dwg. HV-210 dated December 14, 1965, approved for inlet diameters of 1 1/2 inch through 6 inches for a maximum set pressure of 275 p.s.i. for orifices F, G, H, J, K, L, M, N, and P; 165 p.s.i. for orifice Q; and 100 p.s.i. for orifice R, with a maximum temperature of 800° F., manufactured by Crosby Valve & Gage Co., Wrentham, Mass., effective January 21, 1966.

GAUGING DEVICES, LIQUID LEVEL, LIQUEFIED COMPRESSED GAS

Approval No. 162.019/2/4, No. 62B (Modification W4) MGM and No. 62B (Modification W4) /SS MGM liquid level gauge for liquefied compressed gas service, dwg. No. 107, manufactured by Metal Goods Manufacturing Co., 110 South Park Avenue, Bartlesville, Okla., effective February 28, 1966. (It supersedes Approval No. 162.019/2/3 dated July 26, 1961.)

Approval No. 162.019/7/1, Model Nos. 60D and 60D/SS liquid level gauge for compressed gas service, dwg. No. 176, manufactured by Metal Goods Manufacturing Co., 110 South Park Avenue, Bartlesville, Okla., effective February 28, 1966. (It supersedes Approval No. 162.019/7/0 dated Dec. 4, 1961.)

Approval No. 162.019/26/2, No. 175 MGM liquid level gauge for liquefied compressed gas service, dwg. No. 183, manufactured by Metal Goods Manufacturing Co., 110 South Park Avenue, Bartlesville, Okla., effective February 28, 1966. (It supersedes Approval No. 162.019/26/1 dated July 26, 1961.)

BOILERS, AUXILIARY, AUTOMATICALLY CONTROLLED PACKAGED

Approval No. 162.026/6/0, Clayton steam generator, Model RO-1650, light oil fired (fuel oil no heavier than standard No. 2, gravity 30-48 API at 60° F.), maximum operating pressure 150 p.s.i., 57.3 boiler horsepower, manufactured by Clayton Manufacturing Co., Post Office Box 550, El Monte, Calif., effective February 9, 1966. (Plans approved Apr. 19, 1965; performance test completed Sept. 24, 1965.) (It supersedes Approval No. 162.026/6/0 dated Feb. 8, 1966, to show correction in description.)

Carburetor Division, 696 Hart Avenue,
Detroit, Mich. 48214, effective January
31, 1966.

Approval No. 162.041/46/0, Bendix Model B175-24 backfire flame arrester, Bendix dwg. B175-24 dated April 24, 1963, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective January 31, 1966.

Approval No. 162.041/47/0, Bendix Model B175-25 backfire flame arrester, Bendix dwg. B175-25 dated April 24, 1963, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective January 31, 1966.

Approval No. 162.041/48/0, Bendix Model B175-29 backfire flame arrester, Bendix dwg. B175-29 dated February 17, 1964, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective January 31, 1966.

Approval No. 162.041/49/0, Bendix Model B175-30 backfire flame arrester, Bendix dwg. B175-30 dated February 17, 1964, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective January 31, 1966.

Approval No. 162.041/50/0, Bendix Model B175-31 backfire flame arrester. Bendix dwg. B175-31 dated February 17, 1964, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective January 31, 1966.

Approval No. 162.041/51/0, Bendix Model B175-32 backfire flame arrester, Bendix dwg. B175-32 dated March 5, 1964, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective January 31, 1966.

Approval No. 162.041/52/0, Bendix Model B175-22A backfire flame arrester, Bendix dwg. B175-22A dated January 4, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective January 31, 1966

Approval No. 162.041/53/0, Bendix Model B175-23A backfire flame arrester, Bendix dwg. B175-23A dated January 4, 1965, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective January 21, 1966.

Approval No. 162.041/54/0, Bendix Model B175-24A backfire flame arrester, dwg. B175-24A dated January 4, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective January 21, 1966.

Approval No. 162.041/55/0, Bendix Model B175-25A backfire flame arrester, dwg. B175-25A dated January 4, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February

Approval No. 162.041/56/0, Bendix Model B175-26A backfire flame arrester, dwg. B175-26A dated January 5, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue

Approval No. 162.041/45/0, Bendix Model B175-23 backfire flame arrester, Bendix dwg. B175-23 dated April 7, 1965, manufactured by Bendix Corp. Zenith

Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/57/0, Bendix Model B175-27A backfire flame arrester, dwg. B175-27A dated January 5, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/58/0, Model B175-28A backfire flame arrester, dwg. B175-28A dated January 5, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/59/0, Bendix Model B175-29A backfire flame arrester, dwg. B175-29A dated January 4, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/60/0, Bendix Model B175-30A backfire flame arrester, dwg. B175-30A dated January 4, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/61/0, Bendix Model B175-31A backfire flame arrester, dwg. B175-31A dated January 4, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/62/0, Bendix Model B175-32A backfire flame arrester, dwg. B175-32A dated January 4, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/63/0, Bendix Model B175-33A backfire flame arrester, dwg. B175-33A dated January 5, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/64/0, Bendix Model C175-11 backfire flame arrester, dwg. C175-11 dated January 6, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/65/0, Bendix Model C175-11A backfire flame arrester, drawing C175-11A dated January 6, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/66/0, Bendix Model C175-35 backfire flame arrester, dwg. C175-35 dated January 10, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/67/0, Bendix Model B175-38 backfire flame arrester, Bendix dwg. B175-38 dated December 8, 1965, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/71/0, Bendix Model B175-34 backfire flame arrester, dwg. B175-34 dated August 3, 1964, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/72/0, Bendix Model B175-37 backfire flame arrester, Bendix dwg. B175-37 dated May 26, 1965, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/73/0, Bendix Model B175-34A backfire flame arrester, dwg. B175-34A dated January 7, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/74/0, Bendix Model B175-36A backfire flame arrester, dwg. B175-36A dated January 7, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/75/0, Bendix Model B175-37A backfire flame arrester, dwg. B175-37A dated January 7, 1966, manufactured by Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit, Mich. 48214, effective February 2, 1966.

Approval No. 162.041/76/0, Fisher Model 3100 backfire flame arrester, dwg. No. 3100 dated January 7, 1966, manufactured by Fisher Corp., 1625 West Maple Road, Troy, Mich., effective February 10, 1966.

Approval No. 162.041/77/0, Palmer Model 7336 backfire flame arrester, Palmer assembly dwg. No. 7336, manufactured by the Palmer Engine Co., Cos Cob, Conn., effective March 7, 1966.

Approval No. 162.041/78/0, Air-Maze No. 2 Unimaze backfire flame arrester, Air-Maze dwgs. A17853-C, A17853-G and A17853-F, manufactured by Air-Maze Division, Rockwell-Standard Corp., 25000 Miles Road, Cleveland, Ohio, effective March 10, 1966.

Approval No. 162.041/79/0, Air-Maze No. 4 Unimaze backfire flame arrester, Air-Maze dwgs. A17854-C, A17854-G and A17854-F, manufactured by Air-Maze Division, Rockwell-Standard Corp., 25000 Miles Road, Cleveland, Ohio, effective March 10, 1966.

INCOMBUSTIBLE MATERIALS

Approval No. 164.009/88/1, "American Bestoglas" woven combination Grade AAA asbestos and fibrous glass (2.5 percent lubricant or less) cloth type incombustible material identical to that described in American Asbestos Textile Corp. letters dated 9 and 17 September 1965, approved in weights of 1/2 through 2 1/2 pounds/square yard, manufactured by American Asbestos Textile Corp., 1032 Stanbridge Street, Norristown, Pa. 19404, Plant: Meredith, N.H., effective February 23, 1966. (It supersedes Approval No. 164.009/88/0 dated Jan. 24, 1966, to show change in address.)

Approval No. 164.009/90/0, "Insul-Coustic SeeGee Adhesive I-C 292" com-

position type incombustible material identical to that described in National Bureau of Standards Test Report No. TG10210-2131:FR3666 dated February 24, 1966, and Insul-Coustic letter dated January 14, 1966, manufactured by Insul-Coustic Division, Birma Production Corp., Jernee Mill Road, Sayreville, N.J. 08872, effective March 10, 1966.

Approval No. 164.009/91/0, "Insul-Coustic SeeGee Coating I-C 596" composition type incombustible material identical to that described in National Bureau of Standards Test Report No. TG10210-2131:FR3666 dated February 24, 1966, and Insul-Coustic letter dated January 14, 1966, manufactured by Insul-Coustic Division, Birma Production Corp., Jernee Mill Road, Sayreville, N.J. 08872, effective March 10, 1966.

PART II—TERMINATIONS OF APPROVALS OF EQUIPMENT, INSTALLATIONS, OR MATERIALS

LIFE PRESERVERS, KAPOK, ADULT AND CHILD (JACKET TYPE) MODELS 3 AND 5

The Badgley Manufacturing Co., 2637 Northeast Union, Portland, Ore. 97211, Approval Nos. 160.002/92/0 and 160.002/93/0 for certain kapok life preservers have expired and are therefore terminated, effective January 13, 1966.

BUOYS, LIFE, RING, CORK OR BALSA WOOD

The American Pad & Textile Co., 511 North Solomon Street, New Orleans, La. 70119, no longer manufactures a particular cork ring life buoy and Approval No. 160.009/33/0 was therefore terminated, effective January 25, 1966.

BUOYANT APPARATUS

The Welin Davit and Boat Division of Continental Copper & Steel Industries, Inc., Perth Amboy, N.J., no longer manufactures a particular buoyant apparatus and Approval No. 160.010/13/2 was therefore terminated, effective January 12, 1966.

WINCHES, LIFEBOAT

The Welin Davit and Boat Division of Continental Copper & Steel Industries, Inc., Perth Amboy, N.J., Approval Nos. 160.015/26/2 and 160.015/27/2 for certain lifeboat winches have expired and are therefore terminated, effective March 24, 1966.

LIFERAFTS

The Welin Davit and Boat Division of Continental Copper & Steel Industries, Inc., Perth Amboy, N.J., no longer manufactures a particular liferaft and Approval No. 160.018/18/0 was therefore terminated, effective January 18, 1966.

DAVITS

The Marine Safety Equipment Corporation, Point Pleasant Beach, N.J., Approval No. 160.032/149/0 for a certain mechanical davit has expired and is therefore terminated, effective March 8, 1966.

MECHANICAL DISENGAGING APPARATUS, LIFEBOAT

The Lunn Laminates, Inc., Straight Path Road, Wyandanch, Long Island, N.Y., no longer manufactures a particular releasing gear and Approval No.

160.033/57/1 was therefore terminated, effective January 18, 1966.

LIFEBOATS

The Welin Davit and Boat Division of Continental Copper & Steel Industries, Inc., Perth Amboy, N.J., no longer manufactures a particular lifeboat and Approval No. 160.035/418/0 was therefore terminated, effective January 25, 1966.

BUOYANT CUSHIONS, KAPOK OR FIBROUS GLASS

NOTE: Approved for use on motorboats of Classes A, 1, or 2 not carrying passengers for hire

The Holiday Line, Inc., 50 Washington Street, Brooklyn, N.Y., 11201 Approval No. 160.048/28/0 for a particular kapok buoyant cushion has expired and is therefore terminated, effective January 4, 1966.

The Montgomery Ward & Co., Inc., 619 West Chicago Avenue, Chicago, Ill. 60610, approvals for kapok buoyant cushions have expired and therefore Approval Nos. 160.048/39/0 and 160.048/49/0 are terminated, effective December 20, 1965.

The Chris-Craft Corp., Algonac, Mich., approval for a kapok buoyant cushion has expired and therefore Approval No. 160.048/63/0 was terminated, effective March 10, 1966.

The Boston Camping Distributor Co., Inc., 150 Oliver Street, Boston, Mass., no longer manufactures a particular kapok buoyant cushion and Approval No. 160.048/64/0 was therefore terminated, effective January 17, 1966.

The Style-Crafters, Inc., Box 3277, Station A, Greenville, S.C., Approval No. 160.048/223/0 for a particular kapok buoyant cushion was terminated due to change in specifications, effective January 27, 1966.

BUOYANT CUSHIONS, UNICELLULAR PLASTIC FOAM

NOTE: Approved for use on motorboats of Classes A, 1, or 2 not carrying passengers for hire

The Chris-Craft Corp., Algonac, Mich., Holland, Mich., Cadillac, Mich., Caruthersville, Mo., Chattanooga, Tenn., Salisbury, Md., now manufactures a particular cushion under a group approval and therefore Approval No. 160.049/5/0 has expired and was therefore terminated, effective March 6, 1966.

INFLATABLE LIFERAFTS

The United States Rubber Co., Inflatable Products & Transportation Containers Department, 10 Eagle Street, Providence, R.I., no longer manufactures certain inflatable liferafts and therefore Approval Nos. 160.051/7/0 and 160.051/8/0 are terminated, effective January 25, 1966.

WORK VESTS, UNICELLULAR PLASTIC FOAM

The Gentex Corporation, Carbondale, Pa. 18407, Approval No. 160.053/10/0 for a particular unicellular plastic foam work vest has expired and is therefore terminated, effective January 5, 1966.

FLAME ARRESTERS, BACKFIRE (FOR CARBURETORS)

The Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit 14, Mich., Approval Nos. 162.015/8/3, 162.015/9/3, 162.015/10/2, 162.015/11/2, 162.015/12/2, 162.015/13/2, 162.015/14/2, 162.015/15/2, 162.015/16/2, 162.015/17/2, 162.015/18/2, 162.015/19/2, 162.015/20/1, 162.015/21/1, 162.015/25/1, 162.015/26/1, and 162.015/27/1, for certain backfire flame arresters for carburetors have terminated due to change in specifications, effective January 1, 1966.

The Air-Maze Division, Rockwell-Standard Corp., 25000 Miles Road, Cleveland 28, Ohio, Approval Nos. 162.015/28/0, 162.015/29/0, 162.015/30/0, 162.015/31/0, 162.015/32/0, 162.015/33/0, 162.015/34/0 and 162.015/35/0, for certain backfire flame arresters for carburetors have terminated due to change in specifications, effective January 1, 1966.

The Dearborn Marine Engine Division, Eaton Manufacturing Co., 31465 Stephenson Highway, Madison Heights, Mich., Approval Nos. 162.015/36/1 and 162.015/37/0, for certain backfire flame arresters for carburetors have terminated due to change in specifications, effective January 1, 1966.

The Curtiss-Wright Corp., Research Division, Quehanna, Pa., Approval No. 162.015/40/0, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Rochester Products Division of General Motors Corp., 10000 Lexington Avenue, Rochester 3, N.Y., Approval No. 162.015/41/0, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The PurOlator Products, Inc., 3927 Fourth Street, Wayne, Mich., Approval No. 162.015/44/0, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Volvo Import, Inc., 452 Hudson Terrace, Englewood Cliffs, N.J., Approval No. 162.015/45/0, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Air-Maze Division, Rockwell-Standard Corp., 25000 Miles Road, Cleveland 28, Ohio, Approval No. 162.015/46/1, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The PurOlator Products, Inc., 3927 Fourth Street, Wayne, Mich., Approval No. 162.015/49/0, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Fisher Industries, 1625 West Maple Road, Troy, Mich., Approval Nos. 162.015/50/0, 162.015/51/0, 162.015/52/0, 162.015/53/0, 162.015/54/2, 162.015/55/0, 162.015/56/2, 162.015/57/2 and 162.015/58/2, for certain backfire flame arresters for carburetors have terminated due to change in specifications, effective January 1, 1966.

The Industrial Strainer Co., 695 Amelia Street, Plymouth, Mich., Approval Nos. 162.015/59/0, 162.015/60/0, 162.015/61/0, 162.015/62/0 and 162.015/63/0, for certain backfire flame arresters for carburetors have terminated due to change in specifications, effective January 1, 1966.

The Barbron Corp., 14580 Lesure Avenue, Detroit 27, Mich., Approval Nos. 162.015/64/0, 162.015/65/0, 162.015/66/0, 162.015/67/0, 162.015/68/0 and 162.015/69/0, for certain backfire flame arresters for carburetors have terminated due to change in specifications, effective January 1, 1966.

The Industrial Strainer Co., 695 Amelia Street, Plymouth, Mich., Approval No. 162.015/70/0, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Fisher Industries, 1625 West Maple Road, Troy, Mich., Approval No. 162.015/71/1, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Palmer Engine Co., Cos Cob, Conn., Approval Nos. 162.015/72/0 and 162.015/73/0, for certain backfire flame arresters for carburetors have terminated due to change in specifications, effective January 1, 1966.

The Fisher Industries, 1625 West Maple Road, Troy, Mich., Approval Nos. 162.015/74/1, 162.015/75/1, 162.015/76/1, 162.015/77/1, 162.015/78/1 and 162.015/79/0, for certain backfire flame arresters for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Palmer Engine Co., Cos Cob, Conn., Approval No. 162.015/80/0, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Fisher Industries, 1625 West Maple Road, Troy, Mich., Approval No. 162.015/81/1, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit 14, Mich., Approval Nos. 162.015/82/1 and 162.015/83/0, for certain backfire flame arresters for carburetors have terminated due to change in specifications, effective January 1, 1966.

The Fisher Industries, 1625 West Maple Road, Troy, Mich., Approval Nos. 162.015/84/0 and 162.015/85/1, for certain backfire flame arresters for carburetors have terminated due to change in specifications, effective January 1, 1966.

The Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit 14, Mich., Approval No. 162.015/86/1, for a particular backfire flame arrester was terminated due to change in specifications, effective January 1, 1966.

The Barbron Corp., 14580 Lesure Avenue, Detroit 27, Mich., Approval No. 162.015/87/0, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit 14, Mich., Approval Nos. 162.015/88/0, 162.015/89/1, 162.015/90/1, 162.015/91/0, 162.015/92/0 and 162.015/93/0, for certain backfire flame arresters for carburetors have terminated due to change in specifications, effective January 1, 1966.

The Fishers Industries, 1625 West Maple Road, Troy, Mich., Approval No. 162.015/94/0, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

The Kiekhaefer Corp., Fond du Lac, Wis., Approval No. 162.015/95/0 for a particular backfire flame arrester for carburetors was terminated, effective January 1, 1966.

The Onan, division of Studebaker Industries, Inc., 2515 University Avenue SE., Minneapolis, Minn. 55414, Approval No. 162.015/96/0, for a particular backfire flame arrester assembly was terminated due to change in specifications, effective January 1, 1966.

The Bendix Corp., Zenith Carburetor Division, 696 Hart Avenue, Detroit 14, Mich., Approval No. 162.015/99/0, for a particular backfire flame arrester for carburetors was terminated due to change in specifications, effective January 1, 1966.

STRUCTURAL INSULATIONS

The Keasbey & Mattison Co., Ambler, Pa., Approval No. 164.007/13/0, for a particular sprayed asbestos fiber type structural insulation was terminated, because the manufacturer is no longer in business, effective January 21, 1966.

INCOMBUSTIBLE MATERIALS

The Keasbey & Mattison Co., Ambler, Pa., Approval Nos. 164.009/4/0 and 164.009/33/0 for certain asbestos cement board type incombustible material were terminated, because the manufacturer is no longer in business, effective January 21, 1966.

The Union Asbestos & Rubber Co., 1111 West Perry Street, Bloomington, Ill., Approval No. 164.009/63/1, for a particular asbestos cement board type incombustible material was terminated, effective August 27, 1965.

Dated: Aug. 31, 1966.

[SEAL] P. E. TRIMBLE,
Vice Admiral, U.S. Coast Guard,
Acting Commandant.

[F.R. Doc. 66-9818; Filed, Sept. 7, 1966;
8:49 a.m.]

DEPARTMENT OF THE INTERIOR

Bureau of Land Management

NEVADA STATE OFFICE AND NEVADA LAND OFFICE

Change of Mailing Address

AUGUST 30, 1966.

Notice is hereby given that the mailing address of the Nevada State Office and Land Office, Bureau of Land Manage-

ment, in Reno, Nev., is changed effective Monday, October 3, 1966. The new mailing address will from that date forward be Bureau of Land Management, Nevada State Office and Nevada Land Office, Room 3008, Federal Building, 300 Booth Street, Reno, Nev. 89502. The use of Post Office Box 1551, Reno, Nev., is being discontinued and the last official mail collection from Post Office Box 1551 will be at 1 p.m. on September 30, 1966.

In accordance with Title 43, Code of Federal Regulations, § 1821.2, applications, payments, and other documents received for filing October 3, 1966, shall be deemed to be filed as of 10 a.m. Thereafter, all mail will be delivered only once daily and considered as filed 10 a.m. on the date received. Mail received by Special Delivery after 4 p.m. will be considered filed at 10 a.m. the following day. Mail received by Special Delivery before 10 a.m. will be considered filed at 10 a.m. on the date received. Mail received by Special Delivery between 10 a.m. and 4 p.m. will be considered filed on the exact time and date received.

NOLAN F. KEIL,
State Director, Nevada.

[F.R. Doc. 66-9807; Filed, Sept. 7, 1966;
8:48 a.m.]

Bureau of Reclamation

MANTI-LASAL NATIONAL FOREST, UTAH

Transfer of Administrative Jurisdiction of Certain Lands

By virtue of the authority vested in the Secretary of the Interior by section 7(c) of the Act of July 9, 1965 (79 Stat. 213), and his delegation of authority to the Commissioner of Reclamation dated February 25, 1966, published March 4, 1966 (31 F.R. 3426), jurisdiction over the following described lands, which lie within the exterior boundaries of the Manti-Lasal National Forest, Utah, and which were acquired by the Bureau of Reclamation in the development of the Joes Valley Reservoir, Emery County Project, is hereby transferred to the Secretary of Agriculture for recreational and other National Forest System purposes:

SALT LAKE BASE AND MERIDIAN

T. 17 S., R. 6 E.,

Sec. 32: Portion of the $W\frac{1}{2}W\frac{1}{2}$, more particularly described as follows:

Beginning at a point on the south line of said section 32, 307.7 feet easterly from the north quarter corner of section 5, T. 18 S., R. 6 E., Salt Lake Base and Meridian, said point also being the southeast corner of the $SW\frac{1}{4}SW\frac{1}{4}$ of said section 32; thence north along the east line of said $SW\frac{1}{4}SW\frac{1}{4}$, 180.5 feet; thence along a regular curve to the left with a radius of 622.96 feet for an arc distance of 116.0 feet (bearing of the tangent at beginning of the curve is N. 11°39' W.); thence N. 22°19' W., 173.5 feet; thence along a regular curve to the right with a radius of 522.96 feet for an arc distance of 202.3 feet; thence N. 0°09' W., 905.8 feet; thence along a regular curve to the left with a radius 2,914.8 feet for an arc distance of 356.1 feet; thence N. 7°09' W., 2,807.8 feet; thence along a regular curve to the left with a radius of 2,914.8 feet for an arc distance of 542.6 feet;

thence N. 17°49' W., 43.1 feet to the north line of said section 32; thence westerly along said north line 673.4 feet to the northwest corner of said section 32; thence southerly along the west line of said section 32, 5,280.0 feet to the southwest corner of said section 32; thence easterly along the south line of said section 32, 1,320.0 feet to the point of beginning, containing 129.35 acres, more or less, and less right-of-way for Utah State Highway No. 29.

T. 18 S., R. 6 E.,

Sec. 5: $SW\frac{1}{4}NW\frac{1}{4}$, $W\frac{1}{2}SW\frac{1}{4}$, $SE\frac{1}{4}SW\frac{1}{4}$;

Sec. 6: $S\frac{1}{2}NE\frac{1}{4}$, $NE\frac{1}{4}SE\frac{1}{4}$, portion of $NW\frac{1}{4}SE\frac{1}{4}$, more particularly described as follows:

Beginning at the northeast corner of said $NW\frac{1}{4}SE\frac{1}{4}$, said point being 1,320.0 feet westerly of the east quarter corner of said section 6; thence westerly along the north line of said $NW\frac{1}{4}SE\frac{1}{4}$, 1,320.0 feet to the northwest corner of said $NW\frac{1}{4}SE\frac{1}{4}$; thence southerly along the east line of said $NW\frac{1}{4}SE\frac{1}{4}$, 191.0 feet; thence S. 36°01' E., 10.12 feet; thence along the arc of a curve to the right, with a radius of 2,804.79 feet an arc distance of 205.60 feet; thence S. 31°49' E., 1,117.32 feet to the south line of said $NW\frac{1}{4}SE\frac{1}{4}$; thence easterly along said south line 611.36 feet to the southeast corner of said $NW\frac{1}{4}SE\frac{1}{4}$; thence northerly along the east line of said $NW\frac{1}{4}SE\frac{1}{4}$, 1,320.0 feet to the point of beginning, containing 30.73 acres, more or less;

Secs. 6 and 7: Portion of $SE\frac{1}{4}SE\frac{1}{4}$ of section 6 and portion of $NE\frac{1}{4}NE\frac{1}{4}$ of section 7, more particularly described as follows:

Beginning at the southeast corner of said section 6; thence northerly along the east line of section 6, 1,320.0 feet to the northeast corner of said $SE\frac{1}{4}SE\frac{1}{4}$; thence westerly along the north line of said $SE\frac{1}{4}SE\frac{1}{4}$, 1,320.0 feet to the northwest corner of said $SE\frac{1}{4}SE\frac{1}{4}$; thence southerly along the west line of the $SE\frac{1}{4}SE\frac{1}{4}$, 988.26 feet; thence S. 31°49' E., 809.88 feet; thence along the arc of a curve to the left with a radius of 272.21 feet for an arc distance of 298.60 feet; thence N. 85°20' E., 63.0 feet; thence along the arc of a curve to the right with a radius of 67.32 feet for an arc distance of 104.47 feet; thence S. 5°45' E., 297.81 feet; thence along the arc of a curve to the right with a radius of 2,804.79 feet for an arc distance of 318.19 feet; thence S. 0°45' W., 165.64 feet to the south line of said $NE\frac{1}{4}NE\frac{1}{4}$ section 7; thence easterly along said south line 464.54 feet to the southeast corner of said $NE\frac{1}{4}NE\frac{1}{4}$ section 7; thence northerly along the east line of said section 7, 1,320.0 feet to the point of beginning, containing 59.07 acres, more or less;

Sec. 7: Portion of $SE\frac{1}{4}NE\frac{1}{4}$, more particularly described as follows:

Beginning at the east quarter corner of said section 7; thence northerly along the east line of said section 7, 1,320.0 feet to the northeast corner of said $SE\frac{1}{4}NE\frac{1}{4}$; thence westerly along the north line of said $SE\frac{1}{4}NE\frac{1}{4}$, 464.54 feet; thence S. 0°45' W., 23.82 feet; thence along the arc of a curve to the left, with a radius of 2,924.79 feet for an arc distance of 187.17 feet; thence S. 2°55' E., 211.77 feet; thence along the arc of a curve to the right, with a radius of 321.97 feet for an arc distance of 146.11 feet; thence S. 23°05' W., 34.53 feet; thence along the arc of a curve to the left, with a radius of 289.18 feet for an arc distance of 204.41 feet; thence S. 17°25' E., 549.75 feet to the south line of said $SE\frac{1}{4}NE\frac{1}{4}$; thence easterly along said south line 336.21 feet to the point of beginning, containing 13.68 acres, more or less;

Sec. 8: $NW\frac{1}{4}NW\frac{1}{4}$.

Pursuant to said section 7(c) of the aforesaid Act of July 9, 1965, the above lands shall become National Forest lands, provided, that all lands and waters within the Joes Valley Reservoir area

needed or used for the operation of the project or for other Reclamation purposes shall continue to be administered by the Commissioner of Reclamation to the extent he determines to be necessary for such operation.

This order shall be effective upon publication in the FEDERAL REGISTER.

Dated: August 30, 1966.

FLOYD E. DOMINY,
Commissioner,
Bureau of Reclamation.

[F.R. Doc. 66-9805; Filed, Sept. 7, 1966;
8:48 a.m.]

Fish and Wildlife Service

[Docket No. A-398]

LEVI MCKINLEY

Notice of Loan Application

Levi McKinley, 1300 No. 2-A West Ninth, Juneau, Alaska 99801, has applied for a loan from the Fisheries Loan Fund to aid in financing the purchase of a used 34.7-foot registered length vessel to engage in the fishery for halibut, salmon, and black cod.

Notice is hereby given pursuant to the provisions of Public Law 89-85 and Fisheries Loan Fund Procedures (50 CFR Part 250, as revised Aug. 11, 1965), that the above-entitled application is being considered by the Bureau of Commercial Fisheries, Fish and Wildlife Service, Department of the Interior, Washington, D.C. 20240. Any person desiring to submit evidence that the contemplated operation of such vessel will cause economic hardship or injury to efficient vessel operators already operating in that fishery must submit such evidence in writing to the Director, Bureau of Commercial Fisheries, within 30 days from the date of publication of this notice. If such evidence is received it will be evaluated along with such other evidence as may be available before making a determination that the contemplated operations of the vessel will or will not cause such economic hardship or injury.

HAROLD E. CROWTHER,
Acting Director,
Bureau of Commercial Fisheries.

SEPTEMBER 2, 1966.

[F.R. Doc. 66-9800; Filed, Sept. 7, 1966;
8:47 a.m.]

[Docket No. Sub-G-14]

HARLAN TRUITT MURPHY

Notice of Hearing

Harlan Truitt Murphy, Davis, N.C., has applied for a fishing vessel construction differential subsidy to aid in the construction of a 86-foot overall steel vessel to engage in the fishery for flounder, sea trout, porgies, king whiting, swordfish, croaker, shrimp (including royal red shrimp), scallops, and lobster.

Notice is hereby given pursuant to the provisions of the U.S. Fishing Fleet Improvement Act (P.L. 88-498) and Notice and Hearing on Subsidies (50 CFR Part 257) that a hearing in the above-entitled

proceedings will be held on October 18, 1966, at 10 a.m., e.d.s.t., in Room 3356, Interior Building, 18th and C Streets, Northwest, Washington, D.C. Any person desiring to intervene must file a petition of intervention with the Director, Bureau of Commercial Fisheries, as prescribed in 50 CFR Part 257 at least 10 days prior to the date set for the hearing. If such petition of intervention is granted, the place of the hearing may be changed to a field location. Telegraphic notice will be given to the parties in the event of such a change along with the new location.

HAROLD E. CROWTHER,
Acting Director,
Bureau of Commercial Fisheries.

SEPTEMBER 2, 1966.

[F.R. Doc. 66-9841; Filed, Sept. 7, 1966;
8:51 a.m.]

National Park Service

[Order 37]

SUPERVISORY ARCHEOLOGIST, SOUTHWEST ARCHEOLOGICAL CENTER, GLOBE, ARIZ.

Delegation of Authority Regarding Execution of Contracts for Supplies, Equipment or Services

Delegation. The Supervisory Archeologist of the Southwest Archeological Center located at Globe, Ariz., may execute and approve contracts and purchase orders not in excess of \$200,000 for supplies, equipment, or services in conformity with applicable regulations and statutory authority and subject to the availability of appropriations.

(245 DM 1, 28 F.R. 915; 5 U.S.C. sec. 22; sec. 2, Reorg. Plan No. 3 of 1950)

GEORGE B. HARTZOG, JR.,
Director.

[F.R. Doc. 66-9821; Filed, Sept. 7, 1966;
8:49 a.m.]

DEPARTMENT OF AGRICULTURE

Agricultural Stabilization and Conservation Service

SUGARBEETS

Notice of Hearing

Notice is hereby given that the Secretary of Agriculture, acting pursuant to the Sugar Act of 1948, as amended, will conduct a public hearing to receive the views and recommendations of interested persons on the need for establishing proportionate shares (farm acreage allotments) for the 1967 crop of sugarbeets in the Domestic Beet Sugar Area. Also, for use by the Secretary, if he determines that proportionate shares are needed, views, and recommendations are desired at the hearing on (a) the level of the national sugarbeet acreage requirement, (b) the method (formula) of allocating the requirement among States and to localities served by non-affiliated single plant processors of

sugarbeets and (c) the method of establishing individual farm proportionate shares.

The Sugar Act provides that the Secretary shall establish proportionate shares for farms in the beet sugar area if he determines that the production of sugar from a crop will be greater than the quantity needed to enable the area to meet its quota and provide a normal carryover inventory, as estimated by the Secretary for the area for the calendar year during which the larger part of the sugar from such crop normally would be marketed.

The hearing on this matter will be held in the Denver Hilton Hotel in Denver, Colo., beginning at 10 a.m. (Denver time) on September 22, 1966.

For consideration by the Department in establishing proportionate shares if needed, views, and recommendations are desired on all phases of the program, particularly on the following points:

1. The level of the national acreage requirement needed to enable the area to meet quota and carryover requirements.

2. The method (formula) of dividing the national requirement (excluding 113,500 acres previously made available under the national sugarbeet acreage reserve, a 1,000 contingency, and acreages for nonaffiliated single plant processors) among sugarbeet producing States.

3. The level of the acreages that should be made available to the aforementioned nonaffiliated single plant processors.

4. The levels of set asides for new producers, appeals, and adjustments.

5. The method (formulae) for establishing area allotments and individual farm proportionate shares.

Views and recommendations may be submitted orally at the hearing, preferably supported in writing in the original and two copies. Views and recommendations may also be submitted in writing (original and two copies) by mailing to the Director, Sugar Policy Staff, Agricultural Stabilization and Conservation Service, U.S. Department of Agriculture, Washington, D.C. 20250, postmarked not later than October 10, 1966.

All written submissions made pursuant to this notice will be made available for public inspection at such times and places and in a manner convenient to the public business (7 CFR 1.27(b)).

Signed at Washington, D.C., on September 2, 1966.

E. A. JAEKE,
Acting Administrator, Agricultural
Stabilization and Conservation
Service.

[F.R. Doc. 66-9846; Filed, Sept. 7, 1966;
8:51 a.m.]

Consumer and Marketing Service

HUMANELY SLAUGHTERED LIVESTOCK

Identification of Carcasses; Changes in Lists of Establishments

Pursuant to section 4 of the Act of August 27, 1958 (7 U.S.C. 1904), and the

statement of policy thereunder in 9 CFR 381.1, the lists (31 F.R. 9557 and 10288) of establishments which are operated under Federal inspection pursuant to the Meat Inspection Act (21 U.S.C. 71 et seq.) and which use humane methods of slaughter and incidental handling of livestock are hereby amended as follows:

The reference to sheep and goats with respect to Utica Veal Co., Inc., Establishment 88, is deleted. The reference to

calves with respect to Baum's Meat Packing, Establishment 792, is deleted. The reference to Parnett Packing Co., Establishment 283, and the reference to cattle and calves with respect to such establishment are deleted.

The following table lists species at additional establishments and additional species at previously listed establishments that have been reported as being slaughtered and handled humanely.

Name of establishment	Establishment No.	Cattle	Calves	Sheep	Goats	Swine	Horses
St. Paul Dressed Beef, Inc.	357	(*)					
Bartel's Meat Co.	487	(*)	(*)				
Avera Provisions Co., Inc.	677					(*)	
City Packing Co.	891	(*)	(*)	(*)	(*)	(*)	
New establishments reporting: 4.							
Idaho Meat Packers.	46		(*)	(*)			
City Packing Co.	80		(*)				
Seattle Packing Co.	191		(*)				
Estes Packing Co.	319		(*)				
Montebello Meat Packing Co.	364			(*)			
City Custom Packing Co., Inc.	387				(*)		
Glenwood Packing Co.	394					(*)	
The Collins Packing Co.	423A		(*)				
Becwar Packing Co.	467			(*)			
Shen-Valley Meat Packers, Inc.	511		(*)				
Texas Meat Packers, Inc.	555		(*)				
Austin Community Livestock Processors, Inc.	590			(*)	(*)	(*)	
Wright Packing Co.	603			(*)			
Parnett's Packing Co.	738			(*)			
Jordan Meat & Livestock Co., Inc.	858					(*)	
Perlin Packing Co., Inc.	974			(*)			
Longhorn Meat Packers, Inc.	976		(*)				
Species Added: 20.							

Done at Washington, D.C., this 1st day of September 1966.

R. K. SOMERS,

Deputy Administrator, Consumer Protection.

[F.R. Doc. 66-9811; Filed, Sept. 7, 1966; 8:48 a.m.]

DEPARTMENT OF HEALTH, EDUCATION, AND WELFARE

Food and Drug Administration CONTINENTAL CAN CO., INC.

Notice of Filing of Petition for Food Additives

Pursuant to the provisions of the Federal Food, Drug, and Cosmetic Act (sec. 409(b)(5), 72 Stat. 1786; 21 U.S.C. 348(b)(5)), notice is given that a petition (FAP 7R2069) has been filed by Continental Can Co., Inc., 633 Third Avenue, New York, N.Y. 10017, proposing an amendment to § 121.2514 *Resinous and polymeric coatings* to provide for the safe use of zinc carbonate as a pigment in resinous and polymeric food-contact coatings.

Dated: September 1, 1966.

J. K. KIRK,

Acting Commissioner of
Food and Drugs.

[F.R. Doc. 66-9836; Filed, Sept. 7, 1966; 8:50 a.m.]

E. I. DU PONT DE NEMOURS & CO.

Notice of Filing of Petition for Food Additives

Pursuant to the provisions of the Federal Food, Drug, and Cosmetic Act (sec.

409(b)(5), 72 Stat. 1786; 21 U.S.C. 348(b)(5)), notice is given that a petition (FAP 7B2055) has been filed by E. I. du Pont de Nemours & Co., 1007 Market Street, Wilmington, Del. 19898, proposing an amendment to § 121.2569 *Resinous and polymeric coatings for polyolefin films* to provide for the safe use of polyvinyl alcohol as a dispersing agent in resinous and polymeric coatings on polyolefin films for food-contact use.

Dated: September 1, 1966.

J. K. KIRK,

Acting Commissioner of
Food and Drugs.

[F.R. Doc. 66-9837; Filed, Sept. 7, 1966; 8:50 a.m.]

FMC CORP.

Notice of Filing of Petition Regarding Pesticide Endosulfan

Pursuant to the provisions of the Federal Food, Drug, and Cosmetic Act (sec. 408(d)(1), 68 Stat. 512; 21 U.S.C. 346a(d)(1)), notice is given that a petition (PP 7F0526) has been filed by FMC Corp., Niagara Chemical Division, 100 Niagara Street, Middleport, N.Y. 14105, proposing the establishment of a tolerance of 2 parts per million for residues of the insecticide endosulfan (6,7,8,9,10,10-hexachloro-1,5,5a,6,9,9a-hexahydro-6,9-methano-2,4,3-benzodioxathiepin-3-oxide) in or on beans, brussels sprouts, carrots, cauliflower, celery, collards, corn

(sweet), kale, mustard greens, peas (succulent type), pineapples, spinach, sugarcane, sunflower seed, sweetpotatoes, and turnip greens.

The analytical method proposed in the petition for determining residues of endosulfan is a microcoulometric-gas chromatographic procedure.

Dated: August 31, 1966.

J. K. KIRK,
Acting Commissioner of
Food and Drugs.

[F.R. Doc. 66-9838; Filed, Sept. 7, 1966; 8:51 a.m.]

GEIGY CHEMICAL CORP.

Notice of Filing of Petition Regarding Pesticide

Pursuant to the provisions of the Federal Food, Drug, and Cosmetic Act (sec. 408(d)(1), 68 Stat. 512; 21 U.S.C. 346a(d)(1)), notice is given that a petition (PP 7F0525) has been filed by Geigy Chemical Corp., Ardsley, N.Y. 10502, proposing the establishment of tolerances for residues of the herbicide atrazine (2-chloro-4-[ethylamino]-6-[isopropylamino]-s-triazine) in or on raw agricultural commodities as follows:

30 parts per million in or on corn forage and sorghum forage.

1 part per million in or on corn grain and sorghum grain.

The analytical methods proposed in the petition for determining residues of atrazine are based on spectrophotometric and thin-layer chromatographic techniques.

Dated: September 1, 1966.

J. K. KIRK,
Acting Commissioner of
Food and Drugs.

[F.R. Doc. 66-9839; Filed, Sept. 7, 1966; 8:51 a.m.]

KOPPERS CO., INC.

Notice of Filing of Petition for Food Additives

Pursuant to the provisions of the Federal Food, Drug, and Cosmetic Act (sec. 409(b)(5), 72 Stat. 1786; 21 U.S.C. 348(b)(5)), notice is given that a petition (FAP 7H2071) has been filed by the Forest Products Division of the Koppers Co., Inc., Pittsburgh, Pa. 15219, proposing an amendment to § 121.2556 *Preservatives for wood* to provide for the safe use of pentachlorophenol as a preservative for wood intended for use in contact with raw agricultural products in an amount not to exceed one percent by weight of the treated wood.

Dated: September 1, 1966.

J. K. KIRK,
Acting Commissioner of
Food and Drugs.

[F.R. Doc. 66-9840; Filed, Sept. 7, 1966; 8:51 a.m.]

DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

Office of the Secretary

ACTING ASSISTANT SECRETARY FOR DEMONSTRATIONS AND INTER- GOVERNMENTAL RELATIONS

Designation

The Director, Office of Intergovernmental Relations and Urban Program Coordination, is hereby designated to serve as Acting Assistant Secretary for Demonstrations and Intergovernmental Relations, with all the power and authority of the Assistant Secretary for Demonstrations and Intergovernmental Relations, during the absence of the Assistant Secretary and during the present vacancy in the position of Deputy Assistant Secretary for Demonstrations and Intergovernmental Relations.

(79 Stat. 670, 5 U.S.C. 624d(d))

Effective date. This designation shall be effective as of August 30, 1966.

ROBERT C. WEAVER,
Secretary of Housing and
Urban Development.

[F.R. Doc. 66-9856; Filed, Sept. 7, 1966;
8:52 a.m.]

CIVIL AERONAUTICS BOARD

[Docket No. 17233]

CONDOR FLUGDIENST G.M.B.H.

Notice of Hearing

Notice is given herewith, pursuant to the provisions of the Federal Aviation Act of 1958, as amended, that a public hearing in the above-entitled proceeding is assigned to be held before the undersigned Examiner on November 7, 1966, at 10 a.m., local time, in Room 911, 1825 Connecticut Avenue, NW., Washington, D.C.

For information concerning the issues involved and other details in this proceeding, interested persons are referred to the Prehearing Conference Report served on August 5, 1966, and other documents which are in the docket of this proceeding on file in the Docket Section of the Civil Aeronautics Board.

Dated at Washington, D.C., September 1, 1966.

[SEAL] EDWARD T. STODOLA,
Hearing Examiner.

[F.R. Doc. 66-9819; Filed, Sept. 7, 1966;
8:49 a.m.]

[Docket No. 16503]

IN-FLIGHT ENTERTAINMENT CHARGE

Notice of Postponement of Oral Argument

By direction of the Board, the oral argument in the above-entitled proceed-

ing, now assigned to be held on September 7, 1966, is postponed to a date to be later assigned.

Dated at Washington, D.C., September 2, 1966.

[SEAL] FRANCIS W. BROWN,
Chief Examiner.

[F.R. Doc. 66-9820; Filed, Sept. 7, 1966;
8:49 a.m.]

FEDERAL COMMUNICATIONS COMMISSION

[Docket No. 16678; FCC 66M-1156]

BAY BROADCASTING CO.

Order Continuing Hearing

In re application of Bay Broadcasting Co., San Francisco, Calif., Docket No. 16678, File No. BPCT-3621; for construction permit for new television broadcast station (Channel 38):

It is ordered, This 31st day of August 1966, by the Hearing Examiner on his own motion that the prehearing conference in the above-entitled matter now scheduled for September 2, 1966, is rescheduled to commence at 9 a.m., September 13, 1966, and the hearing now scheduled for September 13, 1966, is postponed to a date to be announced in a subsequent order.

Released: September 1, 1966.

FEDERAL COMMUNICATIONS
COMMISSION,
[SEAL] BEN F. WAPLE,
Secretary.

[F.R. Doc. 66-9827; Filed, Sept. 7, 1966;
8:49 a.m.]

[Docket No. 16792; FCC 66M-1164]

CITY OF CAMDEN, N.J., AND L & P BROADCASTING CORP.

Order Continuing Prehearing Conference

In re application of City of Camden (Assignor), and L & P Broadcasting Corporation (Assignee), Docket No. 16792, File No. BAL-5702; for assignment of license of Station WCAM, Camden, N.J.:

It is ordered, This 1st day of September 1966, on the Chief Hearing Examiner's own motion, that the hearing conference in the above-entitled proceeding, which heretofore was scheduled to be convened at 9 a.m., September 8, 1966, is continued to 9 a.m., September 15, 1966.

Released: September 1, 1966.

FEDERAL COMMUNICATIONS
COMMISSION,
[SEAL] BEN F. WAPLE,
Secretary.

[F.R. Doc. 66-9828; Filed, Sept. 7, 1966;
8:50 a.m.]

[Docket No. 15461 etc.; FCC 66M-1169]

CHAPMAN RADIO AND TELEVISION CO. ET AL.

Order After Prehearing Conference

In re applications of William A. Chapman and George K. Chapman doing business as Chapman Radio and Television Co., Homewood, Ala., Docket No. 15461, File No. BPCT-3282; Tele-Mac of Birmingham, Inc., Birmingham, Ala., Docket No. 16759, File No. BPCT-3705; Alabama Television, Inc., Birmingham, Ala., Docket No. 16760, File No. BPCT-3706; Birmingham Broadcasting Co., Birmingham, Ala., Docket No. 16761, File No. BPCT-3707; for construction permit for new television broadcast station; Birmingham Television Corp. (WBMG), Birmingham, Ala., Docket No. 16758, File No. BPCT-3663, for modification of construction permit.

The Hearing Examiner having under consideration the prehearing conference in the above-entitled proceeding held today:

It is ordered, This 2d day of September 1966, that the hearing is postponed from October 4, 1966, and will be convened instead at 10 a.m., Monday, December 5, 1966, at the Commission's offices, Washington, D.C.; and

It is ordered further, That the parties or their counsel will exchange all exhibits, with one copy of each provided the presiding officer, by November 1, at which time they will also provide lists to each other and the Examiner of the witnesses they propose to produce in supplementation of their direct cases and statements of the scope of each witness' testimony; that counsel will notify one another informally of the names of witnesses desired for cross-examination by November 21; and that in all respects the rulings, agreements and understandings set out in the transcript of today's prehearing conference will be adhered to with the same force and effect as if these were set forth herein verbatim.

Released: September 2, 1966.

FEDERAL COMMUNICATIONS
COMMISSION,
[SEAL] BEN F. WAPLE,
Secretary.

[F.R. Doc. 66-9829; Filed, Sept. 7, 1966;
8:50 a.m.]

[Docket Nos. 16787, 16788; FCC 66M-1159]

HARRISCOPE, INC., AND FAMILY BROADCASTING, INC.

Order Continuing Hearing

In re applications of Harriscopes, Inc., Casper, Wyo., Docket No. 16787, File No. BP-16713; Family Broadcasting, Inc., LaGrange, Wyo., Docket No. 16788 File No. BP-17204; for construction permits.

Pursuant to a prehearing conference in this proceeding as of this date: *It is ordered*, This 1st day of September 1966,

that the hearing now scheduled for October 4, 1966, be and the same is hereby rescheduled for November 28, 1966, 10 a.m., in the Commission's offices, Washington, D.C.

Released: September 1, 1966.

FEDERAL COMMUNICATIONS
COMMISSION,
[SEAL] BEN F. WAPLE,
Secretary.

[F.R. Doc. 66-9830; Filed, Sept. 7, 1966;
8:50 a.m.]

FEDERAL POWER COMMISSION

[Docket Nos. RI67-39 etc.]

ASHLAND OIL & REFINING CO. ET AL.

Order Providing for Hearings on and Suspension of Proposed Changes in Rates¹

AUGUST 30, 1966.

The Respondents named herein have filed proposed increased rates and

charges of currently effective rate schedules for sales of natural gas under Commission jurisdiction, as set forth in Appendix A hereof.

The proposed changed rates and charges may be unjust, unreasonable, unduly discriminatory, or preferential, or otherwise unlawful.

The Commission finds: It is in the public interest and consistent with the Natural Gas Act that the Commission enter upon hearings regarding the lawfulness of the proposed changes, and that the supplements herein be suspended and their use be deferred as ordered below.

The Commission orders:

(A) Under the Natural Gas Act, particularly sections 4 and 15, the regulations pertaining thereto (18 CFR Ch. I), and the Commission's rules of practice and procedure, public hearings shall be held concerning the lawfulness of the proposed changes.

(B) Pending hearings and decisions thereon, the rate supplements herein are suspended and their use deferred until date shown in the "Date Suspended Until" column, and thereafter until made effective as prescribed by the Natural Gas Act.

(C) Until otherwise ordered by the Commission, neither the suspended supplements, nor the rate schedules sought to be altered, shall be changed until disposition of these proceedings or expiration of the suspension period.

(D) Notices of intervention or petitions to intervene may be filed with the Federal Power Commission, Washington, D.C. 20426, in accordance with the rules of practice and procedure (18 CFR 1.8 and 1.37(f)) on or before October 12, 1966.

By the Commission.

[SEAL] JOSEPH H. GUTRIE,
Secretary.

APPENDIX A

Docket No.	Respondent	Rate schedule No.	Supplement No.	Purchaser and producing area	Amount of annual increase	Date filing tendered	Effective date unless suspended	Date suspended until	Cents per Mcf		Rate in effect subject to refund in docket Nos.
									Rate in effect	Proposed increased rate	
RI67-39	Ashland Oil & Refining Co., Post Office Box 1503, Houston, Tex. 77001.	80	5	Michigan Wisconsin Pipe Line Co. (Northeast Selling Field, Major County, Okla.) (Oklahoma "Other" Area).	\$754	8-2-66	9-2-66	2-2-67	\$16.56	\$19.64	
	do.	162	5	Arkansas Louisiana Gas Co. (Star Field, Kingfisher County, Okla.) (Oklahoma "Other" Area).	2,520	8-1-66	9-1-66	2-1-67	15.0	\$16.8	
	do.	153	3	Panhandle Eastern Pipe Line Co. (Putnam Field, Dewey County, Okla.) (Oklahoma "Other" Area).	3,378	8-2-66	9-2-66	2-2-67	\$17.5	\$19.8	
RI67-40	Cecil Burton (Operator), et al. d.b.a. Pickrell Drilling Co., 705 Fourth National Bank Bldg., Wichita, Kans. 67202.	1	11	Cities Service Gas Co. (North Medicine Field, Barber County, Kans.).	1,370	8-8-66	9-8-66	2-8-67	\$12.0	\$14.0	
RI67-41	Tidewater Oil Co., Post Office Box 1404, Houston, Tex. 77001, Attn: Mr. A. M. Mouser.	100	2	Tennessee Gas Pipeline Co., a division of Tenneco, Inc. (Callou Island Field, Terrebonne Parish, La.) (South Louisiana).	777	8-15-66	9-15-66	2-15-67	\$18.5	\$19.5	
RI67-42	Occidental Petroleum Corp. (Operator), et al., 5000 Stockdale Highway, Bakersfield, Calif. 93309.	7	5	Valley Gas Transmission, Inc. (Ramirena Northeast and C. A. Winn Fields, Live Oak County, Tex.) (R.R. District No. 2).	1,870	8-15-66	9-15-66	2-15-67	14.0	\$15.0	

¹ The stated effective date is the effective date proposed by Respondent.

² "Fractured" rate increase. Includes 16.89 cents base rate plus 1.01 cents tax reimbursement and 1.50 cents upward B.t.u. adjustment. Seller is contractually due a base rate of 19.5 cents plus tax reimbursement and B.t.u. adjustment, which is the initial contract rate.

³ Pressure base is 14.65 p.s.i.a.

⁴ Subject to upward B.t.u. adjustment of 1/100 cent for each additional B.t.u. in excess of 1000 B.t.u.'s per cubic foot and proportionate downward B.t.u. adjustment from base rate for gas containing less than 1000 B.t.u.'s per cubic foot.

⁵ Permanently certificated initial rate which includes 15.0 cents base rate inclusive of tax reimbursement plus 1.50 cents upward B.t.u. adjustment (present B.t.u. content=1156 B.t.u.'s per cubic foot).

⁶ Respondent filing from permanently certificated rate to initial contract rate.

⁷ Includes 15.0 cents base rate plus upward B.t.u. adjustment before increase and 17.0 cents base rate plus upward B.t.u. adjustment after increase (present B.t.u. content of gas is 1168 B.t.u.'s per cubic foot).

Cecil Burton (Operator), et al., doing business as Pickrell Drilling Co. (Burton) request a retroactive effective date of December 23, 1964, the contractually provided effective date, for their proposed rate increase. Good cause has not been shown for waiving the 30-day notice requirement provided in section 4(d) of the Natural Gas Act to permit an earlier effective date for Burton's rate filing and such request is denied.

All of the producers' proposed increased rates and charges exceed the applicable area price levels for increased rates as set forth

⁸ Does not consolidate for hearing or disposal of the several matters herein.

in the Commission's statement of general policy No. 61-1, as amended (18 CFR Ch. I, Pt. 2, § 2.56).

[F.R. Doc. 66-9747; Filed, Sept. 7, 1966;
8:45 a.m.]

[Docket Nos. G-6352 etc.]

CONTINENTAL OIL CO. ET AL.

Findings and Order After Hearing

AUGUST 30, 1966.

Findings and order after statutory hearing issuing certificates of public con-

venience and necessity, reinstating certificate, amending certificates, permitting and approving abandonment of service, terminating certificates, substituting respondent, making successor co-respondent, redesignating proceedings, requiring filing of agreements and undertakings, accepting offer of settlement and accepting related rate schedules and supplements for filing.

Each of the Applicants listed herein has filed an application pursuant to section 7 of the Natural Gas Act for a cer-

⁹ Base rate subject to proportionate upward and downward B.t.u. adjustment for gas containing more or less than 1000 B.t.u.'s per cubic foot.

¹⁰ Filing completed Aug. 18, 1966.

¹¹ Includes Amendment dated Oct. 30, 1964, which provides for increased rate.

¹² The stated effective date is the first day after expiration of the statutory notice.

¹³ Renegotiated rate increase.

¹⁴ Subject to downward B.t.u. adjustment.

¹⁵ Periodic rate increase.

¹⁶ Pressure base is 15.025 p.s.i.a.

¹⁷ Inclusive of 1.5 cents per Mcf tax reimbursement.

¹⁸ Settlement rate as provided by Commission order issued June 15, 1962, as amended, in Docket Nos. G-13310, et al.

tificate of public convenience and necessity authorizing the sale and delivery of natural gas in interstate commerce, for permission and approval to abandon service, or a petition to amend an existing certificate authorization, all as more fully described in the respective applications and petitions (and any supplements or amendments thereto) which are on file with the Commission.

The Applicants herein have filed related FPC Gas Rate Schedules and propose to initiate or abandon, add or delete natural gas service in interstate commerce as indicated by the tabulation herein. All sales certificated herein are either equal to or below the ceiling prices established by the Commission's statement of general policy No. 61-1, as amended, or involve sales for which permanent certificates have been previously issued; except that initial sales from the Permian Basin area of Texas are authorized to be made at or below the applicable area base rates and under the conditions prescribed in Opinion Nos. 468 and 468-A.

Houston Natural Gas Production Company (Operator), et al., Applicant in Docket No. G-10181, proposes to continue the sale of natural gas heretofore authorized in said docket and made pursuant to Emerald Oil & Carbonic Co. (Operator), et al., FPC Gas Rate Schedule No. 5. Said rate schedule will be redesignated as that of Houston. Emerald filed a change in rate under said rate schedule which has been suspended in Docket No. RI63-326¹ and has not been made effective. Accordingly, Houston will be substituted in lieu of Emerald as respondent in said proceeding and the proceeding will be redesignated.

John A. Hairford, Applicant in Docket Nos. CI67-23 and CI67-24, proposes to continue in part sales of natural gas authorized in Docket Nos. G-3673 and G-10474, respectively, to be made pursuant to Petroleum, Inc. (Operator), et al., FPC Gas Rate Schedule Nos. 3 and 5, respectively. The contracts comprising said rate schedules will also be accepted for filing as rate schedules of Applicant. The presently effective rates under said rate schedules are in effect subject to refund in Docket Nos. RI63-362² (Petroleum, Inc. (Operator), et al., FPC Gas Rate Schedule No. 5) and RI63-391² (Petroleum, Inc. (Operator), et al., FPC Gas Rate Schedule No. 3). Therefore, Applicant will be made co-respondent in said proceedings, the proceedings will be redesignated, and Applicant will be required to file agreements and undertakings to assure the refunds of any amounts collected by him in excess of the amounts determined to be just and reasonable in said proceedings.

By order issued July 2, 1963, in Docket No. G-11174, et al., J. Ray McDermott & Co., Inc. (Operator), et al., was authorized in Docket No. G-17239 to continue the sale of natural gas theretofore authorized in Docket No. G-4180 to be made pursuant to Heep Oil Corp. and Herman

F. Heep FPC Gas Rate Schedule No. 3 and the certificate issued in Docket No. G-4180 was vacated. Subsequent to the vacation of the certificate in Docket No. G-4180 Herman F. Heep Estate, et al., filed a rate schedule to continue in part the sale of natural gas theretofore authorized in Docket No. G-4180. A review of the records of the Commission reveals that in Docket No. G-17239 J. Ray McDermott sought authorization to continue only the sale of natural gas from the interests of Heep Oil Corp. and not from the interests of Herman F. Heep and that the certificate issued in Docket No. G-4180 should not have been vacated. Therefore, the certificate issued in Docket No. G-4180 will be reinstated and amended by deleting therefrom authorization to sell natural gas from the interests assigned to J. Ray McDermott and to LAB Oil Co., Applicant herein in Docket No. CI66-713.

On June 27, 1966, LAB Oil Co. filed an offer of settlement in Docket No. CI66-713 pursuant to § 1.18(e) of the Commission's rules of practice and procedure with respect to sales it proposes to continue as successor in interest to J. Ray McDermott & Co., Inc., which sales were heretofore authorized to be made pursuant to McDermott's FPC Gas Rate Schedule No. 7 at a rate of 17.24347 cents per Mcf at 14.65 p.s.i.a. subject to refund in Docket Nos. G-19873 and RI60-341. LAB is presently selling gas from the acreage acquired from McDermott pursuant to a temporary certificate issued March 25, 1966, in Docket No. CI66-713 at the 17.24347-cent rate subject to refund. Under the terms of the offer, LAB proposes to eliminate the periodic price escalation clauses from the subject rate schedules and to substitute therefor in each a life-of-contract rate of 15.0 cents per Mcf rate. Additionally, it proposes to refund all amounts of monies collected in excess of the settlement rates, subject to refund, with applicable interest. The refund amount will be approximately \$1,550 exclusive of interest, and LAB's current annual revenue from these sales will be reduced by \$3,000. LAB's proposal is consistent with the provisions of the Second and Ninth Amendments to the Commission's statement of general policy No. 61-1 (18 CFR 2.56) and we shall approve the same. However, we desire to make it clear that acceptance of LAB's offer of settlement shall not be construed as approval of any future increased rates that may be filed by LAB under the subject rate schedules in accordance with its reservation of the right to file increases to cover possible future tax increases, and is without prejudice to any findings or order of the Commission in any future proceedings, including area rate or other similar proceedings, involving LAB's rates and rate schedules.

After due notice, a petition to intervene by Long Island Lighting Co. and a notice of intervention by The Public Service Commission of the State of New York were filed in Docket No. CI66-713, in the matter of the application filed February 7, 1966, in said docket. A petition to intervene by Long Island Lighting Co. was filed in Docket No. CI66-

1302, in the matter of the application filed June 22, 1966, in said docket. The petitions to intervene and the notice of intervention have been withdrawn and no other petitions to intervene, notices of intervention, or protests to the granting of any of the respective applications or petitions in this order have been received.

At a hearing held on August 25, 1966, the Commission on its own motion received and made a part of the record in these proceedings all evidence, including the applications, amendments and exhibits thereto, submitted in support of the respective authorizations sought herein, and upon consideration of the record.

The Commission finds:

(1) Each Applicant herein is a "natural-gas company" within the meaning of the Natural Gas Act as heretofore found by the Commission or will be engaged in the sale of natural gas in interstate commerce for resale for ultimate public consumption, subject to the jurisdiction of the Commission, and will therefore, be a "natural-gas company" within the meaning of said Act upon the commencement of the service under the respective authorizations granted hereinafter.

(2) The sales of natural gas hereinbefore described, as more fully described in the respective applications, amendments and/or supplements herein, will be made in interstate commerce, subject to the jurisdiction of the Commission, and such sales by the respective Applicants, together with the construction and operation of any facilities subject to the jurisdiction of the Commission necessary therefor, are subject to the requirements of subsections (c) and (e) of section 7 of the Natural Gas Act.

(3) The sales of natural gas by the respective Applicants, together with the construction and operation of any facilities subject to the jurisdiction of the Commission necessary therefor, are required by the public convenience and necessity and certificates therefore should be issued as hereinafter ordered and conditioned.

(4) The respective Applicants are able and willing properly to do the acts and to perform the services proposed and to conform to the provisions of the Natural Gas Act and the requirements, rules, and regulations of the Commission thereunder.

(5) It is necessary and appropriate in carrying out the provisions of the Natural Gas Act and the public convenience and necessity require that the certificate heretofore issued in Docket No. G-4180 should be reinstated and amended as hereinafter ordered.

(6) It is necessary and appropriate in carrying out the provisions of the Natural Gas Act and the public convenience and necessity require that the certificate authorizations heretofore issued by the Commission in Docket Nos. G-6352, G-8592, G-10181, G-12663, G-12912, G-16139, G-18597, CI61-709, CI63-172, CI63-523, CI63-966, CI64-530, CI64-1216, CI64-1249, CI65-901, CI65-920, CI65-1303, CI65-1336, CI66-361, CI66-393, and

¹ Consolidated with Docket No. AR64-2, et al.

² Consolidated with Docket No. AR64-1, et al.

CI66-525 should be amended as herein-after ordered and conditioned.

(7) It is necessary and appropriate in carrying out the provisions of the Natural Gas Act that the certificates issued in the following dockets should be amended to reflect the deletion of acreage where new certificates are issued herein to authorize service from the subject acreage:

Amend to delete acreage	New certificates
G-3673	CI67-23
G-8789	CI66-1282
G-10474	CI67-24
G-17239	CI66-713
CI62-78	CI67-15
CP63-193	CI67-43

(8) The sales of natural gas proposed to be abandoned by the respective Applicants, as hereinbefore described, all as more fully described in the tabulation herein and in the respective applications, are subject to the requirements of subsection (b) of section 7 of the Natural Gas Act, and such abandonments should be permitted and approved as hereinafter ordered.

(9) It is necessary and appropriate in carrying out the provisions of the Natural Gas Act that the certificates of public convenience and necessity heretofore issued to the respective Applicants relating to the abandonments hereinafter permitted and approved should be terminated.

(10) It is necessary and appropriate in carrying out the provisions of the Natural Gas Act that Houston Natural Gas Production Co. (Operator), et al., should be substituted in lieu of Emerald Oil & Carbonic Co. (Operator), et al., as respondent in the proceeding pending in Docket No. RI63-326 and that said proceeding should be redesignated accordingly.

(11) It is necessary and appropriate in carrying out the provisions of the Natural Gas Act that John A. Hairford should be co-respondent in the proceedings pending in Docket Nos. RI63-362 and RI63-391, that said proceedings should be redesignated accordingly, and that he should be required to file agreements and undertakings in said proceedings.

(12) The proposed settlement in Docket No. CI66-713 on the basis described herein, as more fully set forth in the offer of settlement filed with the Commission by LAB on June 27, 1966, is consistent with the statement of general policy No. 61-1, as amended, 18 CFR 2.56, and approval thereof as made effective and hereinafter ordered is in the public interest and is appropriate to carry out the provisions of the Natural Gas Act.

(13) It is necessary and appropriate in carrying out the provisions of the Natural Gas Act that the respective related rate schedules and supplements as designated or redesignated in the tabulation herein should be accepted for filing as hereinafter ordered.

The Commission orders:

(A) Certificates of public convenience and necessity are issued upon the terms and conditions of this order, authorizing

the sales by the respective Applicants herein of natural gas in interstate commerce for resale, together with the construction and operation of any facilities subject to the jurisdiction of the Commission necessary for such sales, all as hereinbefore described and as more fully described in the respective applications, amendments, supplements and exhibits in this proceeding.

(B) The certificates granted in paragraph (A) above are not transferable and shall be effective only so long as Applicants continue the acts or operations hereby authorized in accordance with the provisions of the Natural Gas Act and the applicable rules, regulations, and orders of the Commission.

(C) The grant of the certificates issued in paragraph (A) above shall not be construed as a waiver of the requirements of section 4 of the Natural Gas Act or of Part 154 or Part 157 of the Commission's regulations thereunder, and is without prejudice to any findings or orders which have been or may hereafter be made by the Commission in any proceeding now pending or hereafter instituted by or against the respective Applicants. Further, our action in this proceeding shall not foreclose nor prejudice any future proceedings or objections relating to the operation of any price or related provisions in the gas purchase contracts herein involved. Nor shall the grant of the certificates aforesaid for service to the particular customers involved imply approval of all of the terms of the respective contracts particularly as to the cessation of service upon termination of said contracts, as provided by section 7(b) of the Natural Gas Act. Nor shall the grant of the certificates aforesaid be construed to preclude the imposition of any sanctions pursuant to the provisions of the Natural Gas Act for the unauthorized commencement of any sales of natural gas subject to said certificates.

(D) The grant of the certificates issued herein on all applications filed after April 15, 1965, is upon the condition that no increase in rate which would exceed the ceiling prescribed for the given area by paragraph (d) of the Commission's statement of general policy No. 61-1, as amended, shall be filed prior to the applicable dates as indicated by footnotes 1 and 13 in the attached tabulation.

(E) The initial rate for sales authorized in Docket No. CI66-1087 shall be the applicable base area rate prescribed in Opinion No. 468, as modified by Opinion No. 468-A, as adjusted for quality, or the contract rate, whichever is lower; and no increase in rate in excess of said initial rate shall be filed before January 1, 1968.

(F) If the quality of the gas delivered by Applicant in Docket No. CI66-1087 deviates at any time from the quality standards set forth in Opinion No. 468, as modified by Opinion No. 468-A, so as to require a downward adjustment of the existing rate, a notice of change in rate shall be filed pursuant to the provisions of section 4 of the Natural Gas Act; *Provided, however*, That adjustments reflecting changes in B.t.u. content of the

gas shall be computed by the applicable formula and charged without the filing of notice of change in rate.

(G) Applicant in Docket No. CI66-1087 shall file a rate schedule quality statement within 45 days from the date of initial delivery.

(H) Certificates are issued herein to the respective Applicants in Docket Nos. CI66-1041, CI66-1138, CI66-1335, CI66-1336, CI66-1337, CI66-1338, CI66-1339, CI66-1340, CI66-1341, and CI66-1342 authorizing the continuance of sales which were initiated without prior Commission authorization.

(I) Certificates are issued herein to the respective Applicants in Docket Nos. CI66-1233, CI66-1344, and CI66-1345 authorizing the continuance of sales being rendered on June 7, 1954.

(J) Applicants in Docket Nos. CI66-1331, CI67-33, and CI67-41 shall submit billing statements for the first month of service.

(K) The certificate issued herein in Docket No. CI66-1282 is issued at the rate of 15.0 cents per Mcf at 14.65 p.s.i.a. subject to B.t.u. adjustment.

(L) The certificates heretofore issued in Docket Nos. G-6352, G-8592, G-16139, CI63-172, CI63-523, CI65-1336, and CI66-525 are amended by adding thereto or deleting therefrom authorization to sell natural gas to the same purchasers and in the same areas as covered by the original authorizations, pursuant to the rate schedule supplements as indicated in the tabulation herein.

(M) The certificate heretofore issued in Docket No. G-4180 and vacated by order issued July 2, 1963, in Docket No. G-11174, et al., is reinstated and designated as that of Herman F. Heep Estate, et al., and is amended by deleting therefrom authorization to sell natural gas from the interests of Heep Oil Corp. assigned to J. Ray McDermott & Co., Inc. (Operator), et al., authorized in Docket No. G-17239, and from the interests of Herman F. Heep Estate assigned to LAB Oil Co., Applicant herein in Docket No. CI66-713.

(N) The certificates heretofore issued in the following dockets are amended to reflect the deletion of acreage where new certificates are issued herein to authorize service from the subject acreage:

Amend to delete acreage	New certificates
G-3673	CI67-23
G-8789	CI66-1282
G-10474	CI67-24
G-17239	CI66-713
CI62-78	CI67-15
CP63-193	CI67-43

* The certificate issued herein to Applicant pertains only to the interest in the assigned acreage to a depth of 9,431 feet.

(O) The certificates heretofore issued in Docket Nos. G-10181, G-12663, G-12912, G-18597, CI61-709, CI63-966, CI64-530, CI64-1216, CI64-1249, CI65-901, CI65-920, CI65-1303, CI66-361, and CI66-393 are amended by changing the certificate holders to the respective successors in interest as indicated in the tabulation herein.

(P) The authorization granted in paragraph (O) above in Docket No. CI66-393, involving the sale of gas by

Texas Gas Exploration Corp. (Operator), et al., to its parent, Texas Gas Transmission Corp., determines the rate which legally may be paid by the buyer to the seller, but is without prejudice to any action which the Commission may take in any rate proceeding involving either company.

(Q) Permission for and approval of the abandonment of service by the respective Applicants, as hereinbefore described, all as more fully described in the tabulation herein and in the respective applications are granted.

(R) The abandonment herein permitted and approved in Docket No. CI67-40 does not relieve Applicant therein from any refund obligation in the related rate suspension proceeding in Docket No. RI65-348.

(S) The certificates heretofore issued in Docket Nos. G-4366,² G-7562, G-17249, CI60-283, CI63-124, and CI64-1000 are terminated.

(T) Houston Natural Gas Production Co. (Operator), et al., is substituted in lieu of Emerald Oil & Carbonic Co. (Operator), et al., as respondent in the proceeding pending in Docket No. RI63-326 and said proceeding is redesignated accordingly.⁴

(U) John A. Hairford shall be co-respondent in the proceedings pending in Docket Nos. RI63-362 and RI63-391 and the proceedings are redesignated accordingly.⁵

(V) Within 30 days from the issuance of this order John A. Hairford shall execute, in the form set out below, and shall file with the Secretary of the Commission acceptable agreements and undertakings in Docket Nos. RI63-362 and RI63-391 to assure the refunds of any amounts collected by him, together with interest at the rate of 7 percent per annum, for sales pursuant to his FPC Gas Rate Schedule Nos. 2 and 1, respectively, in excess of the amounts determined to be just and reasonable in said proceedings. Unless notified to the contrary by the Secretary of the Commission within 30 days from the date of submission, such agreements and undertakings shall be deemed to have been accepted for filing.

(W) John A. Hairford shall comply with the refunding and reporting procedure required by the Natural Gas Act and § 154.102 of the regulations thereunder, and the agreements and undertakings filed by him in Docket Nos. RI63-362 and RI63-391 shall remain in full force and effect until discharged by the Commission.

(X) The offer of settlement filed with the Commission by LAB on June 27, 1966, is approved in accordance with the provisions of this order. The acceptance by the Commission of LAB's offer of settlement, as amended, is without prejudice to any findings or determinations that may be made in any proceeding now pending, or hereafter instituted by or against LAB and is without prejudice to claims or contentions which may be made by LAB, the Commission staff, or any affected party hereto, in any proceedings.

(Y) LAB shall file, within 30 days from the date of issuance of this order, notices of change in rates under its FPC Gas Rate Schedules to reflect the settlement rates and executed contractual amendments in accordance with the terms of its settlement proposal and as approved herein. The notices of change and contractual amendments shall be submitted in accordance with Part 154 of the Commission's regulations under the Natural Gas Act.

(Z) LAB shall compute the difference between the rates collected subject to refund and the settlement rate with applicable interest to the date of this order, and shall within 45 days from the date of issuance of this order submit a report

to the Commission, with a copy to Tennessee Gas Pipeline Co., a division of Tenneco Inc., setting out the amount of refunds (showing separately the principal and applicable interest) the bases used for such determination, the period covered, and 10 days thereafter shall refund such monies to Tennessee and shall submit to the Commission a copy of a letter from Tennessee agreeing to the correctness of such amounts.

(AA) The respective related rate schedules and supplements as indicated in the tabulation herein are accepted for filing; further, the rate schedules relating to the successions herein are redesignated and accepted, subject to the applicable Commission regulations under the Natural Gas Act to be effective on the dates as indicated in the tabulation herein.

By the Commission.

[SEAL] JOSEPH H. GUTRIDE,
Secretary.

Docket No. and date filed	Applicant	Purchaser, field, and location	FPC rate schedule to be accepted		
			Description and date of document	No.	Supp.
G-6352 C 6-20-66 ¹	Continental Oil Co.	United Gas Pipe Line Co.	Letter agreement 5-10-66.	207	13
			Letter agreement 6-6-66. ²	207	14
G-8592 C 6-17-66 ¹	Sun Oil Co. (Southwest Division).	United Gas Pipe Line Co., Maxie-Pistol Ridge Field, Forrest, Lamar, and Pearl River Counties, Miss.	Amendment 5-25-66 ³	66	12
G-18181 E 10-22-65	Houston Natural Gas Production Co. (Operator), et al. (successor to Emerald Oil & Carbonic Co. (Operator), et al.).	Texas Eastern Transmission Corp., Salem Field, Victoria County, Tex.	Emerald Oil & Carbonic Co. (Operator), et al., FPC GRS No. 2.	17	
			Supplement Nos. 1-8.	17	1-8
			Notice of succession 10-20-65.		
			Assignment 10-1-63 ⁴	17	9
			Assignment 11-1-63 ⁵	17	10
			Effective date: 11-1-63.		
G-12663 E 6-27-66	Herman Geo. Kaiser, (Operator), et al. (successor Shell Oil Co.).	Northern Natural Gas Co., Gingrich and F. Finney Units, Finney County, Kans.	Shell Oil Co., FPC GRS No. 158.	1	
			Supplement Nos. 1-2.	1	1-2
			Notice of succession (undated).		
			Assignment 5-31-66 ⁶	1	3
			Effective date: 6-1-66.		
G-12912 E 6-21-66	David E. Barr (successor to Norristown Gas Co., et al.).	Consolidated Gas Supply Corp., Sherman District, Calhoun County, W. Va.	Norristown Gas Co., et al., FPC GRS No. 1.	2	
			Supplement No. 1.	2	1
			Notice of succession 6-20-66.		
			Assignment 3-8-66.	2	2
			Effective date: 3-8-66.		
G-16139 D 6-27-66	Gulf Oil Corp.	Transwestern Pipeline Co., Panhandle Area, Hemphill County, Tex.	Letter agreement 6-8-66. ⁷	195	28
G-18597 E 6-13-66	Thomas A. Dugan (Operator), et al. (successor to Lakeland Petroleum Corp. (Operator), et al.).	El Paso Natural Gas Co., Cavilan Pictured Cliffs Field, Rio Arriba County, N. Mex.	Lakeland Petroleum Corp. (Operator), et al., FPC GRS No. 12.	5	
			Supplement Nos. 1-2.	5	1-2
			Notice of succession 6-6-66.		
			Letter agreement 7-5-60. ⁸	5	3
			Assignment 10-16-65. ⁹	5	4
			Effective date: 10-16-65.		
			Assignment 7-7-65. ¹⁰	248	4
			Effective date: 7-7-65.		
CI60-578 D 7-26-65	Humble Oil & Refining Co.	Panhandle Eastern Pipe Line Co., East Mokane Field, Beaver County, Okla.	Herman Brown Estate, FPC GRS No. 9.	18	
CI61-700 E 7-5-66	George R. Brown (successor to Herman Brown Estate).	Texas Gas Transmission Corp., North Rousseau Field, LaFayette Parish, La.	Supplement Nos. 1-3.	18	1-3
			Notice of succession 6-29-66.		
			Assignment 12-30-64.	18	4
			Effective date: 12-31-64.		

Filing code: A—Initial service.
B—Abandonment.
C—Amendment to add acreage.
D—Amendment to delete acreage.
E—Succession.
F—Partial succession.

See footnotes at end of table.

¹ The certificate in Docket No. G-4366 is terminated only insofar as it pertains to sales covered by Supplement No. 6 to FPC Gas Rate Schedule No. 37.

² Houston Natural Gas Production Co. (Operator), et al.

³ Petroleum, Inc. (Operator), et al., and John A. Hairford.

NOTICES

Docket No. and date filed	Applicant	Purchaser, field, and location	FPC rate schedule to be accepted		Docket No. and date filed	Applicant	Purchaser, field, and location	FPC rate schedule to be accepted	
			Description and date of document	No.				Description and date of document	No.
CI63-172 D 6-23-66	Mobil Oil Corp. (partial abandonment).	Natural Gas Pipeline Co. of America, Bryan Mill Field, Cass County, Tex.	Notice of partial cancel- lation 6-22-66. ¹	317	CI66-393 E 6-27-66	Texas Gas Exploration Corp. (Operator), et al. (successor to Mar- shall Burlew (Oper- ator), et al.).	Texas Gas Transmission Corp., Midland Field, Midland County, Ks.	Marshall Burlew (Oper- ator), et al. FPC GRS No. 1. Notice of succession 6- 27-66.	16
CI63-523 C 6-29-66 ¹³	George R. Brown (Op- erator), et al.	Transcontinental Gas Pipeline Corp., Live Oak Field, Vermilion Parish, La.	Amendatory agreement 6-7-66. ²	12	CI66-525 C 6-27-66 ¹	Rock Island Oil & Re- fining Co., Inc.	El Paso Natural Gas Co., Basin-Dakota Field, San Juan County, N. Mex.	Assignment 5-25-66. Effective date: 12-17-65. Supplemental agree- ment 4-18-66. ³	16 12
CI63-966 E 6-21-66	Howard W. Sharpley (successor to Biogoo, Inc., et al.).	Consolidated Gas Supply Corp., Glenville Dis- trict, Gilmer County, W. Va.	Notice of succession 6-31-66. Assignment 5-14-62. ¹⁴ Assignment 9-21-62. ¹⁵ Assignment 10-7-64. ¹⁶ Effective date: 8-30-65. Amendment 6-20-66. ¹⁷	5 5 5 5 5	A CI66-713 (G-4180) F 2-7-66	LAB Oil Co.	Tennessee Gas Pipeline Co., a division of Ten- neco, Inc., West Cal- labasco Field, San Patricio County, Tex.	Contract 1-7-53. ¹⁸ Letter agreement 11-4- 53. ¹⁹ Notice of change 9-21- 56. Amendment 5-31-61. ²⁰ Notice of change 9-23- 59. ²¹ Notice of change 4-14- 60. ²² Assignment 12-15-65. ²³ Contract 7-12-63. ²⁴	13 13 13 13 13 13 13 2
CI64-530 E 6-21-66	Roy C. and Freeda M. Davison (successor to George T. Hill, agent for Rigall-Griffith Oil & Gas Co.).	Consolidated Gas Supply Corp., Freeman Creek District, Lewis County, W. Va.	Notice of succession 6-8-66. Assignments 2-23-66. ¹⁸ Effective date: 2-23-66. Letter agreement 6-3-66. ¹⁹	1 1 1	CI66-1041 A 4-28-66 ¹⁸	Dominion Oil & Gas Co.	Carnegie Natural Gas Co., Freemans Creek Dis- trict, Lewis County, W. Va.	Contract 3-25-66. ¹ Contract 10-10-60. ²	1 1
CI64-1216 E 6-27-66	Herman Geo. Kaiser (Operator), et al. (successor to Shell Oil Co.).	Kansas Colorado Util- ities, Inc., West Sparks Field, Stanton, County, Kans.	Shell Oil Co., FPC GRS No. 300. Supplement No. 1. Notice of succession (undated). Assignment 5-31-66. ³ Effective date: 6-1-66. Hays & Company, agent for Delta Petro- leum Co., et al., FPC GRS No. 27.	2 2 2 1	CI66-1138 A 5-11-66 ¹⁸	John M. Traxler.	El Paso Natural Gas Co., Spraberry Trend Area, Reagan County, Tex. Carnegie Natural Gas Co., Cass District, Monongalia County, W. Va. Lone Star Gas Co., East Panhandle Field, Col- lingworth County, Tex.	Contract 3-10-30.	1
CI64-1249 E 6-21-66	A. A. Pursley (suc- cessor to Hays & Co., agent for Delta Petro- leum Co., et al.).	Consolidated Gas Supply Corp., Center District, Gilmer County, W. Va.	Notice of succession 6-8-66. Assignments 11-17-65. ²⁰ Assignment 12-22-66. ²¹ Assignments 1-5-66. ²² Assignment 1-13-66. ²³ Effective date: 3-1-66. George Moses, FPC GRS No. 9.	1 1 1 1 1	CI66-1161 (G-7562) B 5-20-66	T. F. Hunter, estate.	Pennzoil Co., Murphy District, Ritchie Coun- ty, W. Va. Colorado Interstate Gas Co., Greenwood Field, Morrison County, Kans.	Notice of cancellation 5-16-66. ²⁴	1
CI65-901 E 6-21-66	Reeves Lewenthal (suc- cessor to George Moses).	Consolidated Gas Supply Corp., Sherman and Center Districts, Cal- houn and Gilmer Counties, W. Va.	Assignment 10-5-65. ²⁴ Assignment 10-5-66. ²⁵ Carillo Petroleum Corp., FPC GRS No. 1. Notice of succession 6-15-66. Assignment 4-25-66. ²⁶ Assignment 6-6-66. ²⁷ Effective date: 5-1-66. George Moses, FPC GRS No. 11.	1 1 1 1 1	CI66-1233 A 6-2-66 ¹⁸	H. R. Holden, agent for RMW Lease. Edwin L. Cox (Opera- tor), et al. (successor to Colorado Oil & Gas Co.).	Texas Eastern Transmis- sion Corp., El Pastile County, Tex. Valley Gas Transmission, Inc., Chatham Field, Jackson Parish, La.	Contract 4-18-55. ²⁸ Amendment 6-14-56. Assignment 5-21-54. Assignment 3-4-66. ²⁹ Assignment 3-4-66. ³⁰ Compliance 8-5-66. Contract 5-5-66.	64 64 64 64 64 401
CI65-920 E 6-20-66	Sage Gas Gathering Co. (successor to Carillo Petroleum Corp.).	Valley Gas Transmission, Inc., Buena Sierra Field, Duval County, Tex.	Assignment 10-5-65. ²⁴ Assignment 10-5-66. ²⁵ Carillo Petroleum Corp., FPC GRS No. 1. Notice of succession 6-15-66. Assignment 4-25-66. ²⁶ Assignment 6-6-66. ²⁷ Effective date: 5-1-66. George Moses, FPC GRS No. 11.	1 1 1 1 1	CI66-1302 A 6-22-66 ¹	Humble Oil & Refining Co.	Valley Gas Transmission, Inc., Chatham Field, Jackson Parish, La.	Contract 5-23-66. ³	43
CI65-1203 E 6-21-66	Reeves Lewenthal (suc- cessor to George Moses).	Consolidated Gas Supply Corp., Lee District, Calhoun County, W. Va.	Assignment 10-5-65. ²⁴ Assignment 10-5-66. ²⁵ Letter agreement 4-11- 66. ³	2 2 6	CI66-1305 A 6-23-66 ¹	Placid Oil Co.	El Paso Natural Gas Co., Panhandle Field, Wheeler County, Tex. Northern Natural Gas Co., Catesby Field, Ellis County, Okla. Northern Natural Gas Co., Northeast Catesby Field, Ellis County, Okla.	Contract 6-2-64. ⁴⁰ Assignment 4-10-65. ⁴¹ Assignment 12-14-65. ⁴² Contract 5-2-66. ⁴³	1 1 1 8
CI65-1336 C 6-20-66 ¹	The Waverly Oil Works Co.	Equitable Gas Co., Salt Lick District, Braxton County, W. Va.	Assignment 10-5-65. ²⁴ Assignment 10-5-66. ²⁵ Letter agreement 4-11- 66. ³	2 2 6	CI66-1327 A 6-24-66 ¹	Sun Oil Co. (Southwest Division).	United Gas Pipe Line Co., Baxterville Field, Lamar County, Miss. Northern Natural Gas Co., acreage in Ellis and Woodward Coun- ties, Okla.	Contract 5-9-66. ⁴⁴	134
CI66-361 E 6-21-66	Reeves Lewenthal (suc- cessor to George Moses).	Consolidated Gas Supply Corp., Washington District, Calhoun County, W. Va.	George Moses, FPC GRS No. 12. Notice of succession 6- 9-66. Assignment 10-5-65. ²⁴ Effective date: 10-5-65.	3 3 1	CI66-1339 A 6-27-66 ¹³	Cities Service Oil Co.	United Gas Pipe Line Co., Baxterville Field, Lamar County, Miss. Northern Natural Gas Co., acreage in Ellis and Woodward Coun- ties, Okla.	Contract 5-24-66. ⁴⁵	212
					CI66-1380 A 6-27-66 ¹	Humble Oil & Refining Co.	United Fuel Gas Co., Longview Field, Frank- lin Parish, La.	Contract 6-3-66.	400

See footnotes at end of table.

11779

See footnotes at end of table.

FEDERAL REGISTER, VOL. 31, NO. 174—THURSDAY, SEPTEMBER 8, 1966

- ¹² Two leases covering a total of 197.81 acres expired by their own terms and were surrendered by Mobil; no production has occurred from these leases.
- ¹³ July 1, 1967, moratorium date pursuant to Commission's Statement of General Policy 61-1, as amended.
- ¹⁴ From Shaff Mineral Associates, Inc., to William E. Allen to James J. Major.
- ¹⁵ From Allen and Major to Biogco, Inc.
- ¹⁶ From Biogco to Sharpley.
- ¹⁷ Deletes the L. C. Peters lease which expired due to failure of the predecessor, Biogco, Inc., to drill a well thereon.
- ¹⁸ Various assignments, all dated Feb. 23, 1966, conveying title to subject properties from Arch Riggall, et al., to Roy C. and Freeda M. Davison.
- ¹⁹ Adds acreage.
- ²⁰ Various assignments dated Nov. 17, 1965, conveying title to subject properties from Delta Petroleum Co., et al., to A. A. Pursley.
- ²¹ Assignment dated Dec. 22, 1965, conveying title from Gerald T. Raydon to A. A. Pursley.
- ²² Various assignments dated Jan. 5, 1966, conveying title to subject properties from Irene Ryan, et al., to A. A. Pursley.
- ²³ Assignment dated Jan. 13, 1966, conveying title to remaining subject properties from Delta Petroleum Co. to A. A. Pursley.
- ²⁴ Covers transfer of properties from George Moses to Lewenthal.
- ²⁵ Carrillo Petroleum Corp. assigns property to Kenneth S. Harvey, trustee.
- ²⁶ Kenneth S. Harvey, trustee, assigns property to Sage Gas Gathering Co.
- ²⁷ Ratifies basic contract dated Jan. 7, 1953, between Heep Oil Corp. and Herman F. Heep, sellers, and Tennessee as buyer.
- ²⁸ Currently on file as Herman F. Heep Estate, et al., FPC GRS No. 3 and J. Ray McDermott & Co., Inc. (Operator), et al., FPC GRS No. 7.
- ²⁹ Adds acreage to basic contract. Part of the acreage was assigned to McDermott who ratified Heep's contract and made separate filings.
- ³⁰ Provides for life-of-contract rate of 15 cents under Heep's FPC GRS No. 3 and is applicable to interest assigned by Heep. Heep's certificate in Docket No. G-4180 was vacated but said certificate will be reinstated by this order.
- ³¹ Rate increase to 15.0952 cents under McDermott's FPC GRS No. 7 is subject to refund in Docket No. G-19873.
- ³² Rate increase to 17.24347 cents under McDermott's FPC GRS No. 7 is being collected subject to refund in Docket No. RI60-341. Rate applicable to interest assigned by McDermott, whose certificate is in Docket No. G-17239.
- ³³ Assigns Heep's and McDermott's interests in a lease presently covered by their respective rate schedules.
- ³⁴ Service being rendered without prior Commission authorization.
- ³⁵ By letter filed July 11, 1966, Applicant advised willingness to accept a permanent certificate containing conditions similar to those imposed by Opinion No. 408.
- ³⁶ Production of gas no longer economically feasible.
- ³⁷ Sale being rendered on June 7, 1954.
- ³⁸ Contract between Colorado Oil & Gas Co. and buyer; on file as Colorado Oil & Gas Co., FPC GRS No. 25.
- ³⁹ From Colorado Oil & Gas Co. to Applicant.
- ⁴⁰ From Sam P. Wallingford, Inc., et al., to Applicant.
- ⁴¹ Covers formations from the base of the Lansing of the Pennsylvania Age to the base of the St. Louis zone of the Mississippian System.
- ⁴² Contract between Petroleum Specialty Co. and buyer (has not been filed previously).
- ⁴³ Assignment from Petroleum Specialty Co. to Reese Valley Farms, Inc.
- ⁴⁴ Assignment from Reese, Valley Farms, Inc., to Robinson Petroleum Corp.
- ⁴⁵ Between buyer and Humble Oil & Refining Co.
- ⁴⁶ Source of gas depleted.
- ⁴⁷ Ratifies terms and conditions of contract dated July 3, 1958, between buyer and Edwin G. Bradley.
- ⁴⁸ Contract dedicates only the production from depths of 7,940 feet or less.
- ⁴⁹ Contract dedicates only the production for the Tonkawa and Hoover Formations underlying the acreage committed.
- ⁵⁰ Certificate application filed as Roger M. Wheeler, for himself, and as agent for Harry L. Crosby, Jr., and M.H. Alvarez.
- ⁵¹ Ratifies contract of Dec. 7, 1959 (attached to ratification agreement) between El Paso and Val. R. Reese & Associates, Inc., insofar as it covers Bigbee's interest in acreage previously covered under the contract and also dedicates thereunder certain acreage acquired from California Oil Co. Partially supersedes Standard Oil Co. of Texas, a division of Chevron Oil Co., FPC GRS No. 27 (formerly Standard Oil Co. of Texas, a division of California Oil Co., FPC GRS No. 44).
- ⁵² Assignment of operating rights from California Oil Co. (successor to Standard Oil Co. of Texas) to Harry L. Bigbee.
- ⁵³ Conveys interest from Petroleum, Inc. (Operator), et al., to John A. Hairford; Petroleum's FPC GRS Nos. 3 and 5, respectively.
- ⁵⁴ Leases expired and reverted back to lessor. Service ceased in 1964.
- ⁵⁵ Amends the supplemental agreement dated May 14, 1947.
- ⁵⁶ Amends the contract dated May 14, 1947.
- ⁵⁷ Rate of 12 cents per Mcf collected effective subject to refund in Docket No. RI65-348, filed as supplement No. 1 to Miller & Fox Minerals Corp., FPC GRS No. 2 appears to have also covered sales under their FPC GRS No. 4. FPC GRS No. 2 has been canceled.
- ⁵⁸ Basic Contract between Texas Eastern Transmission Corp., as seller and Lone Star Gathering Co., as buyer; on file as Texas Eastern Transmission Corp., FPC GRS No. F-7.
- ⁵⁹ Provides for a depth limitation of 9,431 feet.

[F.R. Doc. 66-9749; Filed, Sept. 7, 1966; 8:45 a.m.]

[Docket Nos. RI67-44 etc.]

TEXACO INC., ET AL.

Order Accepting Contract Amendment, Conditionally Accepting Rate Filing, Providing for Hearings on and Suspension of Proposed Changes in Rates¹

AUGUST 30, 1966.

The above-named Respondents have tendered for filing proposed changes in presently effective rate schedules for sales of natural gas subject to the jurisdiction of the Commission. The proposed changes, which constitute increased rates and charges, are designated as follows:

¹ Does not consolidate for hearing or dispose of the several matters herein.

Docket No.	Respondent	Rate scheduled No.	Supplement No.	Purchaser and producing area	Amount of annual increase	Date filing tendered	Effective date unless suspended	Date suspended until	Cents per Mcf		Rate in effect subject to refund in docket Nos.
									Rate in effect	Proposed increased rate	
RI67-44	Texaco Inc., Post Office Box 2420, Tulsa, Okla. 74102.	148	11	Colorado Interstate Gas Co. (Mocane Field, Beaver County, Okla.) (Panhandle Area).	\$28,792	8-2-66	2-9-2-66	2-2-67	16.29	18.462	
	do	152	2	Panhandle Eastern Pipe Line Co. (South Forgan Field, Beaver County, Okla.) (Panhandle Area).	752	8-2-66	2-9-2-66	2-2-67	15.0	17.0	
	do	158	4	Northern Natural Gas Co. (Barlow Field, Ochiltree County, Tex.) (R.R. District No. 10).	4,499	8-2-66	2-9-2-66	2-2-67	15.5	17.5	
	do	159	3	Northern Natural Gas Co. (Daniel Field, Ochiltree County, Tex.) (R.R. District No. 10).	2,485	8-2-66	2-9-2-66	2-2-67	15.5	16.5	
	do	180	6	Northern Natural Gas Co. (North Hutchinson and East Spearman Fields, Hansford and Hutchinson Counties, Tex.) (R.R. District No. 10).	9,948	8-2-66	2-9-2-66	2-2-67	16.5	17.5	
	do	184	5	Northern Natural Gas Co. (Horizon Field, Hansford County, Tex.) (R.R. District No. 10).	10,047	8-2-66	2-9-2-66	2-2-67	16.5	17.5	
	do	225	3	Natural Gas Pipeline Co. of America (Twin Morrow Field, Hansford County, Tex.) (R.R. District No. 10).	291	8-2-66	2-9-2-66	2-2-67	16.0	17.0	
RI67-45	Texaco Inc. (Operator), et al.	166	10	Kansas Nebraska Natural Gas Co., Inc. (Southeast Camrick Field, Texas County, Okla.) (Panhandle Area).	15,765	8-2-66	2-9-2-66	2-2-67	16.0	17.6	
RI67-46	Sohio Petroleum Co. (Operator), et al., 970 First National Bldg., Oklahoma City, Okla. 73102, Attn: Mr. E. B. Harry, Jr.	17 97	14 9	El Paso Natural Gas Co. (Bakke Field, Andrews County, Tex.) (R.R. District No. 8) (Permian Basin Area).	1,469	6-16-66	2-7-17-66	(accepted)	10.1699	15.0	G-16477. ¹⁶
		97	10			8-2-66	2-9-2-66	2-2-67			

¹ The stated effective date is the first day after expiration of the statutory notice.

² Redetermined rate increase.

³ Pressure base is 14.65 p.s.i.a.

⁴ Includes base rate of 17.0 cents per Mcf plus upward B.t.u. adjustment. Base rate subject to upward and downward B.t.u. adjustment.

⁵ Includes base rate of 15.0 cents per Mcf plus upward B.t.u. adjustment. Base rate subject to upward and downward B.t.u. adjustment.

⁶ Settlement rate in Texaco's company-wide settlement in Docket Nos. G-8969, et al. Settlement order issued Dec. 30, 1963. Moratorium expired on Mar. 1, 1966.

⁷ Two-step periodic rate increase.

⁸ Periodic rate increase.

⁹ Subject to a downward B.t.u. adjustment.

¹¹ Includes 1.0 cent per Mcf paid by buyer for seller's waiving its right to process gas.

¹² Eight-step periodic rate increase.

¹³ Subject to a 1.75 cents per Mcf compression charge by buyer for gas compressed from Joe Morris No. A-2 Gas Unit.

¹⁴ Contract Amendment dated June 1, 1966. Eliminates favored-nations provisions, establishes new periodic escalations which is basis for presently proposed increase, and extends contract term to Jan. 1, 1980.

¹⁵ Renegotiated rate increase.

¹⁶ Docket No. G-16477 is consolidated in Docket No. AR61-1, et al. Area Rate Proceeding.

¹⁷ Basic contract dated Dec. 19, 1956, and covers sale of residue gas derived from casinghead gas.

Texaco Inc. (Texaco) requests a retroactive effective date of March 1, 1966, for Supplement Nos. 4, 3, 6, 5, and 3 to its FPC Gas Rate Schedule Nos. 158, 159, 180, 184, and 225, respectively; an effective date of July 27, 1966, for Supplement No. 11 to its FPC Gas Rate Schedule No. 148, and that Supplement No. 2 to its FPC Gas Rate Schedule No. 152 be permitted to become effective on September 1, 1966. Texaco Inc. (Operator), et al. (also referred to as Texaco herein) request a retroactive effective date of July 27, 1966, for Supplement No. 10 to their FPC Gas Rate Schedule No. 166. Sohio Petroleum Co. (Operator), et al. (Sohio) request that their proposed rate increase be permitted to become effective as of August 31, 1966. Good cause has not been shown for waiving the 30-day notice requirement provided in section 4(d) of the Natural Gas Act to permit earlier effective dates for the aforementioned producers' rate filings and such requests are denied.

Sohio filed a contract amendment and a proposed renegotiated rate increase from 10.1699 cents to 15.0 cents per Mcf for a sale of gas to El Paso Natural Gas Co. in the Permian Basin Area of Texas based on such contract amendment. Sohio has previously filed a rate schedule quality statement, in compliance with Opinion No. 468, which establishes the applicable rate for the subject sale is 12.81 cents per Mcf (area base rate of

14.5 cents plus upward B.t.u. adjustment of 1.10 cents less treating costs of 2.79 cents). Since the proposed increased rate of 15.0 cents exceeds the established applicable rate of 12.81 cents per Mcf, we conclude that such rate should be suspended as ordered herein for 5 months from September 2, 1966, the date of expiration of the statutory notice. Except for the stay of the moratorium in Opinion No. 468, Sohio's rate increase filing would be rejectable. If the moratorium is ultimately upheld upon judicial review, the filing would be rejected ab initio.

The contract amendment dated June 1, 1966, tendered for filing by Sohio on June 16, 1966, eliminates the favored-nations provisions of the contract, establishes new periodic escalations which is the basis for the presently proposed rate increase, and extends the term of the contract to January 1, 1980. The contract amendment has been designated as Supplement No. 9 to Sohio's FPC Gas Rate Schedule No. 97. We believe that it would be in the public interest to accept for filing Sohio's aforementioned contract amendment to become effective as of July 17, 1966, the date of expiration of the statutory notice, but not the proposed rate contained therein which will be suspended as indicated below.

The proposed changed rates and charges may be unjust, unreasonable, unduly discriminatory, or preferential, or otherwise unlawful.

Texaco and Sohio's proposed increased rates and charges exceed the applicable area price levels for increased rates as set forth in the Commission's statement of general policy No. 61-1, as amended (18 CFR Ch. I, Pt. 2, § 2.56).

The Commission finds:

(1) Good cause has been shown for accepting for filing Sohio's proposed contract amendment dated June 1, 1966, designated as Supplement No. 9 to Sohio's FPC Gas Rate Schedule No. 97, and for permitting such supplement to become effective as of July 17, 1966, the date of expiration of the statutory notice.

(2) Except for the supplement set forth in (1) above, it is necessary and proper in the public interest and to aid in the enforcement of the provisions of the Natural Gas Act that the Commission enter upon hearings concerning the lawfulness of the proposed changes, and that the above-designated supplements be suspended and the use thereof deferred as hereinafter ordered.

The Commission orders:

(A) Sohio's contract amendment dated June 1, 1966, designated as Supplement No. 9 to Sohio's FPC Gas Rate Schedule No. 97, is accepted for filing and permitted to become effective as of July 17, 1966.

(B) Pursuant to the authority of the Natural Gas Act, particularly sections 4 and 15 thereof, the Commission's rules

of practice and procedure, and the regulations under the Natural Gas Act (18 CFR Ch. I), public hearings shall be held upon dates to be fixed by notices from the Secretary concerning the lawfulness of the proposed increased rates and charges contained in the above-designated supplements (except supplement No. 9 to Sohio's FPC Gas Rate Schedule No. 96).

(C) Pending hearings and decisions thereon, the above-designated rate supplement are hereby suspended and the use thereof deferred until the date indicated in the above "Date Suspended Until" column, and thereafter until such further time as they are made effective in the manner prescribed by the Natural Gas Act.

(D) Neither the supplements hereby suspended, nor the rate schedules sought to be altered thereby, shall be changed until these proceedings have been disposed of or until the periods of suspension have expired, unless otherwise ordered by the Commission.

(E) Notices of intervention or petitions to intervene may be filed with the Federal Power Commission, Washington, D.C. 20426, in accordance with the rules of practice and procedure (18 CFR 1.8 and 1.37(f)) on or before October 12, 1966.

By the Commission.

[SEAL] JOSEPH H. GUTRIDE,
Secretary.

[F.R. Doc. 66-9753; Filed, Sept. 7, 1966;
8:45 a.m.]

[Docket No. CP67-44]

COMMUNITY NATURAL GAS CO., INC., AND MIDWESTERN GAS TRANSMISSION CO.

Notice of Application

AUGUST 30, 1966.

Take notice that on August 24, 1966, Community Natural Gas Co., Inc. (Applicant), 111 North Main Street, Owensville, Ind. 47565, filed in Docket No. CP67-44 an application pursuant to section 7(a) of the Natural Gas Act for an order of the Commission directing the Midwestern Gas Transmission Co. (Respondent) to establish physical connection of its transportation facilities with the facilities proposed to be constructed by Applicant and to sell and deliver to Applicant volumes of natural gas for resale and distribution by Applicant in the community of Holland, Ind., all as more fully set forth in the application which is on file with the Commission and open to public inspection.

Specifically, Applicant proposes to construct and operate approximately 3 miles of 2-inch lateral line extending from a point of interconnection with the Respondent's transmission system in Pike County, Ind., to the town border of Holland, and to construct additions and improvements to the existing Holland gas system, which system is being purchased by Applicant from the Serv All Development Co., Inc., of Holland, Ind. Applicant

requests that the Commission order Respondent make physical connection of its transmission system with Applicant's lateral line and deliver and meter the natural gas proposed for resale in Holland, Ind., and environs.

The application states that the third year annual and peak day requirements of Applicant are 64,000 Mcf and 560 Mcf respectively, and that the cost of the volumes of natural gas to be purchased by Applicant is computed at 46.90 cents per Mcf under Respondent's SR-1 rate schedule.

The total estimated cost of the proposed construction is \$90,000, which cost will be financed through the sale of common stock in the amount of \$45,000 and a bank loan of \$45,000 for interim financing, which will be permanently financed at a later date.

Protests or petitions to intervene may be filed with the Federal Power Commission, Washington, D.C. 20426, in accordance with the rules of practice and procedure (18 CFR 1.8 or 1.10) on or before September 26, 1966.

GORDON M. GRANT,
Acting Secretary.

[F.R. Doc. 66-9782; Filed, Sept. 7, 1966;
8:46 a.m.]

[Docket No. E-7307]

IDAHO POWER CO.

Notice of Application

AUGUST 30, 1966.

Take notice that on August 19, 1966, Idaho Power Co. (Applicant) filed an application with the Federal Power Commission seeking an order pursuant to section 204 of the Federal Power Act authorizing it to issue up to \$30 million principal amount of first mortgage bonds. Applicant is incorporated under the laws of the State of Maine and is qualified to do business in the States of Idaho, Oregon, and Nevada with its principal place of business office at Boise, Idaho. Applicant is an electrical utility operating primarily in portions of southern and central Idaho, in a portion of Elko County in northern Nevada and in portions of four counties in the eastern part of Oregon. According to the Applicant the first mortgage bonds which will mature in 1996 will be issued as a new series of 30-year bonds under Applicant's mortgage and deed of trust dated as of October 1, 1937, as supplemented, and as to be further supplemented by a new 17th supplemental indenture thereto, and will be sold following competitive bidding in accordance with the Commission's regulations under the Federal Power Act.

According to the Applicant the bonds are to be issued for the purpose of obtaining funds for the payment of short-term notes and the remaining balance of the net proceeds of the sale of said securities is to be used for construction purposes, principally the Hells Canyon Unit of Project 1971, now under construction and scheduled for completion early in 1968. Applicant now has short-term notes outstanding in the amount of

\$10,900,000 and applicant estimates that it will acquire and make additional short-term bank loans aggregating approximately \$9 million prior to the issuance of the first mortgage bonds. Between the period July 1, 1966, to December 31, 1967, Applicant expects to spend \$34.5 million on the Hells Canyon Unit of Project No. 1971, approximately \$7 million on transmission lines and approximately \$11 million on distribution lines and substations.

Any person desiring to be heard or to make any protest with reference to the application should on or before September 23, 1966, file with the Federal Power Commission, Washington, D.C. 20426, petitions or protests in accordance with the Commission's rules of practice and procedure (18 CFR 1.8 or 1.10). The application is on file with the Commission and is available for public inspection.

GORDON M. GRANT,
Acting Secretary.

[F.R. Doc. 66-9783; Filed, Sept. 7, 1966;
8:46 a.m.]

[Docket No. CP67-43]

UNITED GAS PIPE LINE CO.

Notice of Application

AUGUST 30, 1966.

Take notice that on August 24, 1966, United Gas Pipe Line Co. (Applicant), Post Office Box 1407, Shreveport, La. 71102, filed in Docket No. CP67-43 an application pursuant to section 7(b) of the Natural Gas Act for permission and approval for the removal, abandonment, and sale of certain natural gas facilities, all as more fully set forth in the application which is on file with the Commission and open to public inspection.

Specifically, Applicant seeks permission and approval for the removal, abandonment, and sale of the following facilities:

A. Refugio Compressor Station No. 1, consisting of 8 Hope Type 3 VSA 160 horsepower compressor units located in Lot No. 2, Block 6, Fee 2144, Refugio County, Tex.;

B. Edna Compressor Station No. 1, consisting of 24 Hope Type 3 VSA 160 horsepower compressor units located in the Elizabeth McNutt Survey, Fee 2259, Jackson County, Tex.;

C. Sterlington Compressor Station No. 1, consisting of 4 Cooper Bessemer Type TSA 170 horsepower compressor units located in Sections 31 and 32, Township 20 North, Range 4 East, Fee 2271, Ouachita Parish, La.; and

D. Burns Compressor Station, consisting of one Ingersoll Rand Type XVG 150 horsepower compressor unit, located in Section 15, Township 17 South, Range 9 East, SL 3326, St. Mary Parish, La.

Applicant states that none of these stations have been operated since December 1961, and are no longer needed in Applicant's operation. Additionally, Applicant states that service to its customers will not be affected.

Protests or petitions to intervene may be filed with the Federal Power Commission, Washington, D.C. 20426, in accordance with the rules of practice and procedure (18 CFR 1.8 or 1.10) on or before September 26, 1966.

ance with the rules of practice and procedure (18 CFR 1.8 or 1.10) and the regulations under the Natural Gas Act (§ 157.10) on or before September 26, 1966.

Take further notice that, pursuant to the authority contained in and subject to the jurisdiction conferred upon the Federal Power Commission by sections 7 and 15 of the Natural Gas Act and the Commission's rules of practice and procedure, a hearing will be held without further notice before the Commission on this application if no protest or petition to intervene is filed within the time required herein, if the Commission on its own review of the matter finds that a grant of the certificate permission and approval for the proposed abandonment is required by the public convenience and necessity. If a protest or petition for leave to intervene is timely filed, or if the Commission on its own motion believes that a formal hearing is required, further notice of such hearing will be duly given.

Under the procedure herein provided for, unless otherwise advised, it will be unnecessary for Applicant to appear or be represented at the hearing.

GORDON M. GRANT,
Acting Secretary.

[F.R. Doc. 66-9784; Filed, Sept. 7, 1966;
8:46 a.m.]

FEDERAL MARITIME COMMISSION

ISTHMIAN LINES, INC., AND
SEALAND SERVICE, INC.

Notice of Agreement Filed for Approval

Notice is hereby given that the following agreement has been filed with the Commission for approval pursuant to section 15 of the Shipping Act, 1916, as amended (39 Stat. 733, 75 Stat. 763, 46 U.S.C. 814).

Interested parties may inspect and obtain a copy of the agreement at the Washington office of the Federal Maritime Commission, 1321 H Street NW., Room 609; or may inspect agreement at the office of the District Managers, New York, N.Y., New Orleans, La., and San Francisco, Calif. Comments with reference to an agreement including a request for hearing, if desired, may be submitted to the Secretary, Federal Maritime Commission, Washington, D.C. 20573, within 20 days after publication of this notice in the FEDERAL REGISTER. A copy of any such statement should also be forwarded to the party filing the agreement (as indicated hereinafter) and the comments should indicate that this has been done.

Notice of agreement filed for approval by:

Mr. J. D. Kenny, Counsel, Isthmian Lines, Inc., 90 Broad Street, New York, N.Y. 10004.

Agreement 9572, between Isthmian Lines, Inc., and Sealand Service, Inc.,

provides for the establishment of a transshipping arrangement for the transportation of general cargo on pre-paid through bills of lading from loading ports of Sealand within the Commonwealth of Puerto Rico to ports of call of Isthmian in South Viet Nam with transshipment at the port or ports of New York, N.Y., and Baltimore, Md., under terms and conditions set forth in the agreement.

Dated: September 2, 1966.

By order of the Federal Maritime Commission.

FRANCIS C. HURNEY,
Special Assistant to the Secretary.

[F.R. Doc. 66-9831; Filed, Sept. 7, 1966;
8:50 a.m.]

PACIFIC FAR EAST LINE, INC., AND
SAIPAN SHIPPING CO.

Notice of Agreement Filed for Approval

Notice is hereby given that the following agreement has been filed with the Commission for approval pursuant to section 15 of the Shipping Act, 1916, as amended (39 Stat. 733, 75 Stat. 763, 46 U.S.C. 814).

Interested parties may inspect and obtain a copy of the agreement at the Washington office of the Federal Maritime Commission, 1321 H Street NW., Room 609; or may inspect agreements at the office of the District Managers, New York, N.Y., New Orleans, La., and San Francisco, Calif. Comments with reference to an agreement including a request for a hearing, if desired, may be submitted to the Secretary, Federal Maritime Commission, Washington, D.C. 20573, within 20 days after publication of this notice in the FEDERAL REGISTER. A copy of any such statement should also be forwarded to the party filing the agreement (as indicated hereinafter) and the comments should indicate that this has been done.

Notice of agreement filed for approval by:

Mr. Howard C. Adams, Vice President, Pacific Far East Line, Inc., 918 Sixteenth Street NW., Washington, D.C. 20006.

Agreement 9570, between Pacific Far East Line, Inc., and Saipan Shipping Co., provides for the establishment of a transshipping arrangement for the movement of cargo under through bills of lading between Pacific Coast ports of the United States and Hawaii served by PFEL and ports in the Trust Territory of the Pacific served by SAISHIP with transshipment at Guam, M.I., under terms and conditions set forth in the agreement.

Dated: September 2, 1966.

By order of the Federal Maritime Commission.

FRANCIS C. HURNEY,
Special Assistant to the Secretary.

[F.R. Doc. 66-9832; Filed, Sept. 7, 1966;
8:50 a.m.]

OFFICE OF EMERGENCY PLANNING NEBRASKA

Notice of Major Disaster

Pursuant to the authority vested in me by the President under Executive Order 10427 of January 16, 1953, Executive Order 10737 of October 29, 1957, and Executive Order 11051 of September 27, 1962 (18 F.R. 407, 22 F.R. 8799, 27 F.R. 9683); Reorganization Plan No. 1 of 1958, Public Law 85-763, and Public Law 87-296; by virtue of the Act of September 30, 1950, entitled "An Act to authorize Federal assistance to States and local governments in major disasters, and for other purposes" (42 U.S.C. 1855-1855g), as amended; notice is hereby given of a declaration of "major disaster" by the President in his letter dated August 31, 1966, reading in part as follows:

I have determined that the damage in various areas of the State of Nebraska adversely affected by heavy rains and flooding beginning on or about August 12, 1966, is of sufficient severity and magnitude to warrant assistance by the Federal Government to supplement State and local efforts.

I do hereby determine the following areas in the State of Nebraska to have been adversely affected by the catastrophe declared a major disaster by the President in his declaration of August 31, 1966:

The counties of—

Boone.	Nance.
Colfax.	Platte.
Greeley.	Valley.
Howard.	

Dated: September 1, 1966.

FARRIS BRYANT,
Director,
Office of Emergency Planning.

[F.R. Doc. 66-9772; Filed, Sept. 7, 1966;
8:45 a.m.]

SECURITIES AND EXCHANGE COMMISSION

[812-1964]

AMERICAN & FOREIGN POWER CO.,
INC.

Notice of Filing of Application Granting Limited Exemptions to Company and Its Subsidiaries

SEPTEMBER 1, 1966.

Notice is hereby given that American & Foreign Power Co., Inc. ("Applicant"), 100 Church Street, New York, N.Y. 10006, has filed an application and amendment thereto pursuant to section 6(c) of the Investment Company Act of 1940 ("Act") for an order granting limited exemptions to Applicant and its subsidiaries from sections 17(a) and 17(d), 21(b), 23(a) and 23(b), and 30 of the Act and the

rules and regulations thereunder. All interested persons are referred to the amended application on file with the Commission for a statement of the representations therein, which are summarized below.

Applicant, a Maine corporation, is a majority-owned subsidiary of Electric Bond & Share Co., a registered closed-end nondiversified management investment company, which at December 31, 1965, owned 55.63 percent of the outstanding common stock of Applicant. Since 1960, Applicant has sold certain of its utility properties to the governments of the countries where the properties were located, which sales have resulted in the receipt by Applicant of dollar obligations issued, or guaranteed, by the purchasing governments, and which represented the bulk of the purchase prices. In addition, Applicant's Cuban properties were seized without compensation in 1960. As a consequence of these events, Applicant filed an application to be declared not to be an investment company or for complete exemption from the Act, and the Commission issued findings, opinion and order holding that the Latin American government obligations are investment securities within the meaning of the Act and that Applicant is an investment company and no longer primarily a public utility holding company. (Investment Company Act Release No. 4590.) The effectiveness of this order has been stayed to September 3, 1966, pursuant to Applicant's request, subject to the conditions set forth in the Commission's orders of December 23, 1964, and December 29, 1964. (Investment Company Act Releases Nos. 4109 and 4123.)

Applicant and its fully owned investment company subsidiaries propose to register under the Act and seek the following limited exemptions which they deem necessary in the special circumstances of their reinvestment program in Latin America.

A. Transactions with affiliates where the only affiliated relationship arises out of a previous investment made outside the United States (secs. 17(a) and 17(d)):

Section 17(a) of the Act prohibits an affiliated person of a registered investment company, or an affiliated person of such a person, from effecting certain sales, purchases or borrowings from such company, unless the Commission upon application pursuant to section 17(b) grants an exemption from the provisions of section 17(a). Under section 17(d) of the Act and Rule 17d-1 thereunder, it is unlawful for any affiliated person of a registered investment company to participate in or effect any transaction in connection with any joint enterprise or other joint arrangement or profit-sharing plan in which the registered investment company is a participant, unless the Commission upon application grants an exemption regarding such joint enterprise.

Applicant and its subsidiaries request exemption from sections 17(a) and 17(d) of the Act and the rules promulgated

thereunder, to the extent applicable to permit Applicant and its subsidiaries without prior submission to the Commission to enter into transactions of the nature described below with foreign affiliated enterprises or affiliated persons thereof where (i) the term "foreign affiliated enterprise" shall mean an enterprise operating outside the United States (except for incidental activities in the United States) and the affiliation arises solely out of Applicant's previous direct or indirect investment in the foreign affiliated enterprise, and (ii) "affiliated persons" shall mean only those who become such as a result of an investment in the foreign affiliated enterprise:

1. To acquire additional equity securities of foreign affiliated enterprises where such securities are not part of a general offering to the holders of a class of securities of the foreign affiliated enterprise;

2. To lend money or property to non-controlled foreign enterprises;

3. To enter into joint arrangements or guarantees for the purchase of equipment for, the financing of accounts receivable of, and the provision of other similar financial assistance to, foreign affiliated enterprises, together with other affiliated persons of such foreign affiliated enterprises;

4. To enter into or modify contractual arrangements with foreign affiliated enterprises, including arrangements for the rendering of services and royalty, technical, operating and similar agreements.

Notwithstanding the foregoing, Applicant has stipulated that transactions pursuant to the exemptions described above shall conform with the requirements of Rule 17a-6 promulgated under the Act whether or not that rule by its terms is applicable to such transactions: *Provided, however*, That, solely for the purpose of these exemptions and in applying the provisions of Rule 17a-6 for that purpose, (i) the ownership by Electric Bond & Share Co. of stock of Applicant, and the ownership by Applicant of stock of Argentine Electric Co., Brazilian Electric Power Co., and South American Power Co. (all three of which are fully owned subsidiaries of applicant), shall not limit or deny such exemptions, and (ii) a nonpublic company shall mean a foreign affiliated enterprise having not more than 100 security holders who are citizens or residents of or are incorporated under the laws of the United States of America or any state thereof.

In connection with these exemptions, Applicant agrees that such exemptions will not apply to any transaction between it and any of its officers and directors or controlling persons or affiliates of such persons. The complete extent of the exemption sought is that there should be removed from the ambit of section 17, transactions with affiliates and with affiliates of affiliates where the affiliated relationship is solely the result of investments made in one or more foreign countries. Accordingly, Applicant would not be relieved of its obligations under the Act with respect to transactions with Electric Bond & Share Co. or its subsidi-

aries outside Applicant's system, the officers or directors of Electric Bond & Share Co., or applicant's own officers and directors and affiliates of such officers and directors.

B. Loans and advances to controlled companies and subsidiaries and the acquisition of securities in connection therewith (sec. 21(b)):

Section 21(b) of the Act prohibits, with certain exceptions not here relevant, the making of loans by a registered investment company to a person under common control with such registered investment company. Therefore, it would prohibit loans by wholly owned subsidiaries of Applicant to certain nonwholly owned subsidiaries. In order to permit flexibility of operations, Applicant requests that loans or advances by wholly owned subsidiaries of Applicant to nonwholly owned controlled companies and subsidiaries on the same tier, and the acquisition of securities in connection therewith, be exempted from section 21(b) of the Act so long as the lending subsidiary of Applicant continues to be wholly owned by Applicant.

C. Issuance of stock pursuant to exercise of existing stock options (secs. 23(a) and 23(b)):

Section 23(a) states, in part, that no registered closed-end investment company shall issue any of its securities for services. Section 23(b) of the Act provides, with certain exceptions, that no registered closed-end investment company shall sell common stock of which it is the issuer at a price below the current net asset value of such stock, exclusive of any distributing commission or discount.

Applicant has had in force since 1955 a Key Employees' Stock Ownership Plan, which Plan and the principal amendments thereto were approved by Applicant's shareholders. The restricted and qualified stock options issued thereunder provide for purchases of Applicant's common stock at 100 percent of the market price of the stock on the respective dates on which the options were issued. As of May 31, 1966 there were outstanding under this Plan options to purchase 39,810 shares of Applicant's common stock which options are held by 22 persons and have expiration dates running until 1973. No options have been issued under the Plan since December 17, 1964, and Applicant does not propose to issue any further options. Applicant states that the amount of stock presently subject to existing options is approximately 0.5 percent of the total number of shares outstanding, and the dilution in corporate and consolidated earnings that would result from the immediate exercise of all the outstanding options would be about 1 cent per share based upon earnings for the 12-month period ended May 31, 1966, without giving effect to any additional earnings on the funds that would be received by Applicant on the exercise of the options. Applicant requests exemption from sections 23(a) and 23(b) of the Act so as to enable it to issue to the persons holding these options the shares of Applicant's stock

called for upon exercise of the options and thereby fulfill its contractual obligations to the persons holding these options.

D. Exemptions from reporting requirements of the Act for the fully-owned subsidiaries of Applicant which are themselves investment companies (sec. 30):

Applicant has two fully owned subsidiaries which formerly were subholding companies over utility subsidiaries and whose assets now consist principally of government obligations received on the sale of utility properties. These companies are Argentine Electric Cos. and Brazilian Electric Power Co., both organized under the laws of Florida. These companies intend to register as investment companies under the Act. Applicant has another fully owned subsidiary, South American Power Co., also organized under the laws of Florida, which will become an investment company upon the sale of its utility holdings for government obligations. South American Power Co. proposes to register under the Act as an investment company at that time.

Section 30 provides, in relevant part, that every registered investment company shall file with the Commission certain information and reports including such periodic reports as the Commission may require by rule or regulation.

Applicant requests that Argentine Electric Cos., Brazilian Electric Power Co. and South American Power Co. after registration on Forms N-8A and N-8B-1 be exempted from all reporting requirements under section 30 of the Act and the rules thereunder, except as the Commission may direct otherwise, so long as these companies remain fully owned subsidiaries of Applicant.

With respect to the exemptions requested for its wholly owned subsidiaries, Applicant states that these subsidiaries will not take any action which Applicant could not itself take under the terms of the Act and exemptions granted to Applicant.

In support of its request, Applicant states that the investment community in Latin America has many characteristics different from those existing in the United States which would make subjection of Applicant to sections 17(a), 17(d), and 21(b) of the Act for which exemption is requested unnecessary, inappropriate and burdensome, and that the application of these provisions to the developing economies of Latin America could seriously interfere with applicant's ability to carry out its contractual reinvestment commitments.

Notice is further given that any interested person may, not later than September 23, 1966, at 5:30 p.m., submit to the Commission in writing a request for a hearing on the matter accompanied by a statement as to the nature of his interest, the reason for such request and the issues, if any, of fact or of law proposed to be controverted, or he may request that he be notified if the Commission should order a hearing thereon. Any such communication should be addressed: Secretary, Securities and Ex-

change Commission, Washington, D.C. 20549. A copy of such request shall be served personally or by mail (airmail if the person being served is located more than 500 miles from the point of mailing) upon Applicant at the address stated above. Proof of such service (by affidavit or in case of an attorney at law by certificate) shall be filed contemporaneously with the request. At any time after said date, as provided by Rule 0-5 of the rules and regulations promulgated under the Act, an order disposing of the application herein may be issued by the Commission upon the basis of the information stated in said application, unless an order for hearing upon said application shall be issued upon request or upon the Commission's own motion.

By the Commission.

[SEAL]

ORVAL L. DuBOIS,
Secretary.

[F.R. Doc. 66-9822; Filed, Sept. 7, 1966;
8:49 a.m.]

[File No. 7-2599]

AMERICAN SEATING CO.

Notice of Application for Unlisted Trading Privileges and of Opportunity for Hearing

SEPTEMBER 1, 1966.

In the matter of application of the Detroit Stock Exchange, for unlisted trading privileges in a certain security.

The above-named national securities exchange has filed an application with the Securities and Exchange Commission pursuant to section 12(f)(1)(B) of the Securities Exchange Act of 1934 and Rule 12f-1 thereunder, for unlisted trading privileges in the common stock of the following company, which security is listed and registered on one or more other national securities exchanges:

American Seating Co., File 7-2599.

Upon receipt of a request, on or before September 16, 1966, from any interested person, the Commission will determine whether the application shall be set down for hearing. Any such request should state briefly the nature of the interest of the person making the request and the position he proposes to take at the hearing, if ordered. In addition, any interested person may submit his views or any additional facts bearing on the said application by means of a letter addressed to the Secretary, Securities and Exchange Commission, Washington 25, D.C., not later than the date specified. If no one requests a hearing, this application will be determined by order of the Commission on the basis of the facts stated therein and other information contained in the official files of the Commission pertaining thereto.

For the Commission (pursuant to delegated authority).

[SEAL]

ORVAL L. DuBOIS,
Secretary.

[F.R. Doc. 66-9823; Filed, Sept. 7, 1966;
8:49 a.m.]

[File No. 7-2600-2606]

ITEK CORP. ET AL.

Notice of Applications for Unlisted Trading Privileges and of Opportunity for Hearing

SEPTEMBER 1, 1966.

In the matter of applications of the Philadelphia - Baltimore - Washington Stock Exchange; for unlisted trading privileges in certain securities.

The above-named national securities exchange has filed applications with the Securities and Exchange Commission pursuant to section 12(f)(1)(B) of the Securities Exchange Act of 1934 and Rule 12f-1 thereunder, for unlisted trading privileges in the common stocks of the following companies, which securities are listed and registered on one or more other national securities exchanges:

Itek Corp., File 7-2600.
Emerson Electric Co., File 7-2601.
United Whelan Corp., File 7-2602.
Massey-Ferguson, Ltd., File 7-2603.
Walter Kidde & Co., Inc., File 7-2604.
Consolidated Foods Corp., File 7-2605.
Bucyrus-Erie Co., File 7-2606.

Upon receipt of a request, on or before September 16, 1966, from any interested person, the Commission will determine whether the application with respect to any of the companies named shall be set down for hearing. Any such request should state briefly the title of the security in which he is interested, the nature of the interest of the person making the request, and the position he proposes to take at the hearing, if ordered. In addition, any interested person may submit his views or any additional facts bearing on any of the said applications by means of a letter addressed to the Secretary, Securities and Exchange Commission, Washington 25, D.C., not later than the date specified. If no one requests a hearing with respect to any particular application, such application will be determined by order of the Commission on the basis of the facts stated therein and other information contained in the official files of the Commission pertaining thereto.

For the Commission (pursuant to delegated authority).

[SEAL]

ORVAL L. DuBOIS,
Secretary.

[F.R. Doc. 66-9824; Filed, Sept. 7, 1966;
8:49 a.m.]

SMALL BUSINESS ADMINISTRATION

[Declaration of Disaster Area 587]

NEW MEXICO AND TEXAS

Declaration of Disaster Area

Whereas, it has been reported that during the month of August 1966, because of the effects of certain disasters, damage resulted to residences and business property located in Eddy County in

the State of New Mexico, and Hudspeth County in the State of Texas;

Whereas, the Small Business Administration has investigated and has received other reports of investigations of conditions in the areas affected;

Whereas, after reading and evaluating reports of such conditions, I find that the conditions in such areas constitute a catastrophe within the purview of the Small Business Act, as amended.

Now, therefore, as Administrator of the Small Business Administration, I hereby determine that:

1. Applications for disaster loans under the provisions of section 7(b)(1) of the Small Business Act, as amended, may be received and considered by the offices below indicated from persons or firms whose property, situated in the aforesaid Counties and areas adjacent thereto, suffered damage or destruction resulting from floods and accompanying conditions occurring on or about August 22, 1966.

OFFICES

Small Business Administration Regional Office, 500 Gold Avenue SW., Albuquerque, N. Mex. 87101.

Small Business Administration Regional Office, 1616 19th Street, Lubbock, Tex. 79401.

2. Temporary offices will be located in Carlsbad, N. Mex., and Dell City, Tex., addresses to be announced locally.

3. Applications for disaster loans under the authority of this declaration will not be accepted subsequent to February 28, 1967.

Dated: August 26, 1966.

BERNARD L. BOUTIN,
Administrator.

[F.R. Doc. 66-9806; Filed, Sept. 7, 1966;
8:48 a.m.]

INTERSTATE COMMERCE COMMISSION

[Notice 411]

MOTOR CARRIER ALTERNATE ROUTE DEVIATION NOTICES

SEPTEMBER 2, 1966.

The following letter-notices of proposals to operate over deviation routes for operating convenience only have been filed with the Interstate Commerce Commission, under the Commission's Deviation Rules Revised, 1957 (49 CFR 211.1(c)(8)) and notice thereof to all interested persons is hereby given as provided in such rules (49 CFR 211.1(d)(4)).

Protests against the use of any proposed deviation route herein described may be filed with the Interstate Commerce Commission in the manner and form provided in such rules (49 CFR 211.1(e)) at any time, but will not operate to stay commencement of the proposed operations unless filed within 30 days from the date of publication.

Successively filed letter-notices of the same carrier under the Commission's Deviation Rules Revised, 1957, will be numbered consecutively for convenience

in identification and protests if any should refer to such letter-notices by number.

MOTOR CARRIERS OF PROPERTY

No. MC 3560 (Deviation No. 11), GENERAL EXPRESSWAYS, INC., 1205 South Platte River Drive, Denver, Colo. 80223, filed August 26, 1966. Carrier's representative: Ken Wolford (same address as applicant). Carrier proposes to operate as a common carrier, by motor vehicle, of general commodities, with certain exceptions, over a deviation route as follows: From Akron, Ohio, over U.S. Highway 224 to New Castle, Pa., thence over U.S. Highway 422 to Ebensburg, Pa., thence over U.S. Highway 22 to junction U.S. Highway 11 near Amity Hall, Pa., thence over U.S. Highway 11 to Harrisburg, Pa., and return over the same route, for operating convenience only. The notice indicates that the carrier is presently authorized to transport the same commodities over pertinent service routes as follows: (1) From Cleveland, Ohio, over Ohio Highway 176 (formerly portion U.S. Highway 21), to junction unnumbered highway (formerly portion U.S. Highway 21), at or near Ghent, Ohio, thence over unnumbered highway to Montrose, Ohio, thence over Ohio Highway 18 to Akron, Ohio, (2) from Cleveland, Ohio, over U.S. Highway 422 to junction Ohio Highway 8, thence over Ohio Highway 8 to Canton, Ohio, (3) from Canton, Ohio, over U.S. Highway 30 to junction Pennsylvania Turnpike near Irwin, Pa., thence over Pennsylvania Turnpike to junction U.S. Highway 11, thence over U.S. Highway 11 to Harrisburg, Pa.

Thence over U.S. Highway 22 to junction unnumbered highway near Paxtonia, Pa., thence over unnumbered highway via Paxtonia, Manadahl, Grantville, East Hanover, Jonestown, and Fredericksburg, Pa., to junction U.S. Highway 22, thence over U.S. Highway 22 to junction unnumbered highway near Bethel, Pa., thence over unnumbered highway via Bethel and Strausstown, Pa., to junction U.S. Highway 22, thence over U.S. Highway 22 to junction unnumbered highway near Walbert, Pa., thence over unnumbered highway via Allentown, Bethlehem, Butztown, and Wilson, Pa., to Easton, Pa., thence over U.S. Highway 22 to junction unnumbered highway (formerly portion U.S. Highway 22), thence over unnumbered highway to Clinton, N.J., thence over unnumbered highway via Annandale, Lebanon, Potterstown, and Whitehouse, N.J., to junction U.S. Highway 22, thence over U.S. Highway 22 to junction New Jersey Highway 28, thence over New Jersey Highway 28 to junction U.S. Highway 1 near Elizabeth, N.J., and (4) from Canton, Ohio, to Harrisburg, Pa., as specified above, thence over U.S. Highway 230 to Lancaster, Pa., thence over U.S. Highway 30 to junction Business Route U.S. Highway 30 (formerly portion U.S. Highway 30), thence over Business Route U.S. Highway 30 to Downingtown, Pa., thence over U.S. Highway 322 to junction U.S. Highway 1 near Chadds Ford, Pa., and return over the same routes.

No. MC 76032 (Deviation No. 12), NAVAJO FREIGHT LINES, INC., 1205 South Platte River Drive, Denver, Colo. 80223, filed August 19, 1966. Carrier's representative: Ken Wolford (same address as applicant). Carrier proposes to operate as a common carrier, by motor vehicle, of general commodities, with certain exceptions, over deviation routes as follows: (1) From Denver, Colo., over Interstate Highway 25 to Albuquerque, N. Mex., (2) from Albuquerque, N. Mex., over Interstate Highway 40 to junction Interstate Highway 15 at or near Barstow, Calif., thence over Interstate Highway 15 to junction Interstate Highway 10 at or near San Bernardino, Calif., thence over Interstate Highway 10 to Los Angeles, Calif., and (3) from Albuquerque, N. Mex., over Interstate Highway 40 to Amarillo, Tex., and return over the same routes, for operating convenience only. The notice indicates that the carrier is presently authorized to transport the same commodities, over pertinent service routes as follows: (1) From Denver, Colo., over U.S. Highway 85 to Albuquerque, N. Mex. (also from junction U.S. Highway 85 and unnumbered Colorado Highway (formerly shown as Colorado Highway 393) near Larkspur, Colo., over unnumbered highway to junction Colorado Highway 105, near Monument, Colo., thence over Colorado Highway 105 to junction U.S. Highway 85; also from junction unnumbered highway (formerly shown as old U.S. Highway 85) and U.S. Highway 85, north of Crow, Colo., over unnumbered highway to junction U.S. Highway 85), (2) from Los Angeles, Calif., over U.S. Highway 66 to junction unnumbered highway (formerly portion U.S. Highway 66), thence over unnumbered highway via Oro Grande and Lenwood, Calif., to Barstow, Calif., thence over U.S. Highway 66 to Albuquerque, N. Mex., (3) from Los Angeles, Calif., as specified next above to junction New Mexico Highway 6 near Correo, N. Mex., thence over New Mexico Highway 6 to junction U.S. Highway 85, thence over U.S. Highway 85 to Albuquerque, N. Mex., (4) from Los Angeles, Calif., over U.S. Highway 60 to Wickenburg, Ariz., thence over U.S. Highway 89 to junction U.S. Highway 66, thence over U.S. Highway 66 to Albuquerque, N. Mex., (5) from Los Angeles, Calif., over U.S. Highway 60 to Wickenburg, Ariz., thence over U.S. Highway 89 to junction Alternate U.S. Highway 89, thence over Alternate U.S. Highway 89 to junction U.S. Highway 66, at Flagstaff, Ariz., thence over U.S. Highway 66 to Albuquerque, N. Mex., and (6) from Amarillo, Tex., over U.S. Highway 66 to Albuquerque, N. Mex., and return over the same routes.

No. MC 76032 (Deviation No. 13), NAVAJO FREIGHT LINES, INC., 1205 South Platte River Drive, Denver, Colo. 80223, filed August 19, 1966. Carrier's representative: Ken Wolford (same address as applicant). Carrier proposes to operate as a common carrier, by motor vehicle, of general commodities, with certain exceptions, over a deviation route as follows: From Denver, Colo., over

Interstate Highway 70 to Kansas City, Mo., and return over the same route, for operating convenience only. The notice indicates that the carrier is presently authorized to transport the same commodities over a pertinent service route as follows: From Chicago, Ill., over Alternate U.S. Highway 30 to Sterling, Ill., thence over Illinois Highway 2 to junction Illinois Highway 78, thence over Illinois Highway 78 to junction U.S. Highway 24, thence over U.S. Highway 24 to Monroe City, Mo., thence over U.S. Highway 36 to Cameron, Mo., thence over U.S. Highway 69 to Kansas City, Mo., thence over U.S. Highway 40 to Denver, Colo., and return over the same route.

No. MC 108461 (Deviation No. 3), **WHITFIELD TRANSPORTATION, INC.**, 300-316 North Clark Road, Post Office Drawer 9897, El Paso, Tex. 79989, filed August 25, 1966. Carrier proposes to operate as a *common carrier*, by motor vehicle, of *general commodities*, with certain exceptions, over a deviation route as follows: Between Van Horn, Tex., and San Antonio, Tex., over U.S. Highway 90, for operating convenience only. The notice indicates that the carrier is presently authorized to transport the same commodities, over a pertinent service route as follows: From San Antonio, Tex., over U.S. Highway 87 to Comfort, Tex., thence over Texas Highway 27 to junction U.S. Highway 290, thence over U.S. Highway 290 to junction U.S. Highway 80, thence over U.S. Highway 80 to El Paso, Tex., and return over the same route.

By the Commission.

[SEAL]

H. NEIL GARSON,
Secretary.

[F.R. Doc. 66-9849; Filed, Sept. 7, 1966;
8:51 a.m.]

[Notice 962]

MOTOR CARRIER APPLICATIONS AND CERTAIN OTHER PROCEEDINGS

SEPTEMBER 2, 1966.

The following publications are governed by the new Special Rule 1.247 of the Commission's rules of practice, published in the **FEDERAL REGISTER**, issue of December 3, 1963, which became effective January 1, 1964.

The publications hereinafter set forth reflect the scope of the applications as filed by applicant, and may include descriptions, restrictions, or limitations which are not in a form acceptable to the Commission. Authority which ultimately may be granted as a result of the applications here noticed will not necessarily reflect the phraseology set forth in the application as filed, but also will eliminate any restrictions which are not acceptable to the Commission.

APPLICATIONS ASSIGNED FOR ORAL HEARING

MOTOR CARRIERS OF PROPERTY

No. MC 1855 (Sub-No. 15) (Republication), filed March 10, 1966, published **FEDERAL REGISTER** issue of April 7, 1966, and republished, this issue. Applicant:

SCHWENZER BROS. INC., 767 St. George Avenue, Woodbridge, N.J. Applicant's representative: William J. Augello, Jr., 2 West 45th Street, New York, N.Y. 10036. By application filed March 10, 1966, applicant seeks a permit authorizing operations, in interstate or foreign commerce, as a contract carrier by motor vehicle, over irregular routes, of petroleum, petroleum products, methanols, and such commodities as are ordinarily used or distributed by wholesale or retail suppliers, marketers, or distributors of petroleum products, between Sewaren, N.J., on the one hand, and, on the other, steamship piers located in Bergen, Essex, Hudson, and Union Counties, N.J., and railroad piggyback ramps in Bergen, Hudson, Mercer, Somerset, and Union Counties, N.J., in trailers furnished by shippers, consignees or agents thereof, under a continuing contract or contracts with Shell Oil Co., New York, N.Y. An order of the Commission, Operating Rights Board No. 1, dated August 19, 1966, and served August 30, 1966, finds that operation by applicant, in interstate or foreign commerce, as a contract carrier by motor vehicle, over irregular routes, of *petroleum, petroleum products, methanols, and such commodities* as are ordinarily used or distributed by wholesale or retail suppliers, marketers, or distributors of petroleum products, between Sewaren, N.J., on the one hand, and, on the other, (a) points in Bergen, Hudson, and Union Counties, N.J., restricted to the transportation of traffic having a prior or subsequent movement either by rail or water.

(b) Points in Essex County, N.J., restricted to the transportation of traffic having a prior or subsequent movement by water, and (c) points in Mercer and Somerset Counties, N.J., restricted to the transportation of traffic having a prior or subsequent movement by rail; all of said authority is restricted against the movement of such commodities, in bulk, in tank vehicles, and to the performance of service under a continuing contract with Shell Oil Co., of New York, N.Y., will be consistent with the public interest and the national transportation policy; that applicant is fit, willing, and able properly to perform such service and to conform to the requirements of the Interstate Commerce Act and the Commission's rules and regulations thereunder. Because it is possible that other parties may have an interest in and would be prejudiced by the lack of proper notice of the authority described in the findings in this order, a notice of the authority actually granted will be published in the **FEDERAL REGISTER** and issuance of a permit in this proceeding will be withheld for a period of 30 days from the date of such publication, during which period any proper party in interest may file an appropriate protest or other pleading.

No. MC 105809 (Sub-No. 11) (Republication), filed December 27, 1965, published **FEDERAL REGISTER** issue of January 20, 1966, and republished, this issue. Applicant: **ROBERT E. MACK, EDWARD F. MACK, JOSEPH P. HOEY, ALBERT ROLAND FUNK, CARL BROWN, HARRY ROBSON, AND JOHN**

BALLOCK, a partnership, doing business as **MACK TRANSPORTATION COMPANY**, 4330 Torresdale Avenue, Philadelphia, Pa. 19124. Applicant's representative: V. Baker Smith, 2107 Fidelity-Philadelphia Trust Building, Philadelphia, Pa. 19109. By application filed December 27, 1965, applicant seeks a permit authorizing operations, in interstate or foreign commerce, as a contract carrier by motor vehicle, over irregular routes, of general commodities, between the facilities of the Philco Distributors, Inc., located at King of Prussia, Montgomery County, Pa., on the one hand, and, on the other, points in the New York, N.Y., commercial zone, as defined by the Commission in 1 M.C.C. 665, and those in New Jersey, Pennsylvania, Delaware, Maryland, and the District of Columbia, limited to a service in which said carrier leases trucks with drivers to Philco Distributors, Inc., for the exclusive transportation of such shipper's property.

A corrected order of the Commission, Operating Rights Board No. 1, dated July 29, 1966, and served August 29, 1966, finds that operation by applicants, in interstate or foreign commerce, as a contract carrier by motor vehicle, over irregular routes, of *radios, televisions, phonographs, tape recorders, advertising materials, household appliances, and related accessories therefor* when moving in connection therewith, between King of Prussia, Pa., on the one hand, and, on the other, points in New Jersey, Delaware, and Maryland (except Baltimore, Md.), under a continuing contract with Philco Distributors, Inc., a subsidiary of Philco Corp., of Philadelphia, Pa., will be consistent with the public interest and the national transportation policy; that applicants are fit, willing, and able properly to perform such service and to conform to the requirements of the Interstate Commerce Act and the Commission's rules and regulations thereunder. Because it is possible that other parties, who have relied upon the notice of the application as published, which included the restriction set forth in the next preceding paragraph, may have an interest in and would be prejudiced by the lack of proper notice of the authority described in the findings herein, a notice of the authority actually granted will be published in the **FEDERAL REGISTER** and issuance of a permit herein will be withheld for a period of 30 days from the date of such publication, during which period any proper party in interest may file an appropriate protest or other pleading.

APPLICATIONS UNDER SECTIONS 5 AND 210a(b)

The following applications are governed by the Interstate Commerce Commission's Special Rules governing notice of filing of applications by motor carriers of property or passengers under sections 5(a) and 210a(b) of the Interstate Commerce Act and certain other proceedings with respect thereto. (49 CFR 1.240.)

MOTOR CARRIERS OF PROPERTY

No. MC-F-9517. Authority sought for control and merger by **GARRETT FREIGHTLINES, INC.**, 2055 Garrett

Way, Pocatello, Idaho, of the operating rights and property of EASTERN OREGON FREIGHT, INC., John Day, Oreg. Applicants' attorney: Maurice H. Greene, 334 First Security Bank Building, Boise, Idaho. Operating rights sought to be controlled and merged: *General commodities*, except those of unusual value, classes A and B explosives, uncrated household goods, commodities in bulk, and those requiring special equipment, as a *common carrier*, over regular routes, between John Day, Oreg., and Canyon City, Oreg., serving no intermediate points and serving off-route points within 1 mile of the above-specified route, between Canyon City, Oreg., and Burns, Oreg., serving the intermediate points of Seneca and Silvies, Oreg., between Canyon City, Oreg., and Izee, Oreg., serving all intermediate points, between Prairie City, Oreg., and Baker, Oreg., serving the intermediate points of Bates and Austin, Oreg., between Mount Vernon, Oreg., and Pendleton, Oreg., serving the intermediate point of Pilot Rock, Oreg., and those between Pendleton and Pilot Rock, restricted to traffic moving to and from points south of Pilot Rock, and serving all other intermediate points without restriction, between Canyon City, Oreg., and The Dalles, Oreg., serving all intermediate points: *Provided, however*, That no local service shall be rendered between The Dalles, on the one hand, and, on the other, points west thereof, with restrictions; between Portland, Oreg., and Prairie City, Oreg., serving all intermediate points between Condon and Prairie City, Oreg., and the off-route point of Canyon City, Oreg.; one alternate route for operating convenience only; and *livestock*, over irregular routes, between certain specified points in Oregon, on the one hand, and, on the other, certain specified points in Washington and Idaho, from certain specified points in Oregon, to certain specified points in Oregon. GARRETT FREIGHTLINES, INC. is authorized to operate as a *common carrier* in Washington, Montana, Minnesota, Idaho, Utah, Oregon, California, Colorado, Arizona, Indiana, North Dakota, Nevada, New Mexico, Wyoming, South Dakota, Wisconsin, and Michigan. Application has not been filed for temporary authority under section 210a(b).

MOTOR CARRIER OF PASSENGERS

No. MC-F-9516. Authority sought for control by WALLACE S. SWEET and LEE J. OSTER, 313 Broad Street, Utica, N.Y. 13501, of ONONDAGA COACH CORP., 23 Wadsworth Street, Auburn, N.Y. Applicants' attorneys: Daniel H. Greenberg, 110 East 42d Street, New York, N.Y., and James H. Gilroy, Jr., First National Bank Building, Utica, N.Y. 13503. Operating rights sought to be controlled: Passengers and their baggage, as a *common carrier*, over regular routes, between Auburn, N.Y., and Syracuse, N.Y., between Onondaga Hill, N.Y., and junction unnumbered highway and New York Highway 175, between junction New York Highway 175 and New York Highway 173 (at Onondaga Hill, N.Y.), and the Onondaga County Home,

serving all intermediate points; passengers and their baggage in the same vehicle with passengers, between Syracuse, N.Y., and Geneva, N.Y., between Port Byron, N.Y., and Fairmount, N.Y., between Port Byron, N.Y., and Auburn, N.Y., serving all intermediate points, between Onondaga Hill, N.Y., and junction New York Highway 173 and Split Rock Road, located in Onondaga County, N.Y., between junction New York Highway 173 and Split Rock Road, located in Onondaga County, N.Y., and junction New York Highways 173 and 5, located in Onondaga County, N.Y., and between junction Howlett Hill Road and Kasson Road, located in Onondaga County, N.Y., and junction Kasson Road and New York Highway 5, located in Onondaga County, N.Y., serving no intermediate points. WALLACE S. SWEET nor LEE J. OSTER, hold authority from this Commission. However, they are affiliated with CENTRAL N.Y. COACH LINES, INC., 313 Broad Street, Utica, N.Y., which is authorized to operate as a *common carrier* in New York, Connecticut, Delaware, Maryland, Massachusetts, New Jersey, Pennsylvania, Rhode Island, Virginia, and the District of Columbia. Application has not been filed for temporary authority under section 210a(b). NOTE: Petition to dismiss application for want of jurisdiction, filed concurrently.

By the Commission.

[SEAL] H. NEIL GARSON,
Secretary.

[F.R. Doc. 66-9850; Filed, Sept. 7, 1966;
8:52 a.m.]

NOTICE OF FILING OF MOTOR CARRIER INTRASTATE APPLICATIONS

SEPTEMBER 2, 1966.

The following applications for motor common carrier authority to operate in intrastate commerce seek concurrent motor carrier authorization in interstate or foreign commerce within the limits of the intrastate authority sought, pursuant to section 206(a)(6) of the Interstate Commerce Act, as amended October 15, 1962. These applications are governed by Special Rule 1.245 of the Commission's rules of practice, published in the FEDERAL REGISTER, issue of April 11, 1963, page 3533, which provides, among other things, that protests and requests for information concerning the time and place of State Commission hearings or other proceedings, any subsequent changes therein, and any other related matters shall be directed to the State Commission with which the application is filed and shall not be addressed to or filed with the Interstate Commerce Commission.

State Docket No. M-11454, Supp. No. 1, filed August 26, 1966. Applicant: DALE D. MILLER, doing business as MILFORD TRANSFER, Milford, Nebr. Applicant's representative: Donald E. Leonard, Box 2028, 605 South 14th, Lincoln, Nebr. Certificate of public convenience and necessity sought to operate a freight service as follows: Transporting com-

modities generally (except refrigerated products, and commodities requiring special equipment), (1) between points in Seward County, Nebr., on the one hand, and, on the other, Friend and Dorchester, Nebr.; and (2) between Friend and Dorchester, and points in Seward County, Nebr., on the one hand, and, on the other, points in Nebraska, over irregular routes.

HEARING: Not known. Requests for procedural information, including the time for filing protests, concerning this application, should be addressed to M. B. McManaman, Secretary, Nebraska State Railway Commission, Capitol Building, Lincoln, Nebr. 68509, and should not be directed to the Interstate Commerce Commission.

By the Commission.

[SEAL] H. NEIL GARSON,
[F.R. Doc. 66-9851; Filed, Sept. 7, 1966;
8:52 a.m.]

[Notice 248]

MOTOR CARRIER TEMPORARY AUTHORITY APPLICATIONS

SEPTEMBER 2, 1966.

The following are notices of filing of applications for temporary authority under section 210a(a) of the Interstate Commerce Act provided for under the new rules in Ex Parte No. MC 67 (49 CFR Part 240), published in the FEDERAL REGISTER, issue of April 27, 1965, effective July 1, 1965. These rules provide that protests to the granting of an application must be filed with the field official named in the FEDERAL REGISTER publication, within 15 calendar days after the date notice of the filing of the application is published in the FEDERAL REGISTER. One copy of such protest must be served on the applicant, or its authorized representative, if any, and the protest must certify that such service has been made. The protest must be specific as to the service which such protestant can and will offer, and must consist of a signed original and six copies.

A copy of the application is on file, and can be examined, at the Office of the Secretary, Interstate Commerce Commission, Washington, D.C., and also in the field office to which protests are to be transmitted.

MOTOR CARRIERS OF PROPERTY

No. MC 59388 (Sub-No. 24 TA), filed August 29, 1966. Applicant: SOUTHWESTERN TRANSPORTATION COMPANY, a corporation, 733 South Poydras, Post Office Box 6187, Dallas 22, Tex. 75202. Applicant's representative: L. VanHyning (same address as above). Authority sought to operate as a *common carrier*, by motor vehicle, over regular routes, transporting: *General commodities* (except those of unusual value, household goods as defined by the Commission, commodities in bulk, commodities requiring special equipment, and those injurious or contaminating to other lading), from junction Arkansas, Highway 15 near Tucker, Ark., to Lock and Dam No. 5 near Wright, Ark., from

junction Arkansas Highway 15 with unnumbered highway, thence over unnumbered highway to Lock and Dam No. 5, for 180 days. Supporting shipper: Martin K. Eby Construction Co., Inc., Post Office Box 1022, Pine Bluff, Ark. Send protests to: E. K. Willis, Jr., District Supervisor, Interstate Commerce Commission, Bureau of Operation and Compliance, 513 Thomas Building, 1314 Wood Street, Dallas, Tex. 75202.

No. MC 65475 (Sub-No. 7 TA), filed August 30, 1966. Applicant: JETCO, INC., 2780 Jefferson Davis Highway, Arlington, Va. 22202. Applicant's representative: Rex M. Phares (same address as above). Authority sought to operate as a *common carrier*, by motor vehicle, over irregular routes, transporting: *Gypsum wallboard*, from Arlington, Va., to Annapolis Junction, Md., an unincorporated community with a post office near Savage, Md., for 150 days. Supporting shipper: Georgia-Pacific Corp., Bestwall Gypsum Division, 2 Industrial Boulevard, Paoli, Pa. 19301, Attention: C. H. Flynn. Send protests to: Robert D. Caldwell, District Supervisor, Interstate Commerce Commission, Bureau of Operations and Compliance, 12th and Constitution Avenue NW., Room 1220, Washington, D.C. 20423.

No. MC 83539 (Sub-No. 197 TA), filed August 30, 1966. Applicant: C & H TRANSPORTATION CO., INC., Post Office Box 5976, Dallas, Tex. 75222, and 1935 West Commerce Street, Dallas, Tex. 75208. Applicant's representative: Kenneth Weeks (same address as above). Authority sought to operate as a *common carrier*, by motor vehicle, over irregular routes, transporting: *Clay*, from Belle Fourche, S. Dak., and Colloid Spur, Wyo., to points in Illinois, Indiana, Iowa, Minnesota, Missouri, and Wisconsin, for 180 days. Supporting shipper: American Colloid Co., 5100 Suffield Court, Skokie, Ill. 60077. Send protests to: E. K. Willis, Jr., District Supervisor, Interstate Commerce Commission, Bureau of Operations and Compliance, 513 Thomas Building, 1314 Wood Street, Dallas, Tex. 75202.

No. MC 108046 (Sub-No. 4 TA), filed August 29, 1966. Applicant: CURATOLA BROS. TRUCKING, INC., 142-82 Rockaway Boulevard, South Ozone Park, N.Y. Applicant's representative: Edward M. Alfano, 2 West 45th Street, New York, N.Y. 10036. Authority sought to operate as a *contract carrier*, by motor vehicle, over irregular routes, transporting: *Aluminum ladders*, set up and loose, from Amityville, N.Y., to points in New York, New Jersey, Pennsylvania, Maryland, Delaware, District of Columbia, Connecticut, New Hampshire, Vermont, Rhode Island, Massachusetts, Virginia, and Maine, *returned shipments* on return, for 150 days. Supporting shipper: American Ladder Corp., 225 Dixon Avenue, Post Office Box 776, Amityville, Long Island, N.Y. Send protests to: E. N. Carignan, District Supervisor, Bureau of Operations and Compliance, Interstate Commerce Commission, 346 Broadway, New York, N.Y. 10013.

No. MC 108722 (Sub-No. 1 TA), filed August 30, 1966. Applicant: FRANK

RIVIELLO, 860 West Oak Street, Old Forge, Pa. Authority sought to operate as a *common carrier*, by motor vehicle, over irregular routes, transporting: *Coal*, from points in Wayne County, Pa., to points in Broome, Tioga, and Chenango Counties, N.Y., for 150 days. Supporting shipper: Raymond Popple Coal Sales, 300 New Rose Building, Pittston, Pa. Send protests to: Kenneth R. Davis, District Supervisor, Bureau of Operations and Compliance, Interstate Commerce Commission, 309 U.S. Post Office Building, Scranton, Pa. 18503.

No. MC 113678 (Sub-No. 265 TA), filed August 26, 1966. Applicant: CURTIS, INC., 770 East 51st Avenue, Denver, Colo. 80216. Applicant's representative: Oscar Mandel, Post Office Box 16004, Stockyards Station, Denver, Colo. Authority sought to operate as a *common carrier*, by motor vehicle, over irregular routes, transporting: (a) *Frozen foods* and (b) *canned goods*, when moving in the same vehicle with frozen foods, from points in Stanislaus and Fresno, Counties, Calif., to points in Oregon, Washington, Idaho, Montana, Wyoming, Utah, Nevada, Arizona, New Mexico, and Texas, for 180 days. Supporting shippers: Glacier Packing Co., Post Office Box 367, Sanger, Calif., Christoffersen Poultry, Egg & Feed Market, Sixth and Lander Avenue, Turlock, Calif., Mowrer Farms Kitchens, Inc., 2125 West Tuolumne Avenue, Turlock, Calif., San Joaquin Valley Turkey Growers Association, Post Office Box 1845, Modesto, Calif.; Bright Foods, Inc., 107 Kilroy Road, Turlock, Calif. Send protests to: Herbert C. Ruoff, District Supervisor, Interstate Commerce Commission, Bureau of Operations and Compliance, 2022 Federal Office Building, Denver, Colo. 80202.

No. MC 114989 (Sub-No. 7 TA), filed August 30, 1966. Applicant: BRACEY & MARTIN, INC., 1910 South Walnut Street, Hopkinsville, Ky. 42240. Applicant's representative: James C. Havron, Nashville Bank & Trust Building, Nashville, Tenn. 37201. Authority sought to operate as a *contract carrier*, by motor vehicle, over irregular routes, transporting: *Malt beverages*, in containers, from Cincinnati, Ohio, to points in Christian County, Ky., and *empty malt beverage containers*, from points in Christian County, Ky., to Cincinnati, Ohio, for 180 days. Supporting shipper: Cravens Distributing Co., Post Office Box 155, Pembroke, Ky. Send protests to: Wayne L. Merilatt, District Supervisor, Interstate Commerce Commission, Bureau of Operations and Compliance, 426 U.S. Post Office Building, Louisville, Ky. 40202.

No. MC 114989 (Sub-No. 8 TA), filed August 30, 1966. Applicant: BRACEY & MARTIN, INC., 1910 South Walnut Street, Hopkinsville, Ky. 42240. Applicant's representative: James C. Havron, Nashville Bank & Trust Building, Nashville, Tenn. 37201. Authority sought to operate as a *contract carrier*, by motor vehicle, over irregular routes, transporting: *Malt beverages*, in containers, from South Bend, Ind., to Hopkinsville, Ky., and *empty malt beverage containers*, from Hopkinsville, Ky., to South Bend,

Ind., for 180 days. Supporting shipper: Kentucky Ace Beverage Distributors, Inc., Post Office Box 497, Hopkinsville, Ky. Send protests to: Wayne L. Merilatt, District Supervisor, Interstate Commerce Commission, Bureau of Operations and Compliance, 426 U.S. Post Office Building, Louisville, Ky. 40202.

No. MC 114897 (Sub-No. 75 TA), filed August 29, 1966. Applicant: WHITFIELD TANK LINES, INC., Post Office Drawer 9897, 300-316 North Clark Road, El Paso, Tex. 79989. Applicant's representative: J. P. Rose (same address as above). Authority sought to operate as a *common carrier*, by motor vehicle, over irregular routes, transporting: *Sulphuric acid*, in bulk, in tank vehicles, from Bagdad, Ariz., to Jean, Nev., for 150 days. Supporting shipper: J. Till Neville, Branch Manager, McKesson & Robbins, Inc., Post Office Box 14799, Phoenix, Ariz. 85031. Send protests to: Jerry R. Murphy, District Supervisor, Bureau of Operations and Compliance, Interstate Commerce Commission, 109 U.S. Courthouse, Albuquerque, N. Mex. 87101.

No. MC 115826 (Sub-No. 154 TA), filed August 26, 1966. Applicant: W. J. DIGBY, INC., Post Office Box 5088 T.A., 1960 31st Street, Denver, Colo. 80217. Applicant's representative: John F. DeCock (same address as above). Authority sought to operate as a *common carrier*, by motor vehicle, over irregular routes, transporting: (a) *Frozen foods*, (b) *Canned goods* when moving in the same vehicle with frozen foods, from points in Stanislaus and Fresno Counties, Calif., to points in Arizona, Colorado, Idaho, Montana, Nevada, New Mexico, Oregon, Texas, Utah, Washington, and Wyoming, for 180 days. Supporting shippers: Bright Foods, Inc., 711 F Street, Post Office Box 871, Turlock, Calif., Glacier Packing Co., Post Office Box 367, Sanger, Calif., Mowrer Farms Kitchens, Inc., 2125 West Tuolumne Avenue, Turlock, Calif., San Joaquin Valley Turkey Growers Association, Post Office Box 1845, Modesto, Calif., Christoffersen Poultry, Egg & Feed Market, Sixth and Lander Avenue, Turlock, Calif. Send protests to: Herbert C. Ruoff, District Supervisor, Bureau of Operations and Compliance, Interstate Commerce Commission, 2022 Federal Office Building, Denver, Colo. 80202.

No. MC 115826 (Sub-No. 155 TA), filed August 29, 1966. Applicant: W. J. DIGBY, INC., Post Office Box 5088 T.A., 1960 31st Street, Denver, Colo. 80217. Applicant's representative: John F. DeCock (same address as above). Authority sought to operate as a *common carrier*, by motor vehicle, over irregular routes, transporting: *Meats, meat products, and meat byproducts*, as defined by the Commission, from Gooding, Idaho, and points within 5 miles thereof, to points in Minnesota, Wisconsin, Missouri, Nebraska, Kansas, Michigan, Indiana, Ohio, Kentucky, Tennessee, Georgia, North Carolina, South Carolina, and Florida, for 120 days. Supporting shipper: Stockmen's Meat Packing Corp., Post Office Box 358, Gooding, Idaho. Send protests to: Herbert C. Ruoff, Dis-

trict Supervisor, Interstate Commerce Commission, Bureau of Operations and Compliance, 2022 Federal Office Building, Denver, Colo. 80202.

No. MC 128087 (Sub-No. 1 TA), filed August 29, 1966. Applicant: JOHN N. JOHN III, doing business as JOHN N. JOHN TRUCK LINE, 1020 West Second Street, Crowley, La. 70526. Applicant's representative: Aaron and Aaron, Aaron Building, East Court Circle, Post Office Box 422, Crowley, La. 70526. Authority sought to operate as a *common carrier*, by motor vehicle, over irregular routes, transporting: *Urea*, in bags, from Lake Charles, La., to points in Arkansas, Oklahoma, Mississippi, and Texas, with *refused shipments* to be returned to original point or as directed by shipper, for 180 days. Supporting shipper: Agricultural Division, Olin Mathieson Chemical Corp., Post Office Box 991, Little Rock, Ark. Send protests to: W. R. Atkins, District Supervisor, Interstate Commerce Commission, Bureau of Operations and Compliance, T-4009 Federal Office Building, 701 Loyola Avenue, New Orleans, La. 70113.

No. MC 128542 (Sub-No. 1 TA), filed August 29, 1966. Applicant: GARRY BREM, doing business as BREM'S TRUCKING, 11 Fernwood Lane, Gilroy, Calif. 95020. Applicant's representative: Marvin Handler, 405 Montgomery Street, San Francisco, Calif. 94104. Authority sought to operate as a *common carrier*, by motor vehicle, over irregular routes, transporting: *Ore-bearing rock*, from a mine just east of the southeast corner of Yosemite National Park and approximately 10 miles west of the Devils Postpile National Monument (in California) to the smelter of American Smelting & Refining Co. in Hayden, Ariz., for 150 days. Supporting shipper: Mark Mines, Inc., 147 North Church, Gilroy, Calif. Send protests to: William R. Murdoch, District Supervisor, Bureau of Operations and Compliance, Interstate Commerce Commission, 450 Golden Gate Avenue, Box 36004, San Francisco, Calif. 94102.

No. MC 128550 TA, filed August 26, 1966. Applicant: FRANK H. LOCHNER, doing business as LOCHNER'S MOVING & STORAGE, 807 Eighth Avenue SC., Austin, Minn. 55912. Applicant's representative: Gary E. Leonard, 218 First National Bank Building, Austin, Minn. 55912. Authority sought to operate as a *contract carrier*, by motor vehicle, over irregular routes, transporting: *Such commodities as are dealt in by retail department stores and mail order houses*, from between sites of retail store and warehouse of Sears, Roebuck & Co., at Austin, Minn., and points in Chickasaw, Cerro Gordo, Floyd, Hancock, Howard, Mitchell, Winnebago, and Worth Counties, Iowa, under a continuing contractual arrangement with Sears, Roebuck & Co., including *return unsatisfactory merchandise* to store from residence in above-listed counties, for 180 days. Supporting shipper: Sears, Roebuck & Co., Midwestern Territory Executive Offices, 8 East Congress Parkway, Chicago, Ill. Send protests to: C. H. Bergquist, District Supervisor, Bureau of Operations

and Compliance, Interstate Commerce Commission, 448 Federal Building and U.S. Courthouse, 110 South Fourth Street, Minneapolis, Minn. 55401.

No. MC 128551 TA, filed August 29, 1966. Applicant: JAMES J. KENNEDY, JR., doing business as KENNEDY VAN & STORAGE, 3359 Army Street, San Francisco, Calif. Applicant's representative: Alan P. Wohlstetter, 1 Farragut Square, Washington, D.C. 20006. Authority sought to operate as a *common carrier*, by motor vehicle, over irregular routes, transporting: *Household goods*, as defined by the Commission, between points in San Francisco, Marin, Contra Costa, Alameda, and San Mateo Counties, Calif., restricted to shipments having prior or subsequent movement between said points in containers, and further restricted to pickup and delivery services incidental to and in connection with packing, crating, and containerization, or unpacking, uncrating, and decontainerization of such shipments, for 180 days. Supporting shipper: Sunpak International, 1621 Queen Ann Avenue North, Seattle, Wash. 98109. Send protests to: District Supervisor, William R. Murdoch, Interstate Commerce Commission, Bureau of Operations and Compliance, 450 Golden Gate Avenue, Box 36004, San Francisco, Calif. 94102.

No. MC 128552 TA, filed August 29, 1966. Applicant: SPACE, INC., South Industry Road Cidco Park, Box 982, Cocoa, Fla. Authority sought to operate as a *contract carrier*, by motor vehicle, over irregular routes, transporting: *Telephone equipment, material, and supplies* from Cocoa, Fla., to points in Brevard County, Fla., for 180 days. Supporting shipper: Western Electric Co., Inc., 3300 Lexington Road, Winston-Salem, N.C. Send protests to: George H. Fauss, Jr., District Supervisor, Bureau of Operations and Compliance, Interstate Commerce Commission, 428 Post Office Building, Post Office Box 4969, Jacksonville, Fla. 32201.

MOTOR CARRIERS OF PASSENGERS

No. MC 105154 (Sub-No. 7 TA), filed August 29, 1966. Applicant: ROBERT G. WRIGHT, doing business as STAR VALLEY-JACKSON STAGES, 1945 Eagle Drive, Idaho Falls, Idaho 83401. Applicant's representative: Donald M. Olsen, 485 E Street, Idaho Falls, Idaho 83401. Authority sought to operate as a *common carrier*, by motor vehicle, over regular routes, transporting: *Passengers and their baggage and express and newspapers* in the same vehicle with passengers, between Alpine, Wyo., and Teton Village, Wyo., from Alpine over U.S. Highway 89 to Jackson, Wyo., thence over Wyoming Highway 22 to the junction of Wyoming secondary Highway 2001, thence over Wyoming secondary Highway 2001 to junction unnumbered highway, thence over unnumbered highway for approximately three tenths of a mile to Teton Village, and return over the same route, serving all intermediate points. (Applicant presently holds authority to operate between Idaho Falls, Idaho, and Afton, Wyo., with no seasonal restrictions, and between Alpine and

Jackson, Wyo., in seasonal operations extending from May 15 to September 15 of each year. Applicant proposes to tack requested authority with his present authority, and also proposes to conduct operations with no seasonal restrictions.) Supporting shippers: Jackson Hole Ski Corp., Teton Village, Jackson Hole, Wyo., Livingston Motor Co., Jackson, Wyo., Town of Jackson, Jackson, Wyo., Chamber of Commerce of the City of Idaho Falls, Idaho Falls, Idaho, Simpson's, Inc., Post Office Box 340, Idaho Falls, Idaho, Mendenhall's, 360 E Street, Idaho Falls, Idaho, Ideal Hardware, 760 Broadway, Idaho Falls, Idaho. Send protests to: Clyde W. Campbell, District Supervisor, Bureau of Operations and Compliance, Interstate Commerce Commission, 203 Eastman Building, Boise, Idaho 83702.

No. MC 128553 TA, filed August 30, 1966. Applicant: TRANSPORTES FRONTERIZOS DEL NORTE, S.A., Emilio Carranza, 727 Sur, Despacho 205 Monterey, N.L., Mexico. Applicant's representative: Jose Gonzalez R. (same address as above). Authority sought to operate as a *common carrier*, by motor vehicle, over regular routes, transporting: *Passengers, their baggage, express and newspapers*, from the port of entry on the international boundary line between the United States and Mexico at Rio Grande City, Tex., to Rio Grande City, Tex., and return, over U.S. Highway 83 and city streets serving all intermediate points, for 180 days. Supporting shipper: First State Bank & Trust Co., Rio Grande City, Tex.; Galindo Implement Co., Rio Grande City, Tex.; Starr Grocery Co., Rio Grande City, Tex.; Hotel Ringgold, Rio Grande City, Tex.; C. R. Anthony Co., Rio Grande City, Tex.; Laredo Furniture Distributors, Rio Grande City, Tex.; City Auto Parts, Rio Grande City, Tex.; Botica Nueva, C. Miguel Aleman, Tamps., Mex.; Madereria Camargo, Cd. Camargo, Tamps., Mex.; Madereria Chapa, Cuidad Camargo, Tamps., Mex. Send protests to: James H. Berry, District Supervisor, Bureau of Operations and Compliance, Interstate Commerce Commission, 206 Manion Building, 301 Broadway, San Antonio, Tex. 78205.

By the Commission.

[SEAL]

H. NEIL GARSON,
Secretary.

[F.R. Doc. 66-9852; Filed, Sept. 7, 1966;
8:52 a.m.]

[Notice 1408]

MOTOR CARRIER TRANSFER PROCEEDINGS

SEPTEMBER 2, 1966.

Synopses of orders entered pursuant to section 212(b) of the Interstate Commercial rules of practice any interest described thereunder (49 CFR Part 179), appear below:

As provided in the Commission's special rules of practice any interested person may file a petition seeking reconsideration of the following numbered proceedings within 20 days from the date of publication of this notice. Pursuant to section 17(8) of the Interstate Com-

merce Act, the filing of such a petition will postpone the effective date of the order in that proceeding pending its disposition. The matters relied upon by petitioners must be specified in their petitions with particularity.

No. MC-FC-68727. By order of August 31, 1966, the Transfer Board, on reconsideration, approved the transfer to Laurel Transport Corp., Rio Grande, N.J., of certificate No. MC-15102 (Sub-No. 1), issued March 2, 1942, to Eldredge Storage, a corporation, Atlantic City, N.J., authorizing the transportation of: General commodities, with usual exceptions, over irregular routes, between Atlantic City, Linwood, Somers Point, Sea Isle City, Strathmere, Ventnor, Margate and Longport, N.J. Morris J. Winokur, 1920 Two Penn Center Plaza, Philadelphia, Pa. 19120, attorney for applicants.

No. MC-FC-68918. By order of August 31, 1966, the Transfer Board approved the transfer to Kato Express, Inc., Elizabethtown, Ky., of the certificates in Nos. MC-108329 and MC-108329 (Sub-No. 8), issued November 25, 1964, and June 8, 1965, respectively, to Kato, Inc., Elizabethtown, Ky., authorizing the transportation of: Motion picture films, projector equipment and supplies, and advertising matter, between Indianapolis, Ind., on the one hand, and, on the other, points as specified in Kentucky; magazines and periodicals, from Indianapolis, Ind., and Cincinnati, Ohio, to Bowling Green, Lexington, and Paducah, Ky.; and general commodities, excluding household goods, commodities in bulk, and other specified commodities, between Louisville, Ky., on the one hand, and, on the other, points in Hardin, Larue, and Hart Counties, Ky., as restricted. Rudy Yessin, Post Office Box 457, Frankfort, Ky., attorney for applicants.

No. MC-FC-68936. By order of August 31, 1966, the Transfer Board approved the transfer to Wyeth A. Bond, doing business as Advance Transportation Co., Clinton, Mo., of the certificate of registration in No. MC-121305 (Sub-No. 1), issued April 22, 1965, to Paul M. Eaton, doing business as Advance Transportation Co., Clinton, Mo., and corresponding in scope to the grant of authority in certificate of public convenience and necessity No. T-20,891, dated January 24, 1962, as amended July 31,

1962, issued by the Missouri Public Service Commission. Thomas P. Rose, Jefferson Building, Jefferson City, Mo. 65101, attorney for applicants.

No. MC-FC-68967. By order of August 31, 1966, the Transfer Board approved the transfer to Leonard L. Madsen, Council Bluffs, Iowa, of certificate No. MC-42194, issued March 29, 1955, to Edmund V. Liske and Bessie Liske, a partnership, doing business as Kroeger Transfer, Minden, Iowa, authorizing the transportation of: General commodities, excluding household goods, commodities in bulk, and other specified commodities, between Minden, Iowa, and Omaha, Nebr., serving the intermediate points of Neola, Underwood, and Weston, Iowa. R. A. Porter, 201 First National Bank Building, Council Bluffs, Iowa 51501, attorney for applicants.

No. MC-FC-68994. By order of August 31, 1966, the Transfer Board approved the transfer to Feed Transporters, Inc., Oshkosh, Wis., of the operating rights in permit No. MC-126056, issued October 15, 1964, to C. Richard Trine, Pittsford, Mich., and authorizing the transportation of: Animal and poultry feed, over irregular routes, from Burlington, Wis., to points in the Lower Peninsula of Michigan; also, commodities used in the manufacture of animal and poultry feed, insecticides, and poultry, and livestock remedies, from points in the Lower Peninsula of Michigan to Burlington, Wis. Edward Solie, 4513 Vernon Boulevard, Madison, Wis., attorney for applicants.

No. MC-FC-69027. By order of August 31, 1966, the Transfer Board approved the transfer to Edward L. Trasferini, doing business as Rich's Express, Malaga, N.J., of that portion of certificate No. MC-2263, issued June 10, 1965, to Laurel Transport Corp., Rio Grande, N.J., authorizing the transportation of: General commodities, with usual exceptions, over irregular routes, between Philadelphia, Pa., on the one hand, and, on the other, points in Cumberland, Gloucester, and Salem Counties, N.J. Morris J. Winokur, 1920 Two Penn Center Plaza, Philadelphia, Pa. 19120, and H. Charles Ephraim, 1411 K Street NW., Washington, D.C. 20005, attorneys for applicants.

No. MC-FC-69028. By order of August 31, 1966, the Transfer Board ap-

proved the transfer to Laurel Transport Corp., Rio Grande, N.J., of certificate No. MC-87661, issued October 19, 1949, to Edward L. Trasferini, doing business as Rich's Express, Malaga, N.J., authorizing the transportation of: General commodities, except dangerous explosives, articles of unusual dimensions, bulk commodities, and commodities contaminating to other lading, over irregular routes, between points and places in the Philadelphia, Pa., commercial zone, as defined in 17 M.C.C. 533, on the one hand, and, on the other, Vineland, Millville, Minotola, Landisville, Newfield, Clayton, Glassboro, Malaga, Woodbury, Runnemede, Bridgeton, Pitman, Iona, and Franklinville, N.J. Morris J. Winokur, 1920 Two Penn Center Plaza, Philadelphia, Pa. 19120, and H. Charles Ephraim, 1411 K Street NW., Washington, D.C. 20005, attorney for applicants.

[SEAL]

H. NEIL GARSON,
Secretary.[F.R. Doc. 66-9853; Filed, Sept. 7, 1966;
8:52 a.m.]

[Notice 1408-A]

MOTOR CARRIER TRANSFER PROCEEDINGS

SEPTEMBER 2, 1966.

Application filed for temporary authority under section 210(a) (b) in connection with transfer application under section 212(b) and transfer rules (49 CFR Part 179):

No. MC-FC-69050. (Correction) In FEDERAL REGISTER notice of September 1, 1966, on page 11585, the MC-FC-No. 69058 was erroneously given, and in lieu of that number, MC-FC-69050 should be shown as correct for CARDINAL AIR SERVICE CORPORATION, seeking temporary authority to lease the operating rights of ESTATE OF CLIFFORD EARL FARNSWORTH, DECEASED, JANE ELIZABETH DEYOUNG FARNSWORTH, EXECUTRIX, doing business as FARNSWORTH'S AIR FREIGHT SERVICE.

[SEAL]

H. NEIL GARSON,
Secretary.[F.R. Doc. 66-9854; Filed, Sept. 7, 1966;
8:52 a.m.]

CUMULATIVE LIST OF PARTS AFFECTED—SEPTEMBER

The following numerical guide is a list of the parts of each title of the Code of Federal Regulations affected by documents published to date during September.

3 CFR	Page	8 CFR—Continued	Page	28 CFR	Page
PROCLAMATIONS:		221.....	11714	0.....	11720
Nov. 5, 1906 (revoked in part by PLO 4083).....	11755	243.....	11744		
33 (revoked in part by PLO 4083).....	11755	299.....	11714	29 CFR	
1066 (revoked in part by PLO 4083).....	11755	9 CFR		800.....	11720
3739.....	11639	131.....	11607	32 CFR	
3740.....	11705	PROPOSED RULES:		579.....	11642
3741.....	11707	324.....	11614	1455.....	11651
		325.....	11614	32A CFR	
EXECUTIVE ORDER:				NSA (Ch. XVIII):	
April 17, 1926 (revoked in part by PLO 4077).....	11547	12 CFR		AGE-4.....	11651
6143 (revoked in part by PLO 4077).....	11547	1.....	11641	33 CFR	
6276 (revoked in part by PLO 4077).....	11547	13 CFR		80.....	11722
6583 (revoked in part by PLO 4077).....	11547	121.....	11651	95.....	11722
7373 (revoked by PLO 4079).....	11547	14 CFR		43 CFR	
11142 (superseded by EO 11302).....	11741	39.....	11593, 11641, 11714, 11715	2230.....	11546
11301.....	11709	71.....	11546, 11743	3320.....	11548
11302.....	11741		11594, 11595, 11715-11717, 11743	PUBLIC LAND ORDERS:	
5 CFR		75.....	11745	156 (revoked by PLO 4079).....	11547
213.....	11545, 11651	91.....	11641	750 (revoked in part by PLO 4076).....	11546
511.....	11545	95.....	11745	4019 (corrected by PLO 4081).....	11755
534.....	11545, 11651	97.....	11596	4076.....	11546
		151.....	11605, 11747	4077.....	11547
7 CFR		PROPOSED RULES:		4078.....	11547
51.....	11546	39.....	11615	4079.....	11547
52.....	11591	71.....	11615, 11761	4080.....	11755
68.....	11653		11616, 11724, 11725, 11759-11761	4081.....	11755
215.....	11743	75.....	11725	4082.....	11755
701.....	11591	121.....	11725	4083.....	11755
724.....	11655	16 CFR		46 CFR	
811.....	11711	13.....	11719, 11747, 11750-11754	222.....	11607
831.....	11591	15.....	11607	510.....	11652
908.....	11656, 11743	19 CFR		PROPOSED RULES:	
910.....	11656	10.....	11593	10.....	11665
924.....	11657	21 CFR		11.....	11665
926.....	11657	19.....	11717	12.....	11666
927.....	11657	29.....	11754	531.....	11616
931.....	11657	120.....	11754	47 CFR	
946.....	11743	121.....	11608-11610, 11718	0.....	11755
948.....	11658, 11712, 11743	166.....	11754	74.....	11720
981.....	11744	191.....	11719	PROPOSED RULES:	
1446.....	11592	22 CFR		73.....	11761
PROPOSED RULES:		42.....	11755	91.....	11726
55.....	11666	26 CFR		49 CFR	
110.....	11614	1.....	11794	71-79.....	11756
112.....	11614	PROPOSED RULES:		77.....	11549
113.....	11614	1.....	11845, 11850	101.....	11550
905.....	11553	8 CFR		50 CFR	
932.....	11758	103.....	11713	10.....	11658
1013.....	11669	212.....	11714	32.....	11551, 11663
8 CFR		213.....	11714		11552, 11610-11612, 11662, 11721, 11722, 11756, 11757.
103.....	11713	214.....	11714, 11744		

FEDERAL REGISTER

VOLUME 31 • NUMBER 174

Thursday, September 8, 1966 • Washington, D.C.

PART II

Department of the Treasury
Internal Revenue Service

Consolidated Return Regulations



Rules and Regulations

Title 26—INTERNAL REVENUE

Chapter I—Internal Revenue Service, Department of the Treasury

SUBCHAPTER A—INCOME TAX

[T.D. 6894]

PART 1—INCOME TAX; TAXABLE YEAR BEGINNING AFTER DECEMBER 31, 1953

Consolidated Return Regulations

On October 1, 1965, notice of proposed rule making with respect to the amendment of the Income Tax Regulations (26 CFR Part 1) under Subchapter A of Chapter 6 of the Internal Revenue Code of 1954 (relating to consolidated returns), was published in the FEDERAL REGISTER (30 F.R. 190). After consideration of all such relevant matter as was presented by interested persons regarding the rules proposed, §§ 1.1502-14, 1.1502-19, 1.1502-25, 1.1502-31, 1.1502-32, and 1.1502-33 are hereby withdrawn and the remainder of the amendment as proposed is hereby adopted, subject to the changes set forth below:

PARAGRAPH 1. That part of the table of contents, as set forth in the notice of proposed rule making, which precedes "Regulations Applicable to Taxable Years Prior to January 1, 1966" is revised.

PAR. 2. Section 1.1502-1 is revised.

PAR. 3. Section 1.1502-2 is revised.

PAR. 4. Section 1.1502-3 is changed by revising the title, paragraph (a) (2), the title of paragraph (c), paragraph (c) (2) (i) and (ii), example (2) of paragraph (d), paragraph (e) (2), the title of paragraph (f) (2), and example (1) of paragraph (f) (3).

PAR. 5. Section 1.1502-4 is changed by revising the title, that part of paragraph (d) (1) which precedes (i), paragraph (e) (1), and the title of paragraph (f).

PAR. 6. Section 1.1502-5 is changed by revising paragraph (a), that part of paragraph (b) (1) which precedes (i), and example (1) of paragraph (c).

PAR. 7. Section 1.1502-12 is changed by revising paragraph (a) and by adding paragraph (c).

PAR. 8. Section 1.1502-13 is changed by revising paragraph (a) (1) (ii), paragraph (a) (2) (iii), paragraph (b) (1), paragraph (c) (1) (i), paragraph (c) (1) (ii) (b), and paragraph (c) (3), (4), (5), and (6), by deleting paragraph (d) (3) and (4), by adding a new paragraph (d) (3), by revising paragraph (e) (1) and (3) and paragraph (f), and by revising example (2), example (3), example (6) (i), example (7) (i), example (11) (i), and example (18) (i) of paragraph (h), by reserving paragraph (i) and by adding paragraph (j).

PAR. 9. Section 1.1502-14 is reserved.

PAR. 10. Section 1.1502-15 is revised.

PAR. 11. Section 1.1502-17 is changed by revising paragraph (a).

PAR. 12. Section 1.1502-18 is changed by revising paragraphs (a), (b), and (c), by revising examples (1), (2), (3), and (4) of paragraph (d), by revising paragraph (e) (2), and paragraph (f) (1), (2), and (3), and by adding paragraph (f) (5).

PAR. 13. Section 1.1502-19 is reserved.

PAR. 14. Section 1.1502-21 is changed by revising the title of paragraph (c), by revising paragraph (d) (3), and by revising paragraph (e) (1) (i).

PAR. 15. Section 1.1502-22 is changed by revising paragraph (a) (3), by deleting paragraph (a) (4), and by revising the title to paragraph (c).

PAR. 16. Section 1.1502-24 is changed by revising paragraph (c).

PAR. 17. Sections 1.1502-25, 1.1502-31, 1.1502-32, and 1.1502-33 are reserved.

PAR. 18. Section 1.1502-34 is revised.

PAR. 19. Section 1.1502-36 is redesignated as § 1.1502-41, and the designation of reserved sections is revised accordingly.

PAR. 20. Section 1.1502-75 is changed by revising paragraph (a), the title of paragraph (b), paragraph (c) (1) (i), paragraph (c) (1) (iii) (a), (b), and (c), paragraph (c) (3), by deleting paragraph (d) (2) (iii), by adding a new subparagraph (3) to paragraph (d), and by revising paragraph (g) (2) (i) and paragraph (h) (2).

PAR. 21. Section 1.1502-76 is changed by revising paragraph (a) (1), paragraph (b), examples (2) and (3) of paragraph (b) (3), paragraph (b) (4) (ii), paragraph (c) (2), and example (1) of paragraph (c) (3).

PAR. 22. Section 1.1502-77 is changed by revising paragraphs (c) and (d).

PAR. 23. Section 1.1502-79 is changed by revising paragraph (a), the title of paragraph (c), paragraph (c) (1), and the title of paragraph (c) (2).

PAR. 24. Section 1.1502-80 is revised.

PAR. 25. Section 1.1502-31A is changed by revising paragraph (b) (3) (i) and by revising paragraph (b) (21) (i) and (ii).

[SEAL]

HAROLD T. SWARTZ,
Acting Commissioner of
Internal Revenue.

Approved: September 2, 1966.

STANLEY S. SURREY,
Assistant Secretary of
the Treasury.

The Income Tax Regulations (26 CFR Part 1) under subchapter A of chapter 6 of the Internal Revenue Code of 1954, relating to consolidated returns, are amended by revising the regulations under section 1502 to read as follows:

CONSOLIDATED RETURN REGULATIONS

Sec.	
1.1502	Statutory provisions; regulations.
1.1502-0	Effective date.
1.1502-1	Definitions.

CONSOLIDATED TAX LIABILITY

1.1502-2	Computation of tax liability.
1.1502-3	Consolidated investment credit.
1.1502-4	Consolidated foreign tax credit.
1.1502-5	Estimated tax.
1.1502-6	Liability for tax.
1.1502-7 to 1.1502-10	[Reserved]

(COMPUTATION OF CONSOLIDATED TAXABLE INCOME)

1.1502-11	Consolidated taxable income.
-----------	------------------------------

COMPUTATION OF SEPARATE TAXABLE INCOME

1.1502-12	Separate taxable income.
1.1502-13	Intercompany transactions.
1.1502-14	[Reserved]
1.1502-15	Limitation on certain deductions.
1.1502-16	Mine exploration expenditures.
1.1502-17	Methods of accounting.
1.1502-18	Inventory adjustment.
1.1502-19 to 1.1502-20	[Reserved]

COMPUTATION OF CONSOLIDATED ITEMS

1.1502-21	Consolidated net operating loss deduction.
1.1502-22	Consolidated net capital gain or loss.
1.1502-23	Consolidated section 1231 net gain or loss.
1.1502-24	Consolidated charitable contributions deduction.
1.1502-25	[Reserved]
1.1502-26	Consolidated dividends received deduction.
1.1502-27	Consolidated section 247 deduction.
1.1502-28 to 1.1502-30	[Reserved]

BASIS, STOCK OWNERSHIP, AND EARNINGS AND PROFITS RULES

1.1502-31 to 1.1502-33	[Reserved]
1.1502-34	Special aggregate stock ownership rules.
1.1502-35 to 1.1502-40	[Reserved]

SPECIAL TAXES AND TAXPAYERS

1.1502-41	Determination of consolidated net long-term capital gain and consolidated net short-term capital loss.
1.1502-42 to 1.1502-74	[Reserved]

ADMINISTRATIVE PROVISIONS AND OTHER RULES

1.1502-75	Filing of consolidated returns.
1.1502-76	Taxable year of members of group.
1.1502-77	Common parent agent for subsidiaries.
1.1502-78	Tentative carryback adjustment.
1.1502-79	Separate return years.
1.1502-80	Applicability of other provisions of law.

REGULATIONS APPLICABLE TO TAXABLE YEARS PRIOR TO JANUARY 1, 1966

1.1502-0A	Introductory.
1.1502-1A	Privilege of making consolidated returns.
1.1502-2A	Definitions.
1.1502-3A	Applicability of other provisions of law.

- Sec.
1.1502-4A to 1.1502-9A [Reserved]
1.1502-10A Exercise of privilege.
1.1502-11A Consolidated returns for subsequent years.
1.1502-12A Making consolidated return and filing other forms.
1.1502-13A Change in affiliated group during taxable year.
1.1502-14A Accounting period of an affiliated group.
1.1502-15A Liability for tax.
1.1502-16A Common parent corporation agent for subsidiaries.
1.1502-17A Waivers.
1.1502-18A Failure to comply with regulations.
1.1502-19A Tentative carryback adjustments.
1.1502-20A to 1.1502-29A [Reserved]
1.1502-30A Computation of tax.
1.1502-31A Basis of tax computation.
1.1502-32A Method of computation of income for period of less than 12 months.
1.1502-33A Gain or loss from sale of stock, or bonds or other obligations.
1.1502-34A Sale of stock; basis for determining gain or loss.
1.1502-35A Sale of bonds or other obligations; basis for determining gain or loss.
1.1502-36A Limitation on allowable losses on sale of stock, or bonds, or other obligations.
1.1502-37A Liquidations; recognition of gain or loss.
1.1502-38A Basis of property.
1.1502-39A Inventories.
1.1502-40A Bad debts.
1.1502-41A Sale and retirement by corporation of its bonds.
1.1502-42A Capital loss limitations and carryover.
1.1502-43A Credit for foreign taxes.
1.1502-44A Methods of accounting.
1.1502-45A Mine exploration expenditures.
1.1502-46A Depreciation.
1.1502-47A Election to deduct accrued taxes.
1.1502-48A Liability for tax under section 531.
1.1502-49A Additions to tax for failure to pay estimated tax.
1.1502-50A Gain on sale of bonds and other evidences of indebtedness.
1.1502-51A Credit for investment in certain depreciable property.

§ 1.1502 Statutory provisions; regulations.

Sec. 1502. Regulations. The Secretary or his delegate shall prescribe such regulations as he may deem necessary in order that the tax liability of any affiliated group of corporations making a consolidated return and of each corporation in the group, both during and after the period of affiliation, may be returned, determined, computed, assessed, collected, and adjusted, in such manner as clearly to reflect the income tax liability and the various factors necessary for the determination of such liability, and in order to prevent avoidance of such tax liability.

§ 1.1502-0 Effective date.

(a) The provisions of §§ 1.1502-1 through 1.1502-80 shall be applicable to taxable years beginning after December 31, 1965.

(b) The provisions of §§ 1.1502-0A through 1.1502-51A shall be applicable to taxable years beginning before January 1, 1966.

§ 1.1502-1 Definitions.

(a) **Group.** The term "group" means an affiliated group of corporations as de-

fined in section 1504. See § 1.1502-75 (d) as to when a group remains in existence.

(b) **Member.** The term "member" means a corporation (including the common parent) which is included within such group.

(c) **Subsidiary.** The term "subsidiary" means a corporation other than the common parent which is a member of such group.

(d) **Consolidated return year.** The term "consolidated return year" means a taxable year for which a consolidated return is filed or required to be filed by such group.

(e) **Separate return year.** The term "separate return year" means a taxable year of a corporation for which it files a separate return or for which it joins in the filing of a consolidated return by another group.

(f) **Separate return limitation year—**
(1) **In general.** Except as provided in subparagraphs (2) and (3) of this paragraph, the term "separate return limitation year" means any separate return year of a member or of a predecessor of such member. The term "predecessor" means a transferor or distributor of assets to a member in a transaction to which section 381(a) applies.
(2) **Exceptions.** The term "separate return limitation year" shall not include—

(i) A separate return year of the corporation which is the common parent for the consolidated return year to which the tax attribute is to be carried,
(ii) A separate return year of any subsidiary which was a member of the group for each day of such year, or
(iii) A separate return year of a predecessor of any member if such predecessor was a member of the group for each day of such year,

provided that an election under section 1562 (relating to privilege to elect multiple surtax exemptions) was not effective for such year. An election under section 1562 which is effective for a taxable year beginning in 1963 and ending in 1964 shall be disregarded.

(3) **Reverse acquisitions.** In the event of an acquisition to which § 1.1502-75(d) (3) applies, all taxable years of the first corporation and of each of its subsidiaries ending on or before the date of the acquisition shall be treated as separate return limitation years, and the separate return years (if any) of the second corporation and each of its subsidiaries shall not be treated as separate return limitation years (unless they were so treated immediately before the acquisition).

For example, if corporation P merges into corporation T, and the persons who were stockholders of P immediately before the merger, as a result of owning the stock of P, own more than 50 percent of the fair market value of the outstanding stock of T, then a loss incurred before the merger by T (even though it is the common parent), or by a subsidiary of T, is treated as having been incurred in a separate return limitation year. Conversely, a loss incurred before the merger by P, or by a subsidiary of P in a separate

return year during all of which such subsidiary was a member of the group of which P was the common parent and for which section 1562 was not effective, is treated as having been incurred in a year which is not a separate return limitation year.

(g) **Consolidated return change of ownership—**
(1) **In general.** A consolidated return change of ownership occurs during any taxable year (referred to in this subparagraph as the "year of change") of the corporation which is the common parent for the taxable year to which the tax attribute is to be carried, if, at the end of the year of change—

(i) Any one or more of the persons described in section 382(a) (2) own a percentage of the fair market value of the outstanding stock of such corporation which is more than 50 percentage points greater than such person or persons owned at—

(a) The beginning of such taxable year, or

(b) The beginning of the preceding taxable year, and

(ii) The increase in percentage points at the end of such year is attributable to—

(a) A purchase (within the meaning of section 382(a) (4)) by such person or persons of such stock, the stock of another corporation owning stock in such corporation, or an interest in a partnership or trust owning stock in such corporation, or

(b) A decrease in the amount of such stock outstanding or the amount of stock outstanding of another corporation owning stock in such corporation, except a decrease resulting from a redemption to pay death taxes to which section 303 applies.

For purposes of subdivision (i) (a) and (b) of this subparagraph, the beginning of the taxable years specified therein shall be the beginning of such taxable years or October 1, 1965, whichever occurs later.

(2) **Operating rules.** For purposes of this paragraph—

(i) The term "stock" means all shares except nonvoting stock which is limited and preferred as to dividends, and

(ii) Section 318 (relating to constructive ownership of stock) shall apply in determining the ownership of stock, except that section 318(a) (2) (C) and (3) (C) shall be applied without regard to the 50-percent limitation contained therein.

(3) **Old members.** The term "old members" of a group means—

(i) Those corporations which were members of such group immediately preceding the first day of the taxable year in which the consolidated return change of ownership occurs, or

(ii) If the group was not in existence prior to the taxable year in which the consolidated return change of ownership occurs, the corporation which is the common parent for the taxable year to which the tax attribute is to be carried.

(4) **Reverse acquisitions.** If there has been a consolidated return change of ownership of a corporation under sub-

paragraph (1) of this paragraph and the stock or assets of such corporation are subsequently acquired by another corporation in an acquisition to which § 1.1502-75(d)(3) applies so that the group of which the former corporation is the common parent is treated as continuing in existence, then the "old members", as defined in subparagraph (3) of this paragraph, of such group immediately before the acquisition shall continue to be treated as "old members" immediately after the acquisition. For example, assume that corporations P and S comprise group PS, and PS undergoes a consolidated return change of ownership. Subsequently, the stock of P, the common parent, is acquired by corporation T, the common parent of group TU, in an acquisition to which section 368 (a)(1)(B) and § 1.1502-75(d)(3) apply. The PS group is treated as continuing in existence with T as the common parent. P and S continue to be treated as old members, as defined in subparagraph (3) of this paragraph.

CONSOLIDATED TAX LIABILITY

§ 1.1502-2 Computation of tax liability.

The tax liability of a group for a consolidated return year shall be determined by adding together—

(a) The tax imposed by section 11 on the consolidated taxable income for such year (see § 1.1502-11 for the computation of consolidated taxable income);

(b) The tax imposed by section 541 on the consolidated undistributed personal holding company income;

(c) If paragraph (b) of this section does not apply, the aggregate of the taxes imposed by section 541 on the separate undistributed personal holding company income of the members which are personal holding companies;

(d) If paragraph (b) of this section does not apply, the tax imposed by section 531 on the consolidated accumulated taxable income;

(e) The tax imposed by section 594(a) in lieu of the taxes imposed by section 11 or 1201 on the taxable income of a life insurance department of the common parent of a group which is a mutual savings bank;

(f) The tax imposed by section 802(a) on consolidated life insurance company taxable income;

(g) The tax imposed by section 831(a) on the consolidated insurance company taxable income of the members which are subject to such tax;

(h) The tax imposed by section 1201, in lieu of the taxes computed under paragraphs (a) and (g) of this section, computed by reference to the excess of the consolidated net long-term capital gain over the consolidated net short-term capital loss (see § 1.1502-41 for the determination of the consolidated net long-term capital gain and the consolidated net short-term capital loss);

(i) [Reserved]

(j) The tax imposed by section 1333 on war loss recoveries; and

by allowing as a credit against such taxes the investment credit under sec-

tion 38 (see § 1.1502-3), and the foreign tax credit under section 33 (see § 1.1502-4). For purposes of this section, the surtax exemption of the group for a consolidated return year is \$25,000, or if a lesser amount is allowed under section 1561, such lesser amount. See § 1.1561-2(a)(2). For increase in tax due to the application of section 47, see § 1.1502-3(f).

§ 1.1502-3 Consolidated investment credit.

(a) *Determination of amount of consolidated credit—*(1) *In general.* The credit allowed by section 38 for a consolidated return year of a group shall be equal to the consolidated credit earned. The consolidated credit earned is equal to the aggregate of the credit earned (as determined under subparagraph (2) of this paragraph) by all members of the group for the consolidated return year.

(2) *Determination of credit earned.* The credit earned of a member is an amount equal to 7 percent of such member's qualified investment (determined under section 46(c)). For purposes of computing a member's qualified investment, the basis of property shall not include any gain or loss realized with respect to such property by another member in an intercompany transaction (as defined in § 1.1502-13(a)(1)), whether or not such gain or loss is deferred. Thus, if section 38 property acquired in an intercompany transaction has a basis of \$100 to the purchasing member, and if the selling member has a \$20 gain with respect to such property, the basis of such property for purposes of computing the purchaser's qualified investment is only \$80. Such \$80 basis shall also be used for purposes of applying section 47 to such property. See paragraph (f) of this section.

(3) *Consolidated limitation based on amount of tax.* (i) Notwithstanding the amount of the consolidated credit earned for the taxable year, the consolidated credit allowed by section 38 to the group for the consolidated return year is limited to—

(a) So much of the consolidated liability for tax as does not exceed \$25,000, plus

(b) 25 percent of the consolidated liability for tax in excess of \$25,000.

The \$25,000 amount referred to in (a) and (b) of the preceding sentence shall be reduced by any part of such \$25,000 amount apportioned, under paragraph (f)(6) of § 1.46-1, to members of the affiliated group (as defined in section 46(a)(5)) which do not join in the filing of the consolidated return. The amount determined under this subparagraph shall be referred to in this section as the "consolidated limitation based on amount of tax."

(ii) If an organization to which section 593 applies or a cooperative organization described in section 1381(a) joins in the filing of the consolidated return, the \$25,000 amount referred to in subdivision (i) (a) and (b) of this subparagraph (or such \$25,000 amount reduced by any part of such amount apportioned

to members of the affiliated group, as defined in section 46(a)(5)), which do not join in the filing of the consolidated return) shall be apportioned equally among the members of the group filing the consolidated return. The amount so apportioned equally to any such organization shall then be decreased in accordance with the provisions of section 46(d). Finally, the sum of all such equal portions (as decreased under section 46(d)) of each member of the group shall be substituted for the \$25,000 amount referred to in subdivision (i) (a) and (b) of this subparagraph.

(4) *Consolidated liability for tax.* For purposes of subparagraph (3) of this paragraph, the consolidated liability for tax shall be the income tax imposed for the taxable year upon the group by chapter 1 of the Code, reduced by the consolidated foreign tax credit allowable under § 1.1502-4. The tax imposed by section 531 (relating to imposition of accumulated earnings tax) or by section 541 (relating to imposition of personal holding company tax) shall not be considered tax imposed by chapter 1 of the Code. In addition, any increase in tax resulting from the application of section 47 (relating to certain dispositions, etc., of section 38 property) shall not be treated as tax imposed by chapter 1 for purposes of computing the consolidated liability for tax.

(b) *Carryback and carryover of unused credits—*(1) *Allowance of unused credit as consolidated carryback or carryover.* A group shall be allowed to add to the amount allowable as a credit under paragraph (a)(1) of this section for any consolidated return year an amount equal to the aggregate of the consolidated investment credit carryovers and carrybacks to such year. The consolidated investment credit carryovers and carrybacks to the taxable year shall consist of any consolidated unused credits of the group, plus any unused credits of members of the group arising in separate return years of such members, which may be carried over or back to the taxable year under the principles of section 46(b). However, such consolidated carryovers and carrybacks shall not include any consolidated unused credits apportioned to a corporation for a separate return year pursuant to paragraph (c) of § 1.1502-79 and shall be subject to the limitations contained in paragraphs (c) and (e) of this section. A consolidated unused credit for any consolidated return year is the excess of the consolidated credit earned over the consolidated limitation based on amount of tax for such year.

(2) *Absorption rules.* For purposes of determining the amount, if any, of an unused credit (whether consolidated or separate) which can be carried to a taxable year (consolidated or separate), the amount of such unused credit which is absorbed in a prior consolidated return year under section 46(b) shall be determined by—

(i) Applying all unused credits which can be carried to such prior year in the order of the taxable years in which such

unused credits arose, beginning with the taxable year which ends earliest, and

(ii) Applying all such unused credits which can be carried to such prior year from taxable years ending on the same date on a pro rata basis.

(c) *Limitation on investment credit carryovers and carrybacks from separate return limitation years*—(1) *General rule.* In the case of an unused credit of a member of the group arising in a separate return limitation year (as defined in paragraph (f) of § 1.1502-1) of such member (and in a separate return limitation year of any predecessor of such member), the amount which may be included under paragraph (b) of this section (computed without regard to the limitation contained in paragraph (e) of this section) shall not exceed the amount determined under subparagraph (2) of this paragraph.

(2) *Computation of limitation.* The amount referred to in subparagraph (1) of this paragraph with respect to a member of the group is the excess, if any, of—

(i) The limitation based on amount of tax of the group, minus such limitation recomputed by excluding the items of income, deduction, and foreign tax credit of such member, over

(ii) The sum of (a) the investment credit earned by such member for such consolidated return year, and (b) the unused credits attributable to such member which may be carried to such consolidated return year arising in unused credit years ending prior to the particular separate return limitation year.

(d) *Examples.* The provisions of paragraphs (a), (b), and (c) of this section may be illustrated by the following examples:

Example (1). Corporation P is incorporated on January 1, 1966. On that same day P incorporates corporation S, a wholly owned subsidiary. P and S file consolidated returns for calendar years 1966 and 1967. P's and S's credit earned, the consolidated credit earned, and the consolidated limitation based on amount of tax for 1966 and 1967 are as follows:

	Credit earned	Consolidated credit earned	Consolidated limitation based on amount of tax
1966:			
P	\$60,000	\$90,000	\$100,000
S	30,000		
1967:			
P	40,000	\$65,000	\$50,000
S	25,000		

(i) P's and S's credit earned for 1966 are aggregated and the group's consolidated credit earned, \$90,000, is allowable in full to the group as a credit under section 38 for 1966 since such amount is less than the consolidated limitation based on amount of tax for 1966, \$100,000.

(ii) Since the consolidated limitation based on amount of tax for 1967 is \$50,000, only \$50,000 of the \$65,000 consolidated credit earned for such year is allowable to the group under section 38 as a credit for 1967. The consolidated unused credit for 1967 of \$15,000 (\$65,000 less \$50,000) is a consolidated investment credit carryback and carryover to

the years prescribed in section 46(b). In this case the consolidated unused credit is a consolidated investment credit carryback to 1966 (since P and S were not in existence in 1964 and 1965) and a consolidated investment credit carryover to 1968 and subsequent years. The portion of the consolidated un-

Consolidated carryback to 1966		\$15,000
1966 consolidated limitation based on tax	\$100,000	
Less: Consolidated credit earned for 1966	\$90,000	
Consolidated unused credits attributable to years preceding 1967	0	90,000
Limit on amount of 1967 consolidated unused credit which may be added as a credit for 1966		10,000
Balance of 1967 consolidated unused credit to be carried to 1968		5,000

Example (2) (i) Assume the same facts as in example (1), except that all the stock of corporation T, also a calendar year taxpayer, is acquired by P on January 1, 1968, and that P, S, and T file a consolidated return for 1968. In 1966 T had an unused credit of \$10,000 which has not been absorbed and is available as an investment credit carryover to 1968. Such carryover is from a separate return limitation year. P's and S's credit earned for 1968 is \$10,000 each and T's credit earned is \$8,000; the consolidated credit earned is therefore \$28,000. The group's consolidated limitation based on amount of tax for 1968 is \$50,000. Such limitation recomputed by excluding the items of income, deduction, and foreign tax credit of T is \$30,000. Thus, the amount determined under paragraph (c) (2) (i) of this section is \$20,000 (\$50,000 minus \$30,000). Accordingly, the limitation on the carryover of T's unused credit is \$12,000, the excess of \$20,000 over \$8,000 (the sum of T's credit earned for the taxable year and any carryovers from prior unused credit years (none in this case)). Therefore T's \$10,000 unused credit from 1966 may be carried over to the consolidated return year without limitation.

T's carryover to 1968		\$10,000
Consolidated limitation based on amount of tax minus recomputed limitation	\$12,000	
Less: T's credit earned for 1968	\$8,000	
Unused credits attributable to T arising in unused credit years preceding 1966	0	8,000
Limit on amount of 1966 unused credit of T which may be added to consolidated investment credit carryover		4,000
Balance of 1966 unused credit of T to be carried to 1969 (subject to the limitation contained in paragraph (c) of this section)		6,000

(e) *Limitation on investment credit carryovers where there has been a consolidated return change of ownership*—

(1) *General rule.* If a consolidated return change of ownership (as defined in paragraph (g) of § 1.1502-1) occurs during the taxable year or an earlier taxable year, the amount which may be included under paragraph (b) of this section in the consolidated investment credit carryovers to the taxable year with respect to the aggregate unused credits attributable to old members of the group (as defined in paragraph (g) (3) of § 1.1502-1) arising in taxable years (consolidated or separate) ending on the same day and before the taxable year in which the consolidated return change of ownership occurred shall not exceed the amount determined under subparagraph (2) of this paragraph.

(2) *Computation of limitation.* The amount referred to in subparagraph (1) of this paragraph shall be the excess of the consolidated limitation based on the amount of tax for the taxable year, recomputed by including only the items of income, deduction, and foreign tax credit of the old members, over the sum of—

used credit for 1967 which is allowable as a credit for 1966 is \$10,000. This amount shall be added to the amount allowable as a credit to the group for 1966. The balance of the consolidated unused credit for 1967 to be carried to 1968 is \$5,000. These amounts are computed as follows:

(ii) The group's consolidated credit earned for 1968, \$28,000, is allowable in full as a credit under section 38 since such amount is less than the consolidated limitation based on amount of tax, \$50,000.

(iii) The group's consolidated investment credit carryover to 1968 is \$15,000, consisting of the consolidated unused credits of the group (\$5,000), plus T's separate return year unused credit (\$10,000). The entire \$15,000 consolidated carryover shall be added to the amount allowable to the group as a credit under section 38 for 1968, since such amount is less than \$22,000 (the excess of the consolidated limitation based on tax, \$50,000, over the sum of the consolidated credit earned for 1968, \$28,000, and unused credits arising in prior unused credit years, zero).

Example (3). Assume the same facts as in example (2), except that the amount determined under paragraph (c) (2) (i) of this section is \$12,000. Therefore, the limitation on the carryover of T's unused credit is \$4,000. Accordingly, the consolidated investment credit carryover is only \$9,000 since the amount of T's separate return year unused credit which may be added to the group's \$5,000 consolidated unused credit is \$4,000. These amounts are computed as follows:

(i) The aggregate investment credits earned by the old members for the taxable year, and

(ii) The aggregate unused investment credits attributable to the old members which may be carried to the taxable year arising in unused credit years ending prior to the particular unused credit year or years.

(f) *Early dispositions, etc., of section 38 property*—(1) *Dispositions of section 38 property during and after consolidated return year.* If property is subject to section 47(a) (1) or (2) with respect to a member during a consolidated return year, any increase in tax shall be added to the tax liability of the group under § 1.1502-2 (regardless of whether the property was placed in service in a consolidated or separate return year). Also, if property is subject to section 47(a) (1) or (2) with respect to a corporation during a taxable year for which such corporation files on a separate return basis, any increase in tax shall be added to the tax liability of such corporation (regardless of whether such property was placed in service in a consolidated or separate return year).

(2) *Exception for transfer to another member.* (i) Except as provided in subdivisions (ii) and (iii) of this subparagraph, a transfer of section 38 property from one member of the group to another member of such group during a consolidated return year shall not be treated as a disposition or cessation within the meaning of section 47(a)(1). If such section 38 property is disposed of, or otherwise ceases to be section 38 property or becomes public utility property with respect to the transferee, before the close of the estimated useful life which was taken into account in computing qualified investment, then section 47(a)(1) or (2) shall apply to the transferee with respect to such property (determined by taking into account the period of use, qualified investment, other dispositions, etc., of the transferor). Any increase in tax due to the application of section 47(a)(1) or (2) shall be added to the tax liability of such transferee (or the tax liability of a group, if the transferee joins in the filing of a consolidated return).

(ii) Except as provided in subdivision (iii) of this subparagraph, if section 38 property is disposed of during a consolidated return year by one member of the group to another member of such group which is an organization to which section 593 applies or a cooperative organization described in section 1381(a), the tax under chapter 1 of the Code for such consolidated return year shall be increased by an amount equal to the aggregate decrease in the credits allowed under section 38 for all prior taxable years which would result solely from treating such property, for purposes of determining qualified investment, as placed in service by such organization to which section 593 applies or such cooperative organization described in section 1381(a), as the case may be, but with due regard to the use of the property before such transfer.

(iii) Section 47(a)(1) shall apply to a transfer of section 38 property by a corporation during a consolidated return year if such corporation is liquidated in a transaction to which section 334(b)(2) applies.

(3) *Examples.* The provisions of this paragraph may be illustrated by the following examples:

Example (1). P, S, and T file a consolidated return for calendar year 1967. In such year S places in service section 38 property having an estimated useful life of more than 8 years. In 1968, P, S, and T file a consolidated return and in such year S sells such property to T. Such sale will not cause section 47(a)(1) to apply.

Example (2). Assume the same facts as in example (1), except that P, S, and T filed separate returns for 1967. The sale from S to T will not cause section 47(a)(1) to apply.

Example (3). Assume the same facts as in example (1), except that P, S, and T continue to file consolidated returns through 1971 and in such year T disposes of the property to individual A. Section 47(a)(1) will apply to the group and any increase in tax shall be added to the tax liability of the group. For the purposes of determining the actual period of use by

T, such period shall include S's period of use.

Example (4). Assume the same facts as in example (3), except that T files a separate return in 1971. Again, the actual periods of use by S and T will be combined in applying section 47. If the disposition results in an increase in tax under section 47(a)(1), such additional tax shall be added to the separate tax liability of T.

Example (5). Assume the same facts as in example (1), except that in 1969, P sells all the stock of T to a third party. Such sale will not cause section 47(a)(1) to apply.

§ 1.1502-4 Consolidated foreign tax credit.

(a) *In general.* The credit under section 901 for taxes paid or accrued to any foreign country or possession of the United States shall be allowed to the group only if the common parent corporation chooses to use such credit in the computation of the tax liability of the group for the consolidated return year. If this choice is made, no deduction may be taken on the consolidated return for such taxes paid or accrued by any member of the group. See section 275(a)(4).

(b) *Limitation effective under section 904(a) for the group.* (1) *Common parent's limitation effective for group.* The determination of whether the overall limitation or the per-country limitation applies for a consolidated return year shall be made by reference to the limitation effective with respect to the common parent corporation for such year. If the limitation effective with respect to a member for its immediately preceding separate return year differs from the limitation effective with respect to the common parent corporation for the consolidated return year, then such member shall, if the overall limitation is effective with respect to the common parent, be deemed to have made an election to use such overall limitation, or, if the per-country limitation is effective with respect to the common parent, be deemed to have revoked its election to use the overall limitation. Consent of the Secretary or his delegate (if otherwise required) is hereby given to such member for such election or revocation. Any such election or revocation shall apply only prospectively beginning with such consolidated return year.

(2) *Limitation effective for subsequent years.* The limitation effective with respect to a member for the last year for which it joins in the filing of a consolidated return with a group shall remain in effect for a subsequent separate return year and may be changed by such corporation for such subsequent year only in accordance with the provisions of section 904(b) (and this paragraph if it joins in the filing of a consolidated return with another group). Any retroactive change in the limitation by the common parent corporation for such member's last consolidated return year shall change the election effective with respect to such member for such last period. Thus, if the common parent (P) elects the overall limitation with respect to calendar year 1966, such election would be effective with respect to its

subsidiary S for 1966. If S leaves the group at the beginning of calendar year 1967, such election shall be effective for 1967 with respect to S (unless S revokes such election for 1967 or a subsequent year in accordance with section 904(b), or this paragraph if it joins in the filing of a consolidated return with another group). However, if P retroactively changes back to the per-country limitation with respect to 1966, such limitation would be effective with respect to S for 1966 and subsequent years (unless S elects the overall limitation for any such subsequent year).

(c) *Computation of consolidated foreign tax credit.* The foreign tax credit for the consolidated return year shall be determined on a consolidated basis under the principles of sections 901 through 905 and section 960. For example, if the per-country limitation applies to the consolidated return year, taxes paid or accrued for such year (including those deemed paid or accrued under sections 902 and 960 (a) and paragraph (e) of this section) to each foreign country or possession by the members of the group shall be aggregated. If the overall limitation applies, taxes paid or accrued for such year (including those deemed paid or accrued) to all foreign countries and possessions by members of the group shall be aggregated. If the overall limitation applies and a member of the group qualifies as a Western Hemisphere trade corporation, see section 1503(b).

(d) *Computation of limitation on credit.* For purposes of computing the group's applicable limitation under section 904(a), the following rules shall apply:

(1) *Computation of taxable income from foreign sources.* The numerator of the applicable limiting fraction under section 904(a) shall be an amount (not in excess of the amount determined under subparagraph (2) of this paragraph) equal to the aggregate of the separate taxable incomes of the members from sources within each foreign country or possession of the United States (if the per-country limitation is applicable), or from sources without the United States (if the overall limitation is applicable), determined under § 1.1502-12, adjusted for the following items taken into account in the computation of consolidated taxable income:

(i) The portion of the consolidated net operating loss deduction, the consolidated charitable contributions deduction, the consolidated dividends received deduction, and the consolidated section 922 deduction, attributable to such foreign source income;

(ii) Any such foreign source net capital gain (determined without regard to any net capital loss carryover);

(iii) Any such foreign source net capital loss and section 1231 net loss, reduced by the portion of the consolidated net capital loss attributable to such foreign source loss; and

(iv) The portion of any consolidated net capital loss carryover attributable to such foreign source income which is absorbed in the taxable year.

(2) *Computation of entire taxable income.* The denominator of the applicable limiting fraction under section 904(a) (that is, the entire taxable income of the group) shall be the consolidated taxable income of the group computed in accordance with § 1.1502-11.

(3) *Computation of tax against which credit is taken.* The tax against which the limiting fraction under section 904(a) is applied shall be the consolidated tax liability of the group determined under § 1.1502-2, but without regard to paragraphs (b), (c), (d), and (j) thereof, and without regard to any credit against such liability.

(e) *Carryover and carryback of unused foreign tax—(1) Allowance of unused foreign tax as consolidated carryover or carryback.* The aggregate of the consolidated unused foreign tax carryovers and carrybacks to the taxable year, to the extent absorbed for such year under the principles of section 904(d), shall be deemed to be paid or accrued to a foreign country or possession for such year. The consolidated unused foreign tax carryovers and carrybacks to the taxable year shall consist of any consolidated unused foreign tax, plus any unused foreign tax of members for separate return years of such members, which may be carried over or back to the taxable year under the principles of section 904 (d) and (e). However, such consolidated carryovers and carrybacks shall not include any consolidated unused foreign taxes apportioned to a corporation for a separate return year pursuant to § 1.1502-79(d) and shall be subject to the limitations contained in paragraphs (f) and (g) of this section. A consolidated unused foreign tax is the excess of the foreign taxes paid or accrued by the group (or deemed paid or accrued by the group, other than by reason of section 904(d)) over the applicable limitation for the consolidated return year.

(2) *Absorption rules.* For purposes of determining the amount, if any, of an unused foreign tax (consolidated or separate) which can be carried to a taxable year (consolidated or separate), the amount of such unused tax which is absorbed in a prior consolidated return year under section 904(d) shall be determined by—

(i) Applying all unused foreign taxes which can be carried to such prior year in the order of the taxable years in which such unused taxes arose, beginning with the taxable year which ends earliest, and

(ii) Applying all such unused taxes which can be carried to such prior year from taxable years ending on the same date on a pro rata basis.

(f) *Limitation on unused foreign tax carryover or carryback from separate return limitation years—(1) General rule.* In the case of an unused foreign tax of a member of the group arising in a separate return limitation year (as defined in paragraph (f) of § 1.1502-1) of such member, the amount which may be included under paragraph (e) of this section (computed without regard to the limitation contained in paragraph (g) of this section) shall not exceed the

amount determined under subparagraph (2) of this paragraph.

(2) *Computation of limitation.* The amount referred to in subparagraph (1) of this paragraph with respect to a member of the group is the excess, if any, of—

(i) The section 904(a) limitation of the group, minus such limitation recomputed by excluding the items of income and deduction of such member, over

(ii) The sum of (a) the foreign taxes paid (or deemed paid, other than by reason of section 904(d)) by such member for the consolidated return year, and (b) the unused foreign tax attributable to such member which may be carried to such consolidated return year arising in taxable years ending prior to the particular separate return limitation year.

(g) *Limitation on unused foreign tax carryover where there has been a consolidated return change of ownership—(1) General rule.* If a consolidated return change of ownership (as defined in paragraph (g) of § 1.1502-1) occurs during the taxable year or an earlier taxable year, the amount which may be included under paragraph (e) of this section in the consolidated unused foreign tax carryovers to the taxable year with respect to the aggregate unused credits attributable to the old members of the group (as defined in paragraph (g) (3) of § 1.1502-1) arising in taxable years (consolidated or separate) ending on the same day and before the taxable year in which the consolidated return change of ownership occurred shall not exceed the amount determined under subparagraph (2) of this paragraph.

(2) *Computation of limitation.* The amount referred to in subparagraph (1) of this paragraph shall be the excess of the section 904(a) limitation of the group for the taxable year, recomputed by including only the items of income and deduction of the old members of the group, over the sum of—

(i) The aggregate foreign taxes paid (or deemed paid, other than by reason of section 904(d)) by the old members for the taxable year, and

(ii) The aggregate unused foreign tax attributable to the old members which can be carried to the taxable year arising in taxable years ending prior to the particular unused foreign tax year or years.

(h) *Amount of credit with respect to interest income.* If any member of the group has interest income described in section 904(f) (2) (for a year for which it filed on a consolidated or separate basis), the group's foreign tax credit with respect to such interest shall be computed separately in accordance with the principles of section 904(f) and this section.

(i) [Reserved]

(j) *Examples.* The provisions of this section may be illustrated by the following examples:

Example (1). Domestic corporation P is incorporated on January 1, 1966. On that same day it also incorporates domestic corporations S and T, wholly owned subsidiaries. P, S, and T file consolidated returns for 1966 and 1967 on the basis of a calendar year. T engages in business solely in country

A. S transacts business solely in countries A and B. P does business solely in the United States. During 1966 T sold an item of inventory to P at a profit of \$2,000. Under § 1.1502-13 such profit is deferred and none of the circumstances of restoration contained in paragraph (d), (e), or (f) of § 1.1502-13 have occurred as of the close of 1966. The taxable income for 1966 from foreign and United States sources, and the foreign taxes paid on such foreign income are as follows:

Corporation	U.S. taxable income	Country A		Country B		Total Taxable income
		Taxable income	Foreign tax paid	Taxable income	Foreign tax paid	
P	\$40,000					\$40,000
T		\$20,000	\$12,000			20,000
S		10,000	6,000	\$10,000	\$3,000	20,000
						\$80,000

Such taxable income was computed by taking into account the rules provided in § 1.1502-12. Thus, the \$2,000 deferred profit is not included in T's taxable income for 1966 (but will be included for the taxable year for which one of the events specified in paragraph (d), (e), or (f) of § 1.1502-13 occurs). The consolidated taxable income of the group (computed in accordance with § 1.1502-11) is \$80,000. The consolidated tax liability against which the credit may be taken (computed in accordance with paragraph (d) (3) of this section) is \$31,900.

(i) Assuming P chooses to use the foreign taxes paid as a credit and the group is subject to the per-country limitation, the group may take as a credit against the consolidated tax liability \$11,962.50 of the amount paid to country A, plus the \$3,000 paid to country B. Such amounts are computed as follows: The aggregate taxes paid to country A of \$18,000 is limited to \$11,962.50 (\$31,900 times \$30,000/\$80,000). The unused foreign tax with respect to country A is \$6,037.50 (\$18,000 less \$11,962.50), and is a consolidated unused foreign tax which shall be carried to the years prescribed by section 904(d). A credit of \$3,000 is available with respect to the taxes paid to country B since such amount is less than the limitation of \$3,987.50 (\$31,900 times \$10,000/\$80,000).

(ii) Assuming the overall limitation is in effect for the taxable year, the group may take \$15,950 as a credit, computed as follows: The aggregate taxes paid to all foreign countries of \$21,000 is limited to \$15,950 (\$31,900 times \$40,000/\$80,000). The unused foreign tax is \$5,050 (\$21,000 less \$15,950), and is a consolidated unused foreign tax which shall be carried to the years prescribed by section 904(d).

Example (2). Assume the same facts as in example (1), except that T has a \$10,000 long-term capital gain (derived from a sale to a nonmember in country A) and P has a \$10,000 long-term capital loss (derived from a sale to a nonmember in the United States). Notwithstanding that the consolidated net capital gain of the group is zero, T's capital gain shall be reflected in full in the computation of taxable income from foreign sources.

Example (3). Assume the same facts as in example (1), except that the group had a consolidated section 172 deduction of \$8,000 which is attributable to a net operating loss sustained by T. The \$8,000 consolidated net operating loss deduction is offset against T's income from country A, thus reducing T's taxable income from country A to \$12,000.

§ 1.1502-5 Estimated tax.

(a) *General rule—(1) Consolidated estimated tax.* If a group files a consolidated return for two consecutive tax-

able years, it shall file its declaration of estimated tax on a consolidated basis for each subsequent taxable year, until such time as separate returns are properly filed under § 1.1502-75(c). Until such time, the group shall be treated as a single corporation for purposes of sections 6016 and 6154 (relating to declaration and payment of estimated tax by corporations). If separate returns are filed by the members for a taxable year, the amount of any estimated tax payments made with respect to a consolidated declaration of estimated tax for such year shall be credited against the separate tax liabilities of the members in any manner designated by the common parent which is satisfactory to the Commissioner. The consolidated declaration of estimated tax shall be filed, and payments shall be made, to the district director with whom the common parent would file a separate return. A statement should be attached to the declaration setting forth the name, address, taxpayer account number, and district director of each member.

(2) *Estimated tax on a separate basis.* If a group is not required to file a consolidated declaration of estimated tax for a taxable year, then each member shall be treated as a separate corporation for such taxable year for purposes of sections 6016 and 6154, except as otherwise provided in section 243(b)(3)(C)(v). If a consolidated return is filed for such year, the amount of any estimated tax payments made for such year shall be credited against the tax liability of the group.

(b) *Additions to tax for failure to pay estimated tax under section 6655—(1) Consolidated declaration of estimated tax required to be filed.* If a group is required to file a consolidated declaration of estimated tax for the taxable year under paragraph (a)(1) of this section, then—

(i) If such group files a consolidated return for the taxable year, it shall be limited to a single \$100,000 exemption for purposes of applying section 6655 to payments of estimated tax for such year. For purposes of section 6655(d)(1), the "tax shown on the return" shall be the tax shown on the consolidated return for the preceding taxable year, and for purposes of section 6655(d)(2), the "facts shown on the return" shall be the facts shown on the consolidated return for the preceding taxable year.

(ii) If such group does not file a consolidated return for the taxable year, each member of the group shall, except as otherwise provided in section 243(b)(3)(C)(v), be entitled to a separate \$100,000 exemption for purposes of applying section 6655 to payments of estimated tax for such year. For purposes of section 6655(b)(2), the "amount, if any, of the installment paid" by any member shall be an amount apportioned to such member in a manner designated by the common parent which is satisfactory to the Commissioner. For purposes of section 6655(d)(1), the "tax shown on the return" for any member shall be the portion of the tax shown on the consolidated return for the preceding

year allocable to such member under subparagraph (3) of this paragraph. For purposes of section 6655(d)(2), the "facts shown on the return" shall be the facts shown on the consolidated return for the preceding year and the tax computed under such section shall be allocated under the rules of subparagraph (3) of this paragraph.

(2) *Separate declaration of estimated tax.* If the members of a group are treated as separate corporations for the taxable year under paragraph (a)(2) of this section, then, except as otherwise provided in section 243(b)(3)(C)(v), each such member is entitled to a separate \$100,000 exemption for purposes of applying section 6655 to payments of estimated tax for such year, whether or not the group files a consolidated return for such year. If the group files a consolidated return for such year, then for purposes of section 6655(b)(1), the "tax shown on the return" for any member shall be the portion of the tax shown on the consolidated return allocable to such member under subparagraph (3) of this paragraph. If the group filed a consolidated return for the preceding taxable year, then for purposes of section 6655(d)(1), the "tax shown on the return" for any member shall be the portion of the tax shown on the consolidated return for such preceding year allocable to such member under subparagraph (3) of this paragraph. For purposes of section 6655(d)(2), the "facts shown on the return" shall be the facts shown on the consolidated return for the preceding year and the tax computed under such section shall be allocated under the rules of subparagraph (3) of this paragraph.

(3) *Rules for allocation of consolidated tax liability.* For purposes of subparagraphs (1) and (2) of this paragraph, the tax shown on a consolidated return shall be allocated to the members of the group under the method which the group has elected pursuant to section 1552.

(c) *Examples.* The provisions of this section may be illustrated by the following examples:

Example (1). Corporations P and S-1 file a consolidated return for the first time for calendar year 1966. P and S-1 also file consolidated returns for 1967 and 1968. For 1966 and 1967 P and S-1 may file separate declarations of estimated tax, and they are entitled to separate \$100,000 exemptions. For 1968, however, the group must compute its estimated tax on a consolidated basis, and it is limited to a single \$100,000 exemption. In determining whether P and S-1 come within the exception provided in section 6655(d)(1) for 1968, the "tax shown on the return" is the tax shown on the consolidated return for 1967.

Example (2). Assume the same facts as in example (1). Assume further that corporation S-2 was a member of the group during 1967, and joined in the filing of the consolidated return for such year, but ceased to be a member of the group on September 15, 1968. In determining whether the group (which no longer includes S-2) comes within the exception provided in section 6655(d)(1) for 1968, the "tax shown on the return" is the tax shown on the consolidated return for 1967.

Example (3). Assume the same facts as in example (1). Assume further that corporation S-2 becomes a member of the group on June 1, 1968, and joins in the filing of the consolidated return for 1968. In determining whether the group (which now includes S-2) comes within the exception provided in section 6655(d)(1) for 1968, the "tax shown on the return" is the tax shown on the consolidated return for 1967. Any tax of S-2 for any separate return year is not included as a part of the "tax shown on the return" for purposes of applying section 6655(d)(1).

Example (4). Corporations X and Y filed consolidated returns for the calendar years 1966 and 1967 and separate returns for 1968. X and Y are each entitled to a separate \$100,000 exemption for 1968 for purposes of applying section 6655. In determining whether X or Y comes within the exception provided in section 6655(d)(1) for 1968, the "tax shown on the return" is the amount of tax shown on the consolidated return for 1967 allocable to X and to Y in accordance with paragraph (b)(3) of this section.

§ 1.1502-6 Liability for tax.

(a) *Several liability of members of group.* Except as provided in paragraph (b) of this section, the common parent corporation and each subsidiary which was a member of the group during any part of the consolidated return year shall be severally liable for the tax for such year computed in accordance with the regulations under section 1502 prescribed on or before the due date (not including extensions of time) for the filing of the consolidated return for such year.

(b) *Liability of subsidiary after withdrawal.* If a subsidiary has ceased to be a member of the group and if such cessation resulted from a bona fide sale or exchange of its stock for fair value and occurred prior to the date upon which any deficiency is assessed, the district director may, if he believes that the assessment or collection of the balance of the deficiency will not be jeopardized, make assessment and collection of such deficiency from such former subsidiary in an amount not exceeding the portion of such deficiency which the district director may determine to be allocable to it. If the district director makes assessment and collection of any part of a deficiency from such former subsidiary, then for purposes of any credit or refund of the amount collected from such former subsidiary the agency of the common parent under the provisions of § 1.1502-77 shall not apply.

(c) *Effect of intercompany agreements.* No agreement entered into by one or more members of the group with any other member of such group or with any other person shall in any case have the effect of reducing the liability prescribed under this section.

§§ 1.1502-7 to 1.1502-10 [Reserved]

COMPUTATION OF CONSOLIDATED TAXABLE INCOME

§ 1.1502-11 Consolidated taxable income.

The consolidated taxable income for a consolidated return year shall be determined by taking into account—

(a) The separate taxable income of each member of the group (see § 1.1502-

12 for the computation of separate taxable income);

(b) Any consolidated net operating loss deduction (see § 1.1502-21 for the computation of the consolidated net operating loss deduction);

(c) Any consolidated net capital gain (see § 1.1502-22 for the computation of the consolidated net capital gain);

(d) Any consolidated section 1231 net loss (see § 1.1502-23 for the computation of the consolidated section 1231 net loss);

(e) Any consolidated charitable contributions deduction (see § 1.1502-24 for the computation of the consolidated charitable contributions deduction);

(f) Any consolidated section 922 deduction (see § 1.1502-25 for the computation of the consolidated section 922 deduction);

(g) Any consolidated dividends received deduction (see § 1.1502-26 for the computation of the consolidated dividends received deduction); and

(h) Any consolidated section 247 deduction (see § 1.1502-27 for the computation of the consolidated section 247 deduction).

COMPUTATION OF SEPARATE TAXABLE INCOME

§ 1.1502-12 Separate taxable income.

The separate taxable income of a member of a group shall be computed in accordance with the provisions covering the determination of taxable income of separate corporations except that—

(a) Transactions between members and transactions with respect to stock, bonds, or other obligations of members shall be reflected according to the provisions of §§ 1.1502-13 and 1.1502-14;

(b) Any deduction which is disallowed under § 1.1502-15 shall be taken into account as provided in that section;

(c) The deduction allowable under section 615 shall be taken into account to the extent provided in § 1.1502-16;

(d) The method of accounting under which such computation is made and the adjustments to be made because of any change in method of accounting shall be determined under § 1.1502-17;

(e) Inventory adjustments shall be made as provided in § 1.1502-18;

(f) Any amount included in income under § 1.1502-19 shall be taken into account;

(g) In the computation of the deduction under section 167, property shall not lose its character as new property as a result of a transfer from one member of the group to another member during a consolidated return year;

(h) No net operating loss deduction shall be taken into account;

(i) [Reserved]

(j) No capital gains or losses shall be taken into account;

(k) No gains and losses subject to section 1231 shall be taken into account;

(l) No deduction under section 170 with respect to charitable contributions shall be taken into account;

(m) No deduction under section 922 (relating to the deduction for Western Hemisphere trade corporations) shall be taken into account;

(n) No deductions under section 243 (a) (1), 244(a), 245, or 247 (relating to deductions with respect to dividends received and dividends paid) shall be taken into account; and

(o) Basis shall be determined under §§ 1.1502-31 and 1.1502-32, and earnings and profits shall be determined under § 1.1502-33. The term "separate taxable income" shall include a case in which the determination under this section results in an excess of deductions over gross income.

§ 1.1502-13 Intercompany transactions.

(a) Definitions. For purposes of §§ 1.1502-1 through 1.1502-80—

(1) "Intercompany transaction." (i) Except as provided in subdivision (ii) of this subparagraph, the term "intercompany transaction" means a transaction during a consolidated return year between corporations which are members of the same group immediately after such transaction. Thus, for example, an intercompany transaction would include a sale of property by one member of a group (hereinafter referred to as the "selling member") to another member of the same group ("purchasing member"), the performance of services by one member of a group ("selling member") for another member of the same group ("purchasing member"), or the payment of interest by one member of a group ("purchasing member") to another member of the same group ("selling member"); during a consolidated return year.

(ii) The term "intercompany transaction" does not include a distribution by one member of a group to another member of the same group with respect to the distributing member's stock, or a contribution to capital on which no gain is realized. Thus, for example, dividend distributions, redemptions, and liquidations are not intercompany transactions. The term also does not include sales and other dispositions of, and bad debts with respect to, obligations of other members of the group. See § 1.1502-14, relating to amounts received with respect to stock, bonds, or other obligations of a member of the group.

(2) "Deferred intercompany transaction." The term "deferred intercompany transaction" means—

(i) The sale or exchange of property,

(ii) The performance of services in a case where the amount of the expenditure for such services is capitalized (for example, a builder's fee, architect's fee, or other similar cost which is included in the basis of property), or

(iii) Any other expenditure in a case where the amount of the expenditure is capitalized (for example, prepaid rent, or interest which is included in the basis of property), in an intercompany transaction.

(b) Treatment of intercompany transactions other than deferred intercompany transactions—(1) General rule. Gain or loss on intercompany transactions (other than deferred intercompany transactions) shall not be deferred or eliminated. Thus, for example, if, during a consolidated return year, a pur-

chasing member makes an interest payment on an indebtedness to a selling member in an intercompany transaction, the purchasing member shall take the deduction for interest into account and the selling member shall take the interest income into account.

(2) Special rule. If, in an intercompany transaction (other than a deferred intercompany transaction), one member would otherwise properly take an item of income or a deduction into account for a consolidated return year earlier than the year (whether consolidated or separate) for which another member of the group can properly take into account the corresponding item of income or deduction, then both the item of income and the deduction shall be taken into account for the later year (whether consolidated or separate). On the other hand, if one member properly takes an item of income or a deduction into account for a separate return year earlier than the consolidated return year for which the other member can properly take into account the corresponding item of income or deduction, then such other member shall take the corresponding deduction or item of income into account for such later consolidated return year.

(c) Deferral of gain or loss on deferred intercompany transactions—(1) General rule. (i) To the extent gain or loss on a deferred intercompany transaction is recognized under the Code for a consolidated return year, such gain or loss shall be deferred by the selling member (hereinafter referred to as "deferred gain or loss").

(ii) The following rules apply with respect to the deferral of gain or loss on deferred intercompany transactions:

(a) The selling member may not report gain on the installment method under section 453;

(b) A selling member shall take into account the gain or loss on a deferred intercompany transaction in accordance with the provisions of paragraphs (d), (e), and (f) of this section, notwithstanding that such selling member, under its method of accounting, would not otherwise recognize such gain or loss until a later taxable year. Thus, for example, a selling member must take into account its gain on a deferred intercompany transaction for the first taxable year for which the purchasing member is allowed a deduction for depreciation with respect to the property involved, even though the selling member, under its method of accounting, would not otherwise recognize such gain until a later taxable year.

(iii) See paragraphs (d), (e), and (f) of this section, relating to the time and manner of restoring deferred gain or loss. See paragraph (a) of § 1.1502-31, relating to basis of property acquired in a deferred intercompany transaction.

(2) Determination of amount of deferred gain or loss. In determining the amount of deferred gain or loss, the cost of property, services, or any other expenditure shall include both direct costs and indirect costs which are properly includible in the cost of goods sold or

cost of the services or other expenditure. See § 1.471-3 for costs properly included in cost of goods sold.

(3) *Election not to defer.* A group may elect with the consent of the Commissioner not to defer gain or loss on any deferred intercompany transactions with respect to all property or any class or classes of property. Applications for such consent must be filed with the Commissioner of Internal Revenue, Washington, D.C. 20224, on or before the due date of the consolidated return (not including extensions of time) for the taxable year for which the election is to apply. An election under this subparagraph shall, unless revoked with the consent of the Commissioner, apply to all members of the group for the consolidated return year for which made and all subsequent consolidated return years ending prior to the first year for which such group does not file a consolidated return.

(4) *Character and source of deferred gain or loss.* (i) Except as provided in subdivision (ii) of this subparagraph, the character and source of deferred gain or loss on a deferred intercompany transaction shall be determined at the time of the deferred intercompany transaction as if such transaction had not occurred during a consolidated return year.

(ii) Deferred gain or loss taken into account by the selling member under paragraph (d)(1) of this section, or (as a result of abandonment) under paragraph (f) of this section, shall be treated as ordinary income or loss.

(5) *Accounting for deferred gain or loss.* The amount of deferred gain or loss shall be reflected on permanent records (including work papers). From such permanent records the group must be able to identify the character and source of the deferred gain or loss to the selling member, and must be able to apply the restoration rules of paragraphs (d), (e), and (f) of this section.

(6) *Inheritance of deferred gain or loss.* If the assets of a selling member are acquired by one or more other members in an acquisition to which section 381(a) applies, the member acquiring the greatest portion of the assets (measured by fair market value) of the selling member shall be subject to the provisions of paragraphs (d), (e), and (f) of this section with respect to the entire remaining balance of the deferred gain or loss. If two or more members acquire the same portion (which is greater than that acquired by any other members), the common parent shall select which such member shall be subject to the provisions of paragraphs (d), (e), and (f) of this section. For purposes of this section, a member which inherits the balance of the deferred gain or loss under this subparagraph shall be treated as the selling member.

(d) *Restoration of deferred gain or loss for property subject to depreciation, amortization, or depletion.*—(1) *General rule.* (i) If property (including a capitalized expenditure for services, or any other capitalized expenditure) acquired in a deferred intercompany transaction is, in the hands of any member of the group, subject to depreciation, amortiza-

tion, or depletion, then, for each taxable year (whether consolidated or separate) for which a depreciation, amortization, or depletion deduction is allowed to any member of the group with respect to such property, a portion (as determined under subdivision (ii) of this subparagraph) of the deferred gain or loss attributable to such property shall be taken into account by the selling member.

(ii) The portion of the deferred gain or loss attributable to any property which shall be taken into account by the selling member shall be an amount equal to—

(a) The amount of gain or loss deferred by the selling member at the time of the deferred intercompany transaction (and if a member has transferred the property to another member of the group, the remaining balance at the time of such transfer), multiplied by

(b) A fraction, the numerator of which is the amount of the depreciation, amortization, or depletion deduction with respect to such property allowed to any member of the group for the year (whether consolidated or separate), and the denominator of which is the depreciable basis (i.e., basis reduced by salvage value required to be taken into account, if any) of such property in the hands of such member immediately after such property was transferred to such member.

(2) *Multiple asset accounts.* In the case of property contained in a multiple asset account (or in single asset accounts for which an average rate is used), for purposes of subparagraph (1)(ii)(b) of this paragraph the depreciation deduction allowed for a particular taxable year shall be determined by reference to the rate and method of depreciation applied to such multiple asset account (or average rate and method of depreciation applied to such single asset accounts). Thus, if property with an estimated useful life of 3 years is placed in a multiple asset account which is depreciated on the straight-line method at a rate of 20 percent, the depreciation deduction allowed for each taxable year shall be assumed to be 20 percent of the basis of such property (reduced by the salvage value taken into account).

(3) *Reduction of deferred gain or loss.* The deferred gain or loss shall be reduced by the amount taken into account by the selling member under subparagraph (1) of this paragraph. If the deferred gain includes any ordinary income, the reduction shall first be applied against the ordinary income. Thus, for example, if the selling member has deferred gain of \$100, of which \$70 is capital gain and \$30 is ordinary income, the first \$30 taken into account by the selling member under subparagraph (1) of this paragraph shall be applied against the ordinary income, and any additional amounts so taken into account shall be applied against the capital gain.

(e) *Restoration of deferred gain or loss for installment obligations and sales.*—(1) *Installment obligations.* If an installment obligation (within the meaning of section 453(d)) is transferred in

a deferred intercompany transaction, then on each date on which the obligation is satisfied the selling member shall take into account an amount equal to the deferred gain or loss on such transfer, multiplied by a fraction, the numerator of which is the portion of such obligation satisfied on such date, and the denominator of which is the aggregate unpaid installments immediately after the deferred intercompany transaction.

(2) *Installment sales.* If—

(i) Property acquired in a deferred intercompany transaction is disposed of outside the group, and

(ii) The purchasing member-vendor reports its income on the installment method under section 453,

then on each date on which the purchasing member-vendor receives an installment payment the selling member shall take into account an amount equal to the deferred gain or loss attributable to such property (after taking into account any prior reductions under paragraph (d)(4) of this section) multiplied by a fraction, the numerator of which is the installment payment received and the denominator of which is the total contract price.

(3) *Reduction of deferred gain or loss.* The deferred gain or loss shall be reduced by the amount taken into account by the selling member under subparagraph (1) or (2) of this paragraph. If the deferred gain includes any ordinary income, the reduction shall first be applied against the ordinary income.

(f) *Restoration of deferred gain or loss on dispositions, etc.*—(1) *General rule.* The remaining balance (after taking into account any prior reductions under paragraphs (d)(4) and (e)(3) of this section) of the deferred gain or loss attributable to property, services, or other expenditure shall be taken into account by the selling member as of the earliest of the following dates:

(i) The date on which such property is disposed of outside the group (including abandoned) other than in a transaction described in paragraph (e)(2) of this section (but not including a normal retirement, as defined in paragraph (b) of § 1.167(a)-8, from an average-life multiple asset account or from a single asset account for which an average rate is used). If such property is of a kind which would properly be included in the inventory of a member if on hand at the close of its taxable year, such member shall determine whether or not such item of property has been disposed of outside the group by reference to its method of inventory identification (e.g., first-in, first-out, last-in, first-out, or specific identification);

(ii) In the case of a transaction described in paragraph (e)(2) of this section, the date on which the installment debt is written off, satisfied, discharged, or disposed of outside the group or the property sold is repossessed (except as provided in section 1038), whichever occurs earliest;

(iii) Immediately preceding the time when either the selling member or the

member which owns the property ceases to be a member of the group;

(iv) In the case of property which is stock in trade or other property of a kind which would be properly included in inventory of the member which owns the property if on hand at the close of such member's taxable year, or held primarily for sale to customers in the ordinary course of such member's trade or business, the first day of the first separate return year of the selling member or the member which owns the property;

(v) In the case of an obligation (other than an obligation of a member of the group), the date on which such obligation is satisfied or becomes worthless;

(vi) In the case of stock, the date on which such stock is redeemed (whether or not it is canceled, retired, or held as treasury stock) or becomes worthless.

(vii) If consolidated returns are filed by the group for fewer than three consecutive taxable years immediately preceding a separate return year of the common parent, the first day of such separate return year; or

(viii) In the case of inventory, the date on which its value is written down to market (if the lower-of-cost-or-market method is used by the purchaser), but only to the extent of such write-down.

(2) *Exception.* Subparagraph (1) (iii) of this paragraph shall not apply in a case where—

(i) The selling member, or the member which owns the property as the case may be, ceases to be a member of the group by reason of an acquisition to which section 381(a) applies, and the acquiring corporation is a member, or

(ii) The group is terminated, and immediately after such termination the corporation which was the common parent owns the property involved and is the selling member or is treated as the selling member under paragraph (c) (6) of this section.

Paragraphs (d) and (e) of this section and this paragraph shall apply to such selling member. Thus, for example, subparagraph (1) (iii) of this paragraph shall not apply in a case where corporation P, the common parent of a group consisting of P and corporations S and T, sells an asset to S in a deferred intercompany transaction, and subsequently all of the assets of S are distributed to P in complete liquidation of S. Moreover, if, after the liquidation of S, P sold T, subparagraph (1) (iii) of this paragraph would not apply even though P ceases to be a member of the group.

(3) *Certain divestitures.* If, pursuant to a final judgment or a final order of a court or an agency of the Federal or a State government, any member or members are required to divest themselves of control of any other member and, as a result, any member ceases to be a member, the Commissioner may enter into a closing agreement under section 7121 with the group. Such closing agreement may provide that any deferred gain or loss which would otherwise be taken into account under subparagraph (1) (iii) of

this paragraph shall instead be taken into account over an appropriate period of time related to the period of time within which the deferred income would have been taken into account had the divestiture not taken place, but not in excess of 10 years. Ordinarily, application for such closing agreement will not be granted where such divestiture is occasioned by the acquisition after August 31, 1966, of control of a corporation or of assets. In no event will any such application be granted unless the group establishes to the satisfaction of the Commissioner that the collection of the tax liability attributable to any deferred gain will not be jeopardized by the delay.

(g) *Holding period.* In determining the period for which a purchasing member has held property acquired in a deferred intercompany transaction, the period such property was held by the selling member shall not be included.

(h) *Examples.* This section may be illustrated by the following examples:

Example (1). (i) Corporations P and S file consolidated returns on a calendar year basis. On January 10, 1966, S sells land, which it has used in its trade or business, to P for \$100,000. Immediately before the sale the basis of the land in S's hands is \$60,000. P holds the land primarily for sale to customers in the ordinary course of its trade or business. On July 12, 1967, P sells the land to A, an individual.

(ii) The sale by S to P is a deferred intercompany transaction; S defers its \$40,000 gain on the land (\$100,000 less \$60,000), which is gain from the sale of property described in section 1231. As of July 12, 1967, S takes the \$40,000 deferred gain into account since on such date the property is disposed of outside the group. Such \$40,000

$$\begin{array}{r} \$200 \text{ deferred gain} \times \$80 \text{ depreciation deduction} \\ \$800 \text{ basis to P subject to depreciation} \end{array}$$

Such \$20 gain retains its character as ordinary income.

(iii) As of January 1, 1969, S takes the \$140 remaining balance of the deferred gain (\$200 less \$60) into account since on such date the machine is disposed of outside the group. Such \$140 gain retains its character as ordinary income.

Example (5). (i) The facts are the same as in example (4) except that beginning with 1968 P and S file separate returns.

(ii) Assuming that P, S, and T filed a consolidated return for 1965, the result is the same as in example (4). Thus, for each of the years 1966, 1967, and 1968 S takes into account \$20 of its deferred gain and as of January 1, 1969, S takes the remaining \$140 (\$200 less \$60) into account.

(iii) Assuming that P, S, and T filed separate returns for 1965, as of January 1, 1968, S takes the \$160 remaining balance of the deferred gain (\$200 less \$40) into account since P filed a separate return for 1968 and the group had filed consolidated returns for only 2 consecutive years preceding 1968.

$$\begin{array}{r} \$140 \text{ remaining balance of deferred gain} \times \$66 \text{ depreciation deduction} \\ \$660 \text{ basis to T subject to depreciation} \end{array}$$

(v) For 1969 P takes into account \$10 of its deferred loss, computed as follows:

$$\begin{array}{r} \$100 \text{ deferred loss} \times \$66 \text{ depreciation deduction} \\ \$660 \text{ basis to T subject to depreciation} \end{array}$$

gain is taken into account in determining the consolidated section 1231 net gain or loss for 1967 under § 1.1502-23.

Example (2). Corporations P and S file consolidated returns on a calendar year basis. On August 1, 1966, P transfers property with a fair market value of \$100,000 and an adjusted basis in its hands of \$85,000 to S in exchange for stock and \$10,000 cash. Under section 351(b), only \$10,000 of the \$15,000 gain is recognized by P. The transfer is a deferred intercompany transaction; P defers the \$10,000 gain recognized under section 351(b).

Example (3). Corporations P and S file consolidated returns on a calendar year basis and report income on the cash basis. On July 1, 1966, S pays P \$1,000 interest on a loan made in 1961. The payment of interest is an intercompany transaction other than a deferred intercompany transaction; S does not defer or eliminate the \$1,000 deduction for interest, and P does not defer or eliminate the \$1,000 item of interest income. Thus, consolidated taxable income for 1966 reflects interest income of \$1,000 and a corresponding deduction for interest of \$1,000.

Example (4). (i) Corporations P, S, and T file consolidated returns on a calendar year basis. On January 1, 1966, S, which is in the business of manufacturing machinery, sells a machine to P for \$1,000. The cost of the machine is \$800. P uses the machine in its trade or business and depreciates it on the straight-line method over an estimated useful life of 10 years. Salvage value of \$200 is taken into account. Thus, its annual depreciation deduction with respect to the machine is \$80 (\$800 (\$1,000 less \$200 salvage) divided by 10). On January 1, 1969, P sells the machine to A, an individual.

(ii) The sale by S to P is a deferred intercompany transaction; S defers its \$200 gain on the machine (\$1,000 less \$800), which is characterized as ordinary income. For each of the 3 taxable years (1966, 1967, and 1968) prior to the sale to A, S takes into account \$20 of its deferred gain, computed as follows:

Example (6). (i) The facts are the same as in example (4) except that on January 1, 1969, P sells the machine to T for \$660 in a transaction in which gain is recognized. T uses the machine in its trade or business and depreciates it on the straight-line method over an estimated useful life of 10 years. No salvage value is taken into account. Thus, T's annual depreciation deduction with respect to the machine is \$66 (\$660 divided by 10).

(ii) The sale by S to P is a deferred intercompany transaction; S defers its \$200 gain on the machine (\$1,000 less \$800), which is characterized as ordinary income. For each of the 3 years (1966, 1967, and 1968) prior to the sale to T, S takes into account \$20 of its deferred gain.

(iii) The sale by P to T is also a deferred intercompany transaction; P defers its \$100 loss on the machine (adjusted basis of \$760 (\$1,000 less \$240 total depreciation) less \$660).

(iv) For 1969 S takes into account \$14 of its deferred gain, computed as follows:

Example (7). (i) Corporations P and S file consolidated returns on a calendar year basis. On May 2, 1966, S sells a machine with an adjusted basis of \$50 to P for \$100 in a transaction in which gain is recognized. S used the machine in its trade or business. For purposes of depreciation, P places the machine, which has an estimated useful life of 3 years, in an average life multiple asset account which is depreciated on the straight-

line method at a rate of 20 percent. Under P's consistent depreciation practice it takes a full year's depreciation on all purchases made in the first half of its taxable year.

(ii) The sale by S to P is a deferred intercompany transaction; S defers its \$50 gain on the machine (\$100 less \$50). For each of the taxable years 1966, 1967, 1968, 1969, and 1970 S takes into account \$10 of its deferred gain, computed as follows:

$$\begin{array}{r} \$20 \text{ depreciation deduction} \\ \$50 \text{ deferred gain} \times \frac{\$100 \text{ basis to P subject to depreciation}}{\$100} \end{array}$$

Such \$10 is characterized as gain from the sale or exchange of property which is neither a capital asset nor property described in section 1231, notwithstanding the character of the \$50 gain determined at the time of the sale.

Example (8). The facts are the same as in example (7) and in addition during 1969 the machine is disposed of outside the group. Such disposal is treated as a normal retirement (as defined in paragraph (b) of § 1.167(a)-8). The result is the same as in

example (7). Thus, S takes into account \$10 for each of the years 1966, 1967, 1968, 1969, and 1970 even though the property was disposed of in 1969.

Example (9). (i) The facts are the same as in example (7) except that the multiple asset account is depreciated over a 5-year average useful life on the double declining balance method.

(ii) For 1966 S takes into account \$20 of its deferred gain, computed as follows:

$$\begin{array}{r} \$40 (\$100 \times 40\%) \text{ depreciation deduction} \\ \$50 \text{ deferred gain} \times \frac{\$100 \text{ basis to P subject to depreciation}}{\$100} \end{array}$$

For 1967 S takes into account \$12 of its deferred gain, computed as follows:

$$\begin{array}{r} \$24 (\$60 (\$100 \text{ less } \$40) \times 40\%) \text{ depreciation deduction} \\ \$50 \text{ deferred gain} \times \frac{\$100 \text{ basis to P subject to depreciation}}{\$100} \end{array}$$

Example (10). (i) P Corporation and S Corporation, its wholly-owned subsidiary, file consolidated returns on a calendar year basis. On January 10, 1966, S sells land, with a basis of \$60,000, to P for \$100,000. As of the close of business on June 10, 1969, P sells 25 percent of the outstanding stock of S to A, an individual.

(ii) The sale by S to P is a deferred intercompany transaction; S defers its \$40,000 gain on the land (\$100,000 less \$60,000). As of June 10, 1969, S takes the \$40,000 gain into account for 1969 since it ceases to be a member of the group as of the close of business on such date.

Example (11). (i) Corporations P and S file consolidated returns on a calendar year basis. On January 15, 1966, P sells an obligation payable in installments, with a basis of \$48 in its hands, to S for \$60. At the time of the sale the debtor owes 3 annual installments of \$20 payable each year on July 1. Such installments are paid timely.

(ii) The sale by P to S is a deferred intercompany transaction; P defers its \$12 gain on the obligation (\$60 less \$48).

(iii) For each of the years 1966, 1967, and 1968 P takes into account \$4 of its deferred gain, computed as follows:

$$\begin{array}{r} \$20 \text{ portion satisfied} \\ \$12 \text{ deferred gain} \times \frac{\$60 \text{ aggregate unpaid portions}}{\$60} \end{array}$$

Example (12). (i) Corporations P and S file consolidated returns on a calendar year basis. On January 2, 1966, S, a manufacturer, sells a machine to P, a distributor, for \$2,000. The machine cost S \$1,200. On February 1, 1966, P sells the machine to A, an individual, for \$2,200 and, under section 453, reports its income thereon on the installment plan. A makes monthly payments of \$110 starting with March 1966.

(ii) The sale by S to P is a deferred intercompany transaction; S defers its \$800 gain (\$2,000 less \$1,200).

(iii) For 1966 S takes into account \$400 of its deferred gain, computed as follows:

$$\begin{array}{r} \$1,100 \text{ installment payments received} \\ \$800 \text{ deferred gain} \times \frac{\$2,200 \text{ total contract price}}{\$2,200} \end{array}$$

Example (13). Corporations P and S file consolidated returns on a calendar year basis for 1966 and 1967. S reports income on the accrual method while P reports income on the cash method. On December 31, 1966, S would properly accrue interest of \$1,000 which is payable to P. On February 1, 1967, S pays P the \$1,000. Both the deduction and the item of income are taken into account for 1967, the later year. Thus, S takes the \$1,000 interest deduction into account for 1967, which is the year P also takes the \$1,000 item of interest income into account. Consolidated taxable income for 1967 reflects both interest income of \$1,000 and a corresponding deduction for interest of \$1,000.

Example (14). The facts are the same as in example (13) except that for 1967 S and P file separate returns. The result is the same as in example (13).

Example (15). (i) The facts are the same as in example (13) except that for 1966 P and S file separate returns.

(ii) For 1966 S takes into account the \$1,000 deduction for interest; for 1967 P takes into account the \$1,000 item of interest income.

Example (16). Corporations P and S file consolidated returns on a calendar year basis. On January 10, 1968, P sells an issue of its \$100 par value bonds. S purchases a bond from P for \$110. S does not elect under section 171 to amortize the \$10 premium. P may not take the \$10 premium into account as income until it redeems the bond since S cannot properly take a deduction for the \$10 premium until the bond is redeemed.

Example (17). (i) Corporations P, S, and M file consolidated returns on a calendar year basis. On November 20, 1962, S sold land, with a basis of \$60,000, to P for \$100,000. Under paragraph (b) (1) of § 1.1502-31A the \$40,000 gain was eliminated. Thus, S did not take into account such \$40,000 gain for 1962 and P's basis in the land is only \$60,000. On February 10, 1966, P sells the land to A, an individual, for \$104,000.

(ii) P takes the entire \$44,000 gain (\$104,000 less \$60,000) on the land into account for 1966 since the deferral rules provided in paragraph (c) of this section, as well as the corresponding basis rules provided in paragraph

(a) of § 1.1502-31, were not effective with respect to the sale of such land.

(iii) If, on February 10, 1966, P had sold the land to M for \$104,000, P would defer its \$44,000 gain on the land since the sale by P to M would be a deferred intercompany transaction.

Example (18). (i) Corporations P and S file separate returns on a calendar year basis for 1966 and file consolidated returns on a calendar year basis beginning with 1967. On January 2, 1966, S, a dealer in machinery, sells a machine to P for \$2,000 and, under section 453, reports the income thereon on the installment plan. The machine cost S \$1,200. P makes monthly payments of \$100 starting with January 1966.

(ii) The sale by S to P is not an intercompany transaction since the sale did not occur during a consolidated return year. Therefore, S takes into account the gross profit on each of the 20 monthly payments under section 453.

(i) [Reserved]

(j) **Regulated public utilities.** Subject to the provisions of section 7121, the Commissioner may enter into a closing agreement which, notwithstanding the provisions of §§ 1.1502-13, 1.1502-31, and 1.1502-33, determines the consequences of deferred intercompany transactions or of any matters relating to or affected by such transactions, provided that—

(1) The purchasing members are domestic regulated public utilities as defined in section 7701(a) (4) and (33).

(2) In the taxable year immediately preceding the first taxable year for which this section is effective there was in effect among the members an arrangement relating to intercompany transactions which had a significant effect upon regulated rates of the public utility members of the group, and the accounting of the public utility members under the arrangement was accepted or approved by a regulatory agency having jurisdiction over the accounts of such members, and

(3) The Commissioner is satisfied that the terms of such closing agreement will not for any taxable year result in a reduction of the tax liability of the group (including former members) or of the shareholders of any members (or former members).

A request for such an agreement must be made on or before November 15, 1966.

§ 1.1502-14 [Reserved]

§ 1.1502-15 Limitations of certain deductions.

(a) **Limitation on built-in deductions—**(1) **General rule.** Built-in deductions (as defined in subparagraph (2) of this paragraph) for a taxable year shall be subject to the limitation of § 1.1502-21 (c) (determined without regard to such deductions and without regard to net operating loss carryovers to such year) and the limitation of § 1.1502-22(c) (determined without regard to such deductions and without regard to capital loss carryovers to such year). If as a result of applying such limitations, built-in deductions are not allowable in such consolidated return year, such deductions shall be treated as a net operating loss or net capital loss (as the case may be) sustained in such year and shall be carried to those taxable years (consolidated or separate) to which a consolidated net

operating loss or a consolidated net capital loss could be carried under §§ 1.1502-21, 1.1502-22, and 1.1502-79, except that such losses shall be treated as losses subject to the limitations contained in § 1.1502-21(c) or § 1.1502-22(c) (as the case may be). Thus, for example, if member X sells a capital asset during a consolidated return year at a \$1,000 loss and such loss is treated as a built-in deduction, then such loss shall be subject to the limitation contained in § 1.1502-22(c), which, in general, would allow such loss to be offset only against X's own net capital gain. Assuming X had no net capital gain reflected in such year (after taking into account its capital losses, other than capital loss carryovers and the built-in deduction), such \$1,000 loss shall be treated as a net capital loss and shall be carried over for 5 years under § 1.1502-22, subject to the limitation contained in § 1.1502-22(c) for consolidated return years.

(2) *Built-in deductions.* For purposes of this paragraph, the term "built-in deductions" for a consolidated return year means those deductions or losses of a corporation which, but for this section, would be recognized in such year, or which are recognized in a separate return year and carried over in the form of a net operating or net capital loss to such year, but which are economically accrued in a separate return limitation year (as defined in § 1.1502-1(f)). Such term does not include deductions or losses incurred both economically and taxwise in a year which is not a separate return limitation year, including those deductions and losses incurred in rehabilitating such corporation. Thus, for example, assume P is the common parent of a group filing consolidated returns on the basis of a calendar year and that P purchases all of the stock of S on December 31, 1966. Assume further that on December 31, 1966, S owns a capital asset with an adjusted basis of \$100 and a fair market value of \$50. If the group files a consolidated return for 1967, and S sells the asset for \$30, \$50 of the \$70 loss is treated as a built-in deduction, since it was economically accrued in a separate return limitation year. If S sells the asset for \$80 instead of \$30, the \$20 loss is treated as a built-in deduction. On the other hand, if such asset is a depreciable asset and is not sold by S, depreciation deductions attributable to the \$50 difference between basis and fair market value are treated as built-in deductions.

(3) *Exceptions.* (i) This paragraph shall not limit built-in deductions which would otherwise be recognized in a taxable year if—

(a) The date on which the corporation with the built-in deductions became a member occurred more than 10 years before the first day of such taxable year, or

(b) Immediately before the date the corporation became a member, the aggregate of the adjusted basis of all the assets (other than cash, any marketable security the fair market value of which was not less than 95 percent of its ad-

justed basis, and goodwill) of such corporation did not exceed the fair market value of such assets by more than 15 percent.

(ii) If the corporation with the built-in deduction became a member before October 1, 1965, the provisions of § 1.1502-31A(b) (9) shall apply in lieu of the provisions of this section.

(b) [Reserved]

§ 1.1502-16 Mine exploration expenditures.

(a) *In general.* If the aggregate amount of the expenditures, to which section 615(a) applies, which are paid or incurred by the members of the group during any consolidated return year exceeds the lesser of—

(1) \$100,000, or

(2) \$400,000 minus all such expenditures deducted (or deferred) by corporations which are members of the group during the taxable year (and individuals or corporations which have transferred any mineral property to any such member within the meaning of section 615 (c) (2) (B)) for taxable years ending after December 31, 1950, and prior to the taxable year,

then the deduction (or amount deductible) under section 615 and paragraph (c) of § 1.1502-12 for each member shall be no greater than an allocable portion of such lesser amount (hereinafter referred to as the "consolidated exploration limitation"). Such allocable portion shall be determined under paragraph (b) of this section.

(b) *Allocable portion of limitation.* A member's allocable portion of the consolidated exploration limitation for a consolidated return year shall be—

(1) The amount allocated by the common parent pursuant to a plan, but in no event shall a member be allocated more than the amount it could have deducted (or deferred) had it filed a separate return. Such allocation plan must be included in a statement which also contains the total exploration expenditures of each member for the taxable year, and the expenditures of each member which could have been deducted (or deferred) under section 615 if the member had filed a separate return. Such statement must be attached to a consolidated return filed on or before the due date of such return (including extensions of time), and may not be changed after such date, or

(2) If no statement is filed in accordance with subparagraph (1), then the portion of the consolidated exploration limitation allocable to each member incurring such expenditures is an amount equal to such limitation multiplied by a fraction, the numerator of which is the amount which could have been deducted (or deferred) under section 615 by such member had it filed a separate return and the denominator of which is the aggregate of such amounts for all members of the group.

(c) *Examples.* The provisions of this section may be illustrated by the following examples:

Example (1). Corporation X and its wholly-owned subsidiaries, corporations Y and Z, filed a consolidated return for the calendar year 1966. None of the corporations have incurred exploration expenditures described in section 615 in previous years. During 1966, X incurred exploration expenditures of \$30,000, Y of \$20,000 and Z of \$40,000. The amount deductible (or deferrable) under section 615 for purposes of computing separate taxable income under § 1.1502-12 will be the amount actually expended by each corporation.

Example (2). Assume the same facts as in example (1) except that during 1966 X incurred exploration expenditures of \$25,000, Y of \$75,000 and Z of \$125,000. The consolidated exploration limitation under paragraph (a) of this section is \$100,000 since the aggregate amounts incurred by the members of the group exceed \$100,000 and such amount is less than the limitation described in paragraph (a) (2) of this section (\$400,000). X may allocate the \$100,000 in any manner among the three members, except that X may not be allocated more than \$25,000 nor Y more than \$75,000, the amounts actually expended by X and Y and which they could have deducted (or deferred) had they filed a separate return. If the allocation is not made in accordance with paragraph (b) (1) of this section, the \$100,000 limitation will be allocated under paragraph (b) (2) as follows:

Corporation	Expenditure	Fraction	Limitation	Allocable Portion
X.....	\$25,000	$\frac{25,000}{200,000}$	$\times \$100,000 =$	\$12,500
Y.....	\$75,000	$\frac{75,000}{200,000}$	$\times \$100,000 =$	\$37,500
Z.....	\$125,000	$\frac{100,000}{200,000}$	$\times \$100,000 =$	\$50,000

The denominator of \$200,000 was calculated as follows:
 X = \$25,000
 Y = \$75,000
 Z = \$100,000 (maximum amount allowed if filed separately)
 Total \$200,000

Example (3). Assume the same facts as in example (2) and that on January 1, 1967, X acquired all of the stock of corporation T which prior to its taxable year beginning January 1, 1967, had previously deducted (or deferred) \$310,000 of exploration expenditures. Assume further that in 1967 X incurred \$25,000 of exploration expenditures, Y \$50,000, T \$50,000 and Z none. A consolidated return is filed for 1967. None of the expenditures may be deducted (or deferred) under section 615 since the consolidated exploration limitation is zero. The limitation is zero since the aggregate amount of previously deducted (or deferred) exploration expenditures by the members of the group exceeds \$400,000. (The total of such expenditures is \$410,000, of which \$310,000 is attributable to T and, assuming the allocation of the limitation in example (2) is made under paragraph (b) (2) of this section, of which \$12,500 is attributable to X, \$37,500 to Y, and \$50,000 to Z.)

Example (4). Assume the same facts as in example (3) except that on December 31, 1966, X sold all of the stock of Z to an unrelated party. The consolidated exploration limitation for 1967 will be \$40,000, computed by subtracting from \$400,000 the aggregate amount of previously deducted (or deferred) exploration expenditures incurred by the members of the group prior to 1967. (The total of such expenditures is \$360,000, of which \$12,500 is attributable to X, \$37,500 to Y and \$310,000 to T. Amounts previously deducted (or deferred) by Z are not taken into account since it was not a member of

the group at any time during 1967. Amounts previously deducted (or deferred) by Z shall be taken into account by it for subsequent separate return years.)

§ 1.1502-17 Methods of accounting.

(a) *General rule.* The method of accounting to be used by each member of the group shall be determined in accordance with the provisions of section 446 as if such member filed a separate return. For treatment of depreciable property after a transfer within the group, see paragraph (g) of § 1.1502-12.

(b) *Adjustments required where method of accounting changed.* In any case in which a member of a group changes its method of accounting for a consolidated return year, the provisions of section 481(a) shall be applicable. If the requirements of section 481(b) are met because the adjustments under section 481(a) are substantial, the increase in tax for any prior year shall be computed upon the basis of a consolidated return or a separate return, whichever was filed for such prior year.

(c) *Example.* The provisions of this section may be illustrated by the following example:

Example. X and its wholly-owned subsidiary Y filed separate returns for their calendar years ending December 31, 1965. During calendar year 1965, X employed an accrual method of accounting, established a reserve for bad debts, and elected under section 171 to amortize bond premiums with respect to its fully taxable bonds. During calendar year 1965, Y employed the cash receipts and disbursements method, used the specific charge-off method with respect to its bad debts, and did not elect to amortize bond premiums under section 171 with respect to its bonds. X and Y filed a consolidated return for 1966. For 1966 X and Y must continue to compute income under their respective methods of accounting (unless a change in method under section 446 is made).

(a) *Definition of intercompany profit amount.* For purposes of this section, the term "intercompany profit amount" for a taxable year means an amount equal to the profits of a corporation (other than those profits which such corporation has elected not to defer pursuant to § 1.1502-13(c)(3)) arising in transactions with other members of the group with respect to goods which are, at the close of such corporation's taxable year, included in the inventories of other members of the group. See § 1.1502-13(c)(2) with respect to the determination of profits. See the last sentence of § 1.1502-13(f)(1)(i) for rules for determining which goods are considered to be disposed of outside the group and therefore not included in inventories of other members.

(b) *Addition of initial inventory amount to taxable income.* If a corporation—

(1) Is a member of a group filing a consolidated return for the taxable year,

(2) Was a member of such group for its immediately preceding taxable year, and

(3) Filed a separate return for such preceding year,

then the intercompany profit amount of such corporation for such separate re-

turn year (hereinafter referred to as the "initial inventory amount") shall be added to the income of such corporation for the consolidated return year (or years) in which the goods to which the initial inventory amount is attributable are disposed of outside the group or such corporation becomes a nonmember. Such amount shall be treated as gain from the sale or exchange of property which is neither a capital asset nor property described in section 1231.

(c) *Recovery of initial inventory amount.*—(1) *Unrecovered inventory amount.* The term "unrecovered inventory amount" for any consolidated return year means the lesser of—

(i) The intercompany profit amount for such year, or

(ii) The initial inventory amount.

However, if a corporation ceases to be a member of the group during a consolidated return year, its unrecovered inventory amount for such year shall be considered to be zero.

(2) *Recovery during consolidated return years.* (i) To the extent that the unrecovered inventory amount of a corporation for a consolidated return year is less than such amount for its immediately preceding year, such decrease shall be treated for such year by such corporation as a loss from the sale or exchange of property which is neither a capital asset nor property described in section 1231.

(ii) To the extent that the unrecovered inventory amount for a consolidated return year exceeds such amount for the preceding year, such increase shall be treated as gain from the sale or exchange of property which is neither a capital asset nor property described in section 1231.

(3) *Recovery during first separate return year.* For the first separate return year of a member following a consolidated return year, the unrecovered inventory amount for such consolidated return year (minus any part of the initial inventory amount which has not been added to income pursuant to paragraph (b) of this section) shall be treated as a loss from the sale or exchange of property which is neither a capital asset nor property described in section 1231.

(d) *Examples.* The provisions of paragraphs (a), (b), and (c) of this section may be illustrated by the following examples:

Example (1). Corporations P, S, and T report income on the basis of a calendar year. Such corporations file separate returns for 1965. P manufactures widgets which it sells to both S and T, who act as distributors. The inventories of S and T at the close of 1965 are comprised of widgets which they purchased from P and with respect to which P derived profits of \$5,000 and \$8,000, respectively. P, S, and T file a consolidated return for 1966. During 1966, P sells widgets to S and T with respect to which it derives profits of \$7,000 and \$10,000, respectively. The inventories of S and T as of December 31, 1966, are comprised of widgets on which P derived net profits of \$4,000 and \$8,000, respectively. P's initial inventory amount is \$13,000, P's intercompany profit amount for 1965 (such \$13,000 amount is the profits of P with respect to

goods sold to S and T and included in their inventories at the close of 1965). Assuming that S and T identify their goods on a first-in, first-out basis, the entire opening inventory amount of \$13,000 is added to P's income for 1966 as gain from the sale or exchange of property which is neither a capital asset nor property described in section 1231, since the goods to which the initial inventory amount is attributable were disposed of in 1966 outside the group. However, since P's unrecovered inventory amount for 1966, \$12,000 (the intercompany profit amount for the year, which is less than the initial inventory amount), is less than the unrecovered inventory amount for 1965, \$13,000, this decrease of \$1,000 is treated by P for 1966 as a loss from the sale or exchange of property which is neither a capital asset nor property described in section 1231.

Example (2). Assume the same facts as in example (1) and that at the close of 1967, a consolidated return year, the inventories of S and T are comprised of widgets on which P derived profits of \$5,000 and \$3,000, respectively. Since P's unrecovered inventory amount for 1967, \$8,000, is less than \$12,000, the unrecovered inventory amount for 1966, this decrease of \$4,000 is treated by P for 1967 as a loss from the sale or exchange of property which is neither a capital asset nor property described in section 1231.

Example (3). Assume the same facts as in examples (1) and (2) and that in 1968, a consolidated return year, P's intercompany profit amount is \$11,000. P will report \$3,000 (the excess of \$11,000, P's unrecovered inventory amount for 1968, over \$8,000, P's unrecovered inventory amount for 1967) for 1968 as a gain from the sale or exchange of property which is neither a capital asset nor property described in section 1231.

Example (4). Assume the same facts as in examples (1), (2), and (3) and that in 1969 P, S, and T file separate returns. P will report \$11,000 (its unrecovered inventory amount for 1968, \$11,000, minus the portion of the initial inventory amount which has not been added to income during 1966, 1967, and 1968, zero) as a loss from the sale or exchange of property which is neither a capital asset nor property described in section 1231.

Example (5). Corporations P and S file a consolidated return for the first time for the calendar year 1966. P manufactures machines and sells them to S, which sells them to users throughout the country. At the close of 1965, S has on hand 20 machines which it purchased from P and with respect to which P derived profits of \$3,500. During 1966, P sells 6 machines to S on which it derives profits of \$1,300, and S sells 5 machines which it had on hand at the beginning of the year (S specifically identifies the machines which it sells) and on which P had derived profits of \$900. P's initial inventory amount is \$3,500, of which \$900 is added to P's income in 1966 as gain from the sale or exchange of property which is neither a capital asset nor property described in section 1231, since such \$900 amount is attributable to goods disposed of in 1966 outside the group, which goods were included in S's inventory at the close of 1965. If P and S continue to file consolidated returns, the remaining \$2,600 of the initial inventory amount will be added to P's income as the machines on which such profits were derived are disposed of outside the group.

Example (6). Assume that in example (5) S had elected to inventory its goods under section 472 (relating to last-in, first-out inventories). None of P's initial inventory amount of \$3,500 would be added to P's income in 1966, since none of the goods to which such amount is attributable would be considered to be disposed of during such year under the last-in, first-out method of identifying inventories.

(e) *Section 381 transfer.* If a member of the group is a transferor or distributor of assets to another member of the group within the meaning of section 381(a), then the acquiring corporation shall be treated as succeeding to the initial inventory amount of the transferor or distributor corporation to the extent that as of the date of distribution or transfer such amount has not yet been added to income. Such amount shall then be added to the acquiring corporation's income under the provisions of paragraph (b) of this section. For purposes of applying paragraph (c) of this section—

(1) The initial inventory amount of the transferor or distributor corporation shall be added to such amount of the acquiring corporation as of the close of the acquiring corporation's taxable year in which the date of distribution or transfer occurs, and

(2) The unrecovered inventory amount of the transferor or distributor corporation for its taxable year preceding the taxable year of the group in which the date of distribution or transfer occurs shall be added to such amount of the acquiring corporation.

(f) *Transitional rules—(1) In general.* If—

(i) A group filed a consolidated return for the taxable year immediately preceding the first taxable year to which this section applies,

(ii) Any member of such group made an opening adjustment to its inventory pursuant to paragraph (b) of § 1.1502-39A, and

(iii) Paragraph (c) of § 1.1502-39A has not been applicable for any taxable year subsequent to the taxable year for which such adjustment was made, then subparagraphs (2) and (3) of this paragraph shall apply.

(2) *Closing adjustment to inventory.* (i) For the first consolidated return year to which this section applies, the increase in inventory prescribed in paragraph (c) of § 1.1502-39A shall be made as if such year were a separate return year.

(ii) For the first separate return year of a member to which this section applies, the adjustment to inventory (whether an increase or a decrease) prescribed in paragraph (c) of § 1.1502-39A, minus any adjustment already made pursuant to subdivision (i) of this subparagraph, shall be made to the inventory of such member.

(3) *Addition and recovery of initial inventory amount.* Each selling member shall treat as an initial inventory amount its share of the net amount by which the inventories of all members are increased pursuant to subparagraph (2) (i) of this paragraph for the first taxable year to which this section applies. A member's share shall be such net amount multiplied by a fraction, the numerator of which is its initial inventory amount (computed under paragraph (b) as if such taxable year were its first consolidated return year), and the denominator of which is the sum of such initial inventory amounts of all members. Such initial inventory amount shall be added to the income of such selling member and shall be recovered at the time and in

the manner prescribed in paragraphs (b) and (c) of this section.

(4) *Example.* The provisions of this paragraph may be illustrated by the following example:

Example. (1) Corporations P, S, and T file consolidated returns for calendar 1966, having filed consolidated returns continuously since 1962. P is a wholesale distributor of groceries selling to chains of supermarkets, including those owned by S and T. The opening inventories of S and T for 1962 were reduced by \$40,000 and \$80,000, respectively, pursuant to paragraph (b) of § 1.1502-39A. At the close of 1965, S and T have on hand in their inventories goods on which P derived profits of \$80,000 and \$90,000, respectively. The inventories of S and T at the close of 1966 include goods which they purchased from P during the year on which P derived profits of \$85,000 and \$105,000, respectively.

(ii) The opening inventories of S and T for 1966, the first year to which this section applies, are increased by \$40,000 and \$80,000, respectively, pursuant to the provisions of subparagraph (2) (i) of this paragraph. P will take into account (as provided in paragraphs (b) and (c) of this section) an initial inventory amount of \$120,000 as of the beginning of 1966, the net amount by which the inventories of S and T were increased in such year. Since the increases in the inventories of S and T are the maximum allowable under paragraph (c) of § 1.1502-39A (i.e., the amount by which such inventories were originally decreased), no further adjustments will be made pursuant to subparagraph (2) (ii) of this paragraph to such inventories in the event that separate returns are subsequently filed.

(5) *Election not to eliminate.* If a group filed a consolidated return for the taxable year immediately preceding the first taxable year to which this section applies, and for such preceding year the members of the group did not eliminate gain or loss on intercompany inventory transactions pursuant to the adoption under § 1.1502-31A(b) (1) of a consistent accounting practice taking into account such gain or loss, then for purposes of this section each member shall be treated as if it had filed a separate return for such immediately preceding year.

§§ 1.1502-19 and 1.1502-20 [Reserved]

COMPUTATION OF CONSOLIDATED ITEMS

§ 1.1502-21 Consolidated net operating loss deduction.

(a) *In general.* The consolidated net operating loss deduction shall be an amount equal to the aggregate of the consolidated net operating loss carryovers and carrybacks to the taxable year (as determined under paragraph (b) of this section).

(b) *Consolidated net operating loss carryovers and carrybacks—(1) In general.* The consolidated net operating loss carryovers and carrybacks to the taxable year shall consist of any consolidated net operating losses (as determined under paragraph (f) of this section) of the group, plus any net operating losses sustained by members of the group in separate return years, which may be carried over or back to the taxable year under the principles of section 172(b). However, such consolidated carryovers

and carrybacks shall not include any consolidated net operating loss apportioned to a corporation for a separate return year pursuant to paragraph (a) of § 1.1502-79, and shall be subject to the limitations contained in paragraphs (c), (d), and (e) of this section and to the limitation contained in § 1.1502-15.

(2) *Rules for applying section 172(b) (1)—(i) Regulated transportation corporations.* For purposes of applying section 172(b) (1) (C) (relating to net operating losses sustained by regulated transportation corporations), in the case of a consolidated net operating loss sustained in a taxable year for which a member of the group was a regulated transportation corporation (as defined in section 172(j) (1)), the portion, if any, of such consolidated net operating loss which is attributable to such corporation (as determined under paragraph (a) (4) of § 1.1502-79) shall be a carryover to the sixth taxable year following the loss year only if such corporation is a regulated transportation corporation for such sixth year, and shall be a carryover to the seventh taxable year following the loss year only if such corporation is a regulated transportation corporation for both such sixth and seventh years.

(ii) *Trade expansion losses.* In the case of a carryback of a consolidated net operating loss from a taxable year for which a member of the group has been issued a certification under section 317 of the Trade Expansion Act of 1962 and with respect to which the requirements of section 172(b) (3) (A) have been met, section 172(b) (1) (A) (ii) shall apply only to the portion of such consolidated net operating loss attributable to such member.

(iii) *Foreign expropriation losses.* An election under section 172(b) (3) (C) (relating to 10-year carryover of portion of net operating loss attributable to a foreign expropriation loss) may be made for a consolidated return year only if the sum of the foreign expropriation losses (as defined in section 172(k)) of the members of the group for such year equals or exceeds 50 percent of the consolidated net operating loss for such year. If such election is made, the amount which may be carried over under section 172(b) (1) (D) is the smaller of (a) the sum of such foreign expropriation losses, or (b) the consolidated net operating loss.

(3) *Absorption rules.* For purposes of determining the amount, if any, of a net operating loss (whether consolidated or separate) which can be carried to a taxable year (consolidated or separate), the amount of such net operating loss which is absorbed in a prior consolidated return year under section 172(b) (2) shall be determined by—

(i) Applying all net operating losses which can be carried to such prior year in the order of the taxable years in which such losses were sustained, beginning with the taxable year which ends earliest, and

(ii) Applying all such losses which can be carried to such prior year from taxable years ending on the same date on

a pro rata basis, except that any portion of a net operating loss attributable to a foreign expropriation loss to which section 172(b)(1)(D) applies shall be applied last.

(c) *Limitation on net operating loss carryovers and carrybacks from separate return limitation years*—(1) *General rule.* In the case of a net operating loss of a member of the group arising in a separate return limitation year (as defined in paragraph (f) of § 1.1502-1) of such member (and in a separate return limitation year of any predecessor of such member), the amount which may be included under paragraph (b) of this section (computed without regard to the limitation contained in paragraph (d) of this section) in the consolidated net operating loss carryovers and carrybacks to a consolidated return year of the group shall not exceed the amount determined under subparagraph (2) of this paragraph.

(2) *Computation of limitation.* The amount referred to in subparagraph (1) of this paragraph with respect to a member of the group is the excess, if any, of—

(i) Consolidated taxable income (computed without regard to the consolidated net operating loss deduction), minus such consolidated taxable income recomputed by excluding the items of income and deduction of such member, over

(ii) The net operating losses attributable to such member which may be carried to the consolidated return year arising in taxable years ending prior to the particular separate return limitation year.

(3) *Examples.* The provisions of this paragraph and paragraphs (a) and (b) of this section may be illustrated by the following examples:

Example (1). (i) Corporation P formed corporations S and T on January 1, 1965. P, S, and T filed separate returns for the calendar year 1965, a year for which an election under section 1562 was effective. T's return for that year reflected a net operating loss of \$10,000. The group filed a consolidated return for 1966 reflecting consolidated taxable income of \$30,000 (computed without regard to the consolidated net operating loss deduction). Among the transactions occurring during 1966 were the following:

(a) P sold goods to T deriving deferred profits of \$7,000 on such sales, \$2,000 of which was restored to consolidated taxable income on the sale of such goods to outsiders;

(b) T sold a machine to S deriving a deferred profit of \$5,000, \$1,000 of which was restored to consolidated taxable income as a result of S's depreciation deductions;

(c) T distributed a \$3,000 dividend to P; and

(d) In addition to the transactions described above, T had other taxable income of \$6,000.

(ii) The carryover of T's 1965 net operating loss to 1966 is subject to the limitation contained in this paragraph, since 1965 was a separate return limitation year (an election under section 1562 was effective for such year). Thus, only \$7,000 of T's \$10,000 net operating loss is a consolidated net operating loss carryover to 1966, since such carryover is limited to consolidated taxable income (computed without regard to the consoli-

dated net operating loss deduction), \$30,000, minus such consolidated taxable income recomputed by excluding the items of income and deduction of T, \$23,000 (i.e., consolidated taxable income computed without regard to the \$1,000 restoration of T's deferred gain and T's \$6,000 of other income). In making such recomputation, no change is made in the effect on consolidated taxable income of P's sale to T, or of the dividend from T to P.

Example (2). (i) Corporation P was formed on January 1, 1966. P filed separate returns for the calendar years 1966 and 1967 reflecting net operating losses of \$4,000 and \$12,000, respectively. P purchased corporation S on March 15, 1967. S was formed on February 1, 1966, and filed a separate return for the taxable year ending January 31, 1967. S also filed a short period return for the period from February 1 to December 31, 1967, and joined with P in filing a consolidated return for 1968. S sustained net operating losses of \$5,000 and \$6,000 for its taxable years ending January 31, 1967, and December 31, 1967, respectively. An election under section 1562 was not effective for P and S during the period involved. Consolidated taxable income for 1968 (computed without regard to the consolidated net operating loss deduction) was \$16,000; such consolidated taxable income recomputed by disregarding the items of income and deduction of S was \$9,000.

(ii) In order of time, the following losses are absorbed in 1968:

(a) P's \$4,000 net operating loss for the calendar year 1966 (such loss is not subject to the limitation contained in this paragraph since P is the common parent corporation for 1968);

(b) S's \$5,000 net operating loss for the year ended January 31, 1967. Such loss is subject to the limitation contained in this paragraph, since S was not a member of the group on each day of such year. However, such loss can be carried over and absorbed in full since such limitation is \$7,000 (consolidated taxable income computed without regard to the consolidated net operating loss deduction, \$16,000, minus such consolidated taxable income recomputed, \$9,000); and

(c) \$6,000 of P's net operating loss and \$1,000 of S's net operating loss for the taxable years ending December 31, 1967. This is determined by applying the losses from such year which can be carried to 1968 (P's \$12,000 loss and \$2,000 of S's \$6,000 loss, since such \$6,000 loss is limited under this paragraph) on a pro rata basis against the amount of such losses which can be absorbed in that year, \$7,000 (consolidated taxable income of \$16,000 less the \$9,000 of losses absorbed from prior years). The carryover of S's loss to 1968 is subject to the limitation contained in that paragraph, since S was not a member of the group on each day of its taxable year ending December 31, 1967. Such loss is limited to \$2,000, the excess of \$7,000 (as determined under (ii)(b)) over \$5,000 (S's carryover from the year ended January 31, 1967). If a consolidated return is filed in 1969, the consolidated net operating loss carryovers will consist of P's unabsorbed loss of \$6,000 (\$12,000 minus \$6,000) from 1967 and, subject to the limitation contained in this paragraph, S's unabsorbed loss of \$5,000 (\$6,000 minus \$1,000) from its year ended December 31, 1967.

(d) *Limitation on carryovers where there has been a consolidated return change of ownership*—(1) *General rule.* If a consolidated return change of ownership (as defined in paragraph (g) of § 1.1502-1) occurs during the taxable year or an earlier taxable year, the amount which may be included under paragraph (b) of this section in the consolidated net operating loss carryovers to

the taxable year with respect to the aggregate of the net operating losses attributable to old members of the group (as defined in paragraph (g)(3) of § 1.1502-1) arising in taxable years (consolidated or separate) ending on the same day and before the taxable year in which the consolidated return change of ownership occurred shall not exceed the amount determined under subparagraph (2) of this paragraph.

(2) *Computation of limitation.* The amount referred to in subparagraph (1) of this paragraph shall be the excess of—

(i) The consolidated taxable income for the taxable year (determined without regard to the consolidated net operating loss deduction) recomputed by including only the items of income and deduction of the old members of the group, over

(ii) The sum of the net operating losses attributable to the old members of the group which may be carried to the taxable year arising in taxable years ending prior to the particular loss year or years.

(3) *Example.* The provisions of this paragraph may be illustrated by the following example:

Example. (i) Corporation P is formed on January 1, 1967, and on the same day it forms corporation S. P and S file a consolidated return for the calendar year 1967, reflecting a consolidated net operating loss of \$500,000. On January 1, 1968, individual X purchases all of the outstanding stock of P. X subsequently contributes \$1,000,000 to P and P purchases the stock of corporation T. P, S, and T file a consolidated return for 1968 reflecting consolidated taxable income of \$600,000 (computed without regard to the consolidated net operating loss deduction). Such consolidated taxable income recomputed by including only the items of income and deduction of P and S is \$350,000.

(ii) Since a consolidated return change of ownership took place in 1968 (there was more than a 50 percent change of ownership of P), the amount of the consolidated net operating loss from 1967 which can be carried over to 1968 is limited to \$350,000, the excess of \$350,000 (consolidated taxable income recomputed by including only the items of income and deduction of the old members of the group, P and S) over zero (the amount of the consolidated net operating loss carryovers attributable to the old members of the group arising in taxable years ending before 1967).

(e) *Limitations on net operating loss carryovers under section 382*—(1) *Section 382(a).* (i) If at the end of a taxable year (consolidated or separate) there has been an increase in ownership of the stock of the common parent of a group (within the meaning of section 382(a)(1)(A) and (B)), and any member of the group has not continued to carry on a trade or business substantially the same as that conducted before any such increase (within the meaning of section 382(a)(1)(C)), then the portion of any consolidated net operating loss sustained in prior taxable years attributable to such member (as determined under paragraph (a)(3) of § 1.1502-79) shall not be allowed as a carryover to such taxable year or to any subsequent taxable year.

(ii) If the provisions of section 382(a) disallow the deduction of a net operating

loss carryover from a separate return year of a member of the group to a subsequent taxable year, no amount shall be included under paragraph (b) of this section as a consolidated net operating loss carryover to such a subsequent consolidated return year with respect to such separate return year of such member.

(iii) The provisions of this subparagraph may be illustrated by the following example:

Example. P, S, and T file a consolidated return for the calendar year 1969, reflecting a consolidated net operating loss attributable in part to each member. P owns 80 percent of S's stock and S owns 80 percent of T's stock. On January 1, 1970, A purchases 50 percent of P's stock. During 1970 T's business is discontinued. Since there has been a 50 percentage point increase in ownership of P, the common parent of the group, and since T has not continued to carry on the same trade or business after such increase, the portion of the 1969 consolidated net operating loss attributable to T shall not be included in any net operating loss deduction for 1970 or for any subsequent taxable years, whether consolidated or separate.

(2) **Section 382(b).** If a net operating loss carryover from a separate return year of a predecessor of a member of the group to the taxable year is reduced under the provisions of section 382(b), the amount included under paragraph (b) of this section with respect to such predecessor shall be so reduced.

(f) **Consolidated net operating loss.** The consolidated net operating loss shall be determined by taking into account the following:

(1) The separate taxable income (as determined under § 1.1502-12) of each member of the group, computed without regard to any deduction under section 242;

(2) Any consolidated net capital gain;

(3) Any consolidated section 1231 net loss;

(4) Any consolidated charitable contributions deduction;

(5) Any consolidated dividends received deduction (determined under § 1.1502-26 without regard to paragraph (a)(2) of that section); and

(6) Any consolidated section 247 deduction (determined under § 1.1502-27 without regard to paragraph (a)(1)(ii) of that section).

§ 1.1502-22 Consolidated net capital gain or loss.

(a) **Computation.**—(1) **Consolidated net capital gain.** The consolidated net capital gain for the taxable year shall be determined by taking into account—

(i) The aggregate of the capital gains and losses (determined without regard to gains or losses to which section 1231 applies or net capital loss carryovers) of the members of the group for the consolidated return year,

(ii) The consolidated section 1231 net gain for such year (computed in accordance with § 1.1502-23), and

(iii) The consolidated net capital loss carryovers to such year (as determined under paragraph (b) of this section).

(2) **Consolidated net capital loss.** The consolidated net capital loss shall be de-

termined under subparagraph (1) of this paragraph but without regard to subdivision (iii) thereof.

(3) **Special rules.** For purposes of this section, capital gains and losses on intercompany transactions and transactions with respect to stock, bonds, and other obligations of a member of the group shall be reflected as provided in §§ 1.1502-13, 1.1502-14, and 1.1502-19, and capital losses shall be limited as provided in § 1.1502-15.

(4) [Reserved]

(5) **Example.** The provisions of this paragraph may be illustrated by the following example:

Example. (1) Corporations P, S, and T file consolidated returns on a calendar year basis for 1966 and 1967. The members had the following transactions involving capital assets during 1967: P sold an asset with a \$10,000 basis to S for \$17,000 and none of the circumstances of restoration described in paragraph (d), (e), or (f) of § 1.1502-13 occurred by the end of the consolidated return year; S sold an asset to individual A for \$7,000 which S had purchased during 1966 from P for \$10,000, and with respect to which P had deferred a gain of \$2,000; T sold an asset with a basis of \$10,000 to individual B for \$25,000. The group has a consolidated net capital loss carryover to the taxable year of \$10,000.

(ii) The consolidated net capital gain of the group is \$4,000, determined as follows: P's net capital gain of \$2,000, representing the deferred gain on the sale to S during the taxable year 1966, restored into income during taxable year 1967 (the \$7,000 gain on P's deferred intercompany transaction is not taken into account for the current year), plus T's net capital gain of \$15,000, minus S's net capital loss of \$3,000 and the consolidated net capital loss carryover of \$10,000.

(b) **Consolidated net capital loss carryovers.**—(1) **In general.** The consolidated net capital loss carryovers to the taxable year shall consist of any consolidated net capital losses of the group, plus any net capital losses of members of the group arising in separate return years of such members, which may be carried to the taxable year under the principles of section 1212(a). However, such consolidated carryovers shall not include any consolidated net capital loss apportioned to a corporation for a separate return year pursuant to paragraph (b) of § 1.1502-79 and shall be subject to the limitations contained in paragraphs (c) and (d) of this section. For purposes of section 1212(a)(1), the portion of any consolidated net capital loss for any taxable year attributable to a foreign expropriation capital loss is the amount of the foreign expropriation capital losses of all the members for such year (but not in excess of the consolidated net capital loss for such year).

(2) **Absorption rules.** For purposes of determining the amount, if any, of a net capital loss (whether consolidated or separate) which can be carried to a taxable year (consolidated or separate), the amount of such net capital loss which is absorbed in a prior consolidated return year under section 1212(a)(1) shall be determined by—

(i) Applying all net capital losses which can be carried to such prior year in the order of the taxable years in which

such losses were sustained, beginning with the taxable year which ends earliest, and

(ii) Applying all such losses which can be carried to such prior year from taxable years ending on the same date on a pro-rata basis, except that any portion of a net capital loss attributable to a foreign expropriation capital loss to which section 1212(a)(1)(B) applies shall be applied last.

(c) **Limitation on net capital loss carryovers from separate return limitation years.**—(1) **General rule.** In the case of a net capital loss of a member of the group arising in a separate return limitation year (as defined in paragraph (f) of § 1.1502-1) of such member (and in a separate return limitation year of any predecessor of such member), the amount that may be included under paragraph (b) of this section (computed without regard to the limitation contained in paragraph (d) of this section) shall not exceed the amount determined under subparagraph (2) of this paragraph.

(2) **Computation of limitation.** The amount referred to in subparagraph (1) of this paragraph with respect to a member of the group is the excess, if any, of—

(i) The consolidated net capital gain for the taxable year (computed without regard to any net capital loss carryovers), minus such consolidated net capital gain for the taxable year recomputed by excluding the capital gains and losses and the gains and losses to which section 1231 applies of such member, over

(ii) The net capital losses attributable to such member which can be carried to the taxable year arising in taxable years ending prior to the particular separate return limitation year.

(d) **Limitation on capital loss carryovers where there has been a consolidated return change of ownership.**—(1) **General rule.** If a consolidated return change of ownership (as defined in paragraph (g) of § 1.1502-1) occurs during the taxable year or an earlier taxable year, the amount which may be included under paragraph (b) of this section in the consolidated net capital loss carryovers to the taxable year with respect to the aggregate of the net capital losses attributable to old members of the group (as defined in paragraph (g)(3) of § 1.1502-1) arising in taxable years (consolidated or separate) ending on the same day and before the taxable year in which the consolidated return change of ownership occurred shall not exceed the amount determined under subparagraph (2) of this paragraph.

(2) **Computation of limitation.** The amount referred to in subparagraph (1) of this paragraph shall be the excess of—

(i) The consolidated net capital gain (determined without regard to any net capital loss carryovers for the taxable year) recomputed by including only capital gains and losses and gains and losses to which section 1231 applies of the old members of the group, over

(ii) The aggregate net capital losses attributable to the old members of the group which may be carried to the taxable year arising in taxable years ending prior to the particular loss year or years.

§ 1.1502-23 Consolidated section 1231 net gain or loss.

The consolidated section 1231 net gain or loss for the taxable year shall be determined by taking into account the aggregate of the gains and losses to which section 1231 applies of the members of the group for the consolidated return year. Section 1231 gains and losses on intercompany transactions shall be reflected as provided in § 1.1502-13. Section 1231 losses shall be limited as provided in § 1.1502-15.

§ 1.1502-24 Consolidated charitable contributions deduction.

(a) *Determination of amount of consolidated charitable contributions deduction.* The deduction allowed by section 170 for the taxable year shall be the lesser of—

(1) The aggregate deductions of the members of the group allowable under section 170 (determined without regard to section 170(b)(2)), plus the consolidated charitable contribution carryovers to such year, or

(2) Five percent of the adjusted consolidated taxable income as determined under paragraph (c) of this section.

(b) *Carryover of excess charitable contributions.* The consolidated charitable contribution carryovers to any consolidated return year shall consist of any excess consolidated charitable contributions of the group, plus any excess charitable contributions of members of the group arising in separate return years of such members, which may be carried over to the taxable year under the principles of section 170(b)(2) and (3). However, such consolidated carryovers shall not include any excess charitable contributions apportioned to a corporation for a separate return year pursuant to paragraph (e) of § 1.1502-79.

(c) *Adjusted consolidated taxable income.* For purposes of this section, the adjusted consolidated taxable income of the group for any consolidated return year shall be the consolidated taxable income computed without regard to this section, section 242, section 243(a)(2) and (3), § 1.1502-25, § 1.1502-26, and § 1.1502-27, and without regard to any consolidated net operating loss carrybacks to such year.

§ 1.1502-25 [Reserved]

§ 1.1502-26 Consolidated dividends received deduction.

(a) *In general.* The consolidated dividends received deduction for the taxable year shall be the lesser of—

(1) The aggregate of the deductions of the members of the group allowable under sections 243(a)(1), 244(a) and 245 (computed without regard to the limitation provided in section 246(b)), or

(2) 85 percent of the consolidated taxable income computed without regard

to the consolidated net operating loss deduction, consolidated section 247 deduction, and the consolidated dividends received deduction.

Subparagraph (2) of this paragraph shall not apply for any consolidated return year for which there is a consolidated net operating loss. (See paragraph (f) of § 1.1502-21 for the definition of a consolidated net operating loss.)

(b) *Intercompany dividends.* The amount determined under paragraph (a) of this section shall be determined without regard to dividends received from other members of the group during a consolidated return year. (See paragraph (a)(1) of § 1.1502-14 for rules relating to intercompany dividends.)

(c) *Examples.* The provisions of this section may be illustrated by the following examples:

Example (1). Corporations P, S, and S-1 filed a consolidated return for the calendar year 1966 showing consolidated taxable income of \$100,000 (determined without regard to the consolidated net operating loss deduction, consolidated dividends received deduction, and the consolidated section 247 deduction). Such corporations received dividends during such year from nonmember domestic corporations as follows:

Corporation:	Dividends
P	\$6,000
S	10,000
S-1	34,000
Total	50,000

The dividends received deduction allowable to each member under section 243(a)(1) (computed without regard to the limitation in section 246(b)) is as follows: P has \$5,100 (85 percent of \$6,000), S has \$8,500 (85 percent of \$10,000), and S-1 has \$28,900 (85 percent of \$34,000), or a total of \$42,500. Since \$42,500 is less than \$85,000 (85 percent of \$100,000), the consolidated dividends received deduction is \$42,500.

Example (2). Assume the same facts as in example (1) except that consolidated taxable income (computed without regard to the consolidated net operating loss deduction, consolidated dividends received deduction, and the consolidated section 247 deduction) was \$40,000. The aggregate of the dividends received deductions, \$42,500, computed without regard to section 246(b), results in a consolidated net operating loss of \$2,500. See section 172(d)(6). Therefore, paragraph (a)(2) of this section does not apply and the consolidated dividends received deduction is \$42,500.

§ 1.1502-27 Consolidated section 247 deduction.

(a) *Amount of deduction.* The consolidated section 247 deduction for the taxable year shall be an amount computed as follows:

(1) First, determine the amount which is the lesser of—

(i) The aggregate of the dividends paid (within the meaning of section 247(a)) during such year by members of the group which are public utilities (within the meaning of section 247(b)(1)) on preferred stock (within the meaning of section 247(b)(2)), other than dividends paid to other members of the group, or

(ii) The aggregate of the taxable income (or loss) (as determined under

paragraph (b) of this section) of each such member which is a public utility.

(2) Then, multiply the amount determined under subparagraph (1) of this paragraph by the fraction specified in section 247(a)(2).

(b) *Computation of taxable income.* For purposes of paragraph (a)(1)(ii) of this section, the taxable income (or loss) of a member of the group described in paragraph (a)(1)(i) shall be determined under § 1.1502-12, adjusted for the following items taken into account in the computation of consolidated taxable income:

(1) The portion of the consolidated net operating loss deduction, the consolidated charitable contributions deduction, and the consolidated dividends received deduction, attributable to such member;

(2) Such member's net capital gain (determined without regard to any net capital loss carryover attributable to such member);

(3) Such member's net capital loss and section 1231 net loss, reduced by the portion of the consolidated net capital loss attributable to such member; and

(4) The portion of any consolidated net capital loss carryover attributable to such member which is absorbed in the taxable year.

§§ 1.1502-28 to 1.1502-30 [Reserved]

BASIS, STOCK OWNERSHIP, AND EARNINGS AND PROFITS RULES

§§ 1.1502-31 to 1.1502-33 [Reserved]

§ 1.1502-34 Special aggregate stock ownership rules.

For purposes of §§ 1.1502-1 through 1.1502-80, in determining the stock ownership of a member of the group in another corporation (the "issuing corporation") for purposes of determining the application of section 165(g)(3)(A), 332(b)(1), 333(b), 351(a), or 904(f), in a consolidated return year, there shall be included stock owned by all other members of the group in the issuing corporation. Thus, assume that members A, B, and C each own 33 1/3 percent of the stock issued by D. In such case, A, B, and C shall each be treated as meeting the 80-percent stock ownership requirement for purposes of section 332, and no member can elect to have section 333 apply. Furthermore, the special rule for minority shareholders in section 337(d) cannot apply with respect to amounts received by A, B, or C in liquidation of D.

§§ 1.1502-35 to 1.1502-40 [Reserved]

SPECIAL TAXES AND TAXPAYERS

§ 1.1502-41 Determination of consolidated net long-term capital gain and consolidated net short-term capital loss.

(a) *Consolidated net long-term capital gain.* The consolidated net long-term capital gain shall be determined by taking into account (1) those gains and losses to which paragraph (a)(1) of § 1.1502-22 applies which are treated as long term under section 1222, and (2) the consolidated section 1231 net gain (computed in accordance with § 1.1502-23).

(b) *Consolidated net short-term capital loss.* The consolidated net short-term capital loss shall be determined by taking into account (1) those gains and losses to which paragraph (a)(1) of § 1.1502-22 applies which are treated as short term under section 1222, and (2) the consolidated net capital loss carryovers to the taxable year (as determined under paragraph (b) of § 1.1502-22).

§§ 1.1502-42 to 1.1502-74 [Reserved]

ADMINISTRATIVE PROVISIONS AND OTHER RULES

§ 1.1502-75 Filing of consolidated returns.

(a) *Privilege of filing consolidated returns.*—(1) *Exercise of privilege for first consolidated return year.* A group which did not file a consolidated return for the immediately preceding taxable year may file a consolidated return in lieu of separate returns for the taxable year, provided that each corporation which has been a member during any part of the taxable year for which the consolidated return is to be filed consents (in the manner provided in paragraph (b) of this section) to the regulations under section 1502. If a group wishes to exercise its privilege of filing a consolidated return, such consolidated return must be filed not later than the last day prescribed by law (including extensions of time) for the filing of the common parent's return. Such consolidated return may not be withdrawn after such last day (but the group may change the basis of its return at any time prior to such last day).

(2) *Continued filing requirement.* A group which filed (or was required to file) a consolidated return for the immediately preceding taxable year is required to file a consolidated return for the taxable year unless it has an election to discontinue filing consolidated returns under paragraph (c) of this section.

(b) *How consent for first consolidated year exercised.*—(1) *General rule.* The consent of a corporation referred to in paragraph (a)(1) of this section shall be made by such corporation joining in the making of the consolidated return for such year. A corporation shall be deemed to have joined in the making of such return for such year if it files a Form 1122 in the manner specified in paragraph (h)(2) of this section.

(2) *Consent under facts and circumstances.* If a member of the group fails to file Form 1122, the Commissioner may under the facts and circumstances determine that such member has joined in the making of a consolidated return by such group. The following circumstances, among others, will be taken into account in making this determination:

(i) Whether or not the income and deductions of the member were included in the consolidated return;

(ii) Whether or not a separate return was filed by the member for that taxable year; and

(iii) Whether or not the member was included in the affiliations schedule, Form 851.

If the Commissioner determines that the member has joined in the making of the consolidated return, such member shall be treated as if it had filed a Form 1122 for such year for purposes of paragraph (h)(2) of this section.

(3) *Failure to consent due to mistake.* If any member has failed to join in the making of a consolidated return under either subparagraph (1) or (2) of this paragraph, then the tax liability of each member of the group shall be determined on the basis of separate returns unless the common parent corporation establishes to the satisfaction of the Commissioner that the failure of such member to join in the making of the consolidated return was due to a mistake of law or fact, or to inadvertence. In such case, such member shall be treated as if it had filed a Form 1122 for such year for purposes of paragraph (h)(2) of this section, and thus joined in the making of the consolidated return for such year.

(c) *Election to discontinue filing consolidated returns.*—(1) *Good cause.*—(i) *In general.* Notwithstanding that a consolidated return is required for a taxable year, the Commissioner, upon application by the common parent made not later than the 19th day before the due date for the filing of the consolidated return (including extensions of time), may for good cause shown grant permission to a group to discontinue filing consolidated returns. Any such application shall be made to the Commissioner of Internal Revenue, Washington, D.C. 20224.

(ii) *Substantial adverse change in law affecting tax liability.* Ordinarily, the Commissioner will grant a group permission to discontinue filing consolidated returns if the net result of all amendments to the Code or regulations with effective dates commencing within the taxable year has a substantial adverse effect on the consolidated tax liability of the group for such year relative to what the aggregate tax liability would be if the members of the group filed separate returns for such year. Thus, for example, assume P and S filed a consolidated return for the calendar year 1966 and that the provisions of the Code have been amended by a bill which was enacted by Congress in 1966, but which is first effective for taxable years beginning on or after January 1, 1967. Assume further that P makes a timely application to discontinue filing consolidated returns. In order to determine whether the amendments have a substantial adverse effect on the consolidated tax liability for 1967, relative to what the aggregate tax liability would be if the members of the group filed separate returns for 1967, the difference between the tax liability of the group computed on a consolidated basis and taking into account the changes in the law effective for 1967 and the aggregate tax liability of the members of the group computed as if each such member filed separate returns for such year (also taking into account such changes) shall be compared with the difference between the tax liability of such group for 1967 computed on a consolidated basis without regard to the changes in the law

effective in such year and the aggregate tax liability of the members of the group computed as if separate returns had been filed by such members for such year without regard to the changes in the law effective in such year.

(iii) *Other factors.* In addition, the Commissioner will take into account other factors in determining whether good cause exists for granting permission to discontinue filing consolidated returns beginning with the taxable year, including—

(a) Changes in law or circumstances, including changes which do not affect Federal income tax liability.

(b) Changes in law which are first effective in the taxable year and which result in a substantial reduction in the consolidated net operating loss (or consolidated unused investment credit) for such year relative to what the aggregate net operating losses (or investment credits) would be if the members of the group filed separate returns for such year, and

(c) Changes in the Code or regulations which are effective prior to the taxable year but which first have a substantial adverse effect on the filing of a consolidated return relative to the filing of separate returns by members of the group in such year.

(2) *Discretion of Commissioner to grant blanket permission.*—(i) *Permission to all groups.* The Commissioner, in his discretion, may grant all groups permission to discontinue filing consolidated returns if any provision of the Code or regulations has been amended and such amendment is of the type which could have a substantial adverse effect on the filing of consolidated returns by substantially all groups, relative to the filing of separate returns. Ordinarily, the permission to discontinue shall apply with respect to the taxable year of each group which includes the effective date of such an amendment.

(ii) *Permission to a class of groups.* The Commissioner, in his discretion, may grant a particular class of groups permission to discontinue filing consolidated returns if any provision of the Code or regulations has been amended and such amendment is of the type which could have a substantial adverse effect on the filing of consolidated returns by substantially all such groups relative to the filing of separate returns. Ordinarily, the permission to discontinue shall apply with respect to the taxable year of each group within the class which includes the effective date of such an amendment.

(3) *Time and manner for exercising election.* If, under subparagraph (1) or (2) of this paragraph, a group has an election to discontinue filing consolidated returns for any taxable year and such group wishes to exercise such election, then the common parent must file a separate return for such year on or before the last day prescribed by law (including extensions of time) for the filing of the consolidated return for such year. See section 6081 (relating to extensions of time for filing returns).

(d) *When group remains in existence.*—(1) *General rule.* A group shall

be considered as remaining in existence if the common parent corporation remains as the common parent and at least one subsidiary remains affiliated with it, whether or not such subsidiary was a member of the group in a prior year and whether or not one or more corporations have ceased to be subsidiaries at any time after the group was formed. Thus, for example, assume that individual A forms corporation P. P acquires 100 percent of the stock of corporation S on January 1, 1965, and P and S file a consolidated return for the calendar year 1965. On May 1, 1966, P acquires 100 percent of the stock of S-1, and on July 1, 1966, P sells the stock of S. The group (consisting originally of P and S) remains in existence in 1966 since P has remained as the common parent and at least one subsidiary (now S-1) remains affiliated with it.

(2) *Common parent no longer in existence*—(i) *Mere change in identity.* For purposes of this paragraph, the common parent corporation shall remain as the common parent irrespective of a mere change in identity, form, or place of organization of such common parent corporation (see section 368(a)(1)(F)).

(ii) *Transfer of assets to subsidiary.* The group shall be considered as remaining in existence notwithstanding that the common parent is no longer in existence if the members of the affiliated group succeed to and become the owners of substantially all of the assets of such former parent and there remains one or more chains of includible corporations connected through stock ownership with a common parent corporation which is an includible corporation and which was a member of the group prior to the date such former parent ceases to exist.

(3) *Reverse acquisitions*—(i) *In general.* If a corporation (hereinafter referred to as the "first corporation") or any member of a group of which the first corporation is the common parent acquires after October 1, 1965—

(a) Stock of another corporation (hereinafter referred to as the second corporation), and as a result the second corporation becomes (or would become but for the application of this subparagraph) a member of a group of which the first corporation is the common parent, or

(b) Substantially all the assets of the second corporation,

in exchange (in whole or in part) for stock of the first corporation, and the stockholders (immediately before the acquisition) of the second corporation, as a result of owning stock of the second corporation, own (immediately after the acquisition) more than 50 percent of the fair market value of the outstanding stock of the first corporation, then any group of which the first corporation was the common parent immediately before the acquisition shall cease to exist as of the date of acquisition, and any group of which the second corporation was the common parent immediately before the acquisition shall be treated as remaining in existence (with the first corpora-

tion becoming the common parent of the group). Thus, assume that corporations P and S comprised group PS (P being the common parent), that P was merged into corporation T (the common parent of a group composed of T and corporation U), and that the shareholders of P immediately before the merger, as a result of owning stock in P, own 90 percent of the fair market value of T's stock immediately after the merger. The group of which P was the common parent is treated as continuing in existence with T and U being added as members of the group, and T taking the place of P as the common parent.

(ii) For purposes of subdivision (i) of this subparagraph, if the first corporation, and any members of a group of which the first corporation is the common parent, have continuously owned for a period of at least 5 years ending on the date of the acquisition an aggregate of at least 25 percent of the fair market value of the outstanding stock of the second corporation, then the first corporation (and any subsidiary which owns stock of the second corporation immediately before the acquisition) shall, as a result of owning such stock, be treated as owning (immediately after the acquisition) a percentage of the fair market value of the first corporation's outstanding stock which bears the same ratio to (a) the percentage of the fair market value of all the stock of the second corporation owned immediately before the acquisition by the first corporation and its subsidiaries as (b) the fair market value of the total outstanding stock of the second corporation immediately before the acquisition bears to (c) the sum of (1) the fair market value, immediately before the acquisition, of the total outstanding stock of the first corporation, and (2) the fair market value, immediately before the acquisition, of the total outstanding stock of the second corporation (other than any such stock owned by the first corporation and any of its subsidiaries). For example, assume that corporation P owns stock in corporation T having a fair market value of \$100,000, that P acquires the remaining stock of T from individuals in exchange for stock of P, that immediately before the acquisition the total outstanding stock of T had a fair market value of \$150,000, and that immediately before the acquisition the total outstanding stock of P had a fair market value of \$200,000. Assuming P owned at least 25 percent of the fair market value of T's stock for 5 years, then for purposes of this subparagraph, P is treated as owning (immediately after the acquisition) 40 percent of the fair market value of its own outstanding stock, determined as follows:

$$\frac{\$150,000}{\$200,000 + \$50,000} \times 66\frac{2}{3}\% = 40\%$$

Thus, if the former individual stockholders of T own, immediately after the acquisition more than 10 percent of the fair market value of the outstanding stock of P as a result of owning stock of T, the group of which T was the common

parent is treated as continuing in existence with P as the common parent, and the group of which P was the common parent before the acquisition ceases to exist.

(e) *Failure to include subsidiary.* If a consolidated return is required for the taxable year under the provisions of paragraph (a)(2) of this section, the tax liability of all members of the group for such year shall be computed on a consolidated basis even though—

(1) Separate returns are filed by one or more members of the group, or

(2) There has been a failure to include in the consolidated return the income of any member of the group.

If subparagraph (1) of this paragraph applies, the amounts assessed or paid upon the basis of separate returns shall be considered as having been assessed or paid upon the basis of a consolidated return.

(f) *Inclusion of one or more corporations not members of the group*—(1) *Method of determining tax liability.* If a consolidated return includes the income of a corporation which was not a member of the group at any time during the consolidated return year, the tax liability of such corporation will be determined upon the basis of a separate return (or a consolidated return of another group, if paragraph (a)(2) or (b)(3) of this section applies), and the consolidated return will be considered as including only the income of the corporations which were members of the group during that taxable year. If a consolidated return includes the income of two or more corporations which were not members of the group but which constitute another group, the tax liability of such corporations will be computed in the same manner as if separate returns had been made by such corporations unless the Commissioner upon application approves the making of a consolidated return for the other group or unless under paragraph (a)(2) of this section a consolidated return is required for the other group.

(2) *Allocation of tax liability.* In any case in which amounts have been assessed and paid upon the basis of a consolidated return and the tax liability of one or more of the corporations included in the consolidated return is to be computed in the manner described in subparagraph (1) of this paragraph, the amounts so paid shall be allocated between the group composed of the corporations properly included in the consolidated return and each of the corporations the tax liability of which is to be computed on a separate basis (or on the basis of a consolidated return of another group) in such manner as the corporations which were included in the consolidated return may, subject to the approval of the Commissioner, agree upon or in the absence of an agreement upon the method used in allocating the tax liability of the members of the group under the provisions of section 1552(a).

(g) *Computing periods of limitation*—(1) *Income incorrectly included in consolidated return.* If—

(i) A consolidated return is filed by a group for the taxable year, and

(ii) The tax liability of a corporation whose income is included in such return must be computed on the basis of a separate return (or on the basis of a consolidated return with another group), then for the purpose of computing any period of limitation with respect to such separate return (or such other consolidated return), the filing of such consolidated return by the group shall be considered as the making of a return by such corporation.

(2) *Income incorrectly included in separate returns.* If a consolidated return is required for the taxable year under the provisions of paragraph (a) (2) of this section, the filing of separate returns by the members of the group for such year shall not be considered as the making of a return for the purpose of computing any period of limitation with respect to such consolidated return unless there is attached to each such separate return a statement setting forth—

(i) The most recent taxable year of the member for which its income was included in a consolidated return, and

(ii) The reasons for the group's belief that a consolidated return is not required for the taxable year.

(h) *Method of filing return and forms.*—(1) *Consolidated return made by common parent corporation.* The consolidated return shall be made on Form 1120 for the group by the common parent corporation. The consolidated return, with Form 851 (affiliations schedule) attached, shall be filed with the district director with whom the common parent would have filed a separate return.

(2) *Filing of Form 1122 for first year.* If, under the provisions of paragraph

(a) (1) of this section, a group wishes to exercise its privilege of filing a consolidated return, then a Form 1122 must be executed by each subsidiary and must be attached to the consolidated return for such year. In addition, each subsidiary must file a signed copy of Form 1122 on or before the due date for the filing of the common parent's return for such year (including extensions of time) with the district director with whom such subsidiary would have filed its separate return. Form 1122 shall not be required for a taxable year if a consolidated return was filed (or was required to be filed) by the group for the immediately preceding taxable year.

(3) *Persons qualified to execute returns and forms.* Each return or form required to be made or prepared by a corporation must be executed by the person authorized under section 6062 to execute returns of separate corporations.

§ 1.1502-76 Taxable year of members of group.

(a) *Taxable year of members of group.*—(1) *Change to parent's taxable year.* The consolidated return of a group must be filed on the basis of the common parent's taxable year, and each subsidiary must adopt the common parent's annual accounting period for the first consolidated return year for which

the subsidiary's income is includible in the consolidated return. If any member is on a 52-53-week taxable year, the rule of the preceding sentence shall, with the advance consent of the Commissioner, be deemed satisfied if the taxable years of all members of the group end within the same 7-day period. Any request for such consent shall be filed with the Commissioner of Internal Revenue, Washington, D.C. 20224, not later than the 30th day before the due date (not including extensions of time) for the filing of the consolidated return.

(2) *Includible insurance company as member of group.* If an includible insurance company required by section 843 to file its return on the basis of a calendar year is a member of the group and if the common parent of such group files its return on the basis of a fiscal year, then the first consolidated return which includes the income of such insurance company may be filed on the basis of the common parent's fiscal year, provided, however, that if such insurance company is a member of the group on the last day of the common parent's taxable year all members of the group change to a calendar year basis effective immediately after the close of such fiscal year.

(b) *Income to be included in returns for taxable year.*—(1) *Inclusion of income in consolidated return.* The consolidated return of a group must include the income of the common parent for that corporation's entire taxable year (excluding any portion of such taxable year for which its income is properly included in the consolidated return of another group) and, except as provided in subparagraph (5) of this paragraph, the income of each subsidiary for the portion of such taxable year during which it was a member of the group.

(2) *Separate return for period not included in a consolidated return.* If the consolidated return of a group properly includes the income of a corporation for only a portion of such corporation's taxable year (determined without regard to a change of its taxable year under paragraph (a) of this section), then the income for the portion of such taxable year not included in the consolidated return must be included in a separate return (or, if such corporation is a member of another group which files a consolidated return for such portion of such year, then in such consolidated return).

(3) *Examples.* The provisions of subparagraphs (1) and (2) of this paragraph may be illustrated by the following examples:

Example (1). Corporations X and Y filed separate returns for the calendar year 1965. As of the close of June 30, 1966, X acquired all of the stock of Y. If X files a consolidated return for 1966, it must include in such return its income for the entire taxable year and the income of Y for the period July 1, 1966, through December 31, 1966. Y must include its income for the period January 1, 1966, through June 30, 1966, in a separate return.

Example (2). Corporations P and S, a group of corporations, filed a consolidated return for the calendar year 1966. As of the close of June 30, 1967, all of the stock of S was sold to individual A. P must file a consolidated return for 1967 including P's

income for the entire taxable year and the income of S for the period of January 1, 1967, through June 30, 1967. S must file a separate return for the period July 1, 1967, through December 31, 1967.

Example (3). Assume the same facts as in example (2) plus the additional fact that as of the close of July 31, 1967, P acquired all the stock of corporation T (which filed separate returns on the basis of a fiscal year ending November 30), and that P and T filed a consolidated return for 1967. P must file two consolidated returns for 1967. The consolidated return of P and S for 1967 must include P's income for the entire taxable year, excluding that portion of such year (August 1 through December 31) for which its income is includible in the consolidated return of P and T. The consolidated return of P and T for 1967 must include P's income for its entire taxable year, excluding that portion of the taxable year (January 1 through July 31) for which P's income is included in the consolidated return of P and S, and including the income of T for the period August 1 through December 31. T must file a separate return for the period December 1, 1966, through July 31, 1967.

(4) *Allocation of income between separate and consolidated returns.* (i) If the taxable income of a member for a taxable year (determined without regard to a change of its year under paragraph (a) of this section) must be included in part in a consolidated return and in part in a separate return (or a consolidated return of another group), the taxable income to be reported in each such return shall be determined on the basis of its income shown on its permanent records (including work papers).

(ii) If the portion of an item of income or deduction to be reported in each such return cannot be clearly determined from the permanent records, the portion of such item to be included in each such return shall be the amount of the item for the full taxable year (determined without regard to the change of year) multiplied by a fraction, the numerator of which is the number of days for which the member's income is to be included in such return and the denominator of which is the total number of days in such year.

(5) *Period of 30 days or less may be disregarded.* For purposes of the regulations under section 1502—

(i) If within 30 days after the beginning of a corporation's taxable year (determined without regard to the required change to the parent's taxable year) it becomes a member of a group, then such corporation may at its option be considered to have become a member of the group as of the beginning of the first day of such corporation's taxable year, or

(ii) If, during a consolidated return year of a group, a corporation (other than a corporation created or organized in such year by a member of the group) has been a member of such group for a period of 30 days or less, then such corporation may at its option be considered as not having been a member of the group during such year.

(6) *Examples.* The provisions of subparagraph (5) of this paragraph may be illustrated by the following examples:

Example (1). Corporation P, a common parent corporation, filed a consolidated return for the calendar year 1965. As of the

close of July 14, 1966, P acquired all of the stock of corporation S. S filed its separate returns on the basis of the fiscal year ending June 30. P files a consolidated return for 1966. Since S became a member of the group within 30 days after the beginning of its taxable year, S may at its option include its income in such consolidated return for the period July 1, 1966 (the beginning of its taxable year), through December 31, 1966, in lieu of the period July 15, 1966, through December 31, 1966.

Example (2). Assume the same facts as in example (1) except that P acquired all of the stock of S as of the close of December 14, 1966. Since S has been a member of the group for a period of 30 days or less during the group's calendar year 1966, S may at its option not include any of its income in the consolidated return filed for 1966.

(c) *Time for making separate returns for periods not included in consolidated return.*—(1) *Consolidated return filed by due date for separate return.* If the group has filed a consolidated return on or before the due date for the filing of a subsidiary's separate return (including extensions of time and determined without regard to any change of its taxable year required under paragraph (a) of this section), then the separate return for any portion of the subsidiary's taxable year for which its income is not included in the consolidated return of the group must be filed no later than the due date of such consolidated return (including extensions of time).

(2) *Consolidated return not filed by due date for separate return.* If the group has not filed a consolidated return on or before the due date for the filing of a subsidiary corporation's separate return (including extensions of time and determined without regard to any change of its taxable year required under paragraph (a) of this section), then on or before such due date such subsidiary shall file a separate return either for the portion of its taxable year for which its income would not be included in a consolidated return if such a return were filed, or for its complete taxable year. However, if a separate return is filed for such portion of its taxable year and the group subsequently does not file a consolidated return, such subsidiary corporation shall file a substituted return for its complete taxable year not later than the due date (including extensions of time) prescribed for the filing of the common parent's return. On the other hand, if the return is filed for the subsidiary's complete taxable year and the group later files a consolidated return, such subsidiary must file an amended return not later than the due date (including extensions of time) for the filing of the consolidated return of the group. Such amended return shall be for that portion of such subsidiary's taxable year which is not included in the consolidated return. If, under this subparagraph, a

substituted return must be filed, then the return previously filed shall not be considered a return within the meaning of section 6011. If, under this subparagraph, a substituted or amended return must be filed, then, for purposes of sections 6513(a) and 6601(a), the last date prescribed for payment of tax shall be the due date (not including extensions of time) for the filing of the subsidiary's separate return (determined without regard to this subparagraph and without regard to any change of its taxable year required under paragraph (a) of this section).

(3) *Examples.* The provisions of this paragraph may be illustrated by the following examples:

Example (1). Corporation P, which filed a separate return for the calendar year 1966, acquires all of the stock of corporation S as of the close of December 31, 1966. Corporation S reports its income on the basis of a fiscal year ending March 31. On June 15, 1967, the due date for the filing of a separate return by S (assuming no extensions of time), a consolidated return has not been filed for the group (P and S). On such date S may either file a return for the period April 1, 1966, through December 31, 1966, or it may file a return for the complete fiscal year ending March 31, 1967. If S files a return for the short period ending December 31, 1966, and if the group elects not to file a consolidated return for the calendar year 1967, S, on or before March 15, 1968 (the due date of P's return, assuming no extensions of time), must file a substituted return for the complete fiscal year ending March 31, 1967, in lieu of the return previously filed for the short period. Interest is computed from June 15, 1967. If, however, S files a return for the complete fiscal year ending March 31, 1967, and the group elects to file a consolidated return for the calendar year 1967, then S must file an amended return covering the period from April 1, 1966, through December 31, 1966, in lieu of the return previously filed for the complete fiscal year. Interest is computed from June 15, 1967.

Example (2). Assume the same facts as in example (1) except that corporation P acquires all of the stock of corporation S at the close of September 30, 1967, and that P files a consolidated return for the group for 1967 on March 15, 1968 (not having obtained any extensions of time). Since a consolidated return has been filed on or before the due date (June 15, 1968) for the filing of the separate return for the taxable year ending March 31, 1968, the return of S for the short taxable year beginning April 1, 1967, and ending September 30, 1967, should be filed no later than March 15, 1968.

(d) *Taxable year of less than 12 months.* Any period of less than 12 months for which either a separate return or a consolidated return is filed under the provisions of this section shall be considered as a separate taxable year.

§ 1.1502-77 Common parent agent for subsidiaries.

(a) *Scope of agency of common parent corporation.* The common parent, for all purposes other than the making of the consent required by paragraph (a)(1) of § 1.1502-75, shall be the sole agent for each subsidiary in the group, duly authorized to act in its own name in all matters relating to the tax liability for the consolidated return year. No subsidiary shall have authority to act for or to represent itself in any such matter. For example, any election available to a subsidiary corporation in the computation of its separate taxable income must be made by the common parent, as must any change in an election previously made by the subsidiary corporation; all correspondence will be carried on directly with the common parent; the common parent shall file for all extensions of time including extensions of time for payment of tax under section 6164; notices of deficiencies will be mailed only to the common parent, and the mailing to the common parent shall be considered as a mailing to each subsidiary in the group; notice and demand for payment of taxes will be given only to the common parent and such notice and demand will be considered as a notice and demand to each subsidiary; the common parent will file petitions and conduct proceedings before the Tax Court of the United States, and any such petition shall be considered as also having been filed by each such subsidiary. The common parent will file claims for refund or credit, and any refund will be made directly to and in the name of the common parent and will discharge any liability of the Government in respect thereof to any such subsidiary; and the common parent in its name will give waivers, give bonds, and execute closing agreements, offers in compromise, and all other documents, and any waiver or bond so given, or agreement, offer in compromise, or any other document so executed, shall be considered as having also been given or executed by each such subsidiary. Notwithstanding the provisions of this paragraph, any notice of deficiency, in respect of the tax for a consolidated return year, will name each corporation which was a member of the group during any part of such period (but a failure to include the name of any such member will not affect the validity of the notice of deficiency as to the other members); any notice and demand for payment will name each corporation which was a member of the group during any part of such period (but a failure to include the name of any such member will not affect the validity of the notice and demand as to the other members); and any levy, any notice of

a lien, or any other proceeding to collect the amount of any assessment, after the assessment has been made, will name the corporation from which such collection is to be made. The provisions of this paragraph shall apply whether or not a consolidated return is made for any subsequent year, and whether or not one or more subsidiaries have become or have ceased to be members of the group at any time. Notwithstanding the provisions of this paragraph, the district director may, upon notifying the common parent, deal directly with any member of the group in respect of its liability, in which event such member shall have full authority to act for itself.

(b) *Notification of deficiency to corporation which has ceased to be a member of the group.* If a subsidiary has ceased to be a member of the group and if such subsidiary files written notice of such cessation with the district director with whom the consolidated return is filed, then such district director upon request of such subsidiary will furnish it with a copy of any notice of deficiency in respect of the tax for a consolidated return year for which it was a member and a copy of any notice and demand for payment of such deficiency. The filing of such written notification and request by a corporation shall not have the effect of limiting the scope of the agency of the common parent provided for in paragraph (a) of this section and a failure by such district director to comply with such written request shall not have the effect of limiting the tax liability of such corporation provided for in § 1.1502-6.

(c) *Effect of waiver given by common parent.* Unless the district director agrees to the contrary, an agreement entered into by the common parent extending the time within which an assessment may be made or levy or proceeding in court begun in respect of the tax for a consolidated return year shall be applicable—

(1) To each corporation which was a member of the group during any part of such taxable year, and

(2) To each corporation the income of which was included in the consolidated return for such taxable year, notwithstanding that the tax liability of any such corporation is subsequently computed on the basis of a separate return under the provisions of § 1.1502-75.

(d) *Effect of dissolution of common parent corporation.* If the common parent corporation contemplates dissolution, or is about to be dissolved, or if for any other reason its existence is about to terminate, it shall forthwith notify the district director with whom the consolidated return is filed of such fact and designate, subject to the approval of such district director, another member to act as agent in its place to the same extent and subject to the same conditions and limitations as are applicable to the common parent. If the notice thus required

is not given by the common parent, or the designation is not approved by the district director, the remaining members may, subject to the approval of such district director, designate another member to act as such agent, and notice of such designation shall be given to such district director. Until a notice in writing designating a new agent has been approved by such district director, any notice of deficiency or other communication mailed to the common parent shall be considered as having been properly mailed to the agent of the group; or, if such district director has reason to believe that the existence of the common parent has terminated, he may, if he deems it advisable, deal directly with any member in respect of its liability.

§ 1.1502-78 Tentative carryback adjustments.

(a) *General rule.* If a group sustains a consolidated net operating loss for any taxable year, then any application under section 6411 for a tentative carryback adjustment of the taxes for a consolidated return year or years preceding the loss year shall be made by the common parent corporation to the extent such consolidated net operating loss is not apportioned to a corporation for a separate return year pursuant to paragraph (a) of § 1.1502-79. In the case of the portion of a consolidated net operating loss to which the preceding sentence does not apply, and in the case of a net operating loss sustained in a separate return year which may be carried back to a consolidated return year, the corporation or corporations to which any such loss is attributable shall make any application under section 6411.

(b) *Special rules.*—(1) *Payment of refund.* Any refund allowable under an application referred to in paragraph (a) of this section shall be made directly to and in the name of the corporation filing the application, except that in all cases where the loss is deducted from the consolidated taxable income of a consolidated return year, any refund shall be made directly to and in the name of the common parent corporation. The payment of any such refund shall discharge any liability of the Government with respect to such refund.

(2) *Several liability.* If a group filed a consolidated return for a taxable year for which there was an adjustment by reason of an application under section 6411, and if a deficiency is assessed against such group under section 6213 (b) (2), then each member of such group shall be severally liable for such deficiency including any interest or penalty assessed in connection with such deficiency.

(c) *Examples.* The provisions of paragraphs (a) and (b) of this section may be illustrated by the following examples:

Example (1). Corporations P, S, and S-1 filed a consolidated return for the calendar year 1966. P, S, and S-1 also filed a consolidated return for the calendar year 1969.

The group incurred a consolidated net operating loss in 1969 attributable to S-1 which may be carried back to 1966 as a consolidated net operating loss carryback. If a tentative carryback adjustment is desired, P, the common parent, must file an application under section 6411 and any refund will be made to P.

Example (2). Assume the same facts as in example (1) except that P, S, and S-1 filed separate returns for the calendar year 1969, even though they were members of the same group for such year. S-1 incurred a net operating loss in 1969 which may be carried back to 1966. If a tentative carryback adjustment is desired, S-1 must file an application under section 6411 and any refund from such application will be made to P.

Example (3). Corporations X, Y, and Z filed a consolidated return for the calendar year 1966. Z ceased to be a member of the group in 1967. Z filed a separate return for 1968 while X and Y filed a consolidated return for such year. The group incurred a consolidated net operating loss in 1968 attributable to Y, which may be carried back to 1966. Z also incurred a net operating loss for 1968 which may be carried back to 1966. If a tentative carryback adjustment is claimed with respect to the consolidated net operating loss, X, the common parent, must file an application under section 6411. If a tentative carryback adjustment is desired with respect to Z's loss, Z must file an application. Any refunds attributable to either application will be made to X. If an assessment is made under section 6213(b)(2) to recover an excessive tentative allowance made with respect to calendar year 1966, X, Y, and Z are severally liable for such assessment.

Example (4). Corporations L and M filed a consolidated return for the calendar year 1966. Corporation N filed a separate return for such year. Later, N became a member of the group and filed a consolidated return with the group for the calendar year 1968. The group incurred a consolidated net operating loss in 1968 attributable to N which may be carried back to N's separate return for 1966. If a tentative carryback adjustment is desired, N must file an application under section 6411 and any refund will be made directly to N.

§ 1.1502-79 Separate return years.

(a) *Carryover and carryback of consolidated net operating losses to separate return years.*—(1) *In general.* (i) If a consolidated net operating loss can be carried under the principles of section 172(b) and paragraph (b) of § 1.1502-21 to a separate return year of a corporation (or could have been so carried if such corporation were in existence) which was a member in the year in which such loss arose, then the portion of such consolidated net operating loss attributable to such corporation (as determined under subparagraph (3) of this paragraph) shall be apportioned to such corporation (and any successor to such corporation in a transaction to which section 381(a) applies) and shall be a net operating loss carryover or carryback to such separate return year; accordingly, such portion shall not be included in the consolidated net operating loss carryovers or carrybacks to the equivalent consolidated return year. Thus, for example, if a member filed a separate return for the third year preceding a

consolidated return year in which a consolidated net operating loss was sustained and if any portion of such loss is apportioned to such member for such separate return year, such portion may not be carried back by the group to its third year preceding such consolidated return year.

(ii) If a corporation ceases to be a member during a consolidated return year, any consolidated net operating loss carryover from a prior taxable year must first be carried to such consolidated return year, notwithstanding that all or a portion of the consolidated net operating loss giving rise to the carryover is attributable to the corporation which ceases to be a member. To the extent not absorbed in such consolidated return year, the portion of the consolidated net operating loss attributable to the corporation ceasing to be a member shall then be carried to such corporation's first separate return year.

(2) *Nonapportionment to certain members not in existence.* Notwithstanding subparagraph (1) of this paragraph, the portion of a consolidated net operating loss attributable to a member shall not be apportioned to a prior separate return year for which such member was not in existence and shall be included in the consolidated net operating loss carrybacks to the equivalent consolidated return year of the group (or, if such equivalent year is a separate return year, then to such separate return year), provided that such member was a member of the group immediately after its organization.

(3) *Portion of consolidated net operating loss attributable to a member.* The portion of a consolidated net operating loss attributable to a member of a group is an amount equal to the consolidated net operating loss multiplied by a fraction, the numerator of which is the separate net operating loss of such corporation, and the denominator of which is the sum of the separate net operating losses of all members of the group in such year having such losses. For purposes of this subparagraph, the separate net operating loss of a member of the group shall be determined under § 1.1502-12 (except that no deduction shall be allowed under section 242), adjusted for the following items taken into account in the computation of the consolidated net operating loss:

(i) The portion of the consolidated dividends received deduction, the consolidated charitable contributions deductions, and the consolidated section 247 deduction, attributable to such member;

(ii) Such member's net capital gain (determined without regard to any net capital loss carryover attributable to such member);

(iii) Such member's net capital loss and section 1231 net loss, reduced by the portion of the consolidated net capital loss attributable to such member (as de-

termined under paragraph (b) (2) of this section); and

(iv) The portion of any consolidated net capital loss carryover attributable to such member which is absorbed in the taxable year.

(4) *Examples.* The provisions of this paragraph may be illustrated by the following examples:

Example (1). (i) Corporation P was formed on January 1, 1966. P filed a separate return for the calendar year 1966. On March 15, 1967, P formed corporation S. P and S filed a consolidated return for 1967. On January 1, 1968, P purchased all the stock of corporation T, which had been formed in 1967 and had filed a separate return for its taxable year ending December 31, 1967.

(ii) P, S, and T join in the filing of a consolidated return for 1968, which return reflects a consolidated net operating loss of \$11,000. \$2,000 of such consolidated net operating loss is attributable to P, \$3,000 to S, and \$6,000 to T. Such apportionment of the consolidated net operating loss was made on the basis of the separate net operating losses of each member as determined under subparagraph (3) of this paragraph.

(iii) \$5,000 of the 1968 consolidated net operating loss can be carried back to P's separate return for 1966. Such amount is the portion of the consolidated net operating loss attributable to P and S. Even though S was not in existence in 1966, the portion attributable to S can be carried back to P's separate return year, since S (unlike T) was a member of the group immediately after its organization. The 1968 consolidated net operating loss can be carried back against the group's income in 1967 except to the extent (i.e., \$6,000) that it is apportioned to T for its 1967 separate return year and to the extent that it was absorbed in P's 1966 separate return year. The portion of the 1968 consolidated net operating loss attributable to T (\$6,000) is a net operating loss carryback to its 1967 separate return.

Example (2). (i) Assume the same facts as in example (1). Assume further that on June 15, 1969, P sells all the stock of T to an outsider, that P and S file a consolidated return for 1969 (which includes the income of T for the period January 1 through June 15), and that T files a separate return for the period June 16 through December 31, 1969.

(ii) The 1968 consolidated net operating loss, to the extent not absorbed in prior years, must first be carried to the consolidated return year 1969. Any portion of the \$6,000 amount attributable to T which is not absorbed in T's 1967 separate return year or in the 1969 consolidated return year shall then be carried to T's separate return year ending December 31, 1969.

(b) *Carryover of consolidated net capital loss to separate return years—*

(1) *In general.* If a consolidated net capital loss can be carried under the principles of section 1212 (a) and paragraph (b) of § 1.1502-22 to a separate return year of a corporation (or could have been so carried if such corporation were in existence) which was a member of the group in the year in which such consolidated net capital loss arose, then the portion of such consolidated net capital loss attributable to such corporation (as determined under subpara-

graph (2) of this paragraph) shall be apportioned to such corporation (and any successor to such corporation in a transaction to which section 381(a) applies) under the principles of paragraph (a) (1), (2) and (3) of this section and shall be a net capital loss carryover to such separate return year.

(2) *Portion of consolidated net capital loss attributable to a member.* The portion of a consolidated net capital loss attributable to a member of a group is an amount equal to such consolidated net capital loss multiplied by a fraction, the numerator of which is the net capital loss of such member, and the denominator of which is the sum of the net capital losses of those members of the group having net capital losses. For purposes of this subparagraph, the net capital loss of a member of the group shall be determined by taking into account the following:

(i) Such member's net capital gain or loss (determined without regard to any net capital loss carryover); and

(ii) Such member's section 1231 net loss, reduced by the portion of the consolidated section 1231 net loss attributable to such member.

(c) *Carryover and carryback of consolidated unused investment credit to separate return years—*(1) *In general.* If a consolidated unused investment credit can be carried under the principles of section 46(b) and paragraph (b) of § 1.1502-3 to a separate return year of a corporation (or could have been so carried if such corporation were in existence) which was a member of the group in the year in which such unused credit arose, then the portion of such consolidated unused credit attributable to such corporation (as determined under subparagraph (2) of this paragraph) shall be apportioned to such corporation (and any successor to such corporation in a transaction to which section 381(a) applies) under the principles of paragraph (a) (1) and (2) of this section and shall be an investment credit carryover or carryback to such separate return year.

(2) *Portion of consolidated unused investment credit attributable to a member—*(i) *Investment credit carryback.* In the case of a consolidated unused credit which is an investment credit carryback, the portion of such consolidated unused credit attributable to a member of the group is an amount equal to such consolidated unused credit multiplied by a fraction, the numerator of which is the credit earned of such member for the consolidated unused credit year, and the denominator of which is the consolidated credit earned for such unused credit year.

(ii) *Investment credit carryover.* In the case of a consolidated unused credit which is an investment credit carryover, the portion of such consolidated unused credit attributable to a member of the group is an amount equal to such consolidated unused credit multiplied by a fraction, the numerator of which is the

credit earned with respect to any section 38 property placed in service in the consolidated unused credit year and owned by such member (whether or not placed in service by such member) at the close of the last day as of which the taxable income of such member is included in a consolidated return filed by the group, and the denominator of which is the consolidated credit earned for such unused credit year.

(d) *Carryover and carryback of consolidated unused foreign tax*—(1) *In general.* If a consolidated unused foreign tax can be carried under the principles of section 904(d) and paragraph (e) of § 1.1502-4 to a separate return year of a corporation (or could have been so carried if such corporation were in existence) which was a member of the group in the year in which such unused foreign tax arose, then the portion of such consolidated unused foreign tax attributable to such corporation (as determined under subparagraph (2) of this paragraph) shall be apportioned to such corporation (and any successor to such corporation in a transaction to which section 381(a) applies) under the principles of paragraph (a) (1) and (2) of this section and shall be deemed paid or accrued in such separate return year to the extent provided in section 904(d).

(2) *Portion of consolidated unused foreign tax attributable to a member.* The portion of a consolidated unused foreign tax for any year attributable to a member of a group is an amount equal to such consolidated unused foreign tax multiplied by a fraction, the numerator of which is the foreign taxes paid or accrued for such year (including those taxes deemed paid or accrued, other than by reason of section 904(d)) to each foreign country or possession (or to all foreign countries or possessions if the overall limitation is effective) by such member, and the denominator of which is the aggregate of all such taxes paid or accrued for such year (including those taxes deemed paid or accrued, other than by reason of section 904(d)) to each such foreign country or possession (or to all foreign countries or possessions if the overall limitation is effective) by all the members of the group.

(e) *Carryover of consolidated excess charitable contributions to separate return years*—(1) *In general.* If the consolidated excess charitable contributions for any taxable year can be carried under the principles of section 170(b) (2) and paragraph (b) of § 1.1502-24 to a separate return year of a corporation (or could have been so carried if such corporation were in existence) which was a member of the group in the year in which such excess contributions arose, then the portion of such consolidated excess charitable contributions attributable to such corporation (as determined under subparagraph (2) of this paragraph) shall be apportioned to such corporation (and any successor to such corporation in a transaction to which section 381(a) applies) under the principles of paragraph (a) (1) and (2) of this section and shall be deemed paid or accrued in such separate return year to the extent provided in section 904(d).

(2) *Portion of consolidated excess charitable contributions attributable to a member.* The portion of the consolidated excess charitable contributions attributable to a member of a group is an amount equal to such consolidated excess contributions multiplied by a fraction, the numerator of which is the charitable contributions paid by such member for the taxable year, and the denominator of which is the aggregate of all such charitable contributions paid for such year by all the members of the group.

(f) *Intercompany transactions*—(1) *Intercompany transactions other than deferred intercompany transactions.* In certain cases a member of the group must take into account in a separate return year an item of income or a deduction which it otherwise would have taken into account in earlier consolidated return years. See paragraph (b) (2) of § 1.1502-13.

(2) *Deferred intercompany transactions.* See paragraphs (d), (e), and (f) of § 1.1502-13 for rules with respect to restoration of deferred gains and losses in separate return years.

§ 1.1502-80 Applicability of other provisions of law.

The Code, or other law, shall be applicable to the group to the extent the regulations do not exclude its application. Thus, for example, in a transaction to which section 381(a) applies, the acquiring corporation will succeed to the tax attributes described in section 381(c). Furthermore, sections 269, 304, and 482 apply for any consolidated return year.

REGULATIONS APPLICABLE TO TAXABLE YEARS PRIOR TO JANUARY 1, 1966

§ 1.1502-0A Introductory.

The regulations prescribed under section 1502 of the Internal Revenue Code of 1954 are applicable in the case of all corporations (with certain statutory exceptions) to taxable years beginning after December 31, 1953, and ending after August 16, 1954, and with respect to such taxable years, the regulations under section 1502 supersede 26 CFR (1939) part 24 (Regulations 129). Any provision of the regulations under such section, the applicability of which is stated in terms of a specific date (occurring after December 31, 1953) or in terms of taxable years ending after a specific date (occurring after December 31, 1953), shall apply to taxable years ending after such specific date. Each such provision shall in the case of a taxable year subject to 26 CFR (1939) part 24 (Regulations 129), be deemed included in 26 CFR (1939) part 24 (Regulations 129) but shall be applicable only to taxable

years ending after such specific date. The provisions of 26 CFR (1939) part 24 (Regulations 129), superseded by provisions of the regulations under section 1502, the applicability of which is stated in terms of a specific date (occurring after December 31, 1953) shall be deemed to be included in the regulations under such section but shall be applicable only to the period prior to the taking effect of the corresponding provision of the regulations under such section.

§ 1.1502-1A Privilege of making consolidated returns.

(a) Section 1501 gives to the corporations of an affiliated group the privilege of making a consolidated income tax return for the taxable year in lieu of separate returns. This privilege is given, however, upon the condition that all corporations which have been members of the affiliated group at any time during the taxable year for which the return is made consent to the regulations under section 1502 applicable to such taxable year and any amendments thereof duly prescribed prior to the last day prescribed by law for the filing of the return; and the making of the consolidated return is considered as such consent.

(b) With respect to a taxable year to which 26 CFR (1939) Part 24 (Regulations 129), as amended by the regulations under section 1502 is applicable, the regulations to which consent is made are those in 26 CFR (1939) Part 24 (Regulations 129), as amended, and as further amended by the regulations under such section. With respect to a taxable year to which the regulations under section 1502 are applicable, the regulations to which consent is made are the regulations under such section as changed to the extent that portions of 26 CFR (1939) Part 24 (Regulations 129) are applicable. For example, in the case of a fiscal year ending October 31, 1954, the Internal Revenue Code of 1939 and 26 CFR (1939) Part 24 (Regulations 129) are applicable to a consolidated return filed for such year. In such case, if the first distribution in pursuance of a plan of complete liquidation of a member of the affiliated group occurs on or after June 22, 1954, § 1.1502-38A is applicable in lieu of 26 CFR (1939) 24.38 (Regulations 129). On the other hand, if such a distribution occurs before June 22, 1954, 26 CFR (1939) 24.38 (Regulations 129) is applicable. Similarly, in the case of a return filed for the calendar year 1954, the Internal Revenue Code of 1954 and the regulations under section 1502 are applicable. In such case, if the first distribution in pursuance of a plan of complete liquidation of a member of the affiliated group occurs prior to June 22, 1954, 26 CFR (1939) 24.38 (Regulations 129) is applicable in lieu of § 1.1502-38A. If such distribution occurs on or after June 22, 1954, § 1.1502-38A is applicable.

(c) The last day prescribed by law for the filing of the return includes the

last day of the period of any extension of time granted by the Commissioner.

(d) The tax liability of the members of the affiliated group for the taxable year involved will be determined in accordance with the provisions of the regulations to which consent is given and without regard to any changes of the rules therein prescribed made subsequent to the last day prescribed by law for the filing of the return for such year.

§ 1.1502-2A Definitions.

(a) *Code*. The term "Code" means the Internal Revenue Code of 1954 and the sections of statutory law referred to in the regulations under section 1502 unless otherwise stated, are sections of that Code.

(b) *Affiliated group*. (1) The term "affiliated group" is defined in section 1504 and includes the common parent corporation and every other corporation for the period during which such corporation is a member of the affiliated group within the meaning of such section. It does not include any corporation which is not an "includible corporation" as defined by section 1504(b). An includible corporation is defined by such section to mean any corporation, except—

(i) A corporation exempt under section 501 from the taxes imposed by subtitle A;

(ii) An insurance company subject to taxation under section 802 or 821 (except as provided in section 1504(c));

(iii) A foreign corporation (except as provided in section 1504(d));

(iv) A corporation entitled to the benefits of section 931 by reason of receiving a large percentage of its income from sources within possessions of the United States;

(v) A corporation organized under the China Trade Act of 1922 (15 U.S.C. ch. 4);

(vi) A regulated investment company or a real estate investment trust subject to tax under subchapter M, chapter 1 of the Code;

(vii) An unincorporated business enterprise subject to tax as a corporation under section 1361; and

(viii) For periods before September 24, 1959, an electing small business corporation as defined in section 1371(b).

The consolidated income tax return must include every includible corporation which, under the provisions of section 1504, is a member of the affiliated group. No corporation which is connected by stock ownership with an affiliated group of includible corporations through a non-includible corporation may be included in the consolidated return of such group. In no case may a consolidated return be filed by subsidiary corporations as an affiliated group unless the common parent corporation through which the subsidiaries are connected is a member of the group. For instance, there will not be recognized as an affiliated group two domestic industrial corporations, the common parent corporation of which is a regulated investment company subject to tax under part I, subchapter M, chapter 1 of the Code.

(2) An insurance company subject to tax under section 831 is an includible

corporation and may be included in an affiliated group, together with corporations other than insurance companies taxable under section 802 or 821. Insurance companies subject to tax under section 802 or 821 are not includible corporations under section 1504(b). Under section 1504(c), however, a domestic insurance company taxable under section 802 may be included in an affiliated group comprised solely of other domestic insurance companies taxable under section 802; it may not be included in an affiliated group with other corporations. An affiliated group of domestic insurance companies taxable under section 802 may not include a domestic insurance company taxable under section 821 or 831.

(3) In the case of a domestic corporation owning or controlling, directly or indirectly, 100 percent of the capital stock (exclusive of directors' qualifying shares) of a corporation organized under the laws of Canada or of Mexico and maintained solely for the purpose of complying with the laws of such country as to title and operation of property, such foreign corporation may, at the option of the domestic corporation, be treated for income tax purposes as a domestic corporation. The option to treat such foreign corporation as a domestic corporation so that it may be included in a consolidated return must be exercised at the time of making the consolidated return, and cannot be exercised at any time thereafter. If the election is exercised to treat such foreign corporation as a domestic corporation, it must be included in the consolidated return of the affiliated group of which it is a member for each consecutive year thereafter for which such group makes or is required to make a consolidated return.

(4) An affiliated group of corporations, within the meaning of section 1504, is formed at the time that the common parent corporation, which is an includible corporation, becomes the owner directly of stock possessing at least 80 percent of the voting power of all classes of stock and at least 80 percent of each class of nonvoting stock (not including nonvoting stock which is limited and preferred as to dividends) of another includible corporation; a corporation becomes a member of such an affiliated group at the time that one or more members of such group become the owners directly of stock possessing at least 80 percent of the voting power of all classes of its stock and at least 80 percent of each class of its nonvoting stock (not including nonvoting stock which is limited and preferred as to dividends); and a corporation ceases to be a member of such an affiliated group at the time that the members of such group cease to own directly stock possessing at least 80 percent of the voting power of all classes of its stock, or at least 80 percent of each class of its nonvoting stock (not including nonvoting stock which is limited and preferred as to dividends).

(c) *Consolidated return period*. The term "consolidated return period" means the taxable year 1929, or any subsequent taxable year, for which a consolidated

return is made or is required, income tax return, excess profits tax return, or both, including the period during which a subsidiary corporation is engaged in distributing its assets in liquidation.

(d) *Subsidiary*. The term "subsidiary" means a corporation (other than the common parent corporation) which is a member of the affiliated group during any part of the consolidated return period.

(e) *Tax*. The term "tax" means any tax imposed by chapter 1 of the Code, and includes any interest, penalty, additional amount, or addition to the tax, payable in respect thereof.

(f) *Terms defined in Internal Revenue Code*. Terms which are defined in the Code shall, when used in the regulations under section 1502 have the meaning assigned to them by the Code, unless specifically otherwise defined.

(g) *Regulated public utility*. (1) The term "regulated public utility" means a corporation described in section 1503 (c). It includes a corporation (i) whose operations are an integral part of the furnishing or sale of a product or service described in such section by an interconnected and coordinated public utility system or systems and (ii) whose rates for furnishing products or services to the system or systems are established or approved by a regulatory body described in section 1503 (c) (1). For the purpose of determining whether or not 80 percent of the gross income of the corporation is from the furnishing or sale of such product or service, income received in consideration for the product or service described shall include only income received directly therefrom and income from the furnishing or sale of byproducts and residual products which are directly necessary and incidental to the furnishing of such product or service. In determining under subdivision (i) of this subparagraph whether the operations of a particular corporation constitute an integral part of the "furnishing or sale" of a product or service described in section 1503 (c), the income of a corporation shall be deemed to be from such source only to the extent that it is in consideration for necessary processing of either the product described in section 1503 (c) or the essential facilities used in making available to customers such product or service.

§ 1.1502-3A Applicability of other provisions of law.

Any matter in the determination of which the provisions of the regulations under section 1502 are not applicable shall be determined in accordance with the provisions of the Code or other law applicable thereto.

§§ 1.1502-4A to 1.1502-9A [Reserved]

§ 1.1502-10A Exercise of privilege.

(a) *When privilege must be exercised*. The privilege of making a consolidated return under section 1502 for any taxable year of an affiliated group must be exercised at the time of making the return of the common parent corporation for such year. For this purpose, the return is considered as made on the due

date of such return (including any extensions of time granted by the Commissioner), regardless of the actual previous date of filing. Under no circumstances can such privilege be exercised at any time thereafter. The filing of separate returns for a taxable year does not constitute an election binding upon the corporation in subsequent years. If the privilege is exercised at the time of making the return, separate returns cannot thereafter be made for such year. (See, however, § 1.1502-18A, relating to failure to comply with the regulations under section 1502.)

(b) *Effect of tentative returns.* In no case will the privilege under paragraph (a) of this section be considered as exercised at the time of making a so-called "tentative return" (made, for example, in order to obtain an extension of time for making the return required by law). However, if any such tentative return is made upon the basis of a consolidated return or a separate return, the return required by law must be made upon the same basis, unless upon the making of the return required by law (either a separate return or a consolidated return, as the case may be) the payments theretofore made and to be made are adjusted in a manner satisfactory to the Commissioner.

(c) *Estimated tax.* (1) Except as provided in subparagraph (2) of this paragraph, the provisions of section 6016 (relating to declarations of estimated tax by corporations) and section 6154 (relating to payments of estimated tax by corporations) shall be applicable to the several members of an affiliated group in the same manner and to the same extent as in the case of corporations filing separate returns, whether or not such affiliated group files a consolidated return. The declaration of estimated tax shall be filed and payments shall be made to the district director for the internal revenue district prescribed for the filing of a separate income tax return in the case of each member of the group required to file a declaration of estimated tax. If a consolidated return is filed, the amounts of any payments made with respect to the consolidated return period shall be credited against the tax liability of the affiliated group with respect to the consolidated return period.

(2) If the affiliated group intends to file a consolidated return for the taxable year, the common parent corporation may file a declaration of estimated tax for the group. In such case, all of the several members of the affiliated group shall be treated for the purpose of applying the provisions of sections 6016 and 6154 as a single corporation. Where such a declaration is filed, each subsidiary shall notify the district director for the internal revenue district prescribed for the filing of a separate income tax return by such subsidiary that its estimate is included in the declaration made by the common parent corporation. If the affiliated group does not file a consolidated return for the year for which such a declaration is filed, the payments made with respect to such declaration shall be apportioned among the several members of the group in the manner designated by the common parent corporation for the purpose of determining any addition to the tax provided by section 6655.

(3) In any case in which an affiliated group has made payments with respect to a declaration made on a group basis and such group does not file a consolidated return for the taxable year, the payments made thereon shall be applied against the tax liability of the members of the group in a manner satisfactory to the Commissioner.

(4) See § 1.1502-15A (relating to liability for tax) and § 1.1502-49A (relating to additions to tax for failure to pay estimated tax).

§ 1.1502-11A Consolidated returns for subsequent years.

(a) *Consolidated returns required for subsequent years.* If a consolidated return is made under section 1502 for any taxable year, a consolidated return must be made for each subsequent taxable year during which the affiliated group remains in existence unless (1) a corporation (other than a corporation created or organized, directly or indirectly, by a member of the group) has become a member of the group during such subsequent taxable year, or (2) subsequent to the exercise of the election to make consolidated returns, subtitle A of the Code to the extent applicable to corporations, or the regulations under section 1502 which have been consented to, have been amended and any such amendment is of a character which makes substantially less advantageous to affiliated groups as a class the continued filing of consolidated returns, regardless of the effective date of such amendment, or (3) the Commissioner, prior to the time of making the return, upon application made by the common parent corporation and for good cause shown, grants permission to change. For the purpose of subparagraph (2) of this paragraph, the expiration of a provision shall be considered as an amendment to the Code made on the date of such expiration.

(b) *Effect of separate returns when consolidated return is required.* If the making of a consolidated return is required for any taxable year, the tax liability of the members of the affiliated group shall be computed in the same manner as if a consolidated return had been made, even though separate returns are made; amounts assessed upon the basis of separate returns shall be considered as having been assessed upon the basis of a consolidated return; and amounts paid upon the basis of separate returns shall be considered as having been paid by the common parent corporation. In such cases the making of separate returns shall not be considered as the making of a return for the purpose of computing any period of limitation or any deficiency. If a consolidated return for such taxable year is thereafter made, such return shall, for the purpose of computing periods of limitation and any deficiency, be considered as the return for such year.

(c) *When affiliated group remains in existence.* For the purpose of the regulations under section 1502, an affiliated group shall be considered as remaining

in existence if the common parent corporation remains as a common parent and at least one subsidiary remains affiliated with it, whether or not such subsidiary was a member of the group at the time the group was formed and whether or not one or more corporations have become subsidiaries or have ceased to be subsidiaries at any time after the group was formed.

(d) *When affiliated group terminates.* For the purpose of the regulations under section 1502, an affiliated group shall be considered as terminated if the common parent corporation ceases to be the common parent or if there is no subsidiary affiliated with it.

§ 1.1502-12A Making consolidated return and filing other forms.

(a) *Consolidated return made by common parent corporation.* A consolidated return shall be made on Form 1120 by the common parent corporation for the affiliated group. Such return shall be filed at the time and in the office of the district director for the internal revenue district prescribed for the filing of a separate return by such common parent corporation.

(b) *Authorizations and consents.* Each subsidiary must prepare duplicate originals of Form 1122, consenting to the regulations under section 1502 and authorizing the common parent corporation to make a consolidated return on its behalf for the taxable year and authorizing the common parent (or, in the event of its failure, the Commissioner or the district director) to make a consolidated return on its behalf (as long as it remains a member of the affiliated group), for each year thereafter for which, under paragraph (a) of § 1.1502-11A, the making of a consolidated return is required. One of such forms, as prepared by each subsidiary shall be attached to the consolidated return, as a part thereof; and the other shall be filed, at or before the time the consolidated return is filed, in the office of the district director for the internal revenue district prescribed for the filing of a separate return by such subsidiary. No such consent can be withdrawn or revoked at any time after the consolidated return is filed.

(c) *Affiliations schedule filed by common parent corporation.* The common parent corporation shall prepare Form 351 (Affiliations Schedule), which shall be attached to and made a part of the consolidated return.

(d) *Persons qualified to execute returns and forms.* Each return or form required to be made or prepared by a corporation must be executed by the person authorized under section 6062 to execute returns of separate corporations. In cases where receivers or trustees in bankruptcy are operating the property or business of corporations, each return or form required to be made or prepared by such corporation must be executed by the receiver or trustee, as the case may be, pursuant to an order or instructions of the court, and be accompanied by a copy of such order or instructions.

(e) *Signatures in case subsidiary has left affiliated group.* Since Form 1122 is required even though, during the tax-

able year of the common parent corporation, the subsidiary (because of a dissolution or sale of stock, or otherwise) has ceased to be a member of the affiliated group, it may be advisable for the common parent to obtain the proper signatures to the form prior to the time the subsidiary ceases to be a member of the group.

§ 1.1502-13A Change in affiliated group during taxable year.

(a) *General rule.* Except as herein-after provided, a consolidated return must include the income of the common parent corporation and of each subsidiary for the entire taxable year of the affiliated group.

(b) *Formation of affiliated group after beginning of year.* If an affiliated group is formed after the beginning of the taxable year of the corporation which becomes the common parent corporation, the consolidated return must include the income of the common parent for its entire taxable year (excluding any portion of such year during which its income is included in the consolidated return of another affiliated group) and the income of each subsidiary from the time it became a member of the affiliated group.

(c) *Complete termination of affiliated group prior to close of taxable year.* If an affiliated group is terminated prior to the close of the taxable year of the group, the consolidated return must include the income of the common parent corporation for its entire taxable year (excluding any portion of such year during which its income is included in the consolidated return of another affiliated group) and of each subsidiary for the period prior to the termination. (See paragraphs (c) and (d) of § 1.1502-11A in determining whether the group has terminated.)

(d) *Addition to affiliated group of a subsidiary during year.* If a corporation becomes a member of the affiliated group during the taxable year of the group, the consolidated return must include its income from the time when it became a member of the group.

(e) *Elimination from affiliated group of a subsidiary during year.* If a subsidiary ceases to be a member of the affiliated group during the taxable year of the group, the consolidated return must include its income for the period during which it was a member of the group.

(f) *Period of 30 days or less may be disregarded.* A subsidiary may at its option be considered as having been a member of the affiliated group during the entire taxable year of the group (or during the entire period of the existence of the subsidiary, whichever is shorter) if the period during which it was not a member of such group does not exceed 30 days. If a corporation has been a member of the affiliated group for a period of less than 31 days during the taxable year of the group, it may at its option be considered as not having been

a member of the group during the taxable year. An option under this paragraph must be exercised at the time the consolidated return is made.

(g) *Separate returns for periods not included in consolidated return.* If a corporation, during its taxable year (determined without regard to the affiliation), becomes a member of an affiliated group, its income for the portion of such taxable year not included in the consolidated return of such group must be included in a separate return (or, if a member of another affiliated group which makes a consolidated return for such period, then in such consolidated return). If a corporation ceases to be a member of the affiliated group during the taxable year of the group, its income for the period after the time when it ceased to be a member of the group must be included in a separate return (or, if it becomes a member of another affiliated group which makes a consolidated return for such period, then in such consolidated return).

(h) *Time for making separate returns for periods not included in consolidated return.* (1) (i) If the due date for filing a subsidiary's separate return (determined without regard to the affiliation and without regard to extensions of time) precedes the due date for filing the consolidated return of the affiliated group (determined without regard to extensions of time), then, on or before the due date of the subsidiary's separate return, it may make a separate return either for that portion of its taxable year which would not be included in the consolidated return, if such return is filed, or for its complete taxable year. However, if a separate return is filed for only a portion of its taxable year and the group does not elect to make a consolidated return, such subsidiary shall file a return for its complete taxable year not later than the due date (including extensions of time) prescribed for the filing of the consolidated return by the group. There shall be attached to the return for the complete taxable year a statement setting forth that such return is in lieu of the return previously filed. In such case the return previously filed for only a portion of its taxable year shall not be considered a return within the meaning of section 6012. On the other hand, if a return is filed for the subsidiary's complete taxable year and the group later makes a consolidated return, such subsidiary should file an amended return not later than the due date (including extensions of time) for the filing of the consolidated return of the group. Such amended return shall be for that portion of the taxable year which is not included in the consolidated return.

(ii) If the due date for filing a subsidiary's separate return (determined without regard to the affiliation and without regard to extensions of time) is later than the due date for filing the consolidated return of the affiliated group (determined without regard to extensions of time), then the separate return for that portion of the subsidiary's taxable year which is not included in the consolidated return of the group

should be filed no later than the due date (including extensions of time) for the filing of the consolidated return.

(2) The provisions of this paragraph may be illustrated by the following examples:

Example (1). Corporation P, which reports its income on a calendar year basis, acquires all of the stock of Corporation S on January 1, 1959. Corporation S reports its income on a fiscal year ending March 31. On June 15, 1959, the due date for the filing of a separate return by Corporation S, it is anticipated that Corporation P will elect, on the due date of its return, to file a consolidated return for 1959. On June 15, Corporation S may file either a return for a short taxable year beginning April 1, 1958, and ending December 31, 1958, or it may file a return for the complete fiscal year ending March 31, 1959. If it files a return for the short taxable year and Corporation P does not elect to file a consolidated return, Corporation S must file a return for the complete fiscal year ending March 31, 1959, in lieu of the return previously filed for the short period. Interest is computed on any additional tax from June 15, 1959.

Example (2). Assume the same facts as in example (1), except that Corporation P acquires all of the stock of Corporation S on October 1, 1959, and that Corporation P elects to file a consolidated return on March 15, 1960, the due date of its return. The return of Corporation S for the short taxable year beginning April 1, 1959, and ending September 30, 1959, should be filed on March 15, 1960.

§ 1.1502-14A Accounting period of an affiliated group.

(a) The taxable year of an affiliated group which makes a consolidated return shall be the same as the taxable year of the common parent corporation; and, except as provided in paragraph (c) of this section, upon having elected to file a consolidated return, each subsidiary corporation shall, not later than the close of the first consolidated taxable year ending thereafter, adopt an annual accounting period, fiscal year or calendar year as the case may be, in conformity with that of the common parent.

(b) If a change of accounting period is necessary in order to conform the accounting periods of the common parent and of its subsidiaries, Form 1128 shall be submitted at or before the time of filing the consolidated return for the taxable year in which the subsidiary has first adopted the parent corporation's annual accounting period.

(c) If the common parent corporation of an affiliated group has a fiscal year accounting period and any member of the group is an includible insurance company required by section 843 to file its return on a calendar year, the first consolidated return which includes such insurance company may be filed on the basis of the fiscal year accounting period of the common parent, provided, however, the common parent and the other includible corporations change to a calendar year basis effective immediately after the close of such fiscal year. For this purpose, Form 1128 shall be submitted at or before the time such first consolidated return is filed.

(d) With respect to computations for years involved in the change to the consolidated basis, see § 1.1502-32A.

¹This section has no bearing upon the question whether a consolidated return may or must be made, but relates only to the effect of changes in the affiliated group during the taxable year.

§ 1.1502-15A Liability for tax.

(a) *Several liability of members of affiliated group.* Except as provided in paragraphs (b) and (c) of this section, the common parent corporation and each subsidiary, a member of the affiliated group during any part of a consolidated return period, shall be severally liable for the tax (including any deficiency in respect thereof) computed as provided in § 1.1502-30A, and for any addition to the tax computed as provided in § 1.1502-49A for underpayment of estimated tax for the consolidated return period.

(b) *Liability of a corporation in bankruptcy or receivership.* If, at the time of filing a consolidated return, one or more, but not all, of the members of the affiliated group are in bankruptcy under the laws of the United States or in receivership in any court of the United States or of any State, Territory, or the District of Columbia, then the liability under paragraph (a) of this section of each such member of the group with respect to the period covered by such return shall not exceed such portion of the consolidated tax liability for such period as the several corporations included in the consolidated return may, subject to the approval of the Commissioner, agree upon, or, in the absence of such an agreement, an amount equal to its liability for such year computed as if a separate return had been filed.

(c) *Liability of subsidiary after withdrawal.* If a subsidiary has ceased to be a member of the affiliated group, its liability under paragraph (a) of this section shall remain unchanged, except that if such cessation occurred prior to the date upon which any deficiency is assessed and resulted from a bona fide sale of stock for fair value, the Commissioner may, if he believes that the assessment or collection of the balance of the deficiency will not be jeopardized, make assessment and collection of such deficiency from such former subsidiary in an amount not exceeding the portion thereof allocable to it upon the bases of income used in the computations, respectively, of the normal tax, the surtax, and any other tax imposed by chapter 1 of the Code included in such deficiency.

(d) *Effect of intercompany agreements.* Any agreement entered into by one or more members of the affiliated group with any other members of such group or with any other person shall in no case have the effect of reducing the liability prescribed under this section.

(e) *Liability of transferee not affected.* This section shall not be considered as extinguishing or diminishing any liability, at law or in equity, of a transferee of property of a taxpayer, including any liability under any provision of law, State or Federal, relating to liabilities pursuant to corporate dissolution or transfer or distribution of assets, whether or not in connection with a merger or consolidation.

§ 1.1502-16A Common parent corporation agent for subsidiaries.

(a) *Scope of agency of common parent corporation.* Except as provided in paragraphs (b) and (c) of this section, the

common parent corporation shall be for all purposes (other than the making of the subsidiary consent required by paragraph (b) of § 1.1502-12A) in respect of the tax for the taxable year for which a consolidated return is made or is required, the sole agent, duly authorized to act in its own name in all matters relating to such tax, for each corporation which during any part of such year was a member of the affiliated group. The corporations, other than the common parent, shall not have authority to act for or to represent themselves in any such matter. For example, all correspondence will be carried on directly with the common parent; notices of deficiencies will be mailed only to the common parent, and the mailing to the common parent shall be considered as a mailing to each such corporation; notice and demand for payment of taxes will be given only to the common parent, and such notice and demand shall be considered as a notice and demand to each such corporation; the common parent will file petitions and conduct proceedings before the Tax Court of the United States, and any such petition shall be considered as having also been filed by each such corporation; the common parent will file claims for refund or credit; refunds will be made directly to and in the name of the common parent and will discharge any liability of the Government in respect thereof to any such corporation; and the common parent in its name will give waivers, give bonds, and execute closing agreements, offers in compromise, and all other documents, and any waiver or bond so given, or agreement, offer in compromise, or any other document so executed, shall be considered as having also been given or executed by each such corporation. Notwithstanding the provisions of this paragraph, however, any notice of deficiency, in respect of the tax for a consolidated return period, will name each corporation which was a member of the affiliated group during any part of such period, and any assessment (whether of the original tax or of a deficiency) will be made in the name of each such corporation (but a failure to include the name of any such corporation will not affect the validity of the notice of deficiency or the assessment as to the other corporations); any notice and demand for payment will name each corporation which was a member of the affiliated group during any part of such period (but a failure to include the name of any such corporation will not affect the validity of the notice and demand as to the other corporations); and any levy (or warrant or notice in respect thereof), any notice of a lien, or any other proceeding to collect the amount of any assessment, after the assessment has been made, will name the corporation from which such collection is to be made. The provisions of this paragraph shall apply whether or not a consolidated return is made for any subsequent year, and whether or not one or more subsidiaries have become or have ceased to be members of the group at any time. Notwithstanding the provi-

sions of this paragraph, the Commissioner may, if he deems it advisable, deal directly with any member of the group in respect of its ability, in which event such member shall have full authority to act for itself.

(b) *Effect of withdrawal of subsidiary.* For the purpose of the assertion, assessment, and collection of any deficiency, and of a credit or refund of any amount paid by a former subsidiary as a deficiency determined under paragraph (c) of § 1.1502-15A, but for no other purpose, the agency of the common parent corporation in respect of any subsidiary which has ceased to be a member of the affiliated group shall be terminated upon the expiration of 30 days (or prior thereto if the Commissioner consents) from the date upon which such subsidiary files written notice with the Commissioner that it has ceased to be a member of the affiliated group and that it is terminating such agency. For example, if a subsidiary has ceased to be a member of the group (and if the 30-day period has expired) prior to the mailing of a notice of deficiency to the common parent, a separate notice of deficiency will be mailed in due course to the subsidiary in respect of its deficiency if it becomes necessary to enforce its liability.

(c) *Effect of dissolution of common parent corporation.* If the common parent corporation contemplates dissolution, or is about to be dissolved, or if for any other reason its existence is about to terminate, it shall forthwith notify the Commissioner of such fact and designate, subject to the approval of the Commissioner, another member of the affiliated group to act as agent in its place to the same extent and subject to the same conditions and limitations as are applicable to the common parent. If the notice thus required is not given by the common parent, the remaining members of the group may, subject to the approval of the Commissioner, designate another member of the group to act as such agent, and notice of such designation shall be given to the Commissioner. Until a notice in writing designating a new agent has been received by the Commissioner, any notice of deficiency or other communication mailed to the common parent shall be considered as having been properly mailed to the agent of the group; or, if the Commissioner has reason to believe that the existence of the common parent has terminated, he may, if he deems it advisable, deal directly with any member of the group in respect of its liability.

§ 1.1502-17A Waivers.

(a) *Effect of waiver given by common parent corporation.* Any consent given by the common parent corporation (or by an agent in accordance with paragraph (c) of § 1.1502-16A) extending the time within which an assessment may be made or levy or proceeding in court begun, in respect of the tax for a consolidated return period, shall be applicable (1) to each corporation which was a member of the affiliated group during any part of such period (whether or not any such corporation has ceased to be a member of the group), and (2)

to each corporation the income of which was included in the consolidated return, or which filed Form 1122, for such period, even though it is subsequently determined that such corporation was not a member of the group.

(b) *Acceptance of waivers from common parent corporation and alleged subsidiary.* In no case will a separate waiver be accepted from a corporation the income of which was included in the consolidated return (for example, a corporation which the Commissioner determines was not a member of the affiliated group), or which filed Form 1122, unless a waiver is also obtained from the common parent, or unless the Commissioner is dealing directly with such corporation to enforce its liability.

§ 1.1502-18A Failure to comply with regulations.

(a) *Exclusion of a subsidiary from consolidated return.* If there has been a failure to include in the consolidated return the income of any subsidiary, or a failure to file any of the forms required by these regulations, notice thereof shall be given the common parent corporation by the Commissioner, and the tax liability of each member of the affiliated group shall be determined on the basis of separate returns unless such income is included or such forms are filed within the period prescribed in such notice, or any extension thereof, or unless under § 1.1502-11A a consolidated return is required for such year.

(b) *Common parent corporation incorrectly designated in consolidated return.* If a consolidated return includes a corporation as the common parent and such corporation was not (under the provisions of section 1502), the common parent, the tax liability of each corporation included in the return will be computed in the same manner as if separate returns had been made, unless, upon application, the Commissioner approves the making of a consolidated return, or unless under § 1.1502-11A a consolidated return is required for such year.

(c) *Inclusion of one or more subsidiaries not members of affiliated group.* If a consolidated return includes a corporation as a subsidiary and such corporation was not a member of the affiliated group during the consolidated return period, the tax liability of such corporation will be determined upon the basis of a separate return (but see paragraph (a) of this section), and the consolidated return shall be considered as including only the corporations which were members of the group during such period. If the consolidated return includes two or more corporations which are not members of the group but which constitute a separate affiliated group, the tax liability of the corporations constituting the separate group will be computed in the same manner as if separate returns had been made by such corporations, unless the Commissioner, upon application, approves the making of a consolidated return for the separate group, or unless under § 1.1502-11A a consolidated return is required for the separate group.

(d) *Effect of authorization and consent filed pursuant to notice.* If Form

1122 is filed by any corporation, pursuant to a notice under paragraph (a) of this section, such corporation shall be considered for all purposes as having joined in the making of the consolidated return.

(e) *Allocation of payments in the event of change by one or more corporations to separate returns.* In any case in which amounts have been assessed and paid upon the basis of a consolidated return and the tax liability of one or more of the corporations included in the consolidated return is to be computed in the same manner as if separate returns had been made, the amounts so paid shall be allocated between the affiliated group composed of the corporations properly included in the consolidated return and each of the corporations the tax liability of which is to be computed on a separate basis, in such manner as the corporations included in the consolidated return may, subject to the approval of the Commissioner, agree upon, or, in the absence of an agreement, upon the bases used in the respective computations of the normal tax, the surtax and any other tax imposed by chapter 1 of the Code, as shown upon the consolidated return.

§ 1.1502-19A Tentative carryback adjustments.

(a) *Groups with constant membership; consolidated returns only.* In the case of an affiliated group the membership of which remains unchanged and for which consolidated returns are made or are required for the taxable years involved, any statement filed under section 6164 with respect to an expected carryback and any application for a tentative carryback adjustment filed under section 6411 shall be filed by the common parent corporation and shall disclose all material facts and circumstances relating to the group as a whole. Such statement or application shall be filed on the appropriate form prescribed for such purpose, Form 1138 or Form 1139, as the case may be. Any refunds allowable under any such application will be made directly to and in the name of the common parent. The making of any such refund will discharge any liability of the Government in respect thereof to the several affiliated corporations. The common parent corporation and its several subsidiaries shall be severally liable for any amounts assessed pursuant to section 6213(b)(2), together with any interest or penalty assessed in connection therewith.

(b) *Groups with changing membership; cases involving a separate return period.* (1) The membership of an affiliated group may change during a taxable year for which a net operating loss arises, or in the preceding taxable year affected by such net loss. Or an affiliated group making a consolidated return for the year of such net loss may have made separate returns for the preceding year; or a group making separate returns for the year of the net loss may have made a consolidated return for the preceding year. In any such case, the statement provided for in section 6164 and the application for the tentative carryback adjustment provided for in

section 6411 shall be a joint statement or application concurred in and executed by each corporation which was a member of the group at any time during either of the taxable years involved in the deferment or adjustment sought. The time for the payment of taxes shall be extended under section 6164 and the adjustment provided for in section 6411 shall be made only in accordance with an agreement of the several corporations involved to be made a part of such statement or application. Any refund allowable under any such application with respect to a consolidated return period will be made directly to and in the name of the common parent corporation, and the making of any such refund will discharge any liability of the Government in respect thereof to the several affiliated corporations. The common parent corporation and its several subsidiaries shall be severally liable for any amounts assessed pursuant to section 6213(b)(2), together with any interest or penalty assessed in connection therewith.

(2) In the absence of an agreement between the several corporations, or in the event of their failure to set forth the provisions of such an agreement as a part of their statement or application, no extension of time for the payment of any tax under the provisions of section 6164 shall be granted, and no tentative adjustment shall be made under section 6411.

(3) Notwithstanding any agreement between the several affiliated corporations, no tentative adjustment shall be made with respect to either a consolidated or a separate return period in disregard of the several liability of the several corporations with respect to any taxable year for which a consolidated return was made or was required.

§§ 1.1502-20A to 1.1502-29A [Reserved]

§ 1.1502-30A Computation of tax.

(a) *General rule.* In the case of an affiliated group which makes, or is required to make, a consolidated return for any taxable year, the tax liability of each corporation for the period during such year that it was a member of such group shall be computed, subject to the provisions of paragraph (b) of this section, upon the consolidated taxable income and the consolidated taxable income plus the aggregate of the deductions of the several affiliated corporations allowable under section 242, or, in the case of the taxes imposed by section 531, section 541 (except as provided in paragraph (b) (4) of this section), and section 802, upon the consolidated accumulated taxable income, the consolidated undistributed personal holding company income, the consolidated life insurance company taxable income, the consolidated life insurance company taxable income plus the aggregate of the deductions of the several affiliated corporations allowable under section 242, or the consolidated 1954 life insurance company taxable income, as the case may be, determined in each case in accordance with the regulations under section 1502. In the case of an affiliated group realizing long-term capital gains and computing its tax

under the alternative tax provisions of section 1201, the tax shall be computed with reference to the consolidated taxable income, and the excess of the consolidated net long-term capital gain over the consolidated net short-term capital loss. The tax imposed under section 11 (c) or section 831 shall be increased for any taxable year for which an affiliated group makes or is required to make a consolidated return by 2 percent of the consolidated taxable income (computed without regard to the deduction, if any, provided in section 242 for partially tax-exempt interest).

(b) *Special rules.* The general rule prescribed in paragraph (a) of this section is subject to the following special rules:

(1) *In the case of Western Hemisphere trade corporations and regulated public utilities.* If the affiliated group filing a consolidated return includes a Western Hemisphere trade corporation, as defined in section 921, or a regulated public utility, as defined in section 1503 and paragraph (g) of § 1.1502-2A, the increase of 2 percent provided in section 1503(a) in the corporation surtax rate shall be applied only on that portion of the consolidated taxable income attributable to the members of the group other than the Western Hemisphere trade corporation or the regulated public utility without any increase with respect to any partially tax-exempt interest of such Western Hemisphere trade corporation or such regulated public utility.

(2) *In case of mutual savings banks conducting life insurance business.* If the parent corporation of an affiliated group is a mutual savings bank which, if a separate return were filed, would be subject to the alternative tax of section 594 (a) (relating to a mutual savings bank conducting a life insurance business), the provisions of section 594 (a) shall apply to such group and the alternative tax of such group under section 594 (a) shall be computed with reference to the consolidated taxable income of the group attributable to such parent corporation determined without regard to any items of gross income or deductions properly allocable to the business of the life insurance department, and with reference to the income of such life insurance department determined under the provisions of section 594 (a) (2) and paragraph (b) of § 1.1502-31A.

(3) *Changes in methods of accounting.* In any case in which a member of the affiliated group changes its method of accounting, if the year of the change is a year for which a consolidated return is filed (or is required to be filed), and if the requirements of section 481 (b) are met, then the tax under chapter 1 of the Code attributable to the increase in consolidated taxable income required by paragraph (c) of § 1.1502-44A shall not be greater than the tax under chapter 1 (or the corresponding provisions of prior law) which would result if the provisions of section 481(b) were applied to the corporation required to make the change in accounting method, but with the taxes for any year determined on the basis of the regulations under section 1502 (or prior con-

solidated returns regulations) if the income of such corporation was included in a consolidated return for such year, or on the basis of a separate return, if the income of such corporation was reported in a separate return for such year.

(4) *Personal holding companies.* In the case of an affiliated group which makes or is required to make a consolidated return for any taxable year, the tax liability of each corporation for the period during such year that it was a member of such group shall not be computed in the case of the tax imposed by section 541 upon the consolidated undistributed personal holding company income if:

(i) The affiliated group is an ineligible affiliated group as defined in section 542 (b) (2),

(ii) The affiliated group includes as a member (including the common parent corporation) an excluded corporation within the meaning of section 542 (c),

(iii) The consolidated personal holding company income is less than 80 percent of the consolidated section 542 gross income, or

(iv) At no time during the last half of the taxable year more than 50 percent in value of the outstanding stock of the parent corporation was owned directly or indirectly by or for not more than 5 individuals within the meaning of section 542 (a) (2).

If the tax liability of each corporation under section 541 is not computed upon the consolidated undistributed personal holding company income solely by reason of the application of subdivision (iii) or (iv) of this subparagraph (or both), no member of the affiliated group shall be subject to the tax under section 541 for such year or part thereof that it was a member of the affiliated group. If the tax liability of each corporation under section 541 is not computed upon the consolidated undistributed personal holding company income by reason of the application of subdivision (i) or (ii) of this subparagraph (whether or not subdivision (iii) or (iv) of this subparagraph, or both, are applicable), then such liability shall be computed by reference to the tax liability of the several members of the affiliated group which are personal holding companies within the meaning of section 542(a) in the same manner as if such corporations had filed separate returns except that paragraph (b) (1) (i) of § 1.1502-31A shall be applicable (except with respect to dividends received from other members of the group) in the computation of gross income, personal holding company income, and undistributed personal holding company income, and section 562(d) shall be applicable in the computation of dividends paid.

§ 1.1502-31A Basis of tax computation.

In the case of an affiliated group of corporations which makes, or is required to make a consolidated return for any taxable year, and except as otherwise provided in the regulations under section 1502, the tax liability determined under § 1.1502-30A shall be determined subject to the definitions and rules of computa-

tion set forth in paragraphs (a) and (b) of this section.

(a) *Definitions.* (1) *Consolidated taxable income.* The consolidated taxable income shall be the combined taxable income of the several affiliated corporations:

(i) Minus the sum of:

(a) Any consolidated net operating loss deduction,

(b) Any consolidated section 1231 net loss, relating to net losses from involuntary conversions subject to section 1231, and from sales or exchanges of property subject to section 1231.

(c) Any consolidated charitable contribution deduction, but not in excess of 5 percent of the consolidated taxable income computed without regard to such consolidated charitable contribution deduction, any deductions under part VIII (section 241 and following, except section 248), subchapter B, chapter 1 of the Code, any consolidated net operating loss carrybacks, and any deduction under section 922 (special deduction for Western Hemisphere trade corporations),

(d) Any consolidated dividends received deduction,

(e) Any consolidated section 922 deduction,

(f) Any consolidated section 175 deduction, but not in excess of 25 percent of the consolidated section 175 gross income,

(g) Any consolidated section 247 deduction,

(h) Any consolidated section 582(c) net loss, and

(i) [Reserved]

(j) Any consolidated section 181 deduction,

(ii) Plus any consolidated net capital gain, or

(iii) Minus, in the case of an affiliated group including as members one or more corporations subject to the tax imposed by section 831, the combined additional capital loss deductions of such corporations authorized by section 832 (c) (5) (but in an amount not in excess of the consolidated net capital loss).

(2) *Consolidated net operating loss deduction.* The consolidated net operating loss deduction shall be an amount equal to the aggregate of the consolidated net operating loss carryovers and of the consolidated net operating loss carrybacks to the taxable year.

(3) *Consolidated net operating loss carryovers.* (i) The consolidated net operating loss carryovers to the taxable year shall consist of—

(a) The consolidated net operating losses, if any, for the five preceding taxable years (and the consolidated net operating losses, if any, for the sixth and seventh preceding taxable years (not including as a sixth or seventh) preceding taxable year any taxable year ending on or before December 31, 1955) to the extent attributable to members of the affiliated group which are, and were in the taxable year in which the loss originated, regulated transportation corporations as defined in section 172(j) (1)), but only to the extent that the consolidated net operating loss for any such preceding taxable year was not attributable to a corporation making a

separate return or joining in a consolidated return filed by another affiliated group for the taxable year and was not absorbed as a carryover or carryback for preceding or intervening taxable years,

and, with respect to a net operating loss sustained by a corporation in a taxable year for which a separate return was filed, or for which such corporation joined in a consolidated return filed by another affiliated group, but subject to the limitation prescribed in paragraph (b) (3) of this section.

(b) The amount of the net operating losses, if any, of such corporation for the five preceding taxable years (and the net operating losses, if any, for the sixth and seventh preceding taxable years (not including as a sixth or seventh preceding taxable year any taxable year ending on or before December 31, 1955) if such corporation is, and was in the taxable year in which the loss was sustained, a regulated transportation corporation as defined in section 172(j) (1)), to the extent that the net operating loss for any such preceding taxable year was not absorbed as a carryover or carryback for preceding or intervening taxable years.

(ii) For purposes of subdivision (i) of this subparagraph, there shall not be included as a fifth preceding taxable year any taxable year beginning prior to 1950, unless such preceding taxable year began in 1949 and ended in 1950, and unless all members of the group for such preceding taxable year (or the corporation filing a separate return or joining in a consolidated return filed by another affiliated group) commenced business in 1949; and in such case the amount of the consolidated net operating loss (or net operating loss) for such fifth year shall not be treated as a carryover except to the extent that such loss is allocable to 1950.

(iii) For purposes of this section, a net operating loss attributable to a regulated transportation corporation shall not be a net operating loss carryover to the sixth taxable year following the year in which the loss originated unless, for such sixth taxable year, the corporation to which the loss is attributable is a regulated transportation corporation; and shall not be a carryover to the seventh taxable year following the year in which the loss originated unless for both such sixth and seventh years the corporation to which the loss is attributable is such a regulated transportation corporation.

(iv) In the case of a net operating loss for a taxable year beginning in 1955 and ending in 1956, attributable to a regulated transportation corporation, the amount of such loss which may be carried to—

(a) The sixth taxable year following the loss year shall be the amount which bears the same ratio to the amount which would (without regard to the limitation prescribed in paragraph (b) (3) of this section for such sixth taxable year) be carried to such sixth taxable year as the number of days in the loss year after December 31, 1955, bears to the total number of days in the loss year, and

(b) The seventh taxable year following the loss year shall be the amount which bears the same ratio to the amount which would (without regard to the limitation prescribed in paragraph (b) (3) of this section for such seventh taxable year) be carried to such seventh taxable year as the number of days in the loss year after December 31, 1955, bears to the total number of days in the loss year.

The amounts determined under (a) and (b) of this subdivision shall be subject to the limitation prescribed in paragraph (b) (3) of this section.

(v) See paragraph (b) (21) of this section in any case in which a member of the group is an acquiring corporation in a transaction described in section 381(a) or any member of the group is subject to the limitations provided in section 382.

(4) *Consolidated net operating loss carrybacks.* (i) The consolidated net operating loss carrybacks to the taxable year with respect to net operating losses sustained in taxable years ending after December 31, 1957, shall consist of—

(a) The amount of the consolidated net operating loss, if any, for the first succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the taxable year) reduced to the extent absorbed as a carryback, consolidated or separate, as the case may be, for the first two preceding taxable years (and for the third and fourth preceding taxable years with respect to that portion of the consolidated net operating loss attributable to the net operating losses of members for which certifications have been issued under section 317 of the Trade Expansion Act of 1962 and with respect to which the requirements of section 172(b) (3) (A) have been met),

(b) The amount of the consolidated net operating loss, if any, for the second succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the taxable year) reduced to the extent absorbed as a carryback, consolidated or separate, as the case may be, for the first preceding taxable year (and for the second and third preceding taxable years with respect to that portion of the consolidated net operating loss attributable to the net operating losses of members for which certifications have been issued under section 317 of the Trade Expansion Act of 1962 and with respect to which the requirements of section 172(b) (3) (A) have been met),

(c) The amount of the consolidated net operating loss, if any, for the third succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group) reduced to the extent absorbed as a carryback, consolidated or separate, as the case may be, for the first two preceding taxable years with respect to that portion of the consolidated net operating loss attributable to the net operating losses of members for which certifications have been issued under section 317 of the Trade Expansion Act of 1962 and with respect to which the re-

quirements of section 172(b) (3) (A) have been met,

(d) That portion of the consolidated net operating loss for the fourth succeeding taxable year which is attributable to the net operating losses of members for which certifications have been issued under section 317 of the Trade Expansion Act of 1962 and with respect to which the requirements of section 172(b) (3) (A) have been met (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the taxable year), reduced to the extent absorbed as a carryback, consolidated or separate, as the case may be, for the first preceding taxable year,

(e) That portion of the consolidated net operating loss for the fifth succeeding taxable year which is attributable to the net operating losses of members for which certifications have been issued under section 317 of the Trade Expansion Act of 1962 and with respect to which the requirements of section 172(b) (3) (A) have been met (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the taxable year),

and, with respect to a net operating loss sustained by a corporation which, for any of the five succeeding taxable years, files a separate return or joins in a consolidated return filed by another affiliated group, but subject to the limitation prescribed in paragraph (b) (3) of this section,

(f) The amount of the net operating loss, if any, sustained by such corporation for the first succeeding taxable year, reduced to the extent absorbed in a separate return (or in a consolidated return) for the first two preceding taxable years (and for the third and fourth preceding taxable years if a certification of such loss has been issued under section 317 of the Trade Expansion Act of 1962, and the requirements of section 172(b) (3) (A) have been met),

(g) The amount of the net operating loss, if any, sustained by such corporation for the second succeeding taxable year, reduced to the extent absorbed in a separate return (or in a consolidated return) for the first preceding taxable year (and for the second and third preceding taxable years if a certification of such loss has been issued under section 317 of the Trade Expansion Act of 1962, and the requirements of section 172(b) (3) (A) have been met),

(h) The amount of the net operating loss, if any, sustained by such corporation for the third succeeding taxable year, reduced to the extent absorbed in a separate return (or in a consolidated return) for the first and second preceding taxable years if a certification of such loss has been issued under section 317 of the Trade Expansion Act of 1962, and the requirements of section 172(b) (3) (A) have been met,

(i) [Reserved]

(j) The amount of the net operating loss, if any, sustained by such corpora-

tion for the fourth succeeding taxable year (but only if a certification of such loss for such year has been issued under section 317 of the Trade Expansion Act of 1962, and the requirements of section 172(b)(3)(A) have been met), reduced to the extent absorbed in a separate return (or in a consolidated return) for the first preceding taxable year, and

(k) The amount of the net operating loss, if any, sustained by such corporation for the fifth succeeding taxable year (but only if a certification of such loss for such year has been issued under section 317 of the Trade Expansion Act of 1962, and the requirements of section 172(b)(3)(A) have been met).

If the taxable year in which the net operating loss or consolidated net operating loss was sustained is a year beginning in 1957 and ending in 1958, the carryback is subject to section 172(i) or paragraph (b)(4)(v) of this section, respectively. See also paragraph (b)(21) of this section in any case in which a member of the group is an acquiring corporation in a transaction described in section 381(a), or any member of the group is subject to the limitations provided in section 382.

(ii) The consolidated net operating loss carrybacks to the taxable year with respect to net operating losses sustained in taxable years ending before January 1, 1958, shall consist of—

(a) The amount of the consolidated net operating loss, if any, for the first succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the taxable year) reduced to the extent absorbed as a carryback, consolidated or separate, as the case may be, for the first preceding taxable year;

(b) The amount of the consolidated net operating loss, if any, for the second succeeding taxable year to the extent not attributable to those corporations making separate returns in the taxable year;

and, with respect to a net operating loss sustained by a corporation which, for either of the two succeeding taxable years, files a separate return or joins in a consolidated return filed by another affiliated group, but subject to the limitations prescribed in paragraph (b)(3) of this section,

(c) The amount of the net operating loss, if any, sustained by such corporation for the first succeeding taxable year reduced to the extent absorbed by such corporation for the first preceding taxable year or, if the income of such corporation is included in the consolidated return for the first preceding taxable year, reduced to the extent absorbed by such consolidated return; and

(d) The amount of the net operating loss, if any, sustained by such corporation for the second succeeding taxable year.

See, however, paragraph (b)(21) of this section in any case in which a member of the group is an acquiring corporation in a transaction described in section 381 (a) or any member of the group is sub-

ject to the limitations provided in section 382.

(5) *Consolidated net operating loss.* The consolidated net operating loss shall be an amount equal to the excess of the sum of:

(i) The combined net operating losses of the several affiliated corporations having net operating losses,

(ii) The consolidated section 175 deduction, but not in excess of 25 percent of the consolidated section 175 gross income,

(iii) The consolidated section 181 deduction,

(iv) The consolidated section 1231 net loss,

(v) The aggregate of the deductions of the several affiliated corporations under sections 243, 244, and 245 (computed without regard to the limitation contained in section 246(b)) and under section 247 (computed without regard to the limitation of subsection (a)(1)(B) of such section), and

(vi) The consolidated section 582(c) net loss,

over the sum of—

(vii) The combined taxable income of the several affiliated corporations having taxable income, computed without regard to any deductions under section 242 (relating to partially tax-exempt interest), and

(viii) The consolidated net capital gain.

(6) *Consolidated section 1231 net loss.* The consolidated section 1231 net loss shall be the excess of the aggregate of the recognized losses of the character described in section 1231 sustained by the several affiliated corporations over the aggregate of the recognized gains of the character described in section 1231 realized by the several affiliated corporations.

(7) *Consolidated charitable contribution deduction.* The consolidated charitable contribution deduction shall be the aggregate of the amount of the deductions of the several affiliated corporations allowable under section 170 for the taxable year (determined without regard to the 5-percent limitation of section 170 (b)(2)) and an amount equal to the aggregate of the consolidated charitable contribution carryovers to the taxable year.

(8) *Consolidated charitable contribution carryovers.* The consolidated charitable contribution carryovers to the taxable year shall consist of—

(i) The excess, if any, of the amount of the consolidated charitable contribution deduction (computed without regard to any charitable contribution carryovers) for the two preceding taxable years over the limitation of subparagraph (1)(i)(c) of this paragraph for such years to the extent that the consolidated charitable contribution deduction for any such preceding year was not attributable to a corporation making a separate return, or joining in a consolidated return filed by another affiliated group, for the taxable year reduced by—

(a) The amount absorbed as a carryover by the consolidated or separate taxable income for the intervening taxable year, and

(b) The increase in a consolidated or separate net operating loss carryover resulting from such excess,

and, with respect to any excess of charitable contributions over the applicable 5-percent limitation of a corporation in a taxable year for which a separate return was filed, or for which such corporation joined in a consolidated return filed by another affiliated group—

(ii) The amount of such excesses of such corporation for the two preceding taxable years reduced by:

(a) The amount absorbed as a carryover by the consolidated or separate taxable income for the intervening taxable year, and

(b) The increase in a consolidated or separate net operating loss carryover resulting from such excess.

(9) *Consolidated net capital gain.* The consolidated net capital gain shall be the excess of the sum of—

(i) The aggregate of the capital gains of the several affiliated corporations,

(ii) The consolidated section 1231 net gain, and

(iii) The consolidated section 582(c) net gain,

over the sum of—

(iv) The aggregate of the capital losses of such corporations, and

(v) The aggregate of the consolidated net capital loss carryovers to the taxable year.

(10) *Consolidated section 1231 net gain.* The consolidated section 1231 net gain shall be the excess of the aggregate of the recognized gains of the character described in section 1231 realized by the several affiliated corporations over the aggregate of the recognized losses of the character described in section 1231 sustained by the several affiliated corporations.

(11) *Consolidated net capital loss carryover.* The consolidated net capital loss carryovers to the taxable year shall consist of:

(i) The consolidated net capital losses, if any, for the 5 preceding taxable years to the extent that such losses were not attributable to a corporation making a separate return, or joining in a consolidated return filed by another affiliated group, for the taxable year, and were not absorbed by net capital gains for intervening taxable years pursuant to the provisions of section 1212 or corresponding provisions of prior law, consolidated or separate, as the case may be,

and, with respect to net capital losses sustained by a corporation for taxable years for which separate returns were filed, or for which such corporation joined in a consolidated return filed by another affiliated group,

(ii) The net capital losses, if any, sustained by such corporation for its 5 preceding taxable years to the extent that such losses were not absorbed by the net capital gains of such corporation (or, if the income of such corporation was included in a consolidated return, by the consolidated net capital gain) for intervening taxable years pursuant to the provisions of section 1212 or corresponding provisions of prior law.

(12) *Consolidated net capital loss.* The consolidated net capital loss shall be the excess of the aggregate of the capital losses of the several affiliated corporations over the sum of:

- (i) The aggregate of the capital gains of such corporations,
- (ii) The consolidated section 1231 net gain, and
- (iii) The consolidated section 582(c) net gain,

reduced in the case of an affiliated group including as members one or more corporations subject to the tax imposed by section 831, but only for the purpose of net capital loss carryover computations, by whichever of the following amounts is the lesser—

- (iv) The combined additional capital loss deductions of such corporations authorized by section 832(c)(5), or
- (v) The consolidated taxable income computed without regard to capital gains and losses and without regard to any deduction for partially tax-exempt interest provided by section 242.

(13) *Consolidated dividends received deduction.* The consolidated dividends received deduction shall be the aggregate of the deductions of the several affiliated corporations allowable under sections 243, 244, and 245 (computed without regard to the limitation of section 246 (b)), but in an amount not greater than 85 percent of the consolidated taxable income computed without regard to the consolidated net operating loss deduction, the consolidated section 247 deduction, and without regard to any consolidated dividends received deduction. The limitation of the previous sentence shall not apply for any taxable year for which there is a consolidated net operating loss.

(14) *Consolidated section 247 deduction.* The consolidated section 247 deduction, relating to dividends paid by public utilities on preferred stock, shall be an amount computed as follows:

(i) First, determine the amount which is the lesser of,

(a) The aggregate of the dividends paid by members of the affiliated group which are public utilities within the meaning of section 247(b)(1) on preferred stock within the meaning of section 247(b)(2), or

(b) The portion of the consolidated taxable income for the taxable year attributable to such members computed without regard to the consolidated section 247 deduction.

(ii) Then multiply the amount determined under subdivision (i) of this subparagraph by the fraction specified in section 247 (a) (2).

(15) *Consolidated section 922 deduction.* The consolidated section 922 deduction, relating to Western Hemisphere trade corporations, shall be that portion of the consolidated taxable income attributable to those members of the affiliated group which are Western Hemisphere trade corporations (computed without regard to the consolidated section 922 deduction) multiplied by the fraction specified in section 922 (2).

(16) *Consolidated net long-term capital gain.* The consolidated net long-

term capital gain shall be the excess of the sum of:

(i) The aggregate of the long-term capital gains of the several affiliated corporations, and

(ii) The consolidated section 1231 net gain,

over

(iii) The aggregate of the long-term capital losses of such corporations.

(17) *Consolidated net short-term capital loss.* The consolidated net short-term capital loss shall be the sum of—

(i) The aggregate of the short-term capital losses of the several affiliated corporations, and

(ii) The consolidated net capital loss carryovers,

minus

(iii) The aggregate of the short-term capital gains of such corporations.

(18) *Consolidated accumulated taxable income.* The consolidated accumulated taxable income shall be the consolidated taxable income computed without regard to any capital loss carryover, without regard to any charitable contribution deduction under section 170, without regard to any net operating loss deduction, and without regard to any deduction under part VIII (section 241 and following, except section 248) subchapter B of chapter 1 of the Code, minus the sum of:

(i) The combined Federal income and excess profits taxes (other than the excess profits tax imposed by subchapter E, chapter 2 of the Internal Revenue Code of 1939, for taxable years beginning after December 31, 1940) and income, war profits and excess profits taxes of foreign countries and possessions of the United States (to the extent not allowable as a deduction under section 164(b)(6)), accrued during the taxable year by the several affiliated corporations or deemed to be paid by the several domestic affiliates under section 902(a)(1) or 960(a)(1)(C) for the taxable year, but not including the accumulated earnings tax imposed by section 531, the personal holding company tax imposed by section 541, or the taxes imposed by corresponding sections of a prior income tax law,

(ii) The consolidated charitable contribution deduction computed without regard to section 170(b)(2).

(iii) The excess of the sum of the capital losses of the several affiliated corporations (computed without regard to any capital loss carryover) over the sum of the capital gains of such corporations,

(iv) The excess of the consolidated net long-term capital gain over the consolidated net short-term capital loss (computed without regard to any capital loss carryover) minus the taxes imposed by subtitle A attributable to such excess,

(v) In the case of an affiliated group including one or more holding company affiliates of a bank, as defined in section 2 of the Banking Act of 1933 (12 U.S.C. 221a), the consolidated section 601 deduction, relating to earnings or profits devoted to the acquisition of readily marketable assets, other than bank stock,

(vi) The consolidated accumulated earnings credit, and

(vii) The consolidated section 561 dividends paid deduction.

(19) *Consolidated accumulated earnings credit.* The consolidated accumulated earnings credit shall be:

(i) In the case of an affiliated group which is not a mere holding or investment group, an amount equal to such part of the aggregate of the earnings and profits for the taxable year of the several members of the group as are retained for the reasonable needs of the business of the group, minus the deduction allowed by subparagraph (18)(iv) of this paragraph, but not less than the amount (if any) by which \$100,000 (\$60,000 if the taxable year begins before January 1, 1958) exceeds the aggregate of the accumulated earnings and profits of the several members of the group at the close of the preceding taxable year, or

(ii) In the case of an affiliated group which is a mere holding or investment group, the amount (if any) by which \$100,000 (or \$60,000 if the taxable year begins before January 1, 1958) exceeds the aggregate of the accumulated earnings and profits of the several members of the group at the close of the preceding taxable year.

For the purpose of subdivision (i) of this subparagraph, the amount of the earnings and profits for the taxable year of the several members of the group which are retained is the amount by which the aggregate of the earnings and profits of the several members of the group for the taxable year exceed the consolidated section 561 dividends paid deduction for such year. For the purpose of the preceding sentence and subdivision (ii) of this subparagraph, the accumulated earnings and profits of the several members of the group at the close of the preceding taxable year shall be reduced by the dividends paid to other than members of the group under section 563 (a) (relating to dividends paid after the close of the taxable year) which are considered as paid during such taxable year.

(20) *Consolidated section 561 dividend paid deduction.* The consolidated section 561 dividends paid deduction shall be the sum of:

(i) The aggregate of the deductions allowable to the several members of the group with respect to dividends under section 561 (a) (1) and (2) determined without regard to any deductions attributable to payments made or considered to be made of dividends to other members of the group, and

(ii) In case the affiliated group is subject to tax on its consolidated undistributed personal holding company income, the consolidated dividend carryover.

(21) *Consolidated section 542 gross income.* The consolidated section 542 gross income shall be the combined gross income of the several members of the affiliated group computed without regard to any gross income from other members of the group and by including only the excess of the gains of the several members of the group over the losses of the several members of the group from transactions in stocks or securities as described in section 543 (a) (2) and by

including only the excess of the gains of the several members of the group over the losses of the several members of the group with respect to commodity transactions as described in section 543 (a) (3).

(22) *Consolidated personal holding company income.* The consolidated personal holding company income shall be that part of the consolidated section 542 gross income from the sources described in section 543.

(23) *Consolidated undistributed personal holding company income.* The consolidated undistributed personal holding company income shall be the consolidated taxable income computed without regard to any deductions under part VIII (section 241 and following, except section 248), subchapter B, chapter 1 of the Code, without regard to any charitable contribution deduction under section 170, without regard to any net operating loss deduction, and without regard to deductions disallowed by section 545 (b) (8), minus the sum of:

(i) The combined Federal income and excess profits taxes (other than the excess profits tax imposed by subchapter E, chapter 2 of the Internal Revenue Code of 1939 for taxable years beginning after December 31, 1940) and income, war profits and excess profits taxes of foreign countries and possessions of the United States (to the extent not allowable as a deduction under section 164(b) (6)) accrued during the taxable year by the several affiliated corporations or deemed to be paid by the several domestic affiliates under section 902(a) (1) or 960(a) (1) (C) for the taxable year, but not including the accumulated earnings tax imposed by section 531, the personal holding company tax imposed by section 541, or the taxes imposed by the corresponding sections of prior income tax law;

(ii) In lieu of the deduction provided by subparagraph (1) (i) (c) of this paragraph, the consolidated charitable contribution deduction computed without the application of section 170(b) (2) but limited as provided in section 170(b) (1) (A) and (B) (except that the 10-percent and 20-percent limitations therein shall be applied with respect to the consolidated adjusted gross income);

(iii) The amount of the consolidated net operating loss for the preceding taxable year (computed without the deductions provided in part VIII (section 241 and following), except section 248, subchapter B, chapter 1 of the Code, if the current taxable year begins after December 31, 1957) to the extent not attributable to a corporation making a separate return, or joining in a consolidated return filed by another affiliated group for the taxable year, and, with respect to a corporation which filed a separate return or joined in a consolidated return filed by another affiliated group for the preceding taxable year, the net operating loss of such corporation for such preceding taxable year (computed without the deductions provided in part VIII (section 241 and following), except section 248, subchapter B, chapter 1 of the Code, if the current taxable year begins after December 31, 1957) but not in excess of

the portion of the consolidated personal holding company income attributable to such corporation for the taxable year;

(iv) The excess of the consolidated net long-term capital gain for the taxable year over the consolidated net short-term capital loss for such year minus the taxes imposed by subtitle A of the Code attributable to such excess;

(v) The aggregate amount subject to the provisions of section 545 (b) (7) used or irrevocably set aside by the several affiliated corporations to pay or retire indebtedness incurred prior to January 1, 1934, not including such portion of any such indebtedness as was owned on January 1, 1934, or at any time thereafter, directly or indirectly, by another member of the group;

(vi) The sum of the amounts deductible by the several members of the affiliated group allowable under section 545 (b) (9), but there shall be added to the consolidated taxable income any amount required to be included in taxable income under such section;

(vii) The consolidated section 561 dividends paid deduction; and

(viii) In the case of an affiliated group including one or more holding company affiliates of a bank, as defined in section 2 of the Banking Act of 1933 (12 U.S.C. 221a), the consolidated section 601 deduction, relating to earnings or profits devoted to the acquisition of readily marketable assets, other than bank stock.

(24) *Consolidated adjusted gross income.* The consolidated adjusted gross income shall be the consolidated taxable income computed without regard to any charitable contributions deductions, any deductions under part VIII (section 241 and following), except section 248, subchapter B, chapter 1 of the Code, any net operating loss carryback to the taxable year, any deductions under section 922, and without deduction of the amount disallowed by section 545(b) (8).

(25) *Consolidated deficiency dividends deduction.* The consolidated deficiency dividends deduction shall be the aggregate of the amounts determined as provided in section 547 with respect to dividends distributed by the several members of the affiliated group pursuant to a determination of liability for personal holding company tax described in section 547, with respect to the consolidated undistributed personal holding company income of the affiliated group for the taxable year of the group computed without regard to any dividends distributed to members of the affiliated group.

(26) *Consolidated dividend carryover.* The consolidated dividend carryover to the taxable year shall be the sum of—

(i) The excess of—
(a) The consolidated section 561 dividends paid deduction for the first preceding taxable year, determined without regard to any consolidated dividend carryover, over

(b) The consolidated undistributed personal holding company income for such year, determined without regard to any dividends paid deduction and dividend carryover,

to the extent that such deduction and such income are not attributable to a

corporation making a separate return, or joining in a consolidated return filed by another affiliated group, for the taxable year.

(ii) The amount of the consolidated section 561 dividends paid deduction (determined as provided in subdivision (i) (a) of this subparagraph) for the second preceding taxable year reduced by the consolidated undistributed personal holding company income for such year (determined as provided in subdivision (i) (b) of this subparagraph) and further reduced by the amount of the consolidated undistributed personal holding company income for the first preceding taxable year determined without regard to any dividend carryover from the second preceding taxable year to the extent that any such consolidated section 561 dividends paid deduction and any such consolidated undistributed personal holding company income are not attributable to a corporation making a separate return, or joining in a consolidated return filed by another affiliated group for the taxable year,

and, with respect to taxable years for which a member of the affiliated group filed a separate return or for which such member joined in a consolidated return filed by another affiliated group—

(iii) The excess of the deduction allowable to such corporation under section 561 for dividends paid for the first preceding taxable year (determined without regard to any dividend carryover) over the taxable income of such corporation for such year computed with the adjustments provided in section 545 (or if its income was included in the consolidated return of another affiliated group, that portion of the excess of the consolidated section 561 dividends paid deductions (determined as provided in subdivision (i) (a) of this subparagraph) for the first preceding taxable year, over the consolidated undistributed personal holding company income (determined as provided in subdivision (i) (b) of this subparagraph) for such year attributable to such corporation), and

(iv) The excess of the deduction allowable to such corporation under section 561 (determined without regard to any dividend carryover) for the second preceding taxable year over the taxable income of such corporation for such year computed with the adjustments provided in section 545 (or if its income was included in the consolidated return of another affiliated group, that portion of the excess of the consolidated section 561 dividends paid deduction (determined as provided in subdivision (i) (a) of this subparagraph) for the second preceding taxable year, over the consolidated undistributed personal holding company income (determined as provided in subdivision (i) (b) of this subparagraph) for such year, attributable to such corporation) and reduced by—

(a) The excess of the amount of its taxable income so computed for the first preceding taxable year over its dividends paid deduction under section 561, determined without regard to any dividend carryover from the second preceding taxable year (or, if its income was included in the consolidated return of an-

other affiliated group, that portion of the amount of such deduction absorbed in such consolidated return of another affiliated group), or

(b) If the income of such corporation is included in the consolidated return for the first preceding taxable year, the excess, if any, of the consolidated undistributed personal holding company income (determined without regard to any dividends paid deduction and dividend carryover) for the first preceding taxable year over the consolidated section 561 dividends paid deduction for such year, determined without regard to any dividend carryover.

(27) *Consolidated section 601 deduction.* The consolidated section 601 deduction relating to bank affiliates, shall be an amount equal to the aggregate of the earnings or profits of members of the group which are holding company affiliates of a bank as defined in section 2 of the Banking Act of 1933 (12 U.S.C. 221a) devoted to the acquisition of readily marketable assets other than bank stock (not including any asset acquired, directly or indirectly, from another member of the group), subject, in the case of each such affiliate, to the limitations imposed by section 601 determined without regard to the qualifications expressed in paragraph (b) (1) (ii) and (iii) of this section.

(28) *Consolidated life insurance company taxable income.* The consolidated life insurance company taxable income in the case of an affiliated group consisting of corporations subject to the tax imposed by section 802 shall be the consolidated taxable income minus the consolidated section 804 deduction and plus the consolidated section 806 adjustment.

(29) *Consolidated section 804 deduction.* The consolidated section 804 deduction relating to the reserve and other policy liabilities shall be the consolidated taxable income multiplied by a figure to be determined and proclaimed by the Secretary for each taxable year pursuant to section 804.

(30) *Consolidated section 806 adjustment.* The consolidated section 806 adjustment relating to certain reserves provided in section 806 shall be an amount equal to $3\frac{1}{4}$ percent of the combined unearned premiums and unpaid losses of the several affiliated corporations on contracts other than life insurance or annuity contracts computed in the case of each corporation pursuant to the provisions of section 806 but the combined unearned premiums shall not be considered to be less than 25 percent of the combined net premiums on such other contracts written during the taxable year.

(31) *Consolidated 1954 life insurance company taxable income.* The consolidated 1954 life insurance company taxable income in the case of an affiliated group consisting of corporations subject to the tax imposed by section 802 (b) for taxable years beginning in 1954 shall be the consolidated taxable income plus eight times the consolidated section 806 adjustment and minus the consolidated reserve interest credit, if any.

(32) *Consolidated reserve interest credit.* The consolidated reserve interest credit shall be the aggregate of the reserve interest credits of the several members of the affiliated group.

(33) *Consolidated section 175 deduction.* The consolidated section 175 deduction shall be the aggregate of the amount of the deductions of the several affiliated corporations allowable under section 175 for the taxable year (determined without regard to the 25 percent limitation of section 175 (b)) and an amount equal to the aggregate of the consolidated section 175 carryovers to the taxable year.

(34) *Consolidated section 175 gross income.* The consolidated section 175 gross income shall be the combined gross income derived from farming of the several affiliated corporations engaged in the business of farming and having expenditures of the type described in section 175 (a). For this purpose, there shall be eliminated profits and losses on intercompany transactions; and proper adjustment shall be made to eliminate any distortion in the amount of gross income attributable to transactions between members of the affiliated group at markedly fictitious values.

(35) *Consolidated section 175 carryovers.* The consolidated section 175 carryovers to the taxable year shall consist of—

(i) The excess, if any, of the amount of the consolidated section 175 deductions over 25 percent of the consolidated section 175 gross income of preceding taxable years to the extent that such consolidated section 175 deduction for any preceding taxable year was not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the taxable year and was not absorbed as a carryover by the consolidated section 175 gross income for preceding taxable years

and, with respect to any excess of deductions under section 175 over the 25 percent limitation of section 175 (b) of a corporation in a taxable year for which a separate return was filed or for which such corporation joined in a consolidated return filed by another affiliated group, but subject to the limitation prescribed in paragraph (b) (15) of this section.

(ii) The amount of such excesses of such corporation for preceding taxable years to the extent that such excesses were not absorbed as carryovers for preceding taxable years.

(36) *Consolidated section 582(c) net loss.* The consolidated section 582(c) net loss shall be the excess of the aggregate of the losses of the character described in section 582(c) recognized in a taxable year beginning after December 31, 1958, by the several affiliated corporations which are banks over the aggregate of gains of the character described in section 582(c) recognized in such taxable year by the several affiliated corporations which are banks.

(37) *Consolidated section 582(c) net gain.* The consolidated section 582(c) net gain shall be the excess of the aggregate of the gains of the character described in section 582(c) recognized in a taxable year beginning after December 31, 1958, by the several affiliated corporations which are banks over the aggregate of the losses of the character described in section 582(c) recognized in

such taxable year by the several affiliated corporations which are banks.

(38) *Consolidated section 181 deduction.* The consolidated section 181 deduction for the taxable year shall be the sum of—

(i) With respect to the portion of a consolidated unused credit not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for such taxable year, the amount determined under the provisions of section 181, and

(ii) With respect to unused credits arising in unused credit years for which a corporation filed a separate return or joined in a consolidated return filed by another affiliated group, the amount determined under the provisions of section 181.

(b) *Computations.* In the case of affiliated corporations which make, or are required to make, a consolidated return, and except as otherwise provided in the regulations under section 1502:

(1) *Taxable income.* The taxable income of each corporation shall be computed in accordance with the provisions covering the determination of taxable income of separate corporations, except:

(i) There shall be eliminated unrealized profits and losses in transactions between members of the affiliated group and dividend distributions from one member of the group to another member of the group (referred to in the regulations under section 1502 as intercompany transactions);

(ii) No net operating loss deduction shall be taken into account;

(iii) No capital gains or losses shall be taken into account;

(iv) There shall be disregarded all gains and losses from involuntary conversions subject to section 1231, and from sales and exchanges of property subject to section 1231;

(v) In the computation of the deduction under section 171, relating to amortizable bond premium, there shall be disregarded the bonds of one member of the group owned by another member of the group during the taxable year;

(vi) In the computation of the taxable income of a corporation for the taxable year in which it became the common parent corporation of the affiliated group filing a consolidated return, the aggregate deductions of such corporation for such year otherwise allowable in excess of the gross income of such corporation for such year shall be excluded to the extent that such excess is attributable to that portion of such year preceding the date upon which such corporation became the common parent corporation of the group. Any amount excluded under this paragraph shall, to the extent that it constitutes a net operating loss within the provisions of section 172 or a net capital loss within the provisions of section 1222, be considered as a net operating loss or a net capital loss, as the case may be, separately sustained by such corporation and subject to the provisions of paragraph (a) (3) (ii) or (11) (ii) of this section;

(vii) In the case of a corporation which became a member of the affil-

ated group after January 1, 1954, common parent corporation or subsidiary, as the case may be, allowable deductions shall be determined subject to the qualifications prescribed in subparagraph (9) of this paragraph;

(viii) No deduction under section 170 with respect to charitable or other contributions shall be taken into account;

(ix) In the case of the deduction provided in section 615 (relating to mine exploration expenditures), the allowable deduction shall be determined subject to the qualifications prescribed in subparagraph (12) of this paragraph;

(x) In the case of a distribution of inventory to which section 311 (b) is applicable, or in the case of a distribution of property to which section 311 (c) is applicable by one member of the group to another member of the group, the gain recognized under such sections shall be eliminated;

(xi) No deductions under section 243, 244, 245, or 247 (relating to deductions with respect to dividends received and dividends paid) or under section 922 (relating to the special deduction for Western Hemisphere trade corporations), shall be taken into account;

(xii) No deductions under section 175 (relating to soil and water conservation expenditures) shall be taken into account by a member of an affiliated group to which the consolidated section 175 deduction is applicable;

(xiii) In the case of a bank, for taxable years beginning after December 31, 1953, there shall be disregarded all gains and losses from sales and exchanges of property described in section 582(c); and

(xiv) No deduction under section 181 (relating to deduction for certain unused investment credit) shall be taken into account.

Intercompany profits and losses which have been realized by the group through final transactions with persons other than members of the group, and intercompany transactions which do not affect the consolidated taxable income shall not be eliminated. For the purpose of this subparagraph, gain includible in income pursuant to section 357(c) with respect to transfers of assets other than capital assets and other than assets to which section 1231 is applicable, and gain includible in income by reason of the application of paragraph (a) (1) (iii) of § 1.1502-37A, shall not be eliminated. For the purpose of the regulations under section 1502, a transaction not involving a sale or exchange of a capital asset or of property subject to the provisions of section 1231 shall not be considered an intercompany transaction if such transaction occurs in the regular course of the trade or business of the members of the group and if such members adopt, with the consent of the Commissioner and subject to such conditions as he deems proper, a consistent accounting practice of taking into account in the computation of consolidated taxable income the gains and losses reflected in such transactions. As used in this paragraph, the term "taxable income" includes the case in which the allowable deductions of a member (not including

any net operating loss deduction) exceed its gross income. For purposes of section 593(b) (2) (relating to addition to reserve for bad debts), taxable income of an organization to which section 593 applies shall be computed as if such organization filed a separate return for the taxable year.

(2) *Other computations on separate basis.* The various other computations required by the regulations under section 1502 to be made by the several affiliated corporations shall be made in the case of each such corporation in the same manner and under the same conditions as if a separate return were to be filed, but with the following exceptions:

(i) *Taxable income.* The taxable income used in any such computation shall be the taxable income of the corporation determined in accordance with the provisions of this section.

(ii) *Dividends received.* In the computation of the dividends received, there shall be excluded all dividends received from other members of the affiliated group.

(iii) *Capital gains and losses.* Capital gains and losses, short-term capital gains and losses, long-term capital gains and losses, and the additional capital loss deduction authorized by section 832 (c) (5) shall be determined without regard to:

(a) Gains or losses arising in intercompany transactions (other than gains described in section 357 (c)) and gains recognized to the distributing corporation pursuant to section 311 (c) by reason of distributions by one member of the group to another member of the group.

(b) Gains or losses from involuntary conversions and from sales or exchanges of property subject to the provisions of section 1231.

(c) The net capital loss carryovers provided in section 1212.

(d) In the case of a corporation which became a member of the affiliated group subsequent to January 1, 1954, common parent corporation or subsidiary, as the case may be, capital losses to the extent disallowed pursuant to the provisions of subparagraph (9) of this paragraph, and

(e) In the case of a bank, for taxable years beginning after December 31, 1953, gains or losses from sales or exchanges of property described in section 582(c).

(iv) *Net operating loss.* In the computation of the net operating loss, as defined in section 172, the provisions of this section pertaining to the determination of taxable income shall apply.

(v) *Dividends paid.* In the computation of dividends paid, there shall be excluded all dividends paid by one member of the group to another, except as provided in paragraph (b) (4) of § 1.1502-30A.

(vi) *Federal income tax.* In the computation of the Federal income tax, there shall be used the consolidated tax, or a proportionate part thereof, if the tax payable is properly computed on the basis of the consolidated return.

(vii) *Dividends paid by public utility.* In the computation of dividends paid on

the preferred stock of a public utility, there shall be excluded all dividends paid by such public utility to another member of the group.

(viii) *Gains or losses under section 1231.* Gains and losses from involuntary conversions subject to section 1231, and from sales or exchanges of property subject to section 1231 shall be determined without regard to—

(a) Gains and losses from intercompany transactions (other than gains described in section 357 (c)) and gains recognized pursuant to section 311 (c) upon the distribution of property subject to the provisions of section 1231 by one member of the group to another member of the group, and

(b) In the case of a corporation which became a member of the affiliated group subsequent to January 1, 1954, common parent corporation or subsidiary, as the case may be, such portion of any such loss as is disallowed pursuant to the provisions of subparagraph (9) of this paragraph.

(ix) *Mutual savings banks, domestic building and loan associations, and co-operative banks.* In the case of a mutual savings bank, a domestic building and loan association, and a cooperative bank:

(a) In the computation of total deposits or withdrawable accounts at the close of the taxable year for the purpose of section 593 (relating to the deduction for bad debts), there shall be excluded the total deposits or withdrawable accounts of other members of the group, and

(b) In the computation of the deduction provided in section 591 (relating to dividends paid by banking corporations), there shall be excluded amounts paid to, or credited to the accounts of, other members of the group.

(3) *Limitation on net operating loss carryovers and carrybacks from separate return years.* (i) In no case shall there be included in the consolidated net operating loss deduction for the taxable year as consolidated net operating loss carryovers or carrybacks under paragraphs (a) (3) (i) (b), (4) (i) (f), (g), (h), (j), and (k), and (ii) (c) and (d) of this section (relating to net operating losses sustained by a corporation in years for which separate returns were filed, or for which such corporation joined in a consolidated return filed by another affiliated group) an amount exceeding the taxable income of such corporation included in the computation of the consolidated taxable income for the taxable year, adjusted as provided in subdivision (ii) of this subparagraph. This subdivision shall not be applicable to a carryover under paragraph (a) (3) (i) (b) of this section of a net operating loss of a corporation—

(a) Attributable to a period for which it was included in a consolidated return filed by another affiliated group for a taxable year beginning prior to January 1, 1954, all of whose members are included in the consolidated return filed for the taxable year if all of the members of such other affiliated group would have been members of the affiliated group if the law applicable to the taxable year had been applicable to such prior taxable year,

(b) To taxable years beginning after December 31, 1963, attributable to a taxable year beginning before January 1, 1964, in which such corporation was (on each day of such year) a member of the affiliated group, or

(c) Attributable to a taxable year beginning after December 31, 1963, in which such corporation was (on each day of such year) a member of the affiliated group, provided that an election under section 1562 (relating to privilege of groups to elect multiple surtax exemptions) was not effective for such year.

(ii) For purposes of this subparagraph and subparagraph (21) of this paragraph, the taxable income of a corporation included in the computation of consolidated taxable income shall be decreased by its deductions under sections 181, 243, 244, 245, 247, and 922 (and in the case of a member of an affiliated group to which the consolidated section 175 deduction is applicable, the section 175 deduction), and shall be increased by its separate net capital gain, and shall be increased or decreased, as the case may be, with respect to its separate gains and losses from involuntary conversions subject to the provisions of section 1231, and from sales or exchanges of property subject to the provisions of section 1231.

(4) *Law applicable to computations of net operating loss carryovers and carrybacks.* (i) In determining the amount of any net operating loss carryback or carryover, consolidated or separate, to any taxable year, the necessary computations involving any other taxable year shall be made under the law and regulations applicable to such other taxable year. The preceding sentence shall apply with respect to all taxable years whether they begin before, on, or after January 1, 1954.

(ii) In the case of a consolidated net operating loss for a taxable year beginning in 1953 and ending in 1954, the amount of such consolidated net operating loss which shall be carried to the second preceding taxable year shall be the amount which bears the same ratio to such consolidated net operating loss as the number of days in the loss year after December 31, 1953, bears to the total number of days in such year. In determining the amount carried to any other taxable year, the amount absorbed for the second taxable year preceding the loss year shall not exceed the portion of the consolidated net operating loss which is carried to the second preceding taxable year.

(iii) (a) The consolidated net operating loss deduction for a taxable year beginning in 1953 and ending in 1954, shall be the sum of—

(1) That portion of the consolidated net operating loss deduction for such taxable year, computed as though paragraph (a) (2) of § 1.1502-31A applied to such taxable year, which the number of days in such taxable year after December 31, 1953, bears to the total number of days in such taxable year, and

(2) That portion of the consolidated net operating loss deduction for such taxable year, computed in accordance with 26 CFR (1939) 24.31(a) (2) (Regulations 129), which the number of days

in such taxable year before January 1, 1954, bears to the total number of days in such taxable year.

(b) The consolidated net income for any taxable year beginning in 1953 and ending in 1954 which is subtracted from the net operating loss for any other taxable year to determine the portion of such net operating loss which is a carryback or a carryover to a particular taxable year shall be determined in accordance with the principles of section 172(f) (4).

(iv) (a) The consolidated net operating loss deduction for a taxable year beginning after December 31, 1953, and ending before August 17, 1954, shall be computed as if the regulations under section 1502 apply to such taxable year.

(b) The consolidated net income for any taxable year beginning after December 31, 1953, and ending before August 17, 1954, which is subtracted from the consolidated net operating loss for any other taxable year to determine the portion of such net operating loss which is a carryback or a carryover to a particular taxable year shall be determined in accordance with section 172(g) (3).

(v) In the case of a consolidated net operating loss for a taxable year beginning in 1957 and ending in 1958, the amount of such consolidated net operating loss which shall be carried to the third preceding taxable year shall be the amount which bears the same ratio to such consolidated net operating loss as the number of days in the loss year after December 31, 1957, bears to the total number of days in such year. In determining the amount carried to any other taxable year, the amount absorbed for the third taxable year preceding the loss year shall not exceed the portion of the consolidated net operating loss which is carried to the third preceding taxable year.

(vi) For purposes of section 141 of the Internal Revenue Code of 1939 and that part of the regulations promulgated thereunder which relate to subchapter D, chapter 1 of such Code, excess profits net income and consolidated section 433(a) excess profits net income shall be computed as if the regulations under section 1502 did not apply and as if such section and such regulations continued to apply to taxable years beginning after December 31, 1953.

(5) *Limitation on absorption of unused dividend carryovers.* If, in the computation of the consolidated dividend carryover for the second consolidated return period in respect of which the income of a corporation is included in the consolidated return of the group, there is involved a separate unused dividend carryover of such corporation for the second preceding taxable year together with a consolidated unused dividend carryover for the second preceding taxable year, or if, for the second consolidated return period in respect of which the income of two or more members of the group is included in the consolidated return of the group, there are involved the separate unused dividend carryovers of such corporations for the second preceding taxable year, no portion of the excess of the consolidated undistributed personal holding company income (determined without regard to

any dividends paid deduction and dividend carryover) over the consolidated section 561 dividends paid deduction (determined without regard to any dividend carryover) for the first preceding taxable year shall be taken into account more than once in giving effect to the provisions of paragraph (a) (26) (ii) and (iv) of this section (relating to the computation of that part of the consolidated dividend carryover attributable to the unused dividend carryovers of the second preceding taxable year).

(6) *Apportionment of consolidated net operating loss.* If an affiliated group filing a consolidated return sustains a consolidated net operating loss for the taxable year within the provisions of section 172, relating to the net operating loss deduction, and if—

(i) There are included as members of such group one or more corporations which made separate returns, or joined in a consolidated return filed by another affiliated group, either in a preceding taxable year or in a succeeding taxable year, or

(ii) There are included as members of such group one or more corporations which sustain a net operating loss for the taxable year for which a certification is issued under section 317 of the Trade Expansion Act of 1962 and with respect to which the requirements of section 172 (b) (3) (A) are met, or

(iii) In the case of a taxable year ending after December 31, 1955, there are included as members of such group one or more corporations which are regulated transportation corporations for the taxable year (within the meaning of section 172(j) (1)),

then the portion of such consolidated net operating loss attributable to such corporations severally shall be determined, such portion in the case of any such corporation being determined in an amount proportionate to the net losses (capital net losses and ordinary net losses alike) of the several affiliated corporations having net losses, to the extent that such losses were taken into account in the computation of the consolidated net operating loss.

(7) *Apportionment of consolidated net capital loss.* If an affiliated group filing a consolidated return sustains a consolidated net capital loss, and if there are included as members of such group one or more corporations which make separate returns, or join in a consolidated return filed by another affiliated group, in a succeeding taxable year, the portion of such consolidated net capital loss attributable to such corporations severally shall be determined, such portion in the case of any such corporation being an amount which bears the same ratio to the consolidated net capital loss which the net capital loss of such corporation bears to the aggregate of the net capital losses for the taxable year sustained by the several affiliated corporations having net capital losses.

(8) *Limitation on net capital loss carryover from separate return year.* In no case shall there be included in the computation of the consolidated net capital gain for the taxable year as a consolidated net capital loss carryover under paragraph (a) (11) (ii) of this section (relating to net capital losses

separately sustained) an amount exceeding in the aggregate the net capital gains of such corporation (determined without regard to any net capital loss carryover) included in the computation of the consolidated net capital gain for the taxable year increased with respect to its separate net gains from involuntary conversions and from sales or exchanges of property subject to the provisions of section 1231.

(9) *Qualifications on deductions where group membership changed after January 1, 1954.* In the case of an affiliated group formed at any time after January 1, 1954, or having among its members in the taxable year one or more subsidiaries which became members of the group subsequent to January 1, 1954, the consolidated taxable income for the taxable year, and for prior and subsequent taxable years to the extent affected by carrybacks and carryovers from the taxable year, shall be determined subject to the following qualifications:

(i) There shall be excluded in the case of the common parent corporation and in the case of any subsidiaries which were members of the group on January 1, 1954, those deductions from gross income otherwise allowable with respect to—

(a) Sales or exchanges of capital assets,

(b) Involuntary conversions and sales or exchanges of property subject to the provisions of section 1231,

(c) Securities subject to the provisions of section 165 (g) (3), or

(d) Debts subject to the provisions of section 166,

to the extent that such deductions otherwise allowable exceed in the aggregate—

(e) In the case of capital losses, the excess of the aggregate capital gains over the aggregate capital losses of such corporations for the taxable year, or

(f) In the case of ordinary losses, the aggregate of the ordinary taxable income of such corporations for the taxable year, increased in an amount equal to any excess of aggregate capital gains over aggregate capital losses of such corporations,

such capital gains and losses and such ordinary taxable income being determined pursuant to the provisions of the regulations under section 1502 but without regard to the provisions of subparagraphs (1) (iv) and (2) (iii) (b) of this paragraph and without regard to the losses in question:

(ii) There shall be excluded in the case of a subsidiary corporation which became a member of the affiliated group subsequent to January 1, 1954, those deductions from gross income otherwise allowable with respect to—

(a) Sales or exchanges of capital assets,

(b) Involuntary conversions and sales or exchanges of property subject to the provisions of section 1231,

(c) Securities subject to the provisions of section 165 (g) (3), or

(d) Debts subject to the provisions of section 166,

to the extent that such deductions otherwise allowable are attributable to events preceding the date upon which such corporation became a member of the group, and

(e) Being capital losses, exceed (1) the capital gains reduced by all other capital losses of such corporation for the taxable year, in the case in which such corporation was not, on January 1, 1954, a member of an affiliated group within the meaning of section 1504, or (2) in case such corporation was a member of an affiliated group on January 1, 1954, an amount which together with like losses computed subject to the provisions of the regulations under section 1502 in the case of other members of the group during the taxable year which were affiliated with such corporation on January 1, 1954, within the meaning of section 1504 is equal to the aggregate capital gains reduced by the aggregate of all other capital losses of such corporation and of such other members of the group, or

(f) Being ordinary losses exceed (1) the ordinary taxable income of such corporation for the taxable year increased in an amount equal to any excess of capital gains over capital losses for the taxable year, in the case in which such corporation was not, on January 1, 1954, a member of an affiliated group within the meaning of section 1504, or (2) in case such corporation was a member of an affiliated group on January 1, 1954, an amount which, together with like losses computed subject to the provisions of the regulations under section 1502 in the case of other members of the group during the taxable year which were affiliated with such corporation on January 1, 1954, within the meaning of section 1504, is equal to the ordinary taxable income of such corporation for the taxable year increased by the aggregate of the ordinary taxable income and decreased by the aggregate of the ordinary net losses of other members of the affiliated group during the taxable year which were affiliated with such corporation on January 1, 1954, within the meaning of section 1504, and increased further in an amount equal to any excess of aggregate capital gains over aggregate capital losses of such corporations,

such capital gains and losses, and ordinary taxable income and net losses, as the case may be, being determined pursuant to the provisions of the regulations under section 1502 but without regard to the provisions of subparagraphs (1) (iv) and (2) (iii) (b) of this paragraph, and without regard to the losses in question.

(iii) The portion of any loss otherwise allowable as a deduction for the taxable year which is disallowed pursuant to the provisions of subdivisions (i) and (ii) of this subparagraph shall, to the extent that it constitutes a net capital loss or a net operating loss, be considered as a net capital loss or a net operating loss, as the case may be, in respect to those members of the group by reference to which the amount of the deduction disallowed under subdivisions (i) and (ii) of this subparagraph was determined, and, for the purpose of the carryback provisions, the year of the loss shall be considered as a taxable year occurring subsequent to the last taxable year in respect of which the income of such members of the group was included in a consolidated return, and, for the purpose of the carryover provisions, as a

taxable year occurring prior to the first taxable year in respect of which their income was included in a consolidated return;

(iv) The provisions of subdivisions (i) and (ii) of this subparagraph shall not apply with respect to the common parent corporation of an affiliated group formed subsequent to January 1, 1954, or to the common parent corporation or subsidiaries of a group in existence on January 1, 1954, acquiring new members subsequent to January 1, 1954, or with respect to subsidiaries becoming members of the group subsequent to January 1, 1954—

(a) If the group consists solely of the common parent corporation and one or more subsidiaries created, directly or indirectly, by the common parent corporation or by other members of the group;

(b) If, immediately after the corporation involved became a member of the group, common parent corporation or subsidiary, as the case may be, stock possessing at least 80 percent of the voting power of all classes of its stock then outstanding and at least 80 percent of each class of its nonvoting stock then outstanding is owned, directly or indirectly, by substantially the same interests by which such stock was owned on January 1, 1954;

(c) If the affiliated group involved was formed, or the new subsidiary became a member of the group, as an incident to an involuntary conversion or to a transfer made pursuant to an order of the Securities and Exchange Commission, the Federal Communications Commission, the Interstate Commerce Commission, or a similar regulatory body of State or Federal Government; or

(d) To the extent to which, upon consideration of the facts or circumstances presented by the particular case, the Commissioner determines that a consolidated taxable income computed with respect to the affiliated group, but without regard to subdivisions (i) and (ii) of this subparagraph, will not serve to distort the income tax liability of the group or of any of its members.

(10) *Loss to group of investment in an affiliate.* In the case of a loss to one or more members of an affiliated group sustained during the taxable year as the result of the worthlessness of the investment of such members in another affiliate, whether such investment was reflected in the stock, bonds, or open account advances to such other affiliate—

(i) Such losses shall be taken into account in the computation of consolidated taxable income for the year of the loss in an amount not greater in the aggregate than the excess of the consolidated taxable income for such year computed without regard to any such loss over that portion of such consolidated taxable income so computed attributable to such other affiliate; and

(ii) The portion of any such loss otherwise allowable as a deduction for the taxable year which is disallowed pursuant to the provisions of subdivision (i) of this subparagraph shall be considered as a consolidated net operating loss to be taken into account as a consolidated carryback to the two preceding taxable years or, if the loss is sustained in a taxable year ending after December 31, 1957,

the three preceding taxable years and as a consolidated carryover to the five succeeding taxable years, but in an amount not greater for any taxable year than the excess of the consolidated taxable income for such year, computed without regard to such carryover or carryback, as the case may be, over that portion of such consolidated taxable income so computed for such taxable year attributable to such other affiliate.

(11) *Disposal of timber or coal*—(i) *Intercompany transactions.* Section 631 (b) or (c) (relating to the disposal of timber or coal) shall apply to an amount received by a member of the group only to the extent such amount is received by the member of the group as a party to a transaction described in section 631 (b) or (c) with persons not members of the group.

(ii) *Application of sections 531 and 541 to coal royalties.* For the purpose of determining the consolidated accumulated taxable income and the consolidated undistributed personal holding company income the provisions of 631 (c) shall not apply to any amount received by a member of the group upon the disposal of coal.

(12) *Mine exploration expenditures*—(i) *Limitation under section 615 (a).* If the aggregate of the deductions, computed without regard to this sentence, allowable under section 615 (a) to the several members of the group exceeds \$100,000,

(a) The deduction under that section allowable to any member of the group shall be an amount which bears the same ratio to \$100,000 as its deduction computed without regard to this sentence bears to the aggregate of such deductions so computed for the members of the group, except that,

(b) If all the members of the group consent in writing, the deduction under that section allowable to such member shall be the deduction under that section computed without regard to this sentence, or such part thereof as the common parent corporation shall determine at the time the consent is filed, provided, however, that the aggregate of the deductions so allowable for all members of the group shall not exceed \$100,000.

(ii) *Limitation under 615 (c).* If the limitation provided in section 615 (c) is applicable to any member of the group, such limitation shall be deemed applicable to all members of the group.

(13) *Apportionment of unused dividend carryover and allowance of consolidated deficiency dividends deduction*—

(i) *Apportionment of unused dividend carryover.* If an affiliated group filing a consolidated return has an unused consolidated dividend carryover and if there are included as members of such group one or more corporations which make separate returns, or join in a consolidated return filed by another affiliated group or if any member of the group computes its tax liability under section 541 pursuant to the last sentence of paragraph (b) (4) of § 1.1502-30A, in a succeeding taxable year, the portion of such unused consolidated dividend carryover attributable to such corporations severally shall be determined for the purpose of the dividend carryover, such

portion in the case of any such corporation shall be determined in an amount proportionate to the deduction for dividends paid and the taxable incomes of the several affiliated corporations (determined with the adjustments provided in section 545) to the extent that such deduction and such taxable income were taken into account in the computation of the consolidated dividend carryover and the consolidated and undistributed personal holding company income.

(ii) *Deficiency dividends deduction.* For the purpose of applying section 547, relating to deficiency dividends, in case the affiliated group is subject to tax on its consolidated undistributed personal holding company income for the taxable year to which the deficiency in personal holding company tax relates, the consolidated deficiency dividends deduction described in paragraph (a) (25) of this section shall be allowed.

(14) *Apportionment of consolidated charitable contribution deduction.* If an affiliated group filing a consolidated return has an excess of the consolidated charitable contribution deduction over the limitation of paragraph (a) (1) (i) (c) of this section for the taxable year, and if there are included as members of such group one or more corporations which make separate returns or join in a consolidated return filed by another affiliated group in a succeeding taxable year, the portion of such excess attributable to such corporations severally shall be determined, such portion in the case of any such corporation being determined in an amount proportionate to such excess as the contributions of each such corporation bear to the aggregate of such contributions.

(15) *Limitation on section 175 carryovers from separate return years.* In no case shall there be included in the consolidated section 175 deductions for the taxable year as consolidated section 175 carryovers under paragraph (a) (35) (ii) of this section (relating to excess section 175 deductions of a corporation for years for which separate returns were filed or for which such corporation joined in a consolidated return filed by another affiliated group), an amount exceeding in the aggregate the amount by which 25 percent of the gross income of such corporation derived from farming included in the computation of the consolidated section 175 gross income for the taxable year exceeds the amount of the expenditures of such corporation of the taxable year deductible under section 175.

(16) *Apportionment of consolidated section 175 deduction.* If an affiliated group filing a consolidated return has an excess of the consolidated section 175 deduction over the limitation of 25 percent of the consolidated section 175 gross income for the taxable year, and if there are included as members of such group one or more corporations which make separate returns, or are joined in a consolidated return filed by another affiliated group, in a succeeding taxable year, the portion of such excesses attributable to such corporations severally shall be determined; such portion in the case of any such corporation being determined in an amount proportionate to such excess as the deductions of each such cor-

poration bears to the aggregate of such deductions.

(17) *Applicability of consolidated section 175 deduction.* An affiliated group shall not be eligible to use the consolidated section 175 deduction unless all of the members of such group which are engaged in the business of farming during the taxable year have adopted, pursuant to section 175 (d), the method described in section 175. In the case of a corporation which is a member of an affiliated group which is not eligible to use the consolidated section 175 deduction, the deduction provided by section 175 shall be used in the computation of the taxable income of such corporation in the same manner and under the same conditions as if a separate return were to be filed, except that the gross income from farming of such corporation shall be determined without regard to profits or losses on intercompany transactions; and proper adjustment shall be made to eliminate any distortion in the amount of gross income attributable to transactions between members of the group at markedly fictitious values.

(18) *Computation of consolidated accumulated taxable income.* In the computation of consolidated accumulated taxable income no amount shall be taken into account with respect to any income or deductions attributable to members of the affiliated group which are subject to tax under section 541 as described in the last sentence of paragraph (b) (4) of § 1.1502-30A.

(19) *Law applicable to the computation of consolidated dividends carryover.* In the computation of the consolidated section 561 dividends paid deduction, the amount of the consolidated dividends carryover from a year to which subtitle A of the Code is not applicable to a taxable year to which such subtitle applies shall be determined under 26 CFR (1939) part 24 (Regulations 129) if a consolidated return was filed for the year in which the dividends were paid or under the provisions of the Internal Revenue Code of 1939 if a separate return was filed for such year.

(20) *Law applicable to computation of deficiency dividends deduction.* If a deficiency is asserted with respect to a taxable year which began before January 1, 1954, the amount of any "deficiency dividend" shall include only amounts which would have been includible in the computation of the consolidated basic surtax credit, as defined in 26 CFR (1939) Part 24 (Regulations 129), or in the computation under the Internal Revenue Code of 1939 of the basic surtax credit for such taxable year, as the case may be.

(21) *Rules with respect to net operating losses under sections 381 and 382.* (i) If, in the computation of the consolidated net operating loss carryover, there is included an amount with respect to a net operating loss of a corporation, sustained in a taxable year for which it filed a separate return or for which such corporation joined in a consolidated return filed for another affiliated group, which is a transferor or distributor of assets to a member of the affiliated group within the meaning of section 381 (a), the amount allowable as a carryover with

respect to such transferor or distributor shall not exceed the amount of the taxable income of the acquiring corporation included in the computation of the consolidated taxable income for the taxable year, adjusted as provided in subparagraph (3) (ii) of this paragraph. The preceding sentence shall not apply to a carryover—

(a) To taxable years beginning after December 31, 1963, attributable to a net operating loss or losses sustained by a corporation in a taxable year or years beginning before January 1, 1964, in which such corporation was (on each day of any such year) a member of the affiliated group, or

(b) Attributable to a taxable year beginning after December 31, 1963, in which the corporation sustaining the loss was (on each day of such year) a member of the affiliated group, provided that an election under section 1562 (relating to privilege of groups to elect multiple surtax exemptions) was not effective for such year.

(ii) If, in addition to the amount described in subdivision (i) of this subparagraph, there is included an amount with respect to a net operating loss sustained by the acquiring corporation in a year for which it filed separate returns or for which it joined in a consolidated return filed by another affiliated group, the losses sustained by both the acquiring corporation and the transferor or distributor corporation which may be taken into account as a net operating loss deduction in determining the consolidated taxable income may not exceed the taxable income of the acquiring corporation included in the computation of the consolidated taxable income for the taxable year, adjusted as provided in subparagraph (3) (ii) of this paragraph. The preceding sentence shall not apply to a carryover—

(a) To taxable years beginning after December 31, 1963, attributable to a net operating loss or losses sustained by the acquiring corporation in a taxable year or years beginning before January 1, 1964, in which such corporation was (on each day of any such year) a member of the affiliated group, or

(b) Attributable to a net operating loss sustained by the acquiring corporation in a taxable year beginning after December 31, 1963, in which such corporation was (on each day of such year) a member of the affiliated group, provided that an election under section 1562 (relating to privilege of groups to elect multiple surtax exemptions) was not effective for such year.

(iii) For purposes of subdivisions (i) and (ii) of this subparagraph, if the transferor or distributor corporation was a member of another affiliated group which filed a consolidated return, the amount of the consolidated net operating loss of such affiliated group, if any, attributable to such transferor or distributor, shall be treated as the net operating loss of such corporation separately sustained.

(iv) In any case in which a consolidated net operating loss was sustained by an affiliated group which includes a member whose net operating loss is sub-

ject to the limitations upon net operating losses provided by section 382, such section shall be applicable with respect to such member as if the portion of such consolidated net operating loss attributable to such corporation were a net operating loss of such corporation separately sustained.

(22) *Rules with respect to capital loss carryovers under section 381.* (i) If in the computation of the consolidated net capital loss carryovers for a taxable year there is included an amount with respect to a net capital loss of a corporation, sustained in a taxable year for which it filed a separate return or for which such corporation joined in a consolidated return filed by another affiliated group, which is a transferor or distributor of property to a member of the affiliated group within the meaning of section 381 (a), the amount allowable with respect to such transferor or distributor shall not exceed the net capital gains of the acquiring corporation (determined without regard to any net capital loss carryover) included in the computation of the consolidated net capital gain for the taxable year increased with respect to its separate gains for involuntary conversions and from sales or exchanges of property subject to the provisions of section 1231.

(ii) If there is included under paragraph (a) (11) (ii) of this section an amount with respect to net capital losses separately sustained by such acquiring corporation in years for which separate returns were filed or for which such corporation joined in a consolidated return filed by another affiliated group, the limitation described in subdivision (i) of this subparagraph shall be applicable with respect to the aggregate of such losses and the losses of its transferor or distributor corporations.

(iii) For purposes of subdivisions (i) and (ii) of this subparagraph, if the transferor or distributor corporation was a member of another affiliated group which filed a consolidated return, the amount of the consolidated net capital loss of such affiliated group, if any, attributable to such transferor or distributor, shall be treated as the net capital loss of such corporation separately sustained.

(c) *Statements and schedules for subsidiaries.* The statement of gross income and deductions and the several schedules required by the instructions on the return must be prepared and filed by the common parent corporation in columnar form so that the details of the items of gross income, deductions, and credits, for each member of the affiliated group, may be readily audited. Such statements and schedules shall include in columnar form a reconciliation of surplus for each such corporation, together with a reconciliation of the consolidated surplus. Consolidated balance sheets as of the beginning and close of the taxable year of the group, taken from the books of the members of the group, shall accompany the consolidated return prepared in a form similar to that required for reconciliation of surplus. If any member of the affiliated group computes its tax under section

541 in the manner provided in paragraph (b) (4) of § 1.1502-30A, a personal holding company schedule for such corporation shall be filed with the consolidated return.

(d) *Net operating loss deduction, excess charitable contributions, excess section 175 deductions, and dividend carryover before or after consolidated return—*(1) *Net operating loss deduction.* The consolidated net operating loss of an affiliated group shall be used in computing the consolidated net operating loss deduction notwithstanding that one or more members of the group in the taxable year in which such loss originates make separate returns (or join in a consolidated return made by another affiliated group) for a subsequent taxable year (or in the case of a carryback computation for a preceding taxable year), but only to the extent that such consolidated net operating loss is not attributable to such corporations. Such portion of such consolidated net operating loss as is attributable to the several corporations making separate returns (or joining in a consolidated return made by another affiliated group) for a subsequent taxable year (or in the case of a carryback computation for a preceding taxable year) shall be used by such corporations severally as carryovers or as carrybacks in such separate returns or in such consolidated returns of the other affiliated group. Any net operating loss separately sustained by a corporation prior to a first taxable year in respect of which its income is included in the consolidated return of the group (or sustained in either of the two taxable years immediately following a consolidated return year or any of the three taxable years so following if sustained in a taxable year ending after December 31, 1957) shall be used in computing the net operating loss deduction of such corporation (or the consolidated net operating loss deduction of another affiliated group of which it becomes a member) for a subsequent taxable year for which it makes a separate return or joins in a consolidated return of another group, but only to the extent that such net operating loss was not absorbed (either as a carryover or as a carryback) in the computation of the consolidated net operating loss deduction for consolidated return periods.

(2) *Excess charitable contributions.* The excess of the consolidated charitable contributions over the 5-percent limitation of paragraph (a) (1) (i) (c) of this section shall be used in computing the consolidated charitable contribution carryover notwithstanding that one or more members of the group in the taxable year in which such carryover originates make separate returns (or join in a consolidated return made by another affiliated group) for a subsequent taxable year, but only to the extent that such excess charitable contribution is not attributable to such corporations. Such portion of such excess charitable contributions as is attributable to the several corporations making separate returns (or joining in a consolidated return made by another affiliated group) for a subsequent tax-

able year shall be used by such corporations severally as carryovers in such separate returns or in such consolidated returns of the other affiliated group. Any excess of charitable contributions of a corporation for the year prior to a first taxable year in respect of which its income is included in the consolidated return of the group shall be used in computing the charitable contribution deduction of such corporation (or the consolidated charitable contribution deduction of another affiliated group of which it becomes a member) for a subsequent taxable year for which it makes a separate return or joins in a consolidated return of another group, but only to the extent that such excess charitable contribution was not absorbed as a carryover in the consolidated charitable contribution deduction for consolidated return periods. In applying this paragraph, the excess of the consolidated charitable contributions over the 5-percent limitation shall be reduced by the increase in a consolidated or separate net operating loss carryover resulting from such excess.

(3) *Excess section 175 deductions.* The excess of the deductions under section 175 over the limitation of 25 percent provided in paragraph (a) (1) (i) (f) of this section shall be used in computing the consolidated section 175 carryover notwithstanding that one or more members of the group in the taxable year in which such carryover originates make separate returns (or join in a consolidated return made by another affiliated group) for a subsequent taxable year, but only to the extent that such excess section 175 deduction is not attributable to such corporations. Such portion of such excess section 175 deductions as is attributable to the several corporations making separate returns (or joining in a consolidated return made by another affiliated group) for a subsequent taxable year shall be used by such corporations severally as carryovers in such separate returns or in such consolidated returns of the other affiliated group. Any excess of section 175 deductions of a corporation for a year prior to a first taxable year in respect of which its income is included in the consolidated return of the group shall be used in computing the section 175 deduction of such corporation (or the consolidated section 175 deduction of another affiliated group of which it becomes a member) for a subsequent taxable year for which it makes a separate return or joins in a consolidated return of another group, but only to the extent that such excess section 175 deduction was not absorbed as a carryover in the computation of a consolidated section 175 deduction for consolidated return periods.

(4) *Unused consolidated dividend carryover.* The unused consolidated dividend carryover shall be used in computing the consolidated dividend carryover notwithstanding that one or more members of the group in the taxable year in which such carryover originates make separate returns (or join in a consolidated return made by another affiliated group) for a subsequent taxable year, but only to the extent that such unused consolidated dividend carryover is not attributable to such corporations. Such

portion of such unused consolidated dividend carryover as is attributable to the several corporations making separate returns or computing their tax liability under section 541 pursuant to the last sentence of paragraph (b) (4) of § 1.1502-30A (or joining in a consolidated return made by another affiliated group) for a subsequent taxable year shall be used by such corporations severally as carryovers in such separate returns, in such separate computations under section 541, or in such consolidated returns of the other affiliated group. Any unused dividend carryover of a corporation separately produced for a year prior to a taxable year in respect of which its tax liability under section 541 is computed upon the consolidated undistributed personal holding company income shall be used in computing the dividend carryover of such corporation (or the consolidated dividend carryover of another affiliated group of which it becomes a member) for a subsequent taxable year for which it makes a separate return or joins in a consolidated return of another group, but only to the extent that such unused dividend carryover was not absorbed in the computation of the consolidated section 561 dividends paid deduction for the intervening consolidated return period.

(e) *Taxable year of less than 12 months.* Any period of less than 12 months for which either a separate return or a consolidated return is filed under the provisions of § 1.1502-13A shall be considered as a taxable year.

§ 1.1502-32A Method of computation of income for period of less than 12 months.

If a corporation, during the taxable year of the group, becomes a member or ceases to be a member of an affiliated group which makes or is required to make a consolidated return for such year, the income of such corporation to be included in the consolidated return shall be computed on the basis of its income as shown by its books if the accounts are so kept that the income for the period during which it is a member of the group can be clearly and accurately determined. If the accounts are not so kept, the income to be included in the consolidated return shall be computed on the basis of that proportion of its income (subject to the elimination of items exempt from the taxation and the addition of items not allowable as deductions) for the full period covered by its books which the number of days for which its income is included in the consolidated return bears to the number of days in the full period covered by its books; but, in the discretion of the Commissioner, there may be eliminated before the proration is made items of income or deduction clearly and accurately determined to be attributable to particular periods, and, after the proration is made, such eliminated items will be added to (if items of income) or deducted from (if deductible items) the income determined by proration for the period to which such items are applicable.

§ 1.1502-33A Gain or loss from sale of stock, or bonds or other obligations.

Gain or loss from the sale or other disposition (whether or not during a consolidated return period), by a corporation which during any period of time has been a member of an affiliated group which makes or is required to make a consolidated return, of any share of stock or any bond or other obligation issued or incurred by another corporation which during any part of such period was a member of the same group, shall be determined, and the extent to which such gain or loss shall be recognized and shall be taken into account shall also be determined, in the same manner, to the same extent, and upon the same conditions as though such corporations had never been affiliated except—

(a) In the case of a disposition (by sale, or in complete or partial liquidation not involving cash in an amount in excess of the adjusted basis of both the stock and the bonds and other indebtedness liquidated, or otherwise) during a consolidated return period to another member of the group (§§ 1.1502-31A and 1.1502-37A);

(b) That the basis for determining the gain or loss, in the case of shares of stock, or in the case of bonds or other obligations, held during any part of a consolidated return period, shall be determined in accordance with §§ 1.1502-34A and 1.1502-35A; and

(c) As provided in § 1.1502-36A (imposing certain limitations upon losses otherwise allowable upon sales of stock, or bonds or other obligations).

§ 1.1502-34A Sale of stock; basis for determining gain or loss.

(a) *Scope of section.* This section prescribes the basis for determining the gain or loss upon any sale or other disposition (hereinafter referred to as "sale") by a corporation which is (or has been) a member of an affiliated group which makes (or has made) a consolidated return for any taxable year, of any share of stock issued by another member of such group (whether issued before or during the period that it was a member of the group and whether issued before, during, or after the taxable year 1929), and held by the selling corporation during any part of a period for which a consolidated return is made or required under the regulations under section 1502. For the basis in the case of a sale of bonds, see § 1.1502-35A.

(b) *Sales made while selling corporation is member of affiliated group.* If the sale is made within a period during which the selling corporation is a member of the affiliated group, whether or not during a consolidated return period, and whether or not, as a result of such sale, the issuing corporation ceases to be a member of the group, the basis shall be determined as follows:

(1) The aggregate bases of all shares of stock of the issuing corporation held by each member of the affiliated group (exclusive of the issuing corporation) immediately prior to the sale, shall be determined separately for each member of the group, and adjusted in accordance with the other provisions of subtitle A of the Code, but without regard to any adjustment under the last sentence of

section 1051 relating to losses of the issuing corporation sustained by such corporation after it became a member of the group.

(2) From the combined aggregate bases as determined in subparagraph (1) of this paragraph, there shall be deducted the sum of—

(i) All losses of such issuing corporation sustained during taxable years for which consolidated income tax returns were made or were required (whether the taxable year 1929 or any prior or subsequent taxable year) after such corporation became a member of the affiliated group and prior to the sale of the stock to the extent that such losses could not have been availed of by such corporation as net loss or net operating loss in computing its net income or taxable income, as the case may be, for such taxable years if it had made a separate return for each of such years,

(ii) With respect to each of such taxable years for which consolidated returns were made or were required both for income and for excess profits tax purposes, the excess, if any, of all losses of such issuing corporation for such year, properly adjusted in the computation of consolidated excess profits net income over the amount of such losses for such year computed under subdivision (i) of this subparagraph to the extent that such excess could not have been availed of by such corporation as a net operating loss in computing its excess profits net income for such taxable years if it had made a separate return for each of such years, and

(iii) With respect to each of such taxable years for which consolidated returns were made or were required for excess profits tax purposes only, all losses of such issuing corporation for such year, properly adjusted in the computation of consolidated excess profits net income, to the extent that such losses could not have been availed of by such corporation as a net operating loss in computing its excess profits net income for such taxable years if it had made a separate excess profits tax return for each of such years,

reduced by any losses of the issuing corporation apportioned under this section to its stock sold or otherwise disposed of in a prior transaction, disregarding any transaction between members of the affiliated group during a consolidated income or excess profits tax return period which did not constitute a partial liquidation of the issuing corporation. For any taxable year in which the group sustained a consolidated loss not availed of in prior or subsequent years as a deduction under net loss or net operating loss provisions, the amount deducted under this subparagraph shall be further reduced by an amount equal to that proportion of such consolidated loss which the loss of the issuing corporation for the year in which such loss was sustained bears to the aggregate losses of the members of the group for such year.

(3) The sum of the aggregate bases of all shares of stock, after making the deduction under subparagraph (2) of this paragraph, shall then be apportioned among the members of the affiliated group which hold stock of the issuing corporation, by allocating to each

such member that proportion of the sum of the aggregate bases so reduced which the aggregate basis of the stock in the issuing corporation held by such member bears to the sum of the aggregate bases.

(4) The aggregate basis as determined under subparagraph (3) of this paragraph for each member of the affiliated group shall then be equitably apportioned among the several classes of stock of the issuing corporation held by such member according to the circumstances of the case—ordinarily by allocating to each class of such stock that proportion of the aggregate basis which the basis of each class of such stock held by it at the time of the sale is to the sum of the bases of the several classes of such stock held by it.

(5) The basis of each share of stock of each class held by a member of the affiliated group shall then be determined by dividing the basis apportioned to such class under subparagraph (4) of this paragraph by the total number of shares of such class held by it.

(c) *Sales after selling corporation has ceased to be member of affiliated group.* If the sale is made after the selling corporation has ceased to be a member of the affiliated group, such basis shall be determined in accordance with paragraph (b) of this section, except that—

(1) The aggregate basis (under paragraph (b) (1) of this section) shall be determined for all shares of the issuing corporation held by each member of the group immediately prior to the time the selling corporation ceased to be a member of the group (rather than immediately prior to the sale);

(2) The reduction (under paragraph (b) (2) of this section) with respect to losses apportioned to stock sold or otherwise disposed of in prior transactions shall be determined without regard to the transaction which terminated the affiliation and all subsequent transactions;

(3) The allocation (under paragraph (b) (3) of this section) shall be made to each member of the group which held stock of the issuing corporation immediately prior to the time the selling corporation ceased to be a member of the group (rather than to the members holding such stock at the time of the sale); and

(4) The basis of each share of stock held by the selling corporation (determined, as above, as of the time the selling corporation ceased to be a member of the group) shall then be adjusted in accordance with the other provisions of subtitle A of the Code in order to determine the basis at the time of the sale.

(d) *Definition of "loss", "consolidated loss", "net loss", or "net operating loss", and "consolidated excess profits net income".* As used in this section the term "loss" means either the excess over the gross income of the issuing corporation of the sum of its allowable deductions (not including any net loss or net operating loss deduction) allowable in computing consolidated taxable income or the excess over the gross income of the issuing corporation of the sum of its allowable deductions (not including any net loss or net operating loss deduction), plus the proportionate part properly attributable to such corporation of the credits relating to interest on certain

Government obligations and dividends received allowable in computing consolidated normal tax net income, the consolidated special class net income or consolidated net income subject to tax determined in accordance with the Internal Revenue Code of 1939 and provisions of consolidated returns regulations applicable to the period. The term "consolidated loss" means the excess of the sum of the losses, separately computed, over the sum of the normal tax net income, the special class net income, the net income subject to tax or the taxable income determined in accordance with the provisions of subtitle A of the Internal Revenue Code of 1954, or the Internal Revenue Code of 1939, or the Revenue Act, and pursuant to the provisions of consolidated returns regulations applicable to the period; the term "net loss" or "net operating loss" means the net loss or net operating loss, as the case may be, determined in accordance with the provisions of subtitle A of the Internal Revenue Code of 1954, or the Internal Revenue Code of 1939, or the Revenue Act, and pursuant to the provisions of consolidated returns regulations applicable to the period; and the term "consolidated excess profits net income" means the consolidated excess profits net income or consolidated section 433 (a) excess profits net income determined in accordance with the provisions of the Internal Revenue Code of 1939 or the Revenue Act and pursuant to the provisions of consolidated returns regulations applicable to the period.

§ 1.1502-35A Sale of bonds or other obligations; basis for determining gain or loss.

In the case of a sale or other disposition by a corporation, which is (or has been) a member of an affiliated group which makes (or has made) a consolidated income tax or excess profits tax return for any taxable year, of bonds or other obligations issued or incurred by another member of such group (whether or not issued or incurred while it was a member of the group and whether issued or incurred before, during, or after the taxable year 1929) and held by the selling corporation during any part of a period for which a consolidated return is made or required under the regulations under section 1502, the basis of each bond or obligation, for determining the gain or loss upon such sale or other disposition, determined in accordance with the other provisions of subtitle A of the Code, but without regard to any adjustment under the last sentence of section 1051, shall be decreased (except as otherwise provided in this section) by the excess, if any, of the aggregate of the deductions computed under paragraph (b) (2) or (c) of § 1.1502-34A over the sum of the aggregate bases of the stock of the debtor corporation as computed under paragraph (b) (1) or (c) of § 1.1502-34A as the case may be, held by the members of the group. The adjustment with respect to so much of such deductions as is based upon losses sustained during the taxable year 1929 and subsequent taxable years for which the last day prescribed by law for the filing of the return fell on or before March 1, 1945 (the date on which

Treasury Decision 5441 was filed with the Division of the Federal Register, and availed of on consolidated returns filed for such years shall be made only in those cases in which the sales or other disposition of such bonds or other obligations resulted in a loss. See also § 1.1502-40A relating to disallowance of loss upon intercompany bad debts.

§ 1.1502-36A Limitation on allowable losses on sale of stock, or bonds, or other obligations.

(a) *General rule.* No loss shall be allowed under §§ 1.1502-33A, 1.1502-34A, or 1.1502-35A upon the sale or other disposition of stock or bonds or obligations to the extent that such loss is attributable to—

(1) Transfers of assets within the affiliated group (by sale, gift, or otherwise) without consideration or at markedly fictitious values, during the period in which the corporations were affiliated (whether or not a consolidated return was made), or

(2) A distribution during a period in which the corporations were affiliated of earnings or profits accumulated prior to the date upon which the distributing corporation became a member of the group.

(b) *Qualification of general rule.* Paragraph (a) of this section shall not be considered as in any way limiting the operation of the provisions of subtitle A of the Code relating to the basis for determining gain or loss upon the sale or other disposition of property, but as being in amplification of and not in substitution for such provisions; subject, however, to this qualification: that to the extent that the transfers of assets referred to in paragraph (a) of this section are taken into account under the terms of subtitle A in making adjustments in the basis, such transfers will not be taken into account, in denying losses under paragraph (a) of this section.

§ 1.1502-37A Liquidations; recognition of gain or loss.

(a) *During consolidated return period.*

(1) Gain or loss shall not be recognized upon a distribution during a consolidated return period, by a member of an affiliated group to another member of such group, in cancellation or redemption of all or any portion of its stock, except—

(i) Where such distribution is in complete liquidation and redemption of all of its stock (whether in one distribution or a series) and of its bonds and other indebtedness, if any, and falls without the provisions of section 332, and is the result of a bona fide termination of the business and operations of such member of the group, in which case the adjustments specified in §§ 1.1502-34A and 1.1502-35A shall be made, and § 1.1502-36A shall be applicable;

(ii) Where such a distribution without the provisions of section 332 is one made in cash in an amount in excess of the adjusted basis of the stock, and bonds and other indebtedness, in which case gain shall be recognized to the extent of such excess; or

(iii) Where the basis of the property distributed in the hands of the distributee is determined by reference to section 334(b) (2), in which case gain shall be

recognized as provided in section 1245(a) (1).

(2) When the business and operations of the liquidated member of the affiliated group are continued by another member of the group, it shall not be considered a bona fide termination of the business and operations of the liquidated member. With respect to the acquisition of its bonds by the issuing company, see paragraph (b) of § 1.1502-41A.

(3) For the purpose of determining whether an affiliated corporation receiving property in a liquidating distribution qualifies under the provisions of section 332(b) (1), the aggregate amount of the stock of the liquidated corporation owned by the several members of the affiliated group on the date of the adoption of the plan of liquidation and at all times, subsequent thereto and prior to the receipt of the property in liquidation shall be considered as owned by the distributee.

(b) *After consolidated return period.* In case any such distribution is made after a consolidated return period, whether in complete or partial liquidation, except a complete liquidation within the provisions of section 332 (b), with respect to stock and with respect to bonds, debentures, notes, certificates, and other indebtedness of the liquidated corporation acquired prior to or during any taxable year subsequent to 1928 for which a consolidated income or excess profits tax return was filed, the adjustments specified in §§ 1.1502-34A and 1.1502-35A shall be made, and § 1.1502-36A will be applicable.

§ 1.1502-38A Basis of property.

(a) *General rule.* Subject to the provisions of paragraphs (b) and (c) of this section and except as otherwise provided in §§ 1.1502-34A, 1.1502-35A, and 1.1502-39A, the basis during a consolidated return period for determining the gain or loss from the sale or other disposition of property, or upon which exhaustion, wear and tear, obsolescence, amortization, and depletion are to be allowed, shall be determined and adjusted in the same manner as if the corporations were not affiliated, whether such property was acquired before or during a consolidated return period. Except as otherwise provided in § 1.1502-39A, such basis immediately after a consolidated return period (whether the affiliation has been broken or whether the privilege of making a consolidated return is not exercised) shall be the same as immediately prior to the close of such period.

(b) *Intercompany transactions.* The basis prescribed in paragraph (a) of this section shall not be affected by reason of a transfer during a consolidated return period, other than upon liquidation as provided in paragraph (c) of this section (whether by sale, gift, dividend, or otherwise) from a member of the affiliated group to another member of such group.

(c) *Basis after liquidation.* (1) Where property is acquired upon a distribution described in paragraph (a) of § 1.1502-37A in which gain or loss is recognized to the distributee, the basis of such property shall be its fair market value at date of acquisition.

(2) Where property is acquired upon a liquidation to which section 332 is applicable and if the first distribution in pursuance of the plan of liquidation occurs on or after June 22, 1954—

(i) Unless subdivision (ii) of this subparagraph is applicable, the basis of such property shall be the same as it would be in the hands of the transferor;

(ii) If the basis of such property is determined by reference to section 334(b) (2), such section (and, if applicable, section 1245(c)) shall be applicable in determining the basis of property received on the liquidation (except property received by the liquidating corporation from other members of the affiliated group during a consolidated return period) and to any property transferred by the liquidating corporation to other members of the group during a consolidated return period as if such property had not been transferred and was received in such liquidation. In addition, proper adjustment shall be made with respect to the effect of any other transactions between members of the group during a consolidated return period which creates a distortion of income or a substantial variation in basis of property from the basis such property would have had if there had been no such transactions.

(3) Where property is acquired upon a distribution (not a complete liquidation within the provisions of section 332 (b)) in which gain or loss to the distributee is not recognized as provided in paragraph (a) of § 1.1502-37A the basis of such property shall be the same as the basis of the stock and the bonds and other obligations exchanged therefor, adjusted for—

(i) The transfer of assets within the affiliated group by the distributing corporation (by sale, gift, or otherwise) without consideration or at markedly fictitious values, during the period for which the corporations were affiliated (whether or not a consolidated return was made);

(ii) Distributions during a period in which the corporations were affiliated of earnings or profits accumulated prior to the date upon which the distributing corporation became a member of the group; and

(iii) Cash received in the distribution.

(4) Where property was acquired upon a distribution in which gain or loss to the distributee was recognized pursuant to the provisions of section 333 (a) or the corresponding provisions of the Internal Revenue Code of 1939 or the Revenue Act of 1938, the basis of such property shall be the same as the basis of the stock exchanged therefor, adjusted for—

(i) The transfer of assets within the affiliated group by the distributing corporation (by sale, gift, or otherwise) without consideration or at markedly fictitious values, during the period for which the corporations were affiliated (whether or not a consolidated return was made);

(ii) Distribution during a consolidated return period of earnings or profits accumulated prior to the date upon which the distributing corporation became a member of the group;

(iii) Cash received in the distribution; and

(iv) The amount of gain recognized to the distributee in the liquidation.

(d) *Basis not affected by acquisition or sale of stock.* Neither the acquisition of stock of a corporation nor its sale or other disposition shall affect the basis of the property of such corporation for determining gain or loss or upon which exhaustion, wear and tear, obsolescence, amortization, and depletion are to be allowed.

§ 1.1502-39A Inventories.

(a) *Consolidated return for first year of affiliation.* If the income of an affiliated corporation is included in a consolidated return for the period immediately following the date upon which such corporation became a member of the affiliated group, the value of its opening inventory to be used in computing the consolidated taxable income shall be the proper value of the closing inventory used in computing its taxable income for the preceding taxable year.

(b) *Consolidated return after separate return by affiliates.* If—

(1) A corporation which is a member of the affiliated group for the first consolidated return period was a member of the group in the preceding taxable year, or

(2) A corporation which filed a separate return for its previous taxable year was not a member of the affiliated group within the meaning of section 141 of the Internal Revenue Code of 1939, at any time during the last taxable year of the group not subject to section 1502, but which would have been a member of the group during such period if section 1504 had been applicable and is a member of the affiliated group filing a consolidated return for the first taxable year to which section 1502 is applicable,

the value of its opening inventory to be used in computing the consolidated taxable income for the first consolidated return period shall be the proper value of the closing inventory used in computing its taxable income for the preceding taxable year, decreased in the amount of profits or increased in the amount of losses reflected in such inventories which arose in transactions between members of the affiliated group and which have not been realized by the group through final transactions with persons other than members of the group.

(c) *Separate returns made after consolidated returns.* If a corporation which was a member of an affiliated group in a consolidated return period makes or is required to make a separate return for the succeeding taxable year, the value of its opening inventory to be used in computing its taxable income for such succeeding taxable year shall be the proper value of its closing inventory used in computing consolidated taxable income for the last consolidated return period increased in the amount of profits or decreased in the amount of losses eliminated in the computation of such inventory as profits or losses arising in transactions between members of the affiliated group, but in an amount not exceeding, in the case of profits, either the amount of profits arising from such intercompany transactions reflected in the closing inventory of such corporation for such succeeding taxable

year or the amount of such intercompany profits eliminated from its opening inventory for its first consolidated return period pursuant to the provisions of paragraph (b) of this section, and not exceeding, in the case of losses, either the amount of losses arising from intercompany transactions reflected in the closing inventory for such corporation for such succeeding taxable year or the amount of such intercompany losses eliminated from its opening inventory for its first consolidated return period pursuant to the provisions of paragraph (b) of this section.

§ 1.1502-40A Bad debts.

(a) *Deduction during consolidated return period.* No deduction shall be allowed during a consolidated return period to any member of the affiliated group on account of worthlessness in whole or in part of any obligation (including accounts receivable, bonds, notes, debts, and claims of whatsoever nature) of any other corporation which was a member of the group as of the last day of the taxable year or which was liquidated by the group during such year, except as a loss resulting from a bona fide termination of the business and operations of such other corporation, whether in liquidation or otherwise, in which case the loss shall be computed subject to the adjustments specified in § 1.1501-35A and the provisions of § 1.1502-36A shall be applicable.

(b) *Limitation of allowance after consolidated return period.* With respect to obligations (including accounts receivable) of a member of an affiliated group acquired in any way by another member of the group prior to or during any taxable year subsequent to 1928 for which a consolidated income or excess profits tax return was filed, the adjustments prescribed with respect to the allowance of losses upon the sale of bonds shall be applicable to the allowance of any bad debt deduction for any period subsequent to the consolidated return period. See § 1.1502-35A.

§ 1.1502-41A Sale and retirement by corporation of its bonds.

(a) *Issued at discount or premium.* If a corporation which during any taxable year has been a member of an affiliated group which makes or is required to make a consolidated return, has issued its bonds at a discount or premium (whether or not during a consolidated return period), deduction will be allowed for the amortization of the discount, and income included for the amortization of the premium, in the same manner, to the same extent, and upon the same conditions as if the corporation had never been affiliated, except that no deduction for amortization of discount shall be allowed, and no income shall be included for amortization of premium, during a period for which a consolidated return is made, on bonds of one member of the group owned by another member of the group.

(b) *Acquisition of bonds by issuing company.* If a corporation which has been a member of an affiliated group which makes or is required to make a consolidated return, acquires its bonds (whether or not from another member of such group and whether or not during a consolidated return period), gain or

loss shall be recognized in the same manner to the same extent and upon the same conditions as if the corporation had never been affiliated, except that, if such bonds are acquired from another member of the group during a consolidated return period, and in a transaction other than a distribution in a liquidation in which gain or loss to the distributee is recognized pursuant to paragraph (a) of § 1.1502-37A in determining the gain or loss to the issuing company from such acquisition, the basis thereof to such other member of the group shall be deemed the purchase price.

§ 1.1502-42A Capital loss limitations and carryover.

(a) The provisions of sections 165, 832(c)(5), 1211, 1212, and 1231 with respect to gains and losses from sales or exchanges of capital assets shall be applied, in respect of such gains and losses sustained during a consolidated return period as if the affiliated group were the taxpayer.

(b) With respect to a net capital loss sustained by a corporation in a taxable year prior to the first consolidated return period in respect of which its income is included in a consolidated return, such loss (in an amount not in excess of the net capital gain of such corporation for succeeding consolidated return periods) shall, for the purposes of section 1212, relating to net capital loss carryovers, be treated as if such net capital loss had been sustained by the affiliated group.

(c) A consolidated net capital loss of an affiliated group for a consolidated return period shall be considered as a consolidated short-term capital loss in subsequent consolidated return periods notwithstanding that one or more corporations, members of the group in the taxable year in which such loss was sustained, make separate returns for subsequent taxable years (or join in a consolidated return made by another affiliated group), but only to the extent that such consolidated net capital loss is not attributable to such corporations; and such portion of such consolidated net capital loss as is attributable to the several corporations making separate returns (or joining in a consolidated return made by another affiliated group) for a subsequent taxable year shall be considered as a short-term capital loss in such separate returns, or in such consolidated return of the other affiliated group, but only to the extent that such portion of such consolidated net capital loss was not absorbed in intervening taxable years by net capital gains, consolidated or separate, as the case may be. Any net capital loss sustained by a corporation prior to the first taxable year in respect of which its income is included in the consolidated return shall be considered as a short-term capital loss in the separate return of such corporation (or the consolidated return of another affiliated group of which it becomes a member) for a subsequent taxable year for which it makes a separate return or joins in a consolidated return of another group, but only to the extent that such net capital loss was not absorbed in intervening taxable years by net capital gains, consolidated or separate, as the case may be.

§ 1.1502-43A Credit for foreign taxes.

(a) *In general*—(1) *Choice of credit or deduction*. The credit under section 901 for taxes paid or accrued to any foreign country or possession of the United States shall be allowed to an affiliated group filing a consolidated return only if the common parent corporation chooses to use such credit in the computation of the tax liability of the group for the taxable year. If this choice is made, no deduction may be taken under section 164 on the consolidated return for such taxes paid or accrued by any member of the group.

(2) *Amount of credit*. If the per-country limitation on the credit provided in section 904(a)(1) applies in computing the tax liability of the group for the taxable year, the amount of the credit shall be determined under paragraph (b) of this section; if the overall limitation provided in section 904(a)(2) applies, the amount of the credit shall be determined under paragraph (c) of this section. If any member of the group receives "interest income" from sources within any foreign country or any possession, the credit for taxes paid or accrued to such foreign country or possession with respect to such income shall be determined separately under paragraph (d) of this section.

(3) *Definitions*. For purposes of this section—

(i) The term "taxes paid or accrued" includes the amount of taxes deemed paid pursuant to sections 902 and 960(a), and

(ii) The term "interest income" means interest income described in section 904(f)(2) for taxable years beginning after October 16, 1962, but only if such interest income results from transactions consummated after April 2, 1962, and the term "consolidated taxable interest income" means the aggregate interest income of the several members of the affiliated group.

(b) *Amount of credit with respect to noninterest income where per-country limitation applies*—(1) *Taxes allowed as a credit*. Subject to the limitation provided in subparagraph (2) of this paragraph, the credit allowable to an affiliated group filing a consolidated return for taxes paid or accrued with respect to income other than interest income for a taxable year for which the per-country limitation applies shall be an amount equal to the sum of—

(i) The aggregate of the taxes paid or accrued for the taxable year by the several members of the affiliated group to any foreign country or any possession with respect to income other than interest income, and

(ii) The aggregate of the consolidated excess tax paid carryovers and carrybacks to the taxable year under section 904(d) for taxes paid or accrued to such country or possession with respect to income other than interest income.

(2) *Limitation*. The credit allowable under subparagraph (1) of this paragraph for taxes paid or accrued to any foreign country or any possession shall not exceed an amount which bears the same ratio to the total tax of the affiliated group against which the credit is

taken as the consolidated taxable income of the group (computed by excluding any consolidated taxable interest income) from sources within such country or possession (but not in excess of the entire consolidated taxable income of the group) bears to the entire consolidated taxable income. The amount computed under the preceding sentence shall be increased as provided in section 960(b), where applicable.

(3) *Consolidated excess tax paid carryovers*. The consolidated excess tax paid carryovers to the current taxable year for taxes paid or accrued to any foreign country or any possession with respect to income other than interest income shall consist of—

(i) The consolidated excess tax paid, with respect to such income, to such country or possession for the five preceding taxable years (not including as a preceding taxable year any taxable year beginning before January 1, 1958) to the extent that such consolidated excess tax paid for any such preceding taxable year was not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the current taxable year and was not absorbed pursuant to section 904(d) in years preceding the current taxable year (whether or not taken as a credit), and

with respect to the excess tax paid, with respect to income other than interest income, by a corporation in a taxable year for which a separate return was filed, or for which such corporation joined in a consolidated return filed by another affiliated group, but subject to the limitation prescribed in paragraph (g) of this section—

(ii) The amount of such excess tax paid by such corporation to such country or possession for the five preceding taxable years (not including as a preceding taxable year any taxable year beginning before January 1, 1958) to the extent that such excess tax paid for any such preceding taxable year was not absorbed pursuant to section 904(d) in years preceding the current taxable year (whether or not taken as a credit).

(4) *Consolidated excess tax paid carrybacks*. The consolidated excess tax paid carrybacks to the current taxable year for taxes paid or accrued to any foreign country or any possession with respect to income other than interest income shall consist of—

(i) The consolidated excess tax paid, with respect to such income, to such country or possession for the first succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the current taxable year) reduced to the extent absorbed pursuant to section 904(d) in the first preceding taxable year (whether or not taken as a credit), and

(ii) The consolidated excess tax paid, with respect to such income, to such country or possession for the second succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated

group for the current taxable year), and

with respect to the excess tax paid, with respect to income other than interest income, to such country or possession by a corporation which, for either of the two succeeding taxable years, files a separate return or joins in a consolidated return filed by another affiliated group, but subject to the limitation prescribed in paragraph (g) of this section—

(iii) The amount of such excess tax paid by such corporation for the first succeeding taxable year reduced to the extent absorbed pursuant to section 904(d) by such corporation for the first preceding taxable year (whether or not taken as a credit), or if the income of such corporation is included in a consolidated return for the first preceding taxable year, reduced to the extent absorbed pursuant to section 904(d) by such consolidated return (whether or not taken as a credit), and

(iv) The amount of such excess tax paid by such corporation for the second succeeding taxable year.

(c) *Amount of credit with respect to noninterest income where overall limitation applies*—(1) *Taxes allowed as a credit*. Subject to the limitation provided in subparagraph (2) of this paragraph, the credit allowable to an affiliated group filing a consolidated return for taxes paid or accrued with respect to income other than interest income for a taxable year for which the overall limitation applies shall be equal to the sum of—

(i) The aggregate of the taxes paid or accrued for the taxable year by the several members of the affiliated group to all foreign countries and possessions with respect to income other than interest income, and

(ii) The aggregate of the consolidated excess tax paid carryovers and carrybacks to the taxable year under section 904(d) for taxes paid or accrued to all foreign countries and possessions with respect to income other than interest income.

(2) *Limitation*. The credit allowable under subparagraph (1) of this paragraph for taxes paid or accrued to all foreign countries and possessions shall not exceed an amount which bears the same ratio to the total tax of the affiliated group against which the credit is taken as the consolidated taxable income of the group (computed by excluding any consolidated taxable interest income) from sources within the United States (but not in excess of the entire consolidated taxable income of the group) bears to the entire consolidated taxable income. The amount computed under the preceding sentence shall be increased as provided in section 960(b), where applicable.

(3) *Consolidated excess tax paid carryovers*. The consolidated excess tax paid carryovers to the current taxable year for taxes paid or accrued to all foreign countries and possessions with respect to income other than interest income shall consist of—

(i) The consolidated excess tax paid, with respect to such income, to all such countries and possessions for the five preceding taxable years (not including

as a preceding taxable year any taxable year beginning before January 1, 1961) to the extent that such consolidated excess tax paid for any such preceding taxable year was not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the current taxable year and was not absorbed pursuant to section 904(d) in years preceding the current taxable year (whether or not taken as a credit), and

with respect to the excess tax paid, with respect to income other than interest income, by a corporation in a taxable year for which a separate return was filed, or for which such corporation joined in a consolidated return filed by another affiliated group, but subject to the limitation prescribed in paragraph (g) of this section—

(ii) The amount of such excess tax paid by such corporation to all foreign countries and possessions for the five preceding taxable years (not including as a preceding taxable year any taxable year beginning before January 1, 1961) to the extent that such excess tax paid for any such preceding taxable year was not absorbed pursuant to section 904(d) in years preceding the current taxable year (whether or not taken as a credit).

(4) *Consolidated excess tax paid carrybacks.* The consolidated excess tax paid carrybacks to the current taxable year for taxes paid or accrued to all foreign countries and possessions with respect to income other than interest income shall consist of—

(i) The consolidated excess tax paid, with respect to such income, to all such countries and possessions for the first succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the current taxable year) reduced to the extent absorbed pursuant to section 904(d) in the first preceding taxable year (whether or not taken as a credit), and

(ii) The consolidated excess tax paid, with respect to such income, to all such countries and possessions for the second succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the current taxable year), and

with respect to the excess tax paid, with respect to income other than interest income, to all such countries and possessions by a corporation which, for either of the two succeeding taxable years, files a separate return or joins in a consolidated return filed by another affiliated group, but subject to the limitation prescribed in paragraph (g) of this section—

(iii) The amount of such excess tax paid by such corporation for the first succeeding taxable year reduced to the extent absorbed pursuant to section 904(d) by such corporation for the first preceding taxable year (whether or not taken as a credit), or if the income of such corporation is included in a consolidated return for the first preceding taxable year, reduced to the extent absorbed pursuant to section 904(d) by such con-

solidated return (whether or not taken as credit), and

(iv) The amount of such excess tax paid by such corporation for the second succeeding taxable year.

(5) *Carrybacks to certain taxable years.* The excess tax paid (whether consolidated or separate) with respect to income other than interest income for any taxable year for which the overall limitation applies may not be carried back to a taxable year beginning before January 1, 1961; and in determining the carryover or carryback to taxable years beginning on or after January 1, 1961, no amount shall be treated as absorbed for taxable years beginning before such date.

(d) *Amount of credit with respect to interest income.*—(1) *Taxes allowed as a credit.* Subject to the limitation provided in subparagraph (2) of this paragraph, the credit allowable to an affiliated group filing a consolidated return for taxes paid or accrued with respect to interest income shall be an amount equal to the sum of—

(i) The aggregate of the taxes paid or accrued for the taxable year by the several members of the affiliated group to any foreign country or any possession with respect to interest income, and

(ii) The aggregate of the consolidated excess tax paid carryovers and carrybacks to the taxable year under section 904(d) for taxes paid or accrued to such country or possession with respect to interest income.

(2) *Limitation.* The credit allowable under subparagraph (1) of this paragraph for taxes paid or accrued to any foreign country or any possession shall not exceed an amount which bears the same ratio to the total tax of the affiliated group against which the credit is taken as the consolidated taxable interest income of the group from sources within such country or possession (but not in excess of the entire consolidated taxable income of the group) bears to the entire consolidated taxable income. The amount computed under the preceding sentence shall be increased as provided in section 960(b), where applicable.

(3) *Consolidated excess tax paid carryovers.* The consolidated excess tax paid carryovers to the current taxable year for taxes paid or accrued to any foreign country or any possession with respect to interest income shall consist of—

(i) The consolidated excess tax paid, with respect to such income, to such country or possession for the five preceding taxable years to the extent that such consolidated excess tax paid for any such preceding taxable year was not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the current taxable year and was not absorbed pursuant to section 904(d) in years preceding the current taxable year (whether or not taken as a credit), and

with respect to the excess tax paid, with respect to interest income, by a corporation in a taxable year for which a separate return was filed, or for which such corporation joined in a consolidated return filed by another affiliated group,

but subject to the limitation prescribed in paragraph (g) of this section—

(ii) The amount of such excess tax paid by such corporation to such country or possession for the five preceding taxable years to the extent that such excess tax paid for any such preceding taxable year was not absorbed pursuant to section 904(d) in years preceding the current taxable year (whether or not taken as a credit).

(4) *Consolidated excess tax paid carrybacks.* The consolidated excess tax paid carrybacks to the current taxable year for taxes paid or accrued to any foreign country or any possession with respect to interest income shall consist of—

(i) The consolidated excess tax paid, with respect to such income, to such country or possession for the first succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the current taxable year) reduced to the extent absorbed pursuant to section 904(d) in the first preceding taxable year (whether or not taken as a credit), and

(ii) The consolidated excess tax paid, with respect to such income, to such country or possession for the second succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the current taxable year), and with respect to the excess tax paid, with respect to interest income, to such country or possession by a corporation which, for either of the two succeeding taxable years, files a separate return or joins in a consolidated return filed by another affiliated group, but subject to the limitation prescribed in paragraph (g) of this section—

(iii) The amount of such excess tax paid by such corporation for the first succeeding taxable year reduced to the extent absorbed pursuant to section 904(d) by such corporation for the first preceding taxable year (whether or not taken as a credit), or if the income of such corporation is included in a consolidated return for the first preceding taxable year, reduced to the extent absorbed pursuant to section 904(d) by such consolidated return (whether or not taken as a credit), and

(iv) The amount of such excess tax paid by such corporation for the second succeeding taxable year.

(5) *Transitional rules for carrybacks and carryovers.* (i) If the total excess tax paid (consolidated or separate) to any foreign country or any possession for a taxable year beginning on or before October 16, 1962, is a carryover to a taxable year beginning after such date, then (a) the portion of such carryover attributable to taxes paid or accrued with respect to interest income shall be an amount equal to such carryover multiplied by the ratio which the taxes paid or accrued to such foreign country or possession for such year beginning after October 16, 1962, with respect to interest income, bears to the total amount of the taxes paid or accrued to such foreign country or possession for such year, and

(b) the portion of such carryover attributable to taxes paid or accrued with respect to income other than interest income shall be an amount equal to such carryover multiplied by the ratio which the taxes paid or accrued to such foreign country or possession for such year beginning after October 16, 1962, with respect to income other than interest income, bears to the total amount of the taxes paid or accrued to such foreign country or possession for such year.

(ii) The amount of the total excess tax paid (consolidated or separate) to any foreign country or any possession for a taxable year beginning after October 16, 1962, which is a carryback to a taxable year beginning on or before such date shall be determined without regard to the provisions of this paragraph.

(e) *Consolidated excess tax paid*—

(1) *Income other than interest income.* The consolidated excess tax paid to any foreign country or any possession (or to all foreign countries and possessions if the overall limitation provided in section 904(a)(2) applies) for any taxable year with respect to income other than interest income is the excess of the aggregate of the taxes paid or accrued by the several members of the affiliated group to such country or possession (or to all foreign countries and possessions if the overall limitation applies) with respect to income other than interest income over the applicable limitation provided in section 904(a)(1) or (2) (increased to the extent provided in section 960(b)). However, there is no consolidated excess tax paid for a taxable year in which the affiliated group takes a deduction under section 164 for such taxes paid or accrued to a foreign country or possession.

(2) *Interest income.* The consolidated excess tax paid to any foreign country or any possession for any taxable year with respect to interest income is the excess of the aggregate of the taxes paid or accrued by the several members of the affiliated group to such country or possession with respect to interest income over the limitation provided in section 904(a)(1) (increased to the extent provided in section 960(b)). However, there is no consolidated excess tax paid for a taxable year in which the affiliated group takes a deduction under section 164 for such taxes paid or accrued to a foreign country or possession.

(f) *Excess tax paid*—(1) *Income other than interest income.* The excess tax paid to any foreign country or any possession (or to all foreign countries and possessions if the overall limitation provided in section 904(a)(2) applies) with respect to income other than interest income, by a corporation for any taxable year for which a separate return is filed, is the excess of the taxes paid or accrued by the corporation to such country or possession (or to all foreign countries and possessions if the overall limitation applies) with respect to income other than interest income over the applicable limitation provided in section 904(a)(1) or (2) (increased to the extent provided in section 960(b)). However, there is no

excess tax paid for a taxable year in which the corporation takes a deduction under section 164 for such taxes paid or accrued to a foreign country or possession.

(2) *Interest income.* The excess tax paid to any foreign country or any possession with respect to interest income, by a corporation for any taxable year for which a separate return is filed, is the excess of the taxes paid or accrued by the corporation to such country or possession with respect to interest income over the limitation provided in section 904(a)(1) (increased to the extent provided in section 960(b)). However, there is no excess tax paid for a taxable year in which the corporation takes a deduction under section 164 for such taxes paid or accrued to a foreign country or possession.

(g) *Limitation on credit for carryovers and carrybacks of excess tax paid from separate return years.* In no case shall there be included in the credit for taxes paid or accrued to any foreign country or any possession for the taxable year as consolidated excess tax paid carryovers under paragraphs (b)(3)(ii), (c)(3)(ii), and (d)(3)(ii) of this section (relating to excess tax paid by a corporation in years for which separate returns were filed, or for which such corporation joined in a consolidated return filed by another affiliated group) and as consolidated excess tax paid carrybacks under paragraphs (b)(4)(iii) and (iv), (c)(4)(iii) and (iv), and (d)(4)(iii) and (iv) of this section (relating to excess tax paid by a corporation which for either of the two succeeding taxable years files a separate return or joins in a consolidated return filed by another affiliated group), an amount exceeding in the aggregate that which would be allowed as a credit for a carryover or carryback to such corporation if it had filed a separate return for such taxable year.

(h) *Apportionment of consolidated excess tax paid.* If an affiliated group filing a consolidated return has a consolidated excess tax paid with respect to any foreign country or any possession (or with respect to all foreign countries and possessions if the overall limitation applies) for the taxable year attributable to income other than interest income, or has a consolidated excess tax paid with respect to any foreign country or any possession attributable to interest income, and if there are included as members of such group one or more corporations which make separate returns (or join in a consolidated return filed by another affiliated group) for any of the two preceding or five succeeding taxable years, the portion of each such consolidated excess tax paid attributable to such corporations severally shall be determined. The portion of each such consolidated excess tax paid in the case of any such corporation shall be the amount which bears the same ratio to such consolidated excess tax paid as the tax paid or accrued by such corporation to such foreign country or possession (or to all foreign countries and possessions if the overall limitation applies) with re-

spect to income other than interest income, or to such foreign country or possession with respect to interest income, as the case may be, bears to the total tax paid or accrued by the affiliated group to such foreign country or possession (or to all foreign countries and possessions if the overall limitation applies) with respect to income other than interest income, or to such foreign country or possession with respect to interest income, as the case may be.

(i) [Reserved]

(j) *Consolidated excess tax paid before or after consolidated return period.* The consolidated excess tax paid by an affiliated group to any foreign country or any possession (or with respect to all foreign countries and possessions if the overall limitation applies) with respect to income other than interest income, or to any foreign country or any possession with respect to interest income, as the case may be, shall be used in computing the consolidated excess tax paid carryover and carryback of the group notwithstanding that one or more corporations which were members of the group in the taxable year in which such consolidated excess tax paid originates make separate returns (or join in a consolidated return made by another affiliated group) for a subsequent taxable year (or, in the case of a carryback, for a preceding taxable year) but only to the extent that such consolidated excess tax paid is not attributable to such corporation. Such portion of such consolidated excess tax paid as is attributable to the several corporations making separate returns (or joining in a consolidated return made by another affiliated group) for a subsequent taxable year (or, in the case of a carryback, for a preceding taxable year) reduced to the extent absorbed in earlier years shall be used by such corporations severally as carryovers or as carrybacks in such separate returns or in such consolidated returns of another affiliated group. Any excess tax paid by a corporation prior to the first taxable year in which its income is included in the consolidated return of the group (or paid in either of the two years immediately following a consolidated return year) may be used in computing the carryover or carryback of such corporation (or of another affiliated group of which it becomes a member) for a subsequent taxable year for which it makes a separate return or joins in the consolidated return of another affiliated group, but only to the extent that such excess tax paid was not absorbed (either as a carryover or as a carryback).

(k) *Limitation effective under section 904(a).* The determination of whether the overall limitation or the per-country limitation applies during a consolidated return period shall be made by reference to the limitation effective with respect to the common parent corporation for such period. An election made by the common parent for a year for which it filed a separate return may be changed or revoked during a consolidated return period only in accordance with the provisions of section 904(b). If the limitation effective with respect to any affiliate for a taxable year (immediately preced-

ing the consolidated return period) for which it filed a separate return (or joined in a consolidated return filed by another affiliated group) differs from the limitation effective with respect to the common parent corporation for the consolidated return period, then such affiliate shall, if the overall limitation is effective with respect to the common parent, be deemed to have made an election to use such overall limitation, or, if the per-country limitation is effective with respect to the common parent, be deemed to have revoked its election to use the overall limitation. Consent of the Secretary or his delegate is hereby given to such affiliate for such election or revocation. Any such election or revocation shall apply only prospectively beginning with such consolidated return period. The limitation effective with respect to an affiliate for the consolidated return period immediately preceding a year for which it does not join in the filing of the consolidated return shall, except to the extent otherwise provided in this paragraph, remain in effect for such subsequent year in accordance with the provisions of section 904(b).

(1) *Carryovers or carrybacks from overall year to per-country year, and vice versa.* (1) The excess tax paid (whether consolidated or separate) to any foreign country or any possession of the United States with respect to income other than interest income, in a taxable year for which the per-country limitation under section 904(a)(1) applies, may not be carried to a taxable year for which the overall limitation under section 904(a)(2) applies.

(2) The excess tax paid (whether consolidated or separate) to all foreign countries and possessions with respect to income other than interest income, in a taxable year for which the overall limitation applies, may not be carried to a taxable year for which the per-country limitation applies.

(3) Subject to the provisions of section 904(f)(3) and the regulations thereunder, the excess tax paid (whether consolidated or separate) to any foreign country or any possession with respect to interest income may be carried to a taxable year for which the overall limitation applies in respect of taxes paid or accrued with respect to income other than interest income.

§ 1.1502-44A Methods of accounting.

(a) *In general.* All members of the affiliated group shall adopt that method of accounting which clearly reflects the consolidated taxable income. A method of accounting which does not treat with reasonable consistency all items of gross income and deductions of the various members of the group shall not be regarded as clearly reflecting the consolidated taxable income. For example, one member of the group will not be permitted to report items of income or deductions on the cash method of accounting while another member of the same group reports the same or similar items on the accrual method. The provisions of this paragraph are subject to the exceptions stated in paragraph (b) of this section.

(b) *Combination of methods.* If the members of an affiliated group have established different methods of accounting, each member may retain such method with the consent of the Commissioner. *Provided, That the consolidated taxable income is clearly reflected: And provided further, That intercompany transactions affecting such consolidated taxable income shall be eliminated and adjustments on account of such transactions shall be made with reference to a uniform method of accounting to be selected by the members of the group with the consent of the Commissioner.*

(c) *Adjustments required by changes in method of accounting.* In any case in which a member of an affiliated group changes its method of accounting the provisions of section 481 (a) shall be applicable.

§ 1.1502-45A Mine exploration expenditures.

For the purpose of applying the limitation provided in section 615 (c) (whether during a consolidated return period or during a period for which a separate return is made), if during a preceding taxable year for which a consolidated return was made or was required to be made any member of the affiliated group for such preceding taxable year was allowed the deduction provided in section 615 (a) or made the election provided in section 615 (b), each member of the affiliated group for such preceding taxable year shall be deemed to have been allowed such deduction or to have made such election, as the case may be.

§ 1.1502-46A Depreciation.

In the computation of the deduction for depreciation under section 167, property received by one member of the group from another member of the group during a consolidated return period, shall be treated in the same manner as it could be treated if it were held by the transferor.

§ 1.1502-47A Election to deduct accrued taxes.

If all members of the affiliated group were taxpayers which, for each taxable year in which they were subject to the tax imposed by section 500 of the Internal Revenue Code of 1939 deducted Federal income and excess profits taxes when paid for the purpose of computing subchapter A net income under such Code, the affiliated group shall, if the tax liability under section 541 is computed upon the consolidated undistributed personal holding company income, deduct taxes under section 545 when paid unless a member of the common affiliated group elects in its return or the common parent elects in a consolidated return for the group of which it is the common parent for a taxable year ending after June 30, 1954, to deduct the taxes described in section 545, when accrued. In any case in which the common parent corporation or any member of the affiliated group has, prior to the taxable year, elected to deduct such taxes when accrued, each member of the group shall be deemed to have so elected in the first year there-

after in which its income is included in the consolidated personal holding company income. If an election is made by the common parent corporation with respect to a year for which the tax liability under section 541 is computed upon the consolidated undistributed personal holding company income, each member of the group shall be deemed to have made such election in such year. Any such election made or deemed to have been made shall be applicable to each member of the group for the taxable year for which the election is made and for all subsequent taxable years. Any election so made shall be irrevocable.

§ 1.1502-48A Liability for tax under section 531.

In any case in which an affiliated group computes the tax liability under section 541, upon the consolidated undistributed personal holding company income, the tax imposed by section 531 shall not be applicable.

§ 1.1502-49A Additions to tax for failure to pay estimated tax.

(a) Except in the case of an affiliated group described in paragraph (b) of this section, any addition to the tax under section 6655 for underpayment of estimated tax of a member of an affiliated group which files a consolidated return for the taxable year shall be determined by allocating the tax shown on the consolidated return to the several members of the group by any of the methods provided in paragraph (a) of § 1.1552-1 selected by the common parent corporation for the taxable year, without regard to the method elected under section 1552. If the group would use the method of allocation authorized by paragraph (a)(4) of § 1.1552-1, it must be the method elected by the group with the approval of the Commissioner for the purpose of determining earnings and profits. In the application of section 6655 (d) (1) with respect to a member of the group which was included in a consolidated return for the preceding taxable year, whether or not such member is included in a consolidated return for the taxable year, the "tax shown on the return" for the preceding taxable year shall be the portion of the tax shown on such consolidated return determined by allocating such tax to the several members of the group by the procedure described above. In the application of section 6655 (d) (2) if the corporation was included in a consolidated return for the preceding taxable year, the "facts shown on the return" shall be the facts shown on the consolidated return of the group (whether of this or another affiliated group) for the preceding taxable year attributable to such corporation.

(b) In the case of an affiliated group which has filed pursuant to the provisions of paragraph (c) (2) of § 1.1502-10A a declaration of estimated tax for the taxable year for which a consolidated return is filed, any addition to the tax provided by section 6655 shall be determined by reference to the payments made on such declaration and to the tax shown on the consolidated return.

(c) In the application of section 6655 (d) (1) with respect to the affiliated group described in paragraph (b) of this section, the "tax shown on the return" shall be—

(1) If the group filed a consolidated return for the preceding taxable year, the tax shown on such return, or

(2) If the group did not file a consolidated return for the preceding taxable year, the aggregate of the taxes of the several members of the group shown on any separate returns of such corporations for the preceding taxable year, plus the tax shown on a consolidated return for the preceding taxable year attributable to any member of the group which joined in a consolidated return with another affiliated group for such preceding taxable year. The tax attributable to any such corporation which joined in a consolidated return shall be determined by allocating the tax shown on such consolidated return in accordance with the procedure described in paragraph (a) of this section.

(d) In the application of section 6655 (d) (2) with respect to the affiliated group described in paragraph (b) of this section, the "facts shown on the return" shall be—

(1) If the group filed a consolidated return for the preceding taxable year, the facts shown on such return, or

(2) If the group did not file a consolidated return for the preceding taxable year, the facts shown on the separate returns of the members of the affiliated group for the preceding taxable year together with the facts shown on a consolidated return for the preceding taxable year attributable to any member of the group which joined in a consolidated return with another affiliated group for such preceding taxable year.

§ 1.1502-50A. Gain on sale of bonds and other evidences of indebtedness.

In the application of section 1232(a), if one member of the affiliated group acquires a bond or other evidence of indebtedness from another member of the affiliated group during a consolidated return period, the determination of the amount which is treated as gain from the sale or exchange of property which is not a capital asset shall be made by including in the period of time during which such bond or other evidence of indebtedness was held, the period of time during which it was held by any other corporation which transferred it in a transaction to which paragraph (b) (1) (i) of § 1.1502-31A (or the corresponding provision of prior consolidated returns regulations) is applicable without regard to any period of time before the last sale or exchange of such instrument to which such section is not applicable. In the application of section 1232(c), if a bond or other evidence of indebtedness was acquired from another member of an affiliated group during a consolidated return period, then the bond or other evidence of indebtedness shall be deemed to have been purchased at the time of, and as having a market value with coupons attached, determined by reference to the earliest date of purchase by any other corporation which transferred it in a transaction to which paragraph (b) (1)

(i) of § 1.1502-31A (or the corresponding provision of prior consolidated returns regulations) is applicable without regard to any purchase prior to the last purchase to which such section is not applicable.

§ 1.1502-51A. Credit for investment in certain depreciable property.

(a) *Determination of amount of consolidated credit.*—(1) *In general.* Except as otherwise provided in this section, the amount of the consolidated credit allowed by section 38 for the taxable year is the aggregate amount of the "credit earned" for such year of the several members of the affiliated group. Such amount shall be referred to in this section as the "consolidated credit earned". The "credit earned" of each member of the affiliated group is an amount equal to 7 percent of such member's qualified investment (determined under section 46(c)).

(2) *Consolidated limitation based on amount of tax.* (i) Notwithstanding the amount of the consolidated credit earned for the taxable year, the consolidated credit allowed by section 38 to the group for the taxable year is limited to—

(a) So much of the consolidated liability for tax as does not exceed \$25,000, plus

(b) 25 percent of the consolidated liability for tax in excess of \$25,000.

The \$25,000 amount referred to in (a) and (b) of the preceding sentence shall be reduced by any part of such \$25,000 amount apportioned, under section 46(a) (5), to members of the affiliated group (as defined in section 46(a) (5)) which do not join in the filing of the consolidated return. The amount determined under this subparagraph shall be referred to in this section as the "consolidated limitation based on amount of tax".

(ii) If an organization to which section 593 applies or a cooperative organization described in section 1381(a) joins in the filing of the consolidated return, the \$25,000 amount referred to in subdivision (i) (a) and (b) of this subparagraph (or such \$25,000 amount reduced by any part of such amount apportioned to members of the affiliated group which do not join in the filing of the consolidated return) shall be apportioned equally among the members of the affiliated group filing the consolidated return. The portion of such \$25,000 amount (or such reduced amount) so apportioned equally to any such organization shall then be decreased to the ratable share of such portion in accordance with the provisions of section 46(d). Finally, for purposes of computing the consolidated limitation based on amount of tax under subdivision (i) (a) and (b) of this subparagraph, the sum of all such equal portions (as decreased under section 46(d), where applicable) of each member of the affiliated group filing the consolidated return shall be substituted for the \$25,000 amount referred to in subdivision (i) (a) and (b) of this subparagraph.

(3) *Consolidated liability for tax.* For purposes of this section, the consolidated

liability for tax shall be the income tax imposed for the taxable year upon the group by chapter 1 of the Code (including the 2-percent tax on consolidated taxable income), reduced by the credit allowable under section 33 (relating to taxes of foreign countries and possessions of the United States). The tax imposed by section 531 (relating to imposition of accumulated earnings tax) or by section 541 (relating to imposition of personal holding company tax) shall not be considered tax imposed by chapter 1 of the Code. In addition, any increase in tax resulting from the application of section 47 (relating to certain dispositions, etc., of section 38 property) shall not be treated as tax imposed by chapter 1 for purposes of computing the consolidated liability for tax.

(b) *Carryback and carryover of consolidated unused credit.*—(1) *Allowance of consolidated unused credit as carryback or carryover.* (i) A "consolidated unused credit" is the excess of the consolidated credit earned for the taxable year over the consolidated limitation based on amount of tax for such taxable year. Subject to the limitations contained in subparagraphs (2) and (9) (i) of this paragraph, a consolidated unused credit shall be added to the amount allowable as a credit under section 38 for the years to which the consolidated unused credit can be carried. The year with respect to which a consolidated unused credit arises shall be referred to in this section as the "consolidated unused credit year".

(ii) A consolidated unused credit shall be an investment credit carryback to each of the 3 taxable years preceding the consolidated unused credit year and shall be an investment credit carryover to each of the 5 taxable years succeeding the consolidated unused credit year, except that a consolidated unused credit shall be a carryback only to taxable years ending after December 31, 1961. A consolidated unused credit must be carried first to the earliest of the 8 taxable years to which it may be carried, and then to each of the other 7 taxable years (in order of time) to the extent that the consolidated unused credit may not be added (because of the limitation contained in paragraph (a) (2) of this section) to the amount allowable as a credit under section 38 for a prior taxable year.

(2) *Limitation on allowance of consolidated investment credit carryback or carryover.* The amount of the consolidated investment credit carryback or carryover from any particular unused credit year which may be added to the amount allowable as a credit under section 38 for any of the 3 preceding or 5 succeeding taxable years to which such credit may be carried shall not exceed the amount by which the consolidated limitation based on amount of tax for such preceding or succeeding taxable year exceeds the sum of (i) the consolidated credit earned for such preceding or succeeding year, and (ii) other unused credits carried to such preceding or succeeding year which are attributable to unused credit years prior to the particular unused credit year.

(3) *Effect of net operating loss carryback.* If the effect of a net operating loss carryback is to create a consolidated unused credit, such unused credit shall not be treated as a consolidated investment credit carryback. However, the full amount of the unused credit so arising shall be available for use as an investment credit carryover for the five taxable years following the consolidated unused credit year.

(4) *Taxable years beginning before January 1, 1962, and ending after December 31, 1961.* For purposes of determining the amount of unused credits which may be carried back to a consolidated return year beginning before January 1, 1962, and ending after December 31, 1961, and added to the amount allowable as a credit for such year, the consolidated limitation based on amount of tax for such year, determined without regard to this subparagraph, shall be reduced to an amount which bears the same ratio to such limitation as the number of days in such taxable year after December 31, 1961, bears to the total number of days in such year.

(5) *Consolidated investment credit carryover.* The consolidated investment credit carryover which may be added, subject to the limitation contained in subparagraph (2) of this paragraph, to the amount allowable to the group as a credit under section 38 for any taxable year shall be—

(i) The consolidated unused credits, if any, for the five preceding taxable years to the extent that the consolidated unused credit for any such preceding taxable year is not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the taxable year and was not allowed as a credit under section 38 for a preceding or intervening taxable year, and

(ii) With respect to unused credits of a corporation arising in unused credit years for which such corporation filed a separate return or joined in a consolidated return filed by another affiliated group, but subject to the limitation prescribed by subparagraph (7) of this paragraph, such unused credits, if any, for the five preceding taxable years to the extent that the unused credit for any such preceding taxable year was not allowed as a credit under section 38 for a preceding or intervening taxable year.

(6) *Consolidated investment credit carryback.* The consolidated investment credit carryback which may be added, subject to the limitation contained in subparagraph (2) of this paragraph, to the amount allowable to the group as a credit under section 38 for any taxable year shall be—

(i) The amount of the consolidated unused credit, if any, for the first succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the taxable year), reduced to the extent such consolidated unused credit was allowed as a credit under section 38 for the first two preceding taxable years,

(ii) The amount of the consolidated unused credit, if any, for the second succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the taxable year), reduced to the extent such consolidated unused credit was allowed as a credit under section 38 for the first preceding taxable year,

(iii) The amount of the consolidated unused credit, if any, for the third succeeding taxable year (to the extent not attributable to a corporation making a separate return or joining in a consolidated return filed by another affiliated group for the taxable year), and

(iv) With respect to an unused credit of a corporation arising in an unused credit year for which such corporation filed a separate return or joined in a consolidated return filed by another affiliated group, but subject to the limitation prescribed by subparagraph (7) of this paragraph—

(a) The amount of the unused credit, if any, of such corporation for the first succeeding taxable year, reduced to the extent such unused credit was allowed as a credit under section 38 for the first two preceding taxable years,

(b) The amount of the unused credit, if any, of such corporation for the second succeeding taxable year, reduced to the extent such unused credit was allowed as a credit under section 38 for the first preceding taxable year, and

(c) The amount of the unused credit, if any, of such corporation for the third succeeding taxable year.

(7) *Limitation on investment credit carryover and carryback from separate return years.* (i) For any taxable year, the amount included in the consolidated investment credit carryover of the group, under subparagraph (5) (ii) of this paragraph, and in the consolidated investment credit carryback of the group, under subparagraph (6) (iv) (a), (b), and (c) of this paragraph, shall not exceed the limitation determined under subdivision (ii) of this subparagraph.

(ii) For purposes of subdivision (i) of this subparagraph, the limitation for any taxable year shall be an amount equal to the amount by which the portion of the consolidated limitation based on amount of tax for such taxable year attributable to the corporation which filed a separate return, or joined in the filing of a consolidated return by another affiliated group, in a preceding or succeeding taxable year exceeds the sum of—

(a) The credit earned (as defined in paragraph (a) (1) of this section) of such corporation for the taxable year, and

(b) The unused credits of such corporation (or attributable to such corporation) which may be carried to the taxable year arising in unused credit years prior to the particular unused credit year.

(iii) For purposes of subdivision (ii) of this subparagraph, the portion of the consolidated limitation based on amount of tax attributable to a corporation shall be the sum of—

(a) So much of the consolidated liability for tax attributable to such

corporation as does not exceed \$25,000 divided by the number of corporations in such affiliated group (as defined in section 46(a) (5)), and

(b) 25 percent of so much of the consolidated liability for tax attributable to such corporation as exceeds \$25,000 divided by the number of corporations in such affiliated group (as defined in section 46(a) (5)).

(iv) For purposes of subdivision (iii) of this subparagraph, the consolidated liability for tax attributable to a corporation is the consolidated liability for tax for the taxable year multiplied by the ratio which—

(a) The taxable income, if any, of such corporation, bears to

(b) The aggregate of the taxable incomes of the several members of the affiliated group having taxable income.

For purposes of the preceding sentence, taxable income of a corporation means the taxable income of such corporation included in the computation of consolidated taxable income for the taxable year decreased by its deductions under sections 181, 243, 244, 245, 247, and 922 (and in the case of a member of an affiliated group to which the consolidated section 175 deduction is applicable, the section 175 deduction), increased by its separate net capital gain, and increased or decreased, as the case may be, with respect to its separate gains or losses from involuntary conversions subject to the provisions of section 1231, and from sales or exchanges of property subject to the provisions of section 1231.

(8) *Consolidated unused credit attributable to each of the several members—*

(i) *In general.* If an affiliated group filing a consolidated return has a "consolidated unused credit" for a taxable year and if there are included as members of such group one or more corporations which made separate returns, or joined in a consolidated return filed by another affiliated group, for any of the three preceding or five (or six in the case of a section 181 deduction) succeeding taxable years, the portion of such consolidated unused credit for such consolidated unused credit year attributable to such corporations severally shall be determined, such portion in the case of any such corporation being determined under the provisions of subdivisions (ii) and (iii) of this subparagraph.

(ii) *Carryback.* In the case of a carryback of a consolidated unused credit to a taxable year for which the corporation made a separate return or joined in a consolidated return filed by another affiliated group, the portion of such consolidated unused credit for the consolidated unused credit year attributable to such corporation shall be an amount equal to the amount of such consolidated unused credit multiplied by the ratio which—

(a) The credit earned (as defined in paragraph (a) (1) of this section) of such corporation for the consolidated unused credit year, bears to

(b) The consolidated credit earned (as defined in paragraph (a) (1) of this section) for such consolidated unused credit year.

(iii) *Carryover.* In the case of a carryover of a consolidated unused credit to (or a section 181 deduction for) a taxable year for which the corporation makes a separate return or joins in a consolidated return filed by another affiliated group, the portion of such consolidated unused credit for the consolidated unused credit year attributable to such corporation shall be an amount equal to the amount of such consolidated unused credit multiplied by the ratio which—

(a) The portion of the consolidated credit earned with respect to any section 38 property placed in service in the consolidated unused credit year and owned by such corporation (whether or not placed in service by such corporation) at the close of the last day with respect to which the taxable income of such corporation is included in the consolidated return, bears to

(b) The consolidated credit earned for such consolidated unused credit year.

(9) *Consolidated unused credit before or after consolidated return period.* (i) The consolidated unused credit of an affiliated group filing a consolidated return shall be used in computing the consolidated investment credit carryover or carryback to (or section 181 deduction for) a subsequent (or preceding) taxable year of the group notwithstanding that one or more members of the group in the consolidated unused credit year make separate returns (or join in a consolidated return made by another affiliated group) for such subsequent (or preceding) taxable year, but only to the extent that such consolidated unused credit is not attributable (as determined under subparagraph (8) of this paragraph) to the several corporations making separate returns (or joining in a consolidated return made by another affiliated group) for such subsequent (or preceding) taxable year.

(ii) The portion of such consolidated unused credit attributable to the several corporations making separate returns (or joining in a consolidated return made by another affiliated group) for a subsequent (or preceding) taxable year (reduced to the extent allowed as a credit under section 38 for a prior taxable year) shall be used by such corporations severally as investment credit carryovers (or carrybacks) to such separate returns or such consolidated returns of another affiliated group or as section 181 deductions on such separate returns (or such consolidated return of another affiliated group).

(10) *Rules with respect to unused credits under section 381.* (i) If, in the

computation of the consolidated investment credit carryover, there is included an amount with respect to an unused credit of a corporation, arising in a taxable year for which it filed a separate return or for which such corporation joined in a consolidated return filed by another affiliated group, which is a transferor or distributor of assets within the meaning of section 381(a) to a member of the affiliated group, the amount included in the consolidated investment credit carryover with respect to such transferor or distributor shall not exceed the limitation contained in subparagraph (7) of this paragraph determined with reference to the acquiring corporation. The computation shall be made as described in subparagraph (7) of this paragraph as though the acquiring corporation had an unused credit in a year for which it filed a separate return or for which such acquiring corporation had joined in a consolidated return filed by another affiliated group.

(ii) If, in addition to the amount described in subdivision (i) of this subparagraph, there is included an amount with respect to an unused credit of the acquiring corporation in a year for which it filed a separate return or for which it joined in a consolidated return filed by another affiliated group, the unused credits of both the acquiring corporation and the transferor or distributor corporation which may be taken into account as unused credits in determining the consolidated investment credit carryover may not exceed the limitation, determined with reference to the acquiring corporation, computed in a manner described in subparagraph (7) of this paragraph.

(iii) For purposes of subdivisions (i) and (ii) of this subparagraph, if the transferor or distributor corporation was a member of another affiliated group which filed a consolidated return, the amount of the consolidated unused credit of such affiliated group, if any, attributable to such transferor or distributor, shall be treated as the unused credit of such corporation.

(c) *Early dispositions, etc., of section 38 property.*—(1) *Dispositions of section 38 property during and after consolidated return period.* Except as provided in subparagraph (2) of this paragraph—

(i) If property placed in service in a consolidated return period is disposed of or otherwise ceases to be section 38 property, or becomes public utility property, with respect to any corporation during any taxable year (whether consolidated or separate), the provisions of section 47(a) (1) or (2), as the case may be,

shall apply (whether such property was placed in service by such corporation or was received by such corporation in an intercompany transaction to which subparagraph (2) (i) of this paragraph applied) and the increase in tax, if any, shall be added to the tax liability of such group or such corporation, as the case may be.

(ii) If property placed in service in a separate return year is disposed of or ceases to be section 38 property, or becomes public utility property, with respect to any corporation during a taxable year for which such corporation joins in the filing of a consolidated return, the provisions of section 47(a) (1) or (2), as the case may be, shall apply and the increase in tax, if any, shall be added to the tax liability of such group.

(2) *Exceptions.* (i) For purposes of sections 46(c) and 47(a) (1), a transfer of section 38 property from one member of an affiliated group to another member of such group in an intercompany transaction during a consolidated return period shall not be treated as a disposition or cessation. The preceding sentence shall not apply to a transfer of section 38 property unless such property was placed in service by a member of the group in a consolidated return period of such group.

(ii) If, in any taxable year, section 38 property placed in service during a consolidated return period is disposed of by one member of an affiliated group to another member of such group which is an organization to which section 593 applies or a cooperative organization described in section 1381(a), the tax under chapter 1 of the Code for such taxable year shall be increased by an amount equal to the aggregate decrease in the credits allowed under section 38 for all prior taxable years which would result solely from treating such property, for purposes of determining qualified investment, as placed in service by such organization to which section 593 applies or such cooperative organization described in section 1381(a), as the case may be, but with due regard to the use of the property before such transfer. The consolidated investment credit carrybacks and carryovers shall be adjusted under the principles of section 47(a) (3) by reason of such change in use.

(Secs. 1502 and 7805 of the Internal Revenue Code of 1954; 68A Stat. 367, 917; 26 U.S.C. 1502 and 7805)

[F.R. Doc. 66-9813; Filed, Sept. 7, 1966; 8:45 a.m.]

Proposed Rule Making

DEPARTMENT OF THE TREASURY

Internal Revenue Service

[26 CFR Part 1]

CONSOLIDATED RETURN REGULATIONS

Notice of Proposed Rule Making

Pursuant to the Administrative Procedure Act, approved June 11, 1946, regulations proposed to be prescribed as §§ 1.1502-14, 1.1502-19, 1.1502-25, 1.1502-31, 1.1502-32, and 1.1502-33 were published in tentative form with a notice of proposed rule making in the *FEDERAL REGISTER* for October 1, 1965 (30 F.R. 12575). Notice is hereby given that such proposed regulations are withdrawn.

Further, notice is hereby given, pursuant to the Administrative Procedure Act, that the regulations set forth in tentative form below are proposed to be prescribed by the Commissioner of Internal Revenue, with the approval of the Secretary of the Treasury or his delegate. Prior to the final adoption of such regulations, consideration will be given to any comments or suggestions pertaining thereto which are submitted in writing, in duplicate, to the Commissioner of Internal Revenue, Attention: CC:LR:T, Washington, D.C. 20224, within the period of 30 days from the date of publication of this notice in the *FEDERAL REGISTER*. Any person submitting written comments or suggestions who desires an opportunity to comment orally at the public hearing which will be held on these proposed regulations should submit his request, in writing, to the Commissioner within the 30-day period. Notice of the time, place, and date of the public hearing are published simultaneously herewith.¹ The proposed regulations are to be issued under the authority contained in sections 1502 and 7805 of the Internal Revenue Code of 1954 (68A Stat. 367, 917; 26 U.S.C. 1502, 7805).

[SEAL]

ROBERT L. JACK,
Acting Commissioner of
Internal Revenue.

The Income Tax Regulations (26 CFR Part 1) under subchapter A of chapter 6 of the Internal Revenue Code of 1954, relating to consolidated returns, are amended by revising the regulations under section 1502 as follows:

PARAGRAPH 1. Section 1.1502-14 is added to read as follows:

§ 1.1502-14 Stock, bonds, and other obligations of members.

(a) *Intercompany distributions with respect to stock*—(1) *Dividends*. A dividend distributed by one member to

another member during a consolidated return year shall be eliminated. For purposes of this paragraph, the term "dividend" means a distribution which is described in section 301(c)(1) other than a distribution described in section 243(c)(1).

(2) *Section 301 distributions out of other than earnings and profits*. (i) No gain shall be recognized to the distributee on a distribution with respect to stock, from one member to another member during a consolidated return year, which is described in section 301(c)(2) or (3). Such distribution shall be applied against and reduce the adjusted basis (computed by taking into account any adjustment under § 1.1502-32) of such stock in the distributing corporation held by the distributee, and to the extent such distribution exceeds the adjusted basis, the excess shall be (or shall be added to) the excess loss account (see §§ 1.1502-19 and 1.1502-32) for such stock in the distributing corporation held by the distributee. For example, corporation P and its wholly owned subsidiary, corporation S, are members of a group filing consolidated returns on a calendar year basis. On December 31, 1966, S distributed to P with respect to its stock \$5,000 cash and land with an adjusted basis to S of \$6,000 and a fair market value of \$5,000. No part of the distribution constituted a dividend. On December 31, 1966, P had an adjusted basis of \$3,000 in the stock of S. The \$10,000 amount distributed is treated as follows: \$3,000 is applied against and reduces the adjusted basis of the stock to zero, and \$7,000 is treated as P's excess loss account for its stock in S. No gain is recognized by P. Pursuant to § 1.1502-31(b)(1) and section 301(d)(2) P's basis in the land is \$5,000.

(b) *Intercompany distributions in cancellation or redemption of all or part of the stock of the distributing corporation*—(1) *General rule*. Except as provided in subparagraph (2) of this paragraph and in § 1.1502-19, no gain or loss shall be taken into account on the receipt, during a consolidated return year, by one member of property (including cash) distributed in cancellation or redemption of all or a part of the stock of another member.

(2) *Cash in excess of basis*. If a distribution described in subparagraph (1) of this paragraph, other than a distribution to which section 332 applies, includes cash in excess of the sum of the adjusted basis (determined after taking into account any adjustment under § 1.1502-32) of the stock of the distributing corporation held by the distributee which was canceled or redeemed, plus any liabilities assumed by the distributee (or to which the property received is subject), gain shall be taken into account to the extent of such excess.

(3) *Definition of distributions in cancellation or redemption*. For purposes of this paragraph, a distribution is in cancellation or redemption of all or a part of stock only if—

(i) It is in complete liquidation of the distributing corporation,

(ii) It is in partial liquidation of the distributing corporation within the meaning of section 346, and such corporation remains a member of the group immediately after the distribution, or

(iii) It is a distribution in redemption of the stock of the distributing corporation to which section 302(a) applies, and such corporation remains a member of the group immediately after the distribution.

(c) *Treatment of distributing corporation*—(1) *Deferral in other than a complete liquidation*. Except as provided in subparagraph (2) of this paragraph, to the extent gain or loss is recognized to the distributing corporation on a distribution described in paragraph (a) or (b) of this section (including any amount which is treated as gain under section 311, 336, 341(f)(2), 1245(a)(1), or 1250(a)(1)), such gain or loss shall be deferred by the distributing corporation. Such deferred gain or loss shall be taken into account by the distributing corporation at the time and in the manner specified in paragraphs (d), (e), and (f) of § 1.1502-13, as if such distributing corporation were a "selling member" and the distributee were a "purchasing member."

(2) *Complete liquidations*. Gain or loss shall be taken into account by the distributing corporation on a complete liquidation, during a consolidated return year, of one member into another member, in the same manner and to the same extent as if separate returns were filed.

(d) *Gains and losses on obligations of members*—(1) *Deferral of gain or loss*. To the extent gain or loss is recognized under the Code to a member (referred to in this paragraph as a "creditor member") during a consolidated return year because of a sale or other disposition (other than a redemption or cancellation) of an obligation of another member (referred to in this paragraph as the "debtor member"), whether or not such obligation is evidenced by a security, such gain or loss shall be deferred. As used in this paragraph, the term "loss" includes a deduction because of the worthlessness of, or a deduction for a reasonable addition to a reserve for bad debts with respect to, an obligation described in this subparagraph. For treatment of premium and discount with respect to obligations described in this subparagraph, see § 1.1502-13(b).

(2) *Restoration of gain or loss where obligation leaves group*. If an obligation described in subparagraph (1) of this paragraph is sold or disposed of to a non-

¹ See F.R. Doc. 66-9910, *infra*.

member (or if the member holding the obligation becomes a nonmember), any gain or loss deferred under subparagraph (1) of this paragraph with respect to such obligation (whether arising because of such disposition or because of an earlier intercompany disposition) shall be taken into account ratably over the remaining term of the obligation.

(3) *Restoration of gain or loss on other events.* All gain or loss deferred with respect to an obligation under subparagraph (1) of this paragraph which has not been taken into account under subparagraph (2) of this paragraph shall be taken into account immediately before the occurrence of the earliest of the following events:

(i) When the creditor member ceases to be a member.

(ii) When the obligation is redeemed or cancelled.

(iii) When the stock of the debtor member is considered to be disposed of under subdivision (i), (iii), (iv), (v), or (vi) of § 1.1502-19(b) (2).

On the occurrence of the event described in subdivision (i) of this subparagraph, the deferred gain or loss of the creditor member leaving the group shall be taken into account. On the occurrence of any other event described in this subparagraph, the deferred gain or loss of each creditor member shall be taken into account.

(4) *Character of deferred gain or loss.* The character of gain or loss deferred under subparagraph (1) of this paragraph shall be determined at the time of the transaction as if such transaction had not occurred during a consolidated return year.

(5) *Inheritance of deferred items.* Subparagraph (3) (i) of this paragraph shall not apply if the creditor member ceases to be a member because its assets are acquired by one or more members in an acquisition to which section 381(a) applies. The member acquiring the greatest portion of the assets (measured by fair market value) of the creditor member shall be subject to the provisions of this paragraph with respect to the remaining deferred gain or loss. If two or more members acquire the same portion (which is greater than that acquired by any other member), the common parent shall select which such member shall be subject to such provisions.

PAR. 2. Section 1.1502-15 is amended by adding paragraph (b). The added provision reads as follows:

§ 1.1502-15 Limitations on certain deductions.

(b) *Other limitation.* No loss shall be allowed upon the sale or other disposition of stock, bonds, or other obligations of a member or former member to the extent that such loss is attributable to a distribution—

(1) Made in an affiliated year beginning before January 1, 1966, out of earnings and profits accumulated before the date on which the distributing corporation became a member or,

(2) Made in an affiliated year beginning after December 31, 1965, for which

separate returns were filed, out of earnings and profits accumulated before the date on which the distributing corporation became a member.

PAR. 3. Section 1.1502-19 is added to read as follows:

§ 1.1502-19 Excess losses.

(a) *Recognition of income—(1) In general.* Immediately before the disposition (as defined in paragraph (b) of this section) of stock in a subsidiary, there shall be included in the income of each member disposing of such stock that member's excess loss account (determined under §§ 1.1502-14 and 1.1502-32) with respect to the stock disposed of. Such income shall be treated as gain from the sale of the stock (that is, as capital gain or ordinary income, as the case may be) unless, at the time of the disposition, such subsidiary's net worth is zero. In such case such income shall be treated as ordinary income except to the extent that the taxpayer establishes that the excess loss account is attributable to capital losses of the subsidiary which reduced long-term capital gains of the group, section 1231 losses of the subsidiary which reduced section 1231 gains of the group, or distributions by the subsidiary from other than earnings and profits which would have been taxable to the distributee as long-term capital gain if separate returns had been filed, in which case such income shall be treated as gain from the sale of the stock. For purposes of this paragraph, a subsidiary's net worth shall be considered to be zero if the then fair market value of its assets is less than the sum of—

(i) All its liabilities,

(ii) All liabilities which were discharged during consolidated return years to the extent such discharge would have resulted in "cancellation of indebtedness income" but for the insolvency of the subsidiary, and

(iii) The amount to which stock of the subsidiary which is limited and preferred as to dividends is entitled in liquidation.

(2) *Prior law.* To the extent the excess loss account is attributable to an adjustment under § 1.1502-32(d) which was not subsequently reduced under § 1.1502-32(c) (3), it shall be taken into account in the same manner as it would have been taken into account under regulations effective for taxable years beginning before January 1, 1966. For example, assume that P is the common parent of a group which filed a consolidated return for 1965. During such taxable year a member of the group, corporation S, sustained a loss of \$100, all of which was availed of in the consolidated return for 1965. P organized S on January 1, 1965, with a contribution to capital of \$80 and a \$10 loan. The group files a consolidated return for 1966. Under § 1.1502-32(d), P's basis for the stock in S as of January 1, 1966 is reduced to zero, and P has an excess loss account with respect to such stock of \$20. No part of the reduction for

losses availed of is applied to reduce the basis of the debt. During 1966, S has earnings and profits of \$5, and under § 1.1502-32(c) (3), P's excess loss account for its stock of S is reduced to \$15. On December 31, 1966, P sells the stock of S for \$5. P realizes a \$5 gain on such sale. In addition, the excess loss account of \$15 is applied to reduce the basis of S's obligations to zero, and the balance is otherwise taken into account in the same manner and to the same extent as it would have been taken into account under the regulations applicable to 1965.

(b) *Disposition—(1) Disposition of particular share.* Except as otherwise provided in paragraphs (d) and (e) of this section, a member shall be considered for purposes of this section as having disposed of a share of stock in a subsidiary—

(i) On the day such share is transferred to any person, or

(ii) On the day such member receives a distribution in cancellation or redemption of such stock (as defined in § 1.1502-14(b) (3)).

(2) *Disposition of all shares.* Except as otherwise provided in paragraphs (d) and (e) of this section, a member shall be considered for purposes of this section as having disposed of all of its shares of stock in a subsidiary—

(i) On the day such subsidiary ceases to be a member,

(ii) On the day such member ceases to be a member,

(iii) On the last day of each taxable year of such subsidiary in which any of its stock is wholly worthless, or in which an indebtedness of the subsidiary is discharged if such discharge would have resulted in "cancellation of indebtedness income" but for the insolvency of the subsidiary,

(iv) On the last day of each taxable year of the subsidiary for which the Commissioner is satisfied that 10 percent or less of the face amount of any obligation for which the subsidiary is personally liable (primarily or secondarily) is recoverable at maturity by its creditors,

(v) On the day on which a member transfers an obligation for which the subsidiary is personally liable (primarily or secondarily) to any nonmember for an amount which is 25 percent or less of the face amount of such obligation, or

(vi) On the last day of the taxable year preceding the first taxable year for which the group does not file a consolidated return.

(c) *Effect of chain of ownership—(1) Multiple dispositions.* If the stock of more than one subsidiary is disposed of in the same transaction, paragraph (a) (1) of this section shall be applied in the order of the tiers, from the lowest to the highest.

(2) *Examples.* The provisions of this paragraph may be illustrated by the following examples:

Example (1). Assume that corporation P owns all the stock of corporation S with an adjusted basis of zero and an excess loss account of \$5, that S owns all the stock of corporation T with an adjusted basis of zero and an excess loss account of \$15, and that

T owns all of the stock of corporation U with an adjusted basis of zero and an excess loss account of \$10. If T sells the stock of U to a nonmember, T will realize income of \$10, T's earnings and profits will be increased by \$10 (see § 1.1502-33(c)(3)) and S's excess loss account with respect to T's stock will be reduced to \$5 (see § 1.1502-32(b)(2)(i) and (c)(3)). S's earnings and profits will, in turn, be increased by \$10 (see § 1.1502-33(c)(4)) and P's excess loss account with respect to S's stock will be reduced to zero, and its basis for S's stock will be increased to \$5.

Example (2). Assume the same facts as in example (1) except that the stock of T, rather than the stock of U, is sold to a nonmember. Since U ceases to be a member by reason of the sale, T as well as S is considered to have disposed of stock of a subsidiary in the same transaction. Since U is the lowest tier subsidiary, this section is applied first with respect to the excess loss account relating to the stock of U with the same result as in example (1). This section is then also applied with respect to the stock of T. Thus, in addition to the result in example (1), S will realize income of \$5, and P's basis for S's stock will be increased by \$5 to \$10.

Example (3). Corporation P is the common parent of an affiliated group which filed a consolidated return for 1966. Corporations S1 and S2 are wholly owned subsidiaries of P organized on January 1, 1966. Corporation T was also organized on January 1, 1966, its stock being owned 75 percent by S2 and 25 percent by S1. P originally invested \$300 in the stock of S1 and \$200 in the stock of S2; S1 and S2 originally invested \$50 and \$150, respectively, in the stock of T. For the year 1966, there were the following earnings and profits or deficits, computed without regard to § 1.1502-33(c)(4):

S1	\$50
S2	0
T	(400)

There were no consolidated net losses. Under § 1.1502-32(c) the basis and excess loss accounts would be as follows:

	S1 in T	S2 in T	P in S1	P in S2
Original basis	\$50	\$150	\$300	\$200
Deficit of T	(100)	(300)	(100)	(300)
Earnings and profits of S1	50			
Basis or (excess loss account)	(50)	(150)	250	(100)

Assume that the group does not file a consolidated return for 1967. As of December 31, 1966, the following adjustments would be made:

	S1 in T	S2 in T	P in S1	P in S2
Basis or (excess loss account)	(\$50)	(\$150)	\$250	(\$100)
Income to S1	50			
Adjustment under § 1.1502-32(b)(2)			50	
Income to S2		150		
Adjustment under § 1.1502-32(b)(2)				150
Basis of stock	0	0	300	50

(d) **Transfers of stock of subsidiary within the group—(1) In general.** A transfer of stock of a subsidiary from one member to another member in a consolidated return year shall not be treated as a disposition for purposes of paragraph (b) of this section if the basis of such stock in the hands of the transferee is determined by reference to the

basis of such stock in the hands of the transferor. In such case, the transferee member shall succeed to the transferor member's excess loss account with respect to the transferred stock.

(2) **Contributions to capital.** If the transferor in a transfer described in subparagraph (1) of this paragraph owns or receives stock in the transferee, the transferor's excess loss account for the transferred stock shall also be immediately applied to reduce the basis, if any, of the stock which the transferor owns or receives in the transferee. The excess, if any, over such basis shall be the transferor's excess loss account with respect to the stock owned or received. See examples (5) and (6) of paragraph (f) of this section.

(e) **Nontaxable liquidations and reorganizations to which the subsidiary is a party.** If, in a consolidated return year, a subsidiary is the transferor or distributor corporation and another member is the acquiring corporation in a transaction to which section 381(a) applies, any member owning stock in such subsidiary shall not, by reason of such transaction, be considered for purposes of paragraph (b) of this section as having disposed of the stock of such subsidiary. If, pursuant to such transaction, the member owning stock in such subsidiary receives stock in another member in exchange for the owning member's stock in such subsidiary, then any excess loss account with respect to the stock of the subsidiary shall be applied to reduce the basis, to the extent thereof, of the stock in such other member owned or received by the owning member, and any excess over such basis shall be treated as an excess loss account with respect to such stock. For example, assume that corporation P owns all the stock of corporation S with an adjusted basis of zero and an excess loss account of \$20. If S is liquidated into P in a liquidation to which section 334(b)(1) applies, the \$20 excess loss account is eliminated. However, if S is merged into corporation T (another member) in a transaction described in section 368(a)(1)(A), P will apply \$20 against and reduce the basis of any stock of T which P owns, or receives pursuant to the merger, and any excess over such basis will be P's excess loss account with respect to T's stock.

(f) **Examples.** This section may be illustrated by the following examples:

Example (1). Corporation P is the common parent of an affiliated group which files consolidated returns for 1966 through 1970. Included in the group for all such years are corporations S1 and S2 which are wholly owned by P, corporation T which is owned 40 percent by P, and 60 percent by S2, and corporation U which is wholly owned by T. S1, S2, T, and U were each organized on January 1, 1966, with the following investments being made in their stock:

P in S1	\$50
P in S2	110
P in T	40
S2 in T	60
T in U	50

During the period 1966-1970, S1, S2, T, and U made no distributions and had the following earnings and profits or deficits computed without regard to § 1.1502-33(c)(4):

S1	(\$70)
S2	100
T	(120)
U	(80)

There were no consolidated net losses in 1966-1970. Under § 1.1502-32(c) the basis and excess loss accounts for the stock of S1, S2, T, and U would be as follows:

	T in U	P in T	S2 in T	P in S2	P in S1
Original basis	\$50	\$40	\$60	\$110	\$50
Earnings and profits or (deficits):					
of U	(80)	(32)	(48)	(48)	
of T		(48)	(72)	(72)	
of S2				100	
of S1					(70)
Basis or (excess loss account)	(30)	(40)	(60)	90	(20)

On January 1, 1971, P sells its stock in S1 to an unrelated person for \$10. The group files a consolidated return for 1971. P must include in its income for 1971 the \$20 in its excess loss account for S1 and the \$10 gain from the sale of the stock of S1.

Example (2). Assume the same facts as in example (1) except that P does not sell its stock in S1, but on January 1, 1971, P sells its stock in S2 to an unrelated person for \$170. Since S2, T, and U have ceased to be members of the group, the following adjustments must be made:

	T in U	P in T	S2 in T	P in S2
Basis or (excess loss account)	(\$30)	(\$40)	(\$60)	\$90
T's excess loss account in U (see paragraph (c) of this section)	30	12	18	18
S2's excess loss account in T (see paragraph (c) of this section)		(28)	(42)	108
P's excess loss account in T		28		150
Basis or (excess loss account)	0	0	0	150

For the year 1971, P, S2, and T would include in their incomes \$28, \$42, and \$30, respectively. In addition, P would have a gain of \$20 from the sale of the stock of S2, zero bases for its stock in T and S1, and a \$20 excess account for its stock in S1.

Example (3). Assume the same facts as in example (2), except that a consolidated return is not filed for 1971. As of December 31, 1970, P, S2, and T would include in their incomes \$28, \$42, and \$30, respectively (see example (2)), and P would have a \$150 basis for its stock in S2 and a dividend of \$40 from S2 (see § 1.1502-32(e)) and zero bases for its stock in T and S1. In addition, P would include in its income \$20 with respect to its excess loss account in S1 and would have a zero basis for its stock in S1. In 1971, P would have a gain of \$20 from the sale of its stock in S2.

Example (4). Assume the same facts as in example (1), except that P does not sell its stock in S1, but on January 1, 1969, T redeems for \$30 cash, in a transaction qualifying under section 346, one half of its stock held by P. P has income in 1971 of \$20, and P's excess loss account for its remaining stock in T is reduced to \$20. In addition, P has a gain of \$30 on the redemption of the stock of T.

Example (5). Assume the same facts as in example (1), except that instead of selling its stock in S1 to an unrelated person, P transfers its stock in S1 to T in exchange for stock in T in a transaction to which section 351 applies. P's excess loss account of \$20 for the stock in S1 which was transferred

to T increases P's excess loss account for its stock in T from \$40 to \$60. In addition, T has a zero basis and an excess loss account of \$20 for the stock it acquired in S1.

Example (6). Assume the same facts as in example (1), except that P does not sell its stock in S1, but on January 1, 1969, S2 is liquidated into P in a transaction to which section 332 applies (and to which section 334(b)(2) does not apply). P's excess loss account for its stock in S2 is eliminated. No income is realized by S2 by reason of its distribution to P of its stock in T. S2's excess loss account of \$60 for its stock in T is added to, and is merged with, P's excess loss account for its stock in T. Thus, P has an excess loss account of \$100 for all its stock in T.

(g) *Foreign expropriation losses.* The application of this section to foreign expropriation losses is reserved pending the issuance of further regulations.

PAR. 4. Section 1.1502-25 is added to read as follows:

§ 1.1502-25 Consolidated section 922 deduction.

(a) *In general.* The consolidated section 922 deduction for the taxable year shall be determined by multiplying the fraction specified in section 922(2) by that portion of the consolidated taxable income attributable to those members of the group which are Western Hemisphere trade corporations for such year.

(b) *Definition of Western Hemisphere trade corporation.* For purposes of paragraph (a) of this section, in determining whether a member is a Western Hemisphere trade corporation, the definition contained in section 921 shall be applied to such member separately. For purposes of applying the gross income tests of section 921 to such member, the gross income of such member for a consolidated return year shall be determined as if such member had filed a separate return, except that—

(1) Gains and losses on intercompany transactions shall be reflected in gross income in the manner provided by § 1.1502-13;

(2) Gains and losses on transactions with respect to stock, bonds, or other obligations of members of the group shall be reflected in gross income in the manner provided by §§ 1.1502-14 and 1.1502-19; and

(3) The adjustments prescribed by §§ 1.1502-18 and 1.1502-32 shall be made.

(c) *Portion of consolidated taxable income attributable to Western Hemisphere trade corporations.* For purposes of paragraph (a) of this section, the portion of the consolidated taxable income attributable to those members of the group which are Western Hemisphere trade corporations is an amount equal to the consolidated taxable income multiplied by a fraction, the numerator of which is the sum of the separate taxable incomes of those Western Hemisphere trade corporations having separate taxable income, and the denominator of which is the sum of the separate taxable incomes of all of the members having separate taxable income. For purposes of this paragraph, the separate taxable

income of a member shall be determined under § 1.1502-12, adjusted for the following items taken into account in the computation of consolidated taxable income:

(1) The portion of the consolidated net operating loss deduction, the consolidated charitable contributions deduction, and the consolidated dividends received deduction, attributable to such member;

(2) Such member's net capital gain (determined without regard to any net capital loss carryover attributable to such member);

(3) Such member's net capital loss and section 1231 net loss, reduced by the portion of the consolidated net capital loss attributable to such member; and

(4) The portion of any consolidated net capital loss carryover attributable to such member which is absorbed in the taxable year.

PAR. 5. Section 1.1502-31 is added to read as follows:

§ 1.1502-31 Basis of property.

(a) *Deferred intercompany transactions.* The basis of property acquired by a purchasing member in a deferred intercompany transaction shall be determined as if separate returns were filed. Thus, if, in a deferred intercompany transaction, S sells property with an adjusted basis of \$80 to P for \$100, the basis of such property in the hands of P shall be \$100 even though, under § 1.1502-13, S defers its \$20 gain on the sale.

(b) *Basis after liquidation or intercompany distributions with respect to stock—(1) Distributions in kind.* The basis of property received in a distribution to which section 301 applies shall be determined as if separate returns were filed.

(2) *Liquidations and redemptions.* (i) The basis of property acquired in a liquidation to which section 332 applies shall be determined as if separate returns were filed.

(ii) The aggregate basis of all property acquired in a distribution in cancellation or redemption of stock (as defined in § 1.1502-14(b)(3)) by a member to another member, other than a liquidation to which section 332 applies, shall be the same as the adjusted basis of the stock exchanged therefor (adjusted in accordance with the rules prescribed in § 1.1502-32(a)), increased by the amount of any liabilities of the distributing corporation assumed by the distributee or to which the property acquired is subject, and reduced by the amount of cash received in the distribution. Such aggregate basis shall be allocated among the assets received (except cash) in proportion to the fair market values of such assets on the date received.

PAR. 6. Section 1.1502-32 is added to read as follows:

§ 1.1502-32 Investment adjustment.

(a) *In general.* As of the end of each consolidated return year, the basis of the stock (other than stock which is limited and preferred as to dividends) of each subsidiary shall be adjusted in the man-

ner prescribed in paragraph (c) of this section. If a subsidiary owns stock in any other subsidiary, the adjustment with respect to the stock of the higher tier subsidiary shall not be made until after the adjustment is made with respect to the stock of the lower tier subsidiary. In the case of a disposition (as defined in § 1.1502-19(b)) of stock of a subsidiary before the end of the taxable year, the adjustment with respect to such stock shall be made as of the date of disposition. The adjustment required by this section is in addition to any adjustments otherwise required (including reductions in basis under section 301(c)(2)).

(b) *Amount of adjustment—(1) In general.* The amount of the adjustment referred to in paragraph (a) of this section with respect to the stock of any subsidiary shall be the difference between the positive adjustment described in subparagraph (2) of this paragraph, and the negative adjustment described in subparagraph (3) of this paragraph. Such difference is referred to in this section as the "net positive adjustment" or the "net negative adjustment", as the case may be.

(2) *Positive adjustment.* The positive adjustment shall be the sum of—

(i) The amount of the earnings and profits of the subsidiary for the taxable year as determined under § 1.1502-33, but without regard to any distributions made during the taxable year;

(ii) The portion of any consolidated net operating loss for the taxable year attributable to such subsidiary (as determined under § 1.1502-79); and

(iii) The portion of any consolidated net capital loss for the taxable year attributable to such subsidiary (as determined under § 1.1502-79).

(3) *Negative adjustment.* The negative adjustment shall be the sum of—

(i) The amount of the deficit in earnings and profits of the subsidiary for the taxable year (as determined under § 1.1502-33);

(ii) Any net operating loss or net capital loss attributable to the subsidiary (as determined under § 1.1502-79) which is sustained in a prior or subsequent separate return year or consolidated return year and is carried over or back and absorbed in the taxable year;

(iii) Distributions made by the subsidiary during the taxable year out of earnings and profits of the taxable year or earnings and profits accumulated in consolidated return years beginning after December 31, 1965; and

(iv) Distributions made by the subsidiary during the taxable year to other members out of earnings and profits accumulated in separate return years for which the subsidiary was not a member on each day of the taxable year.

(c) *Application of adjustment—(1) In general.* The entire adjustment with respect to each subsidiary shall be allocated to the stock of the subsidiary (other than stock which is limited and preferred as to dividends) owned by other members on the date of the adjustment, even if less than 100 percent of the subsidiary's outstanding stock is owned by members.

(2) *Net negative adjustment.* A member owning stock in the subsidiary shall apply its allocable share of the net negative adjustment to reduce its basis for such stock. Any excess of such adjustment over basis is herein referred to as such member's "excess loss account."

(3) *Net positive adjustment.* A member owning stock in the subsidiary shall apply its allocable share of the net positive adjustment to reduce its excess loss account, if any, with respect to such stock. Any excess of such adjustment over the excess loss account shall be applied to increase the member's basis for such stock.

(4) *Subsequent investment.* If a member transfers property to a subsidiary as a contribution to capital, or acquires stock in the subsidiary (other than stock which is limited and preferred as to dividends), then the amount of the member's excess loss account (with respect to the stock of the subsidiary) at the time of the contribution or acquisition shall be reduced to the extent of the basis of the property contributed or stock acquired, and the basis of the stock acquired shall be decreased by the amount of such reduction.

(5) *Excess loss account.* With respect to the time and manner for taking into account the excess loss account, see § 1.1502-19.

(d) *Transitional rule.* If any subsidiary joined in filing (or was required to join in filing) a consolidated return for a taxable year beginning before January 1, 1966 (whether or not with the same group), then for purposes of determining the basis of stock of such subsidiary as of the first day of the first taxable year to which this section applies, § 1.1502-34A (b) (2) and (c) shall be applied with respect to the stock (other than stock which is limited and preferred as to dividends) of such subsidiary owned by each member as if such stock were disposed of on such date. If the amount of deductions for losses availed of under § 1.1502-34A (b) (2) or (c) (2) exceeds the sum of the aggregate bases of such stock owned by each member, such excess shall be allocated to such stock in accordance with paragraph (c) (1) of this section and shall be treated as an excess loss account with respect to such stock. See § 1.1502-19(a) (2) with respect to the treatment of such excess loss account.

(e) *Adjustment on disposition.* (1) *In general.* As of the last day of the taxable year preceding the first separate return year of a subsidiary, such subsidiary shall be treated as having distributed to each member such member's entire allocable share (as determined under paragraph (c) (1) of this section) of the amount referred to in subparagraph (2) of this paragraph, and each such member shall be treated as having immediately contributed such amount to the capital of such subsidiary.

(2) *Computation.* The amount referred to in subparagraph (1) of this paragraph is the lesser of—

(i) The accumulated earnings and profits of the subsidiary, or

(ii) The excess of—

(a) The net positive adjustments under paragraph (c) (3) of this section for all consolidated return years, over

(b) The net negative adjustments under paragraph (c) (2) of this section for all consolidated return years.

(3) *Example.* This paragraph may be illustrated by the following example:

Example. Assume that in 1967 corporation P organizes corporation S, investing \$500 for all of S's stock. For the taxable year 1967, S has earnings and profits of \$100, thus increasing P's basis in S's stock to \$600 on the last day of 1967. On December 31, 1967, P sells one-half of its stock in S to a non-member for \$350. S will be treated as having distributed a \$100 dividend to P, and P will be treated as having contributed \$100 to the capital of S. P's gain on the sale will be \$50, and its basis for its remaining stock in S will be \$300. S's earnings and profits will be reduced under § 1.1502-33 to zero.

(f) *Section 334(b) (2) adjustments.* If a subsidiary is liquidated pursuant to section 332 and the basis of the assets distributed is determined under section 334(b) (2), the adjustments required by this section shall be modified to the extent necessary to avoid duplications of adjustments required by section 334(b) (2) and the regulations thereunder.

(g) *Examples.* This section may be illustrated by the following examples:

Example (1). On January 1, 1967, corporation P acquires all of the stock of corporation S for \$1,000. On that date S had accumulated earnings and profits of \$200. In 1967, S had no earnings and profits and distributed \$100; in 1968, S had earnings and profits of \$150; in 1969, S had a deficit of \$30 and made a distribution (on the last day of the year) of \$200; in 1970, S had a deficit of \$2,000; in 1971 S had earnings and profits of \$5,000, and made a distribution of \$1,000; in January-June 1972, S had no earnings and profits and made a distribution of \$2,000. Consolidated returns were filed for 1967-1972 in which there were no consolidated net losses. On June 30, 1972, the stock of S was sold to an unrelated person. P's basis in S's stock on June 30, 1972, is computed as follows:

Cost	\$1,000
1967—Distribution of preaffiliation earnings	(100)
Basis	900
1968—Earnings and profits	150
Basis	1,050
1969—Deficit	(30)
Distribution of 1967-1969 earnings	(120)
Distribution of preaffiliation earnings	(80)
Basis	820
1970—Deficit	(2,000)
Excess loss account	(1,180)
1971—Earnings and profits	\$5,000
Distribution of 1971 earnings	(1,000)
Basis	2,820
1972—Distribution of 1967-1971 earnings	(2,000)
Basis on June 30, 1972	820

Example (2). On January 1, 1966, corporation P organized a wholly owned subsidiary, corporation S; on the same date S

organized a wholly owned subsidiary, corporation T. P invested \$1,000 in the stock of S; S invested \$600 in the stock of T. Consolidated returns are filed for the years 1966-1969 for which there were no consolidated net losses. Earnings and profits and deficits of T were as follows:

	T
1966	(\$150)
1967	(900)
1968	600
1969	(100)

Earnings and profits and deficits of S, determined without regard to § 1.1502-33(c) (4), were as follows:

	S
1966	\$100
1967	200
1968	(1000)
1969	500

On December 31, 1969, the adjusted bases and excess loss accounts for the stock of S and T would be computed as follows:

	S in T	P in S
Original basis	\$600	\$1,000
1966:		
Deficit of T	(150)	(150)
Earnings and profits of S	100	100
Basis	450	950
1967:		
Deficit of T	(900)	(900)
Earnings and profits of S	200	200
Basis or (excess loss account)	(450)	250
1968:		
Earnings and profits of T	600	600
Deficit of S	(1,000)	(1,000)
Basis or (excess loss account)	150	(150)
1969:		
Deficit of T	(100)	(100)
Earnings and profits of S	500	500
Basis	50	250

Example (3). Assume that corporation P purchased the stock of corporation S for \$60,000 at the beginning of the calendar year. On August 15, P sold the stock of S for \$70,000. A consolidated return is filed by P and S for the calendar year. S had a \$40,000 net operating loss and deficit for the period it was included in the consolidated return, while P had \$10,000 income for the taxable year (computed without regard to any gain or loss on the sale of S's stock). In computing P's gain on the sale of the stock, P's basis for such stock was decreased by \$40,000, the amount of S's deficit, and increased by the portion of the consolidated net operating or capital loss for the taxable year attributable to S under § 1.1502-79(a) (3). Since there were no such consolidated losses for the taxable year, P's basis for S's stock was \$20,000 and P's gain was \$50,000.

Example (4). Assume the same facts as in example (3) except that P sold the stock of S for \$30,000. In such case, there was a consolidated net capital loss for the taxable year none of which was attributable to S, and a consolidated net operating loss for the taxable year of \$30,000, all of which was attributable to S. P's basis for its stock in S was \$50,000 (original basis of \$60,000, minus S's deficit of \$40,000, plus the consolidated net operating loss attributable to S of \$30,000), and P's loss on the sale of S's stock was \$20,000.

Example (5). Assume that corporation P, the common parent of a group, purchased stock of corporation S on January 1, 1966, for \$50,000. On December 31, 1966, P sold the stock of S for \$80,000. A consolidated return was filed for 1966. During 1966 S had

taxable income and earnings and profits of \$30,000, and the group had consolidated taxable income of \$100,000. In 1967, S had a net operating loss of \$40,000, of which \$30,000 is carried back under § 1.1502-21(c) to the consolidated return for 1966. P's basis as of December 31, 1966, for its stock in S is recomputed as follows:

Original cost.....	\$50,000
Positive adjustment for S's earnings.....	\$30,000
Negative adjustment for carryback.....	(30,000)
Net adjustment.....	0
Basis	50,000

Accordingly, P's recomputed gain on the sale of S's stock is \$30,000.

PAR. 7. Section 1.1502-33 is added to read as follows:

§ 1.1502-33 Earnings and profits.

(a) *Intercompany transactions.* Gain or loss on an intercompany transaction shall be reflected in the earnings and profits of a member for its taxable year in which such gain or loss is taken into account under § 1.1502-13. Thus, for example, gain on a deferred intercompany transaction shall be reflected in the earnings and profits of a member for its taxable year in which such deferred gain is taken into account under paragraph (d), (e), or (f) of § 1.1502-13, rather than for the taxable year in which such gain or loss is deferred.

(b) *Effect of inventory adjustments.* There shall be reflected in the earnings and profits of a member for a taxable year gains and losses taken into account pursuant to § 1.1502-18 for such year.

(c) *Stock and obligations.*—(1) *Dividend distributions.* Dividend distributions from one member to another

member, including dividends under § 1.1502-32(e), shall be reflected in the earnings and profits of the distributee.

(2) *Nondividend distributions.* Distributions to which section 301(c)(3) applies from one member to another member shall not be reflected in the earnings and profits of the distributee.

(3) *Gains or losses on dispositions.* Gains or losses on the disposition of the stock or obligations of a subsidiary (including amounts included in income under § 1.1502-19 and amounts deferred under § 1.1502-14(d)) shall be reflected in the earnings and profits of a member for its taxable year in which such gain or loss is taken into account.

(4) *Investment adjustment.* There shall be reflected in the earnings and profits of a member an amount equal to any increase or decrease pursuant to § 1.1502-32(c) in such member's basis or excess loss account for its stock in a subsidiary. For example, assume that P Corporation invests \$90 in the stock of S and that the basis of such stock is reduced to zero pursuant to § 1.1502-32(c). P's earnings and profits are also reduced by \$90. Subsequently a distribution of \$120 from other than earnings and profits is made by S. No gain is recognized by P (since the excess loss account is increased under § 1.1502-14(a)(2)) and P's earnings and profits are not increased. If P then sells the stock of S to a non-member for \$20, P has gain on the sale of the stock of \$20 and income pursuant to § 1.1502-19 of \$120. Accordingly, P's earnings and profits are increased by \$140.

(5) *Section 381 transactions.* The amount of earnings and profits or deficit of a transferor or distributor corporation which is carried over to the acquiring corporation in a transaction to which

section 381(a) applies shall be adjusted so as not to duplicate any amount previously taken into account under subparagraph (4) of this paragraph.

(6) *Special rule.* The earnings and profits of a subsidiary shall be decreased by the amounts treated as a dividend pursuant to § 1.1502-32(e).

[F.R. Doc. 66-9690; Filed, Sept. 7, 1966; 8:45 a.m.]

[26 CFR Part 1]

CONSOLIDATED RETURN REGULATIONS

Notice of Hearing on Proposed Regulations

The proposed amendment to the regulations under section 1502 of the Code, relating to Consolidated Returns, appears in the FEDERAL REGISTER for September 8, 1966.

A public hearing on the provisions of this proposed amendment to the regulations will be held on Monday, October 10, 1966, at 10 a.m., e.d.s.t., in Conference Room B, Departmental Auditorium, Constitution Avenue between 12th and 14th Streets NW., Washington, D.C.

Persons who plan to attend the hearing are requested to notify the Commissioner of Internal Revenue, Attention: CC:LR:T, Washington, D.C. 20224, by October 5, 1966, telephone (Washington, D.C.) 964-3935.

[SEAL]

LESTER R. URETZ,
Chief Counsel.

By: James F. Dring,
Director, Legislation and
Regulations Division.

[F.R. Doc. 66-9910; Filed, Sept. 7, 1966; 8:52 a.m.]

